



CITY OF
ARCADIA

CITY OF ARCADIA

6th Cycle

Housing Element Update

(2021-2029)



DRAFT May-October 2022



CITY OF ARCADIA 6TH CYCLE Housing Element Update

CITY OF ARCADIA

6th Cycle

Housing Element Update

(2021-2029)

DRAFT May-October 2022



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Contents

Section 1: Introduction	1-1
A. Role of the Housing Element.....	1-1
B. State Policy and Authorization	1-1
1. Background	1-1
2. State Requirements.....	1-1
3. Regional Housing Needs Assessment.....	1-3
4. Relationship to Other Communities	1-3
5. Public Participation	1-4
6. Data Sources	1-5
7. Technical Background Report Organization	1-5
Section 2: Community Profile	2-1
1. Population Characteristics	2-1
A. Population Growth	2-1
B. Age Characteristics.....	2-3
C. Race/Ethnicity Characteristics	2-4
2. Economic Characteristics.....	2-7
A. Employment and Wage Scale.....	2-7
3. Household Characteristics	2-10
A. Household Type	2-10
B. Household Size	2-11
C. Household Income	2-12
3. Housing Problems.....	2-15
A. Overcrowding	2-16
B. Overpayment (Cost Burden) In Relationship to Income	2-18
4. Special Needs Groups	2-20
A. Seniors	2-20
B. Persons with Physical and Developmental Disabilities	2-21
C. Large Households	2-23
D. Single-Parent Households	2-24
E. Farmworkers and Racetrack Workers.....	2-25
F. Students	2-25
G. Extremely Low income Households and Poverty Status	2-26



CITY OF ARCADIA 6TH CYCLE Housing Element Update

H.	Homeless	2-30
5.	Housing Stock Characteristics	2-31
A.	Housing Growth	2-32
B.	Housing Type	2-32
C.	Housing Availability and Tenure	2-33
D.	Vacancy Rates	2-34
E.	Housing Age and Condition	2-36
F.	Housing Costs and Affordability	2-37
Section 3: Housing Constraints, Resources, and Affirmatively Furthering Fair Housing		3-2
1.	Nongovernmental Constraints	3-2
A.	Land Costs and Construction Costs	3-2
B.	Availability of Financing	3-3
C.	Economic Constraints.....	3-6
2.	Governmental Constraints	3-6
A.	Land Use Controls.....	3-6
	State Density Bonus Law	3-8
B.	Residential Development Standards.....	3-9
	Landscaping Requirements	3-13
	Site Coverage and FAR	3-13
	Minimum Unit Sizes	3-13
	Maximum Building Heights.....	3-13
	Parking Standards	3-14
	Definition of a Family	3-15
C.	Homeowners Association Areas.....	3-16
D.	Growth Management Measures	3-20
E.	Specific Plans.....	3-20
	Seabiscuit Pacific Specific Plan – Le Meridien Hotel and Mixed Use Project (SP-SP)....	3-20
F.	Variety of Housing Types Permitted	3-20
	Single-Family Dwelling.....	3-25
	Multi-Family Dwelling	3-25
	Two-Family Dwelling	3-25
	Accessory Dwelling Unit.....	3-25
	Junior Accessory Dwelling Unit	3-25
	Residential Care Facility- Small and Large.....	3-25



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Supportive Housing – Housing Type, Small, and Large	3-25
Transitional Housing – Housing Type, Small, and Large	3-26
Boarding House	3-27
Emergency Shelter	3-27
Hotel and Motel.....	3-27
Live/Work Unit	3-27
Single-Room Occupancy	3-27
Employee Housing.....	3-28
Mobile Homes.....	3-28
Manufactured Homes.....	3-28
Short Term Rentals and Unoccupied Housing	3-28
G. Housing for Persons with Disabilities.....	3-28
Reasonable Accommodation	3-29
H. Development Fees	3-30
I. On-/Off-Site Improvements.....	3-37
Building Codes and Enforcement.....	3-37
Local Processing and Permit Procedures.....	3-38
Permit Processing.....	3-40
Site Plan and Design Review.....	3-41
J. Senate Bill 35	3-42
K. Infrastructure Constraints	3-43
Dry Utilities.....	3-44
Water Supply and Wastewater Capacity	3-44
Fire and Emergency Services	3-45
Police Services	3-46
L. Environmental Constraints.....	3-46
Geologic and Seismic Hazards	3-46
Flooding.....	3-47
Fire Hazards	3-47
Mitigating Environmental Conditions	3-48
3. Affirmatively Furthering Fair Housing (AFFH).....	3-48
A. Needs Assessment	3-48
Countywide AFH Outreach FY 2017	3-49



CITY OF ARCADIA 6TH CYCLE Housing Element Update

2021 – 2029 Housing Element Update Outreach	3-49
Outreach for Persons Experiencing Homelessness	3-49
Compliance with State and Local Fair Housing Laws	3-50
Enforcement and Outreach	3-51
B. Fair Housing Issues.....	3-57
C. Lending Patterns	3-57
D. Hate Crimes	3-59
E. Analysis of Federal, State, and Local Data and Knowledge	3-59
Summary of Local Knowledge Analysis	3-59
Integration and Segregation Patterns and Trends.....	3-59
Racially or Ethnically Concentrated Areas of Poverty (R/ECAP)	3-75
Concentrated Areas of Affluence	3-80
Disparities in Access to Opportunity.....	3-84
G. Discussion of Disproportionate Housing Needs.....	3-107
Existing Needs.....	3-107
Future Growth Need	3-116
Displacement Risk	3-116
Cost of Preservation and Replacement Analysis.....	3-121
Summary of Disproportionate Housing Needs Factors.....	3-121
H. Assessment of Local Contributing Factors to Fair Housing in Arcadia	3-121
AB 686.....	3-123
Potential Effects on Integration and Segregation Trends.....	3-124
AB 686 Sites Analysis AFFH Findings	3-139
I. Summary of Programs to Support Fair Housing	3-140
4. Housing Resources.....	3-141
A. Regional Housing Needs Allocation.....	3-141
Residential Sites Inventory.....	3-142
Selection of Suitable Sites	3-142
Accessory Dwelling Unit Production.....	3-143
Regional Housing Needs Allocation	3-143
Summary of Sites Inventory and RHNA Obligations.....	3-144
5. Financial Resources	3-144
A. Section 8 Housing Choice Voucher	3-145
B. Grants and Programs	3-145



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Community Development Block Grants (CDBG)	3-145
San Gabriel Valley Regional Housing Trust	3-145
CalCHA and CSCDA-CIA	3-145
C. Opportunities for Energy Conservation	3-145
Title 24	3-146
Energy Use and Providers	3-146
Section 4: Review of Past Performance	4-2
Program Evaluation for Households with Special Needs	4-2
Seniors	4-2
Persons with Disabilities	4-5
Large Households	4-5
Farmworkers	4-5
Single-Parent Households	4-6
Persons Experiencing Homelessness	4-6
Extremely Low Income Households	4-7
Review of 5th Cycle Programs	4-8
Appendix A: Adequate Sites	A-1
A. Adequate Sites Analysis Overview	A-1
1. Selection of Sites	A-4
2. Projects in the Pipeline	A-4
3. Redevelopment of Non-Vacant Sites for Residential Use	A-6
4. Accessory Dwelling Units	A-9
5. Selection of Sites to Accommodate Remaining Need	A-12
Downtown Mixed-Use Expansion & Overlay	A-12
Mixed-Use Upzone	A-16
Las Tunas and Live Oak Corridor	A-19
C-G Residential Flex Overlay	A-22
R-3 Upzone	A-24
Arcadia Golf Course	A-29
6. Development of Small Site Parcels	A-31
7. Water, Sewer and Dry Utility Availability	A-34
Water and Sewer	A-34
Utilities	A-35
B. Calculations of Unit Capacity	A-36



CITY OF ARCADIA 6TH CYCLE Housing Element Update

8. Capacity Calculations.....	A-36
Net Unit Calculations	A-36
8. Zoning and General Plan Designations	A-37
9. Adequate Sites Table	A-37
Appendix B: Community Engagement Summary	B-1
1. Housing Element Update Website.....	B-3
2. Community Workshop #1 – Informational Video and Presentation	B-4
3. Online Community Survey.....	B-5
4. Community Workshop #2	B-7
5. Social Media and City Publications	B-8
6. Public Comments.....	B-9
Appendix C: Glossary of Terms	C-1



CITY OF
ARCADIA

Technical Background Report

Section 1

Introduction





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Section 1: Introduction

A. Role of the Housing Element

The Housing Element is a state mandated chapter of the Arcadia's General Plan; it identifies and analyzes the City's housing needs and includes a detailed outline and work program of the City's goals, policies, and quantified objectives. The Housing Element also addresses the maintenance and expansion of the housing supply to accommodate households currently living and expected to live in Arcadia during the 2021-2029 planning period. Through research and analysis, the Housing Element identifies available candidate housing sites and establishes the City's official housing policies and programs to accommodate the Regional Housing Needs Assessment (RHNA) goals as determined by the Southern California Association of Governments (SCAG). The programs and policies established within the Housing Element guide future decision-making to achieve the City's housing goals for the 2021-2029 planning period.

B. State Policy and Authorization

1. Background

As a mandated chapter of the Arcadia General Plan, the Housing Element must meet all requirements of existing state laws. Goals, programs and policies, and quantified objectives within the Housing Element consistent with state law are to be implemented within a timeline to ensure the City accomplishes the identified actions.

2. State Requirements

California State Housing Element Law (California Government Code Article 10.6) establishes the requirements for the Housing Element. State Law requires that local governments review and revise the Housing Element of their comprehensive General Plans once every eight years.

The California Legislature has adopted an overall housing goal for the State to ensure every resident has a decent home and suitable living environment. Section 65580 of the California Government Code states:

- a) The availability of housing is of vital statewide importance, and the early attainment of decent housing and a suitable living environment for every Californian, including farmworkers, is a priority of the highest order.
- b) The early attainment of this goal requires cooperative participation of government and the private sector in an effort to expand housing opportunities and accommodate the housing needs of Californians in all economic levels.
- c) The provisions of housing affordable to low and moderate income households requires the cooperation of all levels of the government.
- d) Local and State governments have a responsibility to use the powers vested in them to facilitate the improvement and development of housing to make adequate provision for housing needs of all economic segments of the community. The Legislature recognizes that in carrying out this responsibility, each local government also has the responsibility to consider economic, environmental, and fiscal factors and community goals set forth in the general plan and to cooperate with other local governments and the state in addressing regional housing needs.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 1-1 summarizes the State Housing Element requirements and identifies where these requirements are addressed in the Housing Element Update.

Table 1-1: Housing Element Requirements

Housing Element Requirements	Gov. Code Requirements	Reference in Housing Element
Analysis of employment trends.	Section 65583.a	Section 2.2
Projection and quantification of existing and projected housing needs for all income groups.	Section 65583.a	Section 3.3.G
An inventory of land suitable for residential development including vacant sites and sites with redevelopment potential.	Section 65583.a	Appendix A
Analysis of existing and potential governmental constraints upon the maintenance, improvement, or development of housing for all income levels.	Section 65583.a	Section 3.2
Analysis of existing and potential nongovernmental (private sector) constraints upon maintenance, improvement or development of housing for all income levels.	Section 65583.a	Section 3.1
Analysis concerning the needs of the homeless.	Section 65583.a	Section 2.4.H
Analysis of special housing needs: handicapped, elderly, large families, farm workers, and female-headed households.	Section 65583.a	Section 2.4
Analysis of opportunities for energy conservation with respect to residential development.	Section 65583.a	Section 3.5.C
Identification of Publicly Assisted Housing Developments.	Section 65583.a	Section 3.5.B
Identification of Units at Risk of Conversion to Market Rate Housing.	Section 65583.a	Section 3.3.G
Identification of the City's goal relative to the maintenance, improvement, and development of housing.	Section 65583.a	Housing Element: Goals, Policies and Programs
Analysis of quantified objectives and policies relative to the maintenance, improvement, and development of housing.	Section 65583.a	Implementation Plan



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Housing Element Requirements	Gov. Code Requirements	Reference in Housing Element
Identification of adequate sites that will be made available through appropriate action with required public services and facilities for a variety of housing types for all income levels.	Section 65583.b	Appendix A
Identification of strategies to assist in the development of adequate housing to meet the needs of low and moderate income households.	Section 65583.c(1)	Appendix A
Description of the Public Participation Program in the formulation of Housing Element Goals, Policies, and Programs.	Section 65583.d	Appendix B
Description of the Regional Housing Needs Assessment (RHNA) prepared by the Southern California Association of Governments.	Section 65583.e	Section 3.4.A
Analysis of Fair Housing, including Affirmatively Furthering Fair Housing.	Section 8899.50	Section 3.3
Review of the effectiveness of the past Element, including the City's accomplishments during the previous planning period.	Section 65583.f	Section 4
<i>Source: State of California, Department of Housing and Community Development.</i>		

Arcadia's Housing Element was last adopted in December 2013 for the 5th cycle of the 2014-2021 planning period. The Housing Element for the 2021-2029 planning period, is part of the 6th update cycle for jurisdictions within the SCAG region and allows for synchronization with the Regional Transportation Plan and Sustainable Communities Strategy (RTP/SCS). The Element sets forth an 8-year strategy to address the City's identified housing needs, including specific programs and activities.

3. Regional Housing Needs Assessment

Section 65583 of the California Government Code sets forth the specific content requirements of a jurisdiction's housing element. Included in these requirements are obligations on the part of local jurisdictions to provide their "fair share" of regional housing needs. Local governments and Councils of Governments (COGs) are required to determine existing and future housing need and the allocation of this need must be approved by the California Department of Housing and Community Development (HCD). Arcadia is a member agency of the Southern California Association of Governments (SCAG). SCAG is responsible for preparing the Regional Housing Needs Assessment (RHNA) for all jurisdictions within the SCAG region.

HCD established the planning period for the current RHNA from October 15, 2021 to October 15, 2029. For the 2021-2029 planning period, the City is allocated a total of 3,214 units, including 1,102 units affordable to very low income households, 570 units affordable to low income, 605 units affordable to moderate-income, and 937 units affordable to above moderate (market-rate) income households.

4. Relationship to Other Communities



CITY OF ARCADIA 6TH CYCLE Housing Element Update

The goals, policies, actions, and programs described in the Housing Element relate to, and are consistent with, the other Elements of the Arcadia General Plan, which was last updated in November 2010. The Housing Element supports and reinforces development policies contained in the Land Use Element. The Land Use Element establishes the location, type, intensity, and distribution of land uses throughout the City, and defines these land uses' build-out potential. By designating residential development, the Land Use Element identifies limits for densities and types of housing units constructed in the City. It also identifies lands designated for a range of other land uses, including employment-generating uses, open space, and public uses. The presence and potential for jobs can affect the current and future local demand for housing at the various income levels in the City.

The Circulation Element of the General Plan also relates to the Housing Element. The Circulation Element establishes a transportation plan to accommodate the movement of people and goods within and through the City. Consequently, the Housing Element must include policies and incentives that consider the types of infrastructure essential for residential housing units in addition to mitigating the effects of growth in the City.

The Housing Element has been reviewed for consistency with the City's other General Plan Elements, and the Housing Element's policies and programs are consistent with the other Elements. As portions of the General Plan may be amended in the future, the Housing Element will be reviewed to ensure internal consistency is maintained.

5. Public Participation

Section 65583 of the Government Code states that, "The local government shall make diligent effort to achieve public participation of all economic segments of the community in the development of the housing element, and the program shall describe this effort." Meaningful community participation is also required in connection with the City's Assessment of Fair Housing (AFH). A discussion of citizen participation is provided below.

As part of the 6th Cycle Housing Element Update process, the City of Arcadia has conducted public outreach efforts beginning in 2021. These recent outreach efforts included a virtual presentation, an online survey, Community Workshop, digital media, advertisement on through social media and newsletters, and noticed Public Hearings. Project materials, including summaries from community workshops and public meetings, notices, and draft public review documents are available on the City's website.

Outreach for the 6th Cycle Housing Element to the community includes the following actions:

- Housing Element Update webpage with all housing materials available in English and Chinese located at: <https://www.arcadiaca.gov/housing>
- Informational Videos and recorded presentations posted to the City's website in June, 2021
- Postcard mailed to every residential postal customer in the City informing the community of the Housing Element in general, how to get involved, and how to access the community survey
- Online Community Survey, in English and Chinese, provided from June 14, 2021 to August 6, 2021
- A Virtual Community Workshop hosted on September 23, 2021 which was recorded and posted to the City's website
- Advertisements and outreach through social media and City newsletters
- Public Review of the Draft Housing Element



CITY OF ARCADIA 6TH CYCLE Housing Element Update

As required by Government Code Section 65585(b)(2), all written comments regarding the Housing Element made by the public have previously been provided to each member of the City Council.

Appendix B contains a summary of all public comments regarding the Housing Element received by the City during the update process.

6. Data Sources

The data used for the completion of this Housing Element comes from a variety of sources. These include, but are not limited to:

- United States Census, 2010
- American Community Survey, 5-Year Estimates, 2019
- Regional Analysis of Impediments to Fair Housing (AI)
- Point-in-Time Homeless Census by the Regional Task Force on the Homeless, 2019
- Home Mortgage Disclosure Act (HMDA) lending data
- California Department of Economic Development
- California Employment Development Division Occupational Wage data, 2020
- Department of Housing and Urban Development, Comprehensive Housing Affordability Strategy (CHAS), 2013-2017

The data sources represent the best data available at the time this Housing Element Update was prepared. The original source documents contain the assumptions and methods used to compile the data.

7. Technical Background Report Organization

This Technical Background Report presents the technical analysis and City's background which informed the City of Arcadia's policy program for the 2021-2029 6th Cycle Planning Period. This Report is comprised of the following sections:

Section 1: Introduction contains a summary of the content, organization and statutory consideration of the Housing Element;

Section 2: Community Profile contains a detailed analysis of the City's population, household and employment base, and the characteristics of the housing stock;

Section 3: Housing Constraints, Resources, and Affirmatively Furthering Fair Housing examining governmental and non-governmental constraints on production, maintenance, and affordability of housing and provides a summary of housing resources, including sites identification, funding, and financial considerations;

Section 4: Review of Past Performance includes a review of the City's progress in implementing the programs under the previously adopted Housing Element.

Appendices provide supplementary background resources including:

- **Appendix A** – Adequate Sites Analysis
- **Appendix B** – Community Engagement Summary
- **Appendix C** – Glossary of Housing Terms



CITY OF
ARCADIA

Technical Background Report

Section 2

Community Profile





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Section 2: Community Profile

The Community Profile provides an overview of the City's housing and population conditions and lays the foundation for policies and programs within the Housing Element. The City of Arcadia strives to achieve a balanced housing stock that meets the varied needs of all income segments of the community. To understand the City's housing needs, the nature of the existing housing stock and the housing market must be comprehensively evaluated. This section of the Technical Background Report discusses the major components of housing needs in Arcadia, including population, household information, economic characteristics, and housing stock characteristics. Each of these components is presented in a regional context, and where relevant, in the context of other nearby communities. This assessment serves as the basis for identifying the appropriate goals, policies, and programs for the City to implement during the 2021-2029 Housing Element Cycle.

1. Population Characteristics

Understanding the characteristics of a population is vital in the process of planning for the future needs of a community. Population growth, age composition, and race/ethnicity influence the type and extent of housing needed and the ability of the local population to afford housing costs. Issues such as population growth, race/ethnicity, age, and employment trends are factors that combine to influence the type of housing needed and the ability to afford housing. The following section describes and analyzes the various population characteristics and trends that affect housing need.

A. Population Growth

Table 2-1 exhibits the population growth in the City of Arcadia and surrounding jurisdictions using the Southern California Association of Governments (SCAG) Regional growth forecast report and US Census data. The 2010 Census reported a total population of 55,704 in the City of Arcadia which is significantly lower than nearby jurisdictions such as Pasadena and El Monte. The Southern California Association of Governments (SCAG) compiled, using data and direction from multiple state entities, a Regional Growth Forecast which produces socio-economic estimates and projections at multiple geographic levels for multiple years. The SCAG Regional Growth Forecast (2016-2045) projected a 2.87 percent population growth for the City of Arcadia from 2010 to 2016. SCAG projects that the City of Arcadia is expected to see a 14.98 percent increase from 2010 to 2045.



CITY OF ARCADIA 6TH CYCLE Housing Element Update


Table 2-1: Population Growth

Jurisdictions	Population			Percent Change	
	2010 Actual	2016 Projected	2045 Projected	2010-2016	2010-2045
Monrovia	36,616	38,000	42,100	3.78%	10.79%
Pasadena	136,449	142,100	155,500	4.14%	9.43%
Arcadia	56,364	57,300	62,200	2.87%	8.55%
El Monte	113,888	114,300	137,500	0.36%	20.30%
Los Angeles County*	-	1,044,500	1,258,000	%	20.44%

Represents an estimate from the SCAG 2016-2040 Regional Growth Forecast.
Sources: American Community Survey, 5-year estimate (2010) and SCAG 2016-2040 Regional Growth Forecast by Jurisdiction Report.
**Los Angeles County data is for the Unincorporated data reported by SCAG*

According to the U.S. Census 5-Year Estimates, Arcadia's total population in 2016 was 57,755 which is 0.8 percent higher than the population projected in SCAG's Regional Growth Forecast. **Figure 2-1** below shows Arcadia's population growth from 2010 to 2019. While the SCAG model may only be able to roughly predict population changes over time, it considers regional trends and acts as a valuable tool for planning for future housing needs.

Figure 2-1: Population Change in Arcadia (2010 – 2019)



Source: American Community Survey, 5-year estimate (2010-2019)




CITY OF ARCADIA 6TH CYCLE Housing Element Update

B. Age Characteristics

The age composition of a community is an important factor in evaluating housing needs because housing demand within the market is often determined by the preferences of certain age groups. Conventionally, young adults and seniors tend to favor apartments, low to moderate-cost condominiums, and smaller or more affordable single-family units because they tend to live on smaller or fixed incomes and have smaller families. The middle-aged demographic, persons between 35-years and 65-years, makes up the major portion of home buyers as well as the market for moderate to high-cost apartments and condominiums because they generally have higher incomes and larger families to accommodate. As the population moves through different stages of life, housing is required to accommodate new or adjusted needs. In order to produce a well-balanced and healthy community, where needs are met, it is essential that a community be provided with appropriate housing to accommodate needs of all ages.

Figure 2-2 compares changes in the age composition of Arcadia's population from 2010 to 2019, while **Table 2-2** compares the age distribution of Arcadia to surrounding jurisdictions. According to the American Community Survey (ACS), age distribution in Arcadia has remained relatively stable over the past decade. As shown in **Figure 2-2**, there has been a slight increase in the population aged 65 years and older (about 14 percent to 19 percent) and a slight decline in the population aged 25 to 44, showing aging in the overall population. Overall, Arcadia's age distribution has remained stable in the past decade.

Figure 2-2: Age Distribution in Arcadia (2010-2019)



Source: American community Survey, 5-Year Estimates, 2010, 2015, and 2019.

Table 2-2 below shows the age characteristics of the City of Arcadia compared to surrounding jurisdictions and Los Angeles County. According to the 2019 ACS, Arcadia had a smaller young adult population (age 20 to 24) as well as a smaller percentage of residents under the age of 14 compared to nearby jurisdictions. Arcadia also has the highest percentage of their population above 45 years of age compared to nearby jurisdictions. Overall, the City's population is older than that of most neighboring cities and the County of Los Angeles.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-2: Age Characteristics / Age Distribution

Jurisdiction	Under 5	5 to 14	15 to 19	20 to 24	25 to 44	45 to 64	65 years+
Monrovia	4.3%	12.7%	5.6%	6.1%	28.9%	28.5%	13.9%
Pasadena	6.6%	9.0%	4.6%	5.7%	33.2%	24.9%	15.9%
Arcadia	5.0%	12.6%	6.3%	3.8%	23.8%	29.3%	19.3%
El Monte	5.8%	13.3%	6.5%	7.9%	28.5%	24.6%	13.4%
Los Angeles County	6.1%	12.1%	6.4%	7.1%	29.8%	25.2%	13.2%

Source: American Community Survey, 5-Year Estimates, 2019

C. Race/Ethnicity Characteristics


Racial and ethnic composition within a City is important to understand and analyze the different needs and implications for housing in a community. It is common for different racial and ethnic groups to have different household characteristics, income levels, and cultural backgrounds which may affect their housing needs, housing choice, and housing types. Cultural influences may reflect preference for a specific type of housing. Ethnicity can also correlate with other characteristics such as location choices, mobility, and income. This is analyzed further in the Affirmatively Furthering Fair Housing discussion within the Housing Constraints section of the Housing Element.

Figure 2-3 displays the 2019 American Community Survey racial and ethnic compositions data for both the City of Arcadia and the County of Los Angeles. According to the data, over half of the population in Arcadia identifies as Asian (64.2 percent) with the next largest population identifying White (30.7 percent), and 4.9 percent as Some Other Race. Conversely, the majority of Los Angeles County identified as White (54.4 percent) with 16.3 identifying as Asian and 22.2 percent identified as Some Other Race. Those who identified as two or more races accounted for 3.5 percent of the population in Arcadia and about four percent in the County. Los Angeles County had a larger percentage of the population who identified as Black, 9.2 percent compared to 2.7 percent in Arcadia. Additionally, both the percentage of American Indian and Native Alaskan population and the Native Hawaiian or Other Pacific Islander population were under two percent in the County and in Arcadia.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 2-3: Racial/Ethnic Composition, 2019



Source: American Community Survey 5-Year Estimates, 2019.

Table 2-3 below displays Racial and Ethnic Composition data for Arcadia, the County and surrounding jurisdictions. Trends similar to those expressed in **Figure 2-3** above show the population identified as Asian is the largest population while the second largest population identified as White in Arcadia. Overall, El Monte had the largest percentage of persons, of any race, who reported Hispanic or Latino (65.7 percent) and the second lowest percentage of persons who reported White (39.9 percent). Persons who reported Native Hawaiian or Other Pacific Islander counted as less than two percent in all jurisdictions as shown in **Table 2-3**. Overall, the racial and ethnic compositions of each city and the County of Los Angeles vary in many aspects, however groups such as American Indian and Alaska Native as well as Native Hawaiian and Other Pacific Islander make up small portions of all populations in Arcadia and its neighboring jurisdictions.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-3: Racial/Ethnic Composition, 2019

Jurisdiction	White	Black	American Indian and Alaska Native	Asian	Native Hawaiian or Other Pacific Islander	Some Other Race	Two or More Races	Hispanic or Latino (of any race)
Monrovia	67.80%	6.80%	2.50%	17.10%	1.30%	11.00%	5.80%	41.10%
Pasadena	54.60%	10.50%	1.20%	19.60%	0.50%	19.00%	4.90%	34.90%
Arcadia	30.70%	2.70%	0.40%	64.20%	0.70%	4.90%	3.50%	11.10%
El Monte	39.90%	0.90%	3.20%	29.10%	1.00%	29.40%	3.30%	65.70%
Los Angeles County	54.40%	9.20%	1.60%	16.30%	0.60%	22.20%	4.00%	48.50%

Source: American Community Survey, 5-Year Estimates, 2019

The Census and the 2019 ACS report significant changes in Arcadia's racial and ethnic demographics from 2010 to 2019, displayed below in **Table 2-4**. The Asian population makes up the largest racial/ethnic group within Arcadia. The percentage of population reported Asian increased about 7.13 percent from 2010 to 2015 and another 6 percent from 2015 to 2019. The largest growth experienced in a population is shown in the Native Hawaiian or Other Pacific Islander population, which grew from 94 persons in 2010 to 418 persons in 2019 (over 344 percent change), however it should be noted that smaller group's growth rates increase more quickly as individuals move into the group. The population reported as Some Other Race experienced an increase (20.98 percent increase) through 2015, then a 29.53 percent decrease through 2019. Persons of any race who reported Hispanic or Latino increased by 6.62 percent in the five years from 2010 to 2015 and decreased by 10 percent through 2019. There were two groups that experienced all around decreases in their populations from 2010 through 2019—American Indian and Alaska Native as well as White. The American Indian and Alaska Native population experienced a population decline of 28.2 percent from 2010 to 2019. The data shows that the population which identified as White decreased 4.84 percent from 2010 to 2015, and also decreased by 4.59 percent growth from 2015 to 2019 (from 18,726 to 17,866 individuals). Overall, many of the racial and ethnic groups are growing in Arcadia with a few exceptions. The Asian population has been the largest racial group within the City from 2010 and remains the dominant group as of 2019.

Table 2-4: Racial/Ethnic Composition, 2019

Race/Ethnicity	2010	2015	2019	Percent Change 2010 to 2015	Percent Change 2015 to 2019
White	19,679	18,726	17,866	-4.84%	-4.59%
Black	654	1,069	1,573	63.46%	47.15%
American Indian and Alaska Native	344	255	247	-25.87%	-3.14%
Asian	32,853	35,194	37,307	7.13%	6.00%



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Native Hawaiian or Other Pacific Islander	94	271	418	188.30%	54.24%
Some Other Race	3,322	4,019	2,832	20.98%	-29.53%
Two or More Races	1,132	1,870	2,012	65.19%	7.59%
Hispanic or Latino	6,725	7,170	6,453	6.62%	-10.00%
Source: American Community Survey, 5-Year Estimates, 2010, 2015, and 2019.					

2. Economic Characteristics

Reporting and analyzing economic characteristics of a community is an important component of the Housing Element. The data provides valuable insight into Arcadia's ability to access the housing market as well as identifies financial restraints consistent with housing needs and accommodations. Incomes associated with different types of employment and the number of workers in a household affect housing affordability and choice. Therefore, to consider a healthy balance between jobs and housing, it is important to consider the employment characteristics of a community. Local employment growth is linked to local housing demand, with the reverse being true when employment rates decrease.

A. Employment and Wage Scale

For a City to achieve a healthy balance between jobs and housing, it is important to consider employment, wage and occupational characteristics and growth changes. The SCAG Growth Forecast Report estimates a large range of employment growth for the City of Arcadia and nearby cities. The data is shown in **Table 2-5**. From 2016 to 2045 the County of Los Angeles is expected to gain 51,000 jobs, an 18.95 percent increase. From 2016 to 2045, Arcadia's employment is expected to grow by 10.74 percent, creating 3,500 jobs. Nearby cities such as Pasadena and El Monte are expected to outpace Arcadia's employment growth from 2016 to 2045 (20.65 percent and 21.24 percent respectively). Increased employment in Arcadia and the surrounding jurisdictions could indicate an opportunity to look at mixed-use development, particularly near transit centers that connect to jurisdictions with growing employment centers.

Table 2-5: Employment Growth (2016-2045)				
Jurisdiction	2016 Projected	2045 Projected	% Change 2016-2045	Numeric Change 2016-2045
Monrovia	22,700	24,800	9.25%	2,100
Pasadena	116,200	140,200	20.65%	24,000
Arcadia	32,600	36,100	10.74%	3,500
El Monte	30,600	37,100	21.24%	6,500
Los Angeles County	269,100	320,100	18.95%	51,000
Source: SCAG 2016-2040 Regional Growth Forecast by Jurisdiction Report.				

Analyzing the employment by sector in a city is important in understanding growth changes, income and wages, access to different types of housing, as well as what housing needs maybe be present. **Table 2-6** displays the data for employment by sector for the City of Arcadia in both 2010 and 2019. The table shows that the largest percentage of employed persons in Arcadia work in education services, healthcare, and social assistance industries (22.57 percent in 2010 and 23.31 percent in 2019). Professional, scientific, management, and administrative services make up the second largest group of employment in Arcadia, however from 2010 through 2019, there has been a slight decline of persons participating in these fields.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Persons working in finance and insurance as well as real estate and rental housing are the third largest employment groups in Arcadia in 2010 and remain as such through 2019. Both manufacturing and retail trade industries employ a fairly large percentage of Arcadia, however, the data shows a decrease of 26.28 percent in retail trade from 2010 through 2019. The City of Arcadia has a relatively high income with a median income about 38 percent higher than the County's median income (see **Table 2-15**). Arcadia's high median income could be due to the higher percentage of persons employed in education, professional, health care, and management industries.

Table 2-6: Employment by Sector (2010 & 2019)

Industry Sector	2010		2019		Percent Change 2010-2019
	# of people employed	% of City Employment	# of people employed	% of City Employment	
Agriculture, forestry, fishing and hunting, and mining	40	0.15%	101	0.38%	152.50%
Construction	919	3.44%	864	3.28%	-5.98%
Manufacturing	2091	7.82%	2,363	8.98%	13.01%
Wholesale trade	1987	7.43%	1,984	7.54%	-0.15%
Retail trade	2698	10.09%	1,989	7.56%	-26.28%
Transportation and warehousing, and utilities	915	3.42%	1,479	5.62%	61.64%
Information	789	2.95%	806	3.06%	2.15%
Finance and insurance, and real estate and rental leasing	3286	12.29%	2,775	10.55%	-15.55%
Professional, scientific, management, and administrative services	3770	14.10%	3,612	13.73%	-4.19%
Education services, health care, and social assistance	6035	22.57%	6,131	23.31%	1.59%
Arts, entertainment, recreation, accommodation, and food services	2291	8.57%	2,081	7.91%	-9.17%
Other services (except public administration)	1057	3.95%	1,015	3.86%	-3.97%
Public Administration	865	3.23%	1,107	4.21%	27.98%
Total	26,743	100.00%	34,867	100.00%	30.38%
<i>Source: American Community Survey, 5-Year Estimates, 2010 and 2019.</i>					

In addition to reporting and analyzing employment sector trends, analyzing the unemployment rate is essential to understanding current housing affordability and needs, as well as projected needs. Economists identify a 3.5 to 4.5 percent unemployment as natural, in that it reflects the real voluntary economic forces



CITY OF ARCADIA 6TH CYCLE Housing Element Update

within a City.¹ According to the ACS data, (**Table 2-7**) in 2019, Arcadia experienced a 2.7 percent unemployment rate, slightly lower than the County's 3.9 percent unemployment rate. Both Pasadena and El Monte had higher unemployment rates in 2019 compared to Arcadia (2.8 and 3.8 percent respectively). Arcadia had one of the lowest unemployment rates in the area in 2019.

Table 2-7: Unemployment Rate, 2019	
Jurisdiction	Unemployment rate
Monrovia	4.0%
Pasadena	2.8%
Arcadia	2.7%
El Monte	3.8%
Los Angeles County	3.9%
<i>Source: American Community Survey, 5-Year Estimates, 2019.</i>	
<i>*Population 16 years and over</i>	

Table 2-8 displays the average annual wage for occupations compiled by the California Employment Development Department (EDD) for the Los Angeles County Metropolitan Statistical Area in 2021. The median income for the City is \$93,574 (See **Table 2-14**). Management, Legal, and Healthcare Practitioners and Technical occupations were among the highest paying professions in the region. Additionally, occupations such as Architecture and Engineering as well as Computer and Mathematical occupations offer above median income pay. Life, Physical, and Social Science occupations offer just below median income salaries and are among the more common occupations in Arcadia.

Table 2-8: Mean Salary by Occupation in Los Angeles County, 2021	
Occupation	Salary
Management	\$140,550
Legal	\$137,750
Healthcare Practitioners and Technical	\$105,055
Architecture and Engineering	\$104,271
Computer and Mathematical	\$104,033
Life, Physical and Social Sciences	\$94,890
Business and Financial Operations	\$87,545
Education, Training and Library	\$75,433
Arts, Design, Entertainment, Sports and Media	\$90,874
Construction and Extraction	\$64,680
Protective Services	\$67,082
Community and Social Service	\$64,145
Installation, Maintenance and Repair	\$60,025
Sales	\$51,016
Office and Administration Support	\$48,540

¹ Natural Rate of Unemployment, Its Components, and Recent Trends, Kimberly Amadeo, ed. Eric Estevez, August 30, 2020



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Production	\$43,266
Transportation and Material Moving	\$45,165
Healthcare Support	\$36,196
Building, Grounds Cleaning, and Maintenance	\$40,449
Personal Care and Service	\$41,313
Farming, Fishing and Forestry	\$37,535
Food Preparation and Serving Related	\$34,405
<i>Source: California Employment Development Division, Occupational Wage data, 2020.</i>	

3. Household Characteristics

A household is considered all persons who occupy one housing unit, as defined by the Census; this may include single persons living alone, families related through marriage, blood or adoption, domestic partnerships and unrelated individuals living together. Nursing facilities, residential care facilities, dormitories, and other group living situations are not considered a housing unit.

Information on household characteristics is important in analyzing and understanding growth and determining the housing needs of a community. Income and affordability are best measured at the household level, as well as the special needs of certain groups, such as large families, single parent households, or low and extremely low income households. For example, if a City has a prominent aging population, who are homeowners but live on fixed incomes, it may consider implementing a home beautification assistance program.

A. Household Type

Table 2-9 displays American Community Survey data from 2019 reporting household characteristics for Arcadia and nearby jurisdictions. The ACS reported that the majority of households in Arcadia were married-couple family households (58 percent). All other surrounding jurisdictions have somewhat lower proportions of married family households when compared to Arcadia. Non-family households, which includes persons living in the same house who are not related, such as roommates, made up about 20 percent of all households in Arcadia in 2019. Female-headed households made up approximately 16.63 percent of total households in Arcadia. El Monte has a slightly higher proportion of female-headed households than Arcadia, however, the other surrounding jurisdictions, including Los Angeles County, have lower proportions of female-headed households in their overall household types. Overall, Arcadia's breakdown of household characteristics is similar to surrounding jurisdictions and the County of Los Angeles.

Table 2-9: Household Characteristics (2019)							
Jurisdiction	Married-couple Family Households	% of Total Households	Female-headed Household, No Spouse Present	% of Total Households	Non-Family Household	% of Total Households	Total Households
Monrovia	5,840	45.17%	1,964	15.19%	4,165	32.22%	12,928
Pasadena	22,980	41.61%	5,722	10.36%	23,983	43.43%	55,224



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Arcadia	11,357	58.18%	3,246	16.63%	3,931	20.14%	19,520
El Monte	14,672	49.05%	5,803	19.40%	5,950	19.89%	29,913
Los Angeles County	1,495,658	45.09%	488,776	14.74%	1,105,856	33.34%	3,316,795
<i>Source: American Community Survey, 5-Year Estimates, 2019.</i>							

Table 2-10 displays the changes in household types in Arcadia from 2010 to 2019. In 2010, the ACS estimated about 59 percent of all households to be married-couple family households, and this number remained nearly identical over the decade. Non-family households saw a decrease from 23.87 percent in 2010 to 20.14 percent in 2019, and female headed households increased from 12.58 percent in 2010 to 16.63 percent in 2019. Overall, total households in Arcadia increased moderately from an estimated 18,983 to an estimated 19,520 over the course of nine years.

Table 2-10: Changes in Household Types						
Household Types	2010	Percent	2015	Percent	2019	Percent
Married-couple Family Households	11,225	59.13%	11,494	58.77%	11,357	58.18%
Female headed Household, No Spouse Present	2,388	12.58%	2,561	13.09%	3,246	16.63%
Nonfamily Household	4,531	23.87%	4,482	22.92%	3,931	20.14%
Total Households	18,983	100.00%	19,559	100.00%	19,520	100.0%
<i>Source: American Community Survey, 5-Year Estimates, 2010, 2015, 2019.</i>						

B. Household Size

Household size is an indicator of both population growth and the character of households. Average household size can be both a result and indicator of housing affordability and other household economic conditions, and it is important in understanding housing needs. Overcrowding is a result of having inadequate space for a household and considered a burden on a household; therefore, cities must analyze their average person per household size to appropriately respond to the type of housing needs in their community.

Table 2-11 displays the average household size for Arcadia as well as surrounding jurisdictions and the County of Los Angeles. According to the ACS 2019 estimates, Arcadia's average household size in 2019 was 2.95. Nearby jurisdictions had a range of 2.49 persons per household in Pasadena, to 3.82 persons per household in El Monte. The County of Los Angeles averaged an estimated 2.99 persons per household. Overall, the City of Arcadia was not demonstrated as an outlier, having an average household size consistent with neighboring cities and the County.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-11: Average Household Size

Jurisdiction	Average Persons per Household
Monrovia	2.83
Pasadena	2.49
Arcadia	2.95
El Monte	3.82
Los Angeles County	2.99
Source: American Community Survey, 5-Year Estimates, 2019.	

Table 2-12 depicts the SCAG 2016 to 2045 Final Growth Forecast expected growth in Arcadia and surrounding jurisdictions. From 2016 to 2045, Arcadia is projected to experience a 16.84 percent in household growth. Among surrounding jurisdictions, El Monte is expected to experience the most population growth followed by Arcadia. The growth rates of Pasadena and Monrovia are lower at 5.94 percent and 10.87 percent respectively. Overall, Los Angeles County can expect a 24.10 percent increase in total households, from 3,319,000 in 2016 to 4,119,000 by 2045.

Table 2-12: Household Growth Forecast, 2016-2045

Jurisdiction	2016	2045	Percent Change from 2016 - 2045
El Monte	27,500	36,300	24.82%
Pasadena	56,300	65,100	5.94%
Arcadia	19,600	22,400	16.84%
Monrovia	14,000	16,700	10.87%
Los Angeles County	3,319,000	4,119,000	24.10%
Source: SCAG 2016-2040 Final Growth Forecast by Jurisdiction Report.			

C. Household Income

Household income is directly connected to affordability; as household income increases, it is more likely that the household can afford market rate housing units, larger units, and/or can pursue ownership opportunities. As household income decreases, households tend to pay a disproportionate amount of their income for housing. This may influence increased incidence of overcrowding and substandard living conditions.

The California State Department of Housing and Community Development (HCD) has identified the following income categories based on the Area Median Income (AMI) of Los Angeles County;

- Extremely Low income: households earning up to 30 percent of the AMI
- Very Low income: households earning between 31 and 50 percent of the AMI
- Low income: households earning between 51 percent and 80 percent of the AMI
- Moderate Income: households earning between 81 percent and 120 percent of the AMI
- Above Moderate Income: households earning over 120 percent of the AMI

Comprehensive Housing Affordability Strategy (CHAS) estimates based on 2013-2017 ACS data is used below. The extremely low, very low, and low income groups are combined and referred to as lower income



CITY OF ARCADIA 6TH CYCLE Housing Element Update

in the sites analysis as these categories qualify as needing affordable housing, however each category is analyzed individually here.² In 2017, approximately 63.58 percent of Arcadia households earned moderate to above moderate incomes (**Table 2-13**), while the remaining 36.42 percent had incomes in the extremely low, very low and low income categories. There were more homeowners in the City than renters, and homeowners typically fell within higher income brackets than lower income earners. Renter income distribution was fairly even throughout the lowest three categories, however there were a large number of renters in the Moderate and Above Moderate categories. Overall, most people living in Arcadia earned within the Moderate and Above Moderate bracket and were homeowners.

Table 2-13: Households by Income Category in Arcadia, 2017

Income Category (% of County AMI)	Households		Percent		Total Households
	Owner	Renter	Owner	Renter	
Extremely Low (30% AMI or less)	1,020	1,495	5.25%	7.69%	2,515
Very Low (31 to 50% AMI)	970	1,145	4.99%	5.89%	2,115
Low (51 to 80% AMI)	1,275	1,180	6.56%	6.07%	2,455
Moderate or Above (over 80% AMI)	8,450	3,910	43.47%	20.11%	12,360
Total	11,715	7,730	60.26%	39.76%	19,440
<i>Source: Department of Housing and Urban Development (HUD) Comprehensive Housing Affordability Strategy (CHAS), 2013-2017.</i>					


Household income is a good measure of a community's affordability levels. The median household income in Arcadia is approximately 37 percent higher than the median income in Los Angeles County (see **Figure 2-4** and **Table 2-14**). While Arcadia's income is significantly higher than the County's, it is comparable to the neighboring City of Pasadena's median income of \$83,068. Arcadia's median income is significantly higher than El Monte and Monrovia. Overall, Arcadia has a higher income than the surrounding jurisdictions analyzed and Los Angeles County.

² Federal housing and community development programs typically assist households with incomes up to 80 percent of the AMI and use different terminology. For example, the Federal Community Development Block Grant (CDBG) program refers households with incomes between 51 and 80 percent AMI as moderate income (compared to low income based on State definition).



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 2-4: Median Household Income by City (2013-2017)



Source: American Community Survey, 5-Year Estimates, 2019.

Table 2-14: Median Household Income

Jurisdiction	Median Income	Percent Above/Below Regional Median
Monrovia	\$77,111	13.33%
Pasadena	\$83,068	22.08%
Arcadia	\$93,574	37.52%
El Monte	\$49,003	-27.98%
Los Angeles County	\$68,044	0.00%


Source: American Community Survey, 5-Year Estimates, 2019.

Figure 2-5 shows that more than half the households in Arcadia (60 percent) had an income of \$75,000 or higher. Of the households which made more than \$75,000 per year, the majority had a household income above \$100,000 per year in 2019, with 16.7 percent households making \$200,000 or more and 11.3 percent of households making \$150,000 to 199,999. About thirteen percent of households made less than \$24,000, and about 15 percent made \$25,000 to \$49,999. Overall, the majority of Arcadia's households have moderate to high incomes.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 2-5: Arcadia Income Breakdown by Category



Source: American Community Survey, 5-Year Estimates, 2019.

3. Housing Problems

The Comprehensive Housing Affordability Strategy (CHAS) developed by the Census Bureau for the Department of Housing and Urban Development provides detailed information on housing needs by income level for different types of households in Los Angeles County including the City of Arcadia. The most recent available CHAS data for Los Angeles was published in August 2019 and was based on 2013-2017 ACS data. Housing problems considered by CHAS include:

- Units with physical defects (lacking complete kitchen or bathroom);
- Overcrowded conditions (housing units with more than one person per room);
- Housing cost burdens, including utilities, exceeding 30 percent of gross income; or
- Severe housing cost burdens, including utilities, exceeding 50 percent of gross income.

The types of problems in Arcadia vary according to household income, type, and tenure (**Table 2-15**). These include:

- In general, owner-households had a lower rate of reported housing problems with just 18.86 percent reporting a housing problem and 38.44 percent reporting no housing problem.
- Approximately 20 percent of renters reported a housing problem and 17.86 percent reported no problems.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

- Additionally, about 13 percent of renters reported a severe housing problem and just over 11 percent of owners reported a severe housing problem.
- Overall, renters were disproportionately affected by any housing problems in the City of Arcadia.

Table 2-15: Housing Assistance Needs of Lower Income Households

Housing Problem Overview*	Owner	% of total HH	Renter	% of total HH	Total	% of total HH
Household has at least 1 of 4 Housing Problems	3,770	18.86%	3,955	19.78%	7,725	38.64%
Household has none of 4 Housing Problems	7,684	38.44%	3,570	17.86%	11,255	56.30%
Cost Burden not available, no other problems	260	1.30%	205	1.03%	465	2.33%
Total	11,715	58.60%	7,730	38.67%	19,990	100.00%
Severe Housing Problem Overview**	Owner	% of total HH	Renter	% of total HH	Total	% of total HH
Household has at least 1 of 4 Severe Housing Problems	2,190	11.27%	2,475	12.73%	4,665	24.00%
Household has none of 4 Severe Housing Problems	9,265	47.66%	5,045	25.95%	14,310	73.61%
Cost Burden not available, no other problems	260	1.34%	205	1.05%	465	2.39%
Total	11,715	64.40%	7,730	35.60%	19,440	100.00%
Source: U.S. Department of Housing and Urban Development (HUD), Comprehensive Housing Affordability Strategy (CHAS) 2012-2016.						
Note: "% of total HH"= Percent of total Households in the City of Arcadia						
* The four housing problems are: incomplete kitchen facilities, incomplete plumbing facilities, more than 1 person per room, and cost burden greater than 30%.						
** The four severe housing problems are: incomplete kitchen facilities, incomplete plumbing facilities, more than 1.5 persons per room, and cost burden greater than 50%.						

A. Overcrowding

A combination of low incomes and high housing costs forces households to live in overcrowded conditions. "Overcrowding" is generally defined as a housing unit occupied by more than one person per room in a



CITY OF ARCADIA 6TH CYCLE Housing Element Update

house (including living room and dining rooms, but excluding hallways, kitchen, and bathrooms). An overcrowded household results from either a lack of affordable housing (which forces more than one household to live together) and/or a lack of available housing units of adequate size. Overcrowding can indicate that a community does not have an adequate supply of affordable housing, especially for large families.

Overcrowded and severely overcrowded households can lead to neighborhood deterioration due to the intensive use of individual housing units leading to excessive wear and tear, and the potential cumulative overburdening of community infrastructure and service capacity. Furthermore, overcrowding in neighborhoods can lead to an overall decline in social cohesion and environmental quality. Such decline can often spread geographically and impact the quality of life and the economic value of property and the vitality of commerce within a city. The combination of lower incomes and high housing costs result in many households living in overcrowded housing conditions.

Table 2-16: Overcrowding by Tenure in Arcadia

Tenure	Overcrowded Housing Units (1.0 to 1.50 persons/room)		Severely Overcrowded Housing Units (>1.51 persons/room)		Total Overcrowded Occupied Housing Units	
	Count	Percent of Total Overcrowded Housing Units	Count	Percent of Total Overcrowded Housing Units	Count	Percent of Total Overcrowded Housing Units
Owner Occupied	131	17.82%	69	9.39%	200	27.21%
Renter Occupied	419	57.01%	116	15.78%	535	72.79%
Total	550	74.83%	185	25.17%	735	100%

Source: American Community Survey, 5-Year Estimates, 2019.

Table 2-16, above, displays data for overcrowding in Arcadia by tenure (homeowner or renter) in 2019. The ACS reported a total of 735 overcrowded and severely overcrowded units in Arcadia in 2019. Out of all overcrowded units, 185, or 25.17 percent were severely overcrowded. Additionally, renters were more often disproportionately affected by overcrowding than homeowners as nearly 73 percent of all overcrowded and severely overcrowded units were occupied by renters. Although these numbers appear high, overcrowded units make up 3.8 percent of total households in Arcadia (735 households out of 19,520).

Table 2-17, below, compares overcrowding in Arcadia to nearby Jurisdictions and the County of Los Angeles. According to the data, Pasadena experienced the highest rate of overcrowding for renters and the lowest for homeowners. Additionally, Arcadia was the only City with lower overcrowding for renters and higher overcrowding for homeowners than the County's averages for owner occupied units and for renter occupied units. All other cities compared had a higher overcrowding rate for renters and a lower overcrowding rate for owner occupied units than the County. However, it should be noted that Arcadia has the one of the lowest amounts of overcrowded units overall, only second to Monrovia.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-17: Overcrowded Housing Units by Tenure				
Jurisdiction	Owner Occupied Overcrowded Units (>1.0 persons/room)		Renter Occupied Overcrowded Units (>1.0 persons/room)	
	Count	Percent of Total Overcrowded Units	Count	Percent of Total Overcrowded Units
Monrovia	134	19.56%	551	80.44%
Pasadena	472	15.61%	2,552	84.39%
Arcadia	200	27.21%	535	72.79%
El Monte	1,215	21.08%	4,550	78.92%
Los Angeles County	86,661	22.48%	298,761	77.52%
Source: American Community Survey, 5-Year Estimates, 2019.				

B. Overpayment (Cost Burden) In Relationship to Income

State and federal standards indicate that a household paying more than 30 percent of its income for housing is overpaying. Overpayment for housing can cause an imbalance on the remainder of a household's budget. Understanding and measuring overpayment for housing in a community is an indicator of the dynamics of demand and supply.

Per the Housing and Urban Development CHAS report, shown in **Table 2-18**, 11,075 households in Arcadia experienced some type of overpayment.³ **Table 2-18** describes the relationship between overpayment and a household's income. It is shown that families that have a lower household income (those below 50 of the HAMFI), are more likely to experience overpayment for housing, most likely because it takes a larger portion of their income. Approximately 56 percent of renter households that make less than 30 percent of the median income experience a cost burden of greater than 50 percent when paying for housing. The data in **Table 2-18** shows that cost burden is more intense for renters in the lower income categories, however when household income increases, home owners are more highly affected. The general pattern is that the amount of households that experience high cost burdens (over 50 percent) decreases as incomes increase.

³ 11,765 may double count households who reported a cost burden, for example a household may have a 50 percent cost burden and reported both a 30 percent and a 50 percent cost burden.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Lower cost burdens, those less than 30 percent of a household's income, generally dip down and then increase when the household income reaches 100 percent of the average.

Table 2-18: Summary of Housing Overpayment

Income by Cost Burden*	Owner				Renter				Total
	Cost Burden > 30%	% of Owner HH	Cost Burden > 50%	% of Owner HH	Cost Burden > 30%	% of Renter HH	Cost Burden > 50%	% of Renter HH	
Household Income is less-than or = 30%	725	20.28%	575	29.04%	1,120	31.46%	1,100	56.12%	3,520
Household Income >30% to less-than or = 50% HAMFI	605	16.92%	455	22.98%	1,095	30.76%	655	33.42%	2,810
Household Income >50% to less-than or = 80% HAMFI	605	16.92%	470	23.74%	775	21.77%	170	8.67%	2,020
Household Income >80% to less-than or = 100% HAMFI	220	6.15%	135	6.82%	175	4.92%	35	1.79%	565
Household Income >100% HAMFI	1,420	39.72%	345	17.42%	395	11.10%	0	0	2,160
Total	3,575	-	1,980	-	3,560	-	1,960	-	11,075

Source: Source: U.S. Department of Housing and Urban Development (HUD), Comprehensive Housing Affordability Strategy (CHAS) 2013-2017.

* Cost burden is the ratio of housing costs to household income. For renters, housing cost is gross rent (contract rent plus utilities). For owners, housing cost is "select monthly owner costs", which includes mortgage payment, utilities, association fees, insurance, and real estate taxes.

Note: HAMFI = HUD Area Median Family Income, this is the median family income calculated by HUD for each jurisdiction, to determine Fair Market Rents (FMRs) and income limits for HUD programs. HAMFI will not necessarily be the same as other calculations of median incomes (such as a simple Census number), due to a series of adjustments that are made.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

4. Special Needs Groups

Certain households may have more difficulty in finding adequate and affordable housing due to special circumstances, therefore, it is important to understand the demographics of persons with special needs to recognize how it influences the housing needs within a community. Special needs populations include seniors, persons with disabilities, female-headed households, large households, and farmworkers. In addition, many often have lower incomes because of their conditions. **Table 2-19** displays the data for persons with special needs in Arcadia and Los Angeles County in the case of farmworkers.

Table 2-19: Special Needs Groups	
Special Needs Groups	# of People or Households
Households with Seniors (65 years and over)*	7,202
Seniors Living Alone	1,694
Persons with Disabilities	10,062
Person with developmental disabilities	7,896
Large Households (5 or more persons per household)	2,179
Single-Parent Households	4,232
Single-Parent, Female Headed Households with Children (under 18 years)	3,246
People Living in Poverty	5,486
Farmworkers**	3,266
Migrant	22
Permanent	1,749
Seasonal	-
Homeless	106
Students	4,200
Source: American Community Survey, 5-Year Estimates, 2019 Los Angeles Point in Time Count, 2020.	
*This number represents the number of individual households that house seniors, not the number of individual seniors within these households.	
**Farmworkers in LA County	

A. Seniors

The senior population, generally defined as those 65 years of age and over, have several concerns that impact housing, including limited and fixed incomes, high health care costs, transit dependency, and living alone. Specific housing needs of the senior population include affordable housing, supportive housing (such as intermediate care facilities), group homes, and other housing that includes a planned service component. A limited income for many seniors often makes it difficult to find affordable housing. **Table 2-20** compares Arcadia's senior population to Los Angeles County and nearby cities. The data reports that in Arcadia 19.08 percent of the population is age 65 or over, or a total of 11,095 persons. Among the senior population, 1,694 live alone, and 7,202 households have persons 65 years and over living in them (see **Table 2-19**). In 2019, the ACS reported 13.25 percent of Los Angeles County's population to be age 65 or over, consistent with surrounding jurisdiction senior population. The highest senior population being Arcadia (19.08 percent), and the County having the lowest (13.25 percent).



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-20: Persons Age 65 and Over

Jurisdiction	Population Count	Percent
Monrovia	5,101	13.86%
Pasadena	22,536	15.95%
Arcadia	11,095	19.08%
El Monte	15,558	13.47%
Los Angeles County	1,335,978	13.25%

Source: American Community Survey, 5-Year Estimates, 2019.

In addition to overpayment problems experienced by seniors, due to relatively fixed incomes, many seniors experience various disabilities and self-care limitations. Approximately 5,626 seniors in Arcadia identified one or more disabilities in 2019, according to the ACS. Among these disabilities, the most common were ambulatory disabilities and independent living difficulty.

B. Persons with Physical and Developmental Disabilities

Physical and developmental disabilities can hinder access to traditionally designed housing units as well as potentially limit the ability to earn adequate income. Physical, mental, and/or developmental disabilities may deprive a person from earning income, restrict mobility, or make self-care difficult. Thus, persons with disabilities often have special housing needs related to limited earning capacity, a lack of accessible and affordable housing, and higher health costs associated with a disability. Additionally, some residents suffer from disabilities that require living in a supportive or institutional setting.

Although no current comparisons of disability with income, household size, or race/ethnicity are available, it is reasonable to assume that a portion of persons with disabilities would have annual incomes within Federal and State income limits, especially those households not in the labor force. Furthermore, many lower income persons with disabilities are likely to require housing assistance and services. Housing needs for disabled persons are compounded by design issues and location factors, which can often be costly. For example, special needs of households with wheelchair-bound or semi-ambulatory individuals may require ramps, holding bars, special bathroom designs, wider doorways, lower cabinets, elevators, and other interior and exterior design features.

Housing opportunities for persons with disabilities can be addressed through the provision of affordable, barrier-free housing. Rehabilitation assistance can be targeted toward renters and homeowners with disabilities for unit modification to improve accessibility. The American Community Survey (ACS) identifies six disability types: hearing disability, vision disability, cognitive disability, ambulatory disability, self-care disability and independent living disability. The Census and the ACS provide clarifying questions to determine persons with disabilities and differentiate disabilities within the population. The ACS defines a disability as a report of one of the six disabilities identified by the following questions:

- **Hearing Disability:** Is this person deaf or does he/she have serious difficulty hearing?
- **Visual Disability:** Is this person blind or do they have serious difficulty seeing even when wearing glasses?
- **Cognitive Difficulty:** Because of a physical, mental, or emotional condition, does this person have serious difficulty concentrating, remembering, or making decisions?



CITY OF ARCADIA 6TH CYCLE Housing Element Update

- Ambulatory Difficulty: Does this person have serious difficulty walking or climbing stairs?
- Self-Care Difficulty: Does this person have difficulty dressing or bathing?
- Independent Living Difficulty: Because of a physical, mental, or emotional condition, does this person have difficulty doing errands alone such as visiting a doctor's office or shopping?

According to the 2019 ACS, about 17 percent of Arcadia's populations reported one or more disabilities as shown in **Table 2-21**. Of that 17 percent, persons with ambulatory difficulty comprised the highest percent (26.43 percent), persons with an independent Living Difficulty were the second largest group (21.53 percent), and the population with a Self-care Difficulty comprised about 15.51 percent of people with disabilities. Overall, persons over the age of 65 were more likely to have a reported disability. For the population under the age of 18, the most common reported disability was cognitive disabilities. Similarly, for those between the ages of 18 and 65, the most common reported disabilities were cognitive difficulty, ambulatory difficulty, and independent living difficulty.

Table 2-21: Disability Status

Disability Type	Under 18 with a Disability	18 to 64 with a Disability	65 years and Over with a Disability	Total	Percent of Population with Disability	Percent of Total Population
Population with a Hearing Difficulty	19	273	1,152	1,444	14.35%	2.49%
Population with a Vision Difficulty	34	280	388	702	6.98%	1.21%
Population with a Cognitive Difficulty	213	689	628	1,530	15.21%	2.64%
Population with an Ambulatory Difficulty	84	628	1,947	2,659	26.43%	4.59%
Population with a Self-care Difficulty	140	376	1,045	1,561	15.51%	2.69%
Population with an independent Living Difficulty	--	633	1,533	2,166	21.53%	3.74%
Total	490	2,879	6,693	10,062	100.00%	17.37%

Source: American Community Survey, 5-Year Estimates, 2019.

*This number may double count as some persons report having one or more disabilities, therefore this total number differs from the total number of persons with a disability in Table 2-18.

State law requires that the Housing Element discuss the housing needs of persons with developmental disabilities. As defined by federal law, "developmental disability" means a severe, chronic disability of an individual that:

- Is attributable to a mental or physical impairment or combination of mental and physical impairments;
- Is manifested before the individual attains age 22;



CITY OF ARCADIA 6TH CYCLE Housing Element Update

- Is likely to continue indefinitely;
- Results in substantial functional limitations in three or more of the following areas of major life activity: a) self-care; b) receptive and expressive language; c) learning; d) mobility; e) self-direction; f) capacity for independent living; or g) economic self-sufficiency; and
- Reflects the individual's need for a combination and sequence of special, interdisciplinary, or generic services, individualized supports, or other forms of assistance that are of lifelong or extended duration and are individually planned and coordinated.

Per Section 4512 of the Welfare and Institutions Code, a "developmental disability" means a disability that originates before an individual attains the age of 18, continues, or can be expected to continue, indefinitely, and constitutes a substantial disability for that individual. A developmental disability includes intellectual disability, cerebral palsy, epilepsy, and autism. This term also includes disabling conditions found to be closely related to intellectual disability or to require treatment like that required for individuals with intellectual disability. This term does not include other handicapping conditions that are solely physical in nature.

According to the San Gabriel/Pomona Regional Center– Disparity Data Report for 2017-2018, a total of 14,809 individuals from the San Gabriel Valley diagnosed with developmental disabilities received services. Of those who received services, 17.5 percent were White, 12.2 percent were Asian, 5.3 percent were Black/African American, and 8.4 percent reported Other. Approximately 56.4 percent of individuals reported their ethnicity as Hispanic or Latino.⁴

Many people with developmental disabilities can live and work independently within a conventional housing environment. Individuals with more severe developmental disabilities require a group living environment where supervision is provided. The most severely affected individuals may require an institutional environment where medical attention and physical therapy are provided. Because developmental disabilities exist before adulthood, the first issue in supportive housing for persons with developmental disabilities is the transition from the person's living situation as a child to an appropriate level of independence as an adult.

There are several housing types appropriate for people living with a development disability: rent subsidized homes, licensed and unlicensed single-family homes, inclusionary housing, Section 8 vouchers, special programs for home purchase, HUD housing, and SB 962 (veterans) homes. The design of housing-accessibility modifications, the proximity to services and transit, and the availability of group living opportunities represent some of the types of considerations that are important in serving the needs of this group. Incorporating 'barrier-free' design in all, new multi-family housing (as required by California and Federal Fair Housing laws) is especially important to provide the widest range of choices for residents with disabilities. Special consideration should also be given to the affordability of housing, as people with disabilities may be living on a fixed income.

C. Large Households

Large Households are defined as households consisting of five or more persons. Such households comprise a special needs groups because many communities have a limited supply of adequately sized and affordable housing units. To save for other necessities such as food, clothing and medical care, it is

⁴ <https://www.sgprc.org/home/showpublisheddocument?id=3571>



CITY OF ARCADIA 6TH CYCLE Housing Element Update

common for lower income large households to reside in smaller units with an inadequate number of bedrooms, which frequently results in overcrowding and can contribute to fast rates of deterioration.

Securing housing large enough to accommodate all members of a household is more challenging for renters, because multi-family rental units are typically smaller than single-family ownership units. While apartment complexes offering two and three bedrooms are common, apartments with four or more bedrooms are rare. It is more likely that a large family will experience overcrowding in comparison to smaller families. Additionally, throughout the region, larger single-family homes, whether to rent or own, are generally not affordable to most lower income households.

According to the ACS 2019 estimates, Arcadia had 2,179 large households. Of those large households, the largest group were five person households (7.3 percent of all large households). **Table 2-22** also shows that, while there is a fairly even split of owner and renter large households, however homeowners were slightly more likely to have a household of five or more.

Table 2-22: Large Households (by Tenure)

Household Size	Owner		Renter		Total	
	Count	Percent	Count	Percent	Count	Percent
5-Person Household	839	7.2%	590	7.5%	1,429	7.3%
6-person household	332	2.9%	76	0.7%	408	2.1%
7-or-more person Households	212	1.8%	130	1.1%	342	1.8%
Total	1383	11.9%	796	6.9%	2,179	11.2%

Source: American Community Survey, 5-Year Estimates, 2019.

D. Single-Parent Households

Single-parent households often require special consideration and assistance due to their greater need for affordable and accessible day care, health care, and other supportive services. Many female-headed households with children are susceptible to having lower incomes than similar two-parent households. Single mothers often face social marginalization pressures that often limit their occupational choices and income earning potential, housing options and access to supportive services.

According to the 2019 ACS, the majority of single parent households in Arcadia are female headed (76.7 percent) as shown in **Table 2-23** below. Los Angeles County estimated about 68.3 percent of single parent homes headed by females. Overall, there were 649 female-headed, single parent households living below the poverty level in Arcadia, about 20 percent of female-headed, single parent households. The County of Los Angeles has a higher percent of female-headed single parent households living below the poverty line at 22.6 percent (110,463 households).

Table 2-23: Single Parent Households

Jurisdiction	Single Parent-Male, No Spouse Present	Single Parent-Female, No Spouse Present	Single Parent Female-Lead Households Living in Poverty



CITY OF ARCADIA 6TH CYCLE Housing Element Update

	Count	% of Single Parent HH	Count	% of Single Parent HH	Count	% of Single Parent-Female HH
Arcadia	986	23.3%	3,246	76.7%	649	20%
Los Angeles County	226,505	61.67%	488,776	68.3%	110,463	22.6%
<i>Source: American Community Survey, 5-Year Estimates, 2019.</i>						

E. Farmworkers and Racetrack Workers

Farmworkers are traditionally defined as persons whose primary incomes are earned through permanent or seasonal agricultural labor. Permanent farm laborers work in the fields, processing plants, or support activities on a generally year-round basis. When workload increases during harvest periods, the labor force is supplemented by seasonal workers, often supplied by a labor contractor. For some crops, farms may hire migrant workers, defined as those whose travel prevents them from returning to their primary residence every evening. Farm workers have special housing needs because they earn lower incomes than many other workers and move throughout the year from one harvest location to the next.

The United States Department of Agriculture, National Agriculture Statistics provides data on hired farm labor across the United States. The data is compiled at both a state and county level. Within the County of Los Angeles, there were a total of 3,266 hired farm workers in 2017. A total of 1,749 are considered permanent, working 150 days or more and a total of 1,517 farmworkers were considered seasonal, working only 150 days or less. Additionally, the County of Los Angeles reported 395 total migrant farmworkers, 365 of which worked on farms with full time hired labor and 30 worked on farms with only contract labor.

While there are farmworkers in the County of Los Angeles, the City of Arcadia does not have any agricultural land nor does the City house a population of farmworkers. The Santa Anita Racetrack in the City of Arcadia brings seasonal racetrack workers in to live and work on the site. The racetrack provides housing for those who work with horses, backstretch workers, and more. This is a special population that is unique to Arcadia and perhaps several additional cities in the State. The City has identified this group as a special needs population that faces challenges with regards to housing and living conditions

F. Students

The college student population can be another factor in housing demand in the City. According to the 2019 5- year estimate there were a total of 3,216 enrolled undergraduate college students that reside in Arcadia and 984 enrolled graduate professional students. Combining the undergraduate and graduate enrolled population equates to 7.2 percent of the population of the City.

Arcadia is located near the Point Loma Nazarene University Arcadia Campus, Kingston College and California Institute of Technology. The 2019 ACS reported that an estimated 4,200 persons in Arcadia were enrolled in college or graduate school, about 7.2 percent of the population. While many of the City's college students most likely reside with their parents, some students reside in Arcadia in their own independent housing. The City of Arcadia recognizes that affordability of housing may provide a burden on students in the City.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

G. Extremely Low income Households and Poverty Status

The 2013-2017 CHAS data indicates there were approximately 2,115 very low income households living in the City of Arcadia. Very low income households are those households that earn 50 percent or less of the median family income (MFI) for Los Angeles County. Extremely low income households are those households, which earn less than 30 percent of the MFI. There are approximately 2,515 extremely low income households in Arcadia (renters and owners). **Table 2-24** below, includes data characterizing affordability and cost burden for various income groups. The four housing problems as identified by the 2013-2017 CHAS report are:

- Incomplete kitchen facilities
- Incomplete plumbing facilities
- More than 1 person per room, and
- Cost burden greater than 30%.

The four severe housing problems, as identified by the 2013-2017 CHAS report are:

- Incomplete kitchen facilities
- Incomplete plumbing facilities
- More than 1.5 persons per room, and
- Cost burden greater than 50%.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-24: Housing Problems for All Households (by Income Category)

Income Category	Owner					
	Household has at least 1 of 4 Housing Problems	% of Owner HH	Household has none of 4 Housing Problems	% of Owner HH	Cost Burden not available, no other Housing Problem	% of Owner HH
Household Income is less-than or = 30%	720	3.70%	40	0.21%	260	1.34%
Household Income >30% to less-than or = 50% HAMFI	605	3.11%	365	1.88%	0	0.00%
Household Income >50% to less-than or = 80% HAMFI	615	3.16%	660	3.39%	0	0.00%
Household Income >80% to less-than or = 100% HAMFI	215	1.11%	495	2.55%	0	0.00%
Household Income >100% HAMFI	1,610	8.28%	6,130	31.52%	0	0.00%
Total	3,770	19.39%	7,685	39.52%	260	1.34%
Income Category	Renter					
	Household has at least 1 of 4 Housing Problems	% of Renter HH	Household has none of 4 Housing Problems	% of Renter HH	Cost Burden not available, no other Housing Problem	% of Renter HH
Household Income is less-than or = 30%	1,145	5.89%	145	0.75%	205	1.05%
Household Income >30% to less-than or = 50% HAMFI	1,095	5.63%	50	0.26%	0	0.00%
Household Income >50% to less-than or = 80% HAMFI	845	4.35%	335	1.72%	0	0.00%
Household Income >80% to less-than or = 100% HAMFI	285	1.47%	505	2.60%	0	0.00%
Household Income >100% HAMFI	580	2.98%	2,530	13.01%	0	0.00%
Total	3,955	20.34%	3,570	18.36%	205	1.05%
Total Households (Owner and Renter)	7,725	39.73%	11,255	57.88%	465	2.39%
Source: U.S. Department of Housing and Urban Development (HUD), Comprehensive Housing Affordability Strategy (CHAS) 2013-2017.						



CITY OF ARCADIA 6TH CYCLE Housing Element Update

According to HCD extremely low income households are defined as households that earn 0 to 30 percent of the local annual median income (AMI). In Arcadia, the threshold is based on the Los Angeles-Long Beach-Glendale, CA HUD Metropolitan's AMI. For a family or household of four people, the maximum amount of annual income in the Los Angeles-Long Beach-Glendale, CA HUD Metropolitan Area is \$35,450 to be considered extremely low income.⁵

Table 2-25 below shows local, regional and statewide data regarding extremely low income households and their tenure. Arcadia has the lowest proportion of extremely low income households compared to the other jurisdictions. Los Angeles County has a higher proportion of extremely low income households in comparison to the State and City. It is more likely that an extremely low income household would own rather than rent housing in Arcadia than in the other jurisdictions. Although there is a higher rate of home ownership, there is a need for stable, affordable housing in the City.

Table 2-25: Extremely Low Income Households¹ by Tenure						
	# of Extremely Low Income Owners	% of Total Extremely Low Income HH	# of Extremely Low Income Renters	% of Total Extremely Low Income HH	Total Extremely Low Income HH	% of Extremely Low Income HH in the Jurisdiction
Arcadia	1,020	41%	1,495	59%	2,515	13%
Los Angeles County	136,760	21%	504,295	79%	641,055	19%
California	536,865	27%	1,424,685	73%	1,961,550	15%

Source: CHAS HUD. 2013-2017 data. Available at <https://www.huduser.gov/portal/datasets/cp.html>.
 1- ELI is defined as households that earn less up to 30 percent of AMI.

Table 2-26 shows cost burden for extremely low income households. The data shows 100 percent of ELI households experience some type of cost burden. Extremely low income families make up the largest group of people to experience a cost burden of greater than 50 percent. Extremely low income households also account for approximately 37 percent of households that experience cost burdens of greater than 30 percent.

Table 2-26: Extremely Low Income Household Overpayment						
	Cost Burden of >30 percent	Percent of Extremely Low Income Households > 30 percent cost burden	Cost burden of > 50 percent	Percent of Extremely Low Income > 50 percent cost burden	Total Extremely Low Income HH Experiencing Cost Burden	Percent of Extremely Low Income Experiencing Cost Burden

⁵ HUD. 2021 Adjusted Home Income Limits. Available at https://www.huduser.gov/portal/datasets/home-datasets/files/HOME_IncomeLmts_State_CA_2021.pdf. Accessed on December 7, 2021.




CITY OF ARCADIA 6TH CYCLE Housing Element Update

Extremely Low Income Owners	725	39%	575	34%	2,515	100%
Extremely Low Income Renters	1,120	61%	1100	66%		
Total	1,845	100%	1,675	100%	-	-

Source: CHAS HUD. 2013-2017 data. Available at <https://www.huduser.gov/portal/datasets/cp.html>.

Figure 2-6: Percent below Poverty Level, by Race and Hispanic or Latino Origin



Source: American Community Survey, 5-Year Estimates, 2019.

According to the 2019 ACS, 5,677 persons were reported to be living in poverty in Arcadia, which is about 9.8 percent of the population for whom poverty status could be determined (57,775 people in the City).

Figure 2-6 displays the percent of persons living in poverty by race or ethnicity and Hispanic or Latino origin, based on own race/ethnicity. The lowest percentage of persons identified as living in poverty was the American Indian and Alaska Native population at zero percent of all persons who reported American Indian and Alaska Native. Native Hawaiian and Other Pacific Islander was the highest percent of persons living in poverty at 26 percent of the population. Additionally, those who reported Hispanic or Latino origin and some other race were disproportionately affected by poverty at 17 and 16 percent. The White, Asian, and those who reported Two or More Races had some of the lowest levels of poverty at 9 percent, 10 percent and 9 percent respectively.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Projected Needs for ELI Households

To calculate projected needs, the City assumed 50 percent of its very low income regional housing needs are extremely low income households. The City was allocated 1,102 very low income units, and as a result, approximately 551 units are projected for extremely low income households. As shown above, the majority of extremely low income households face a variety of housing problems such as high cost burden and low ownership rates. Additionally, some extremely low income households could face other issues such as having special needs or disabilities that could exacerbate housing problems. In order to provide ample housing for extremely low income households, the City allows for a variety of housing types, such as single-room occupancy (SRO) and supportive housing.

H. Homeless

Homelessness has become an increasingly important issue. Factors contributing to the rise in incidents of homelessness include unemployment and underemployment, a lack of affordable housing (especially for extremely low income households), reductions in funding allocations directed to the poor, and the de-institutionalization of persons who are defined mentally ill.

State law mandates that municipalities address the special needs of homeless persons within their jurisdictional boundaries. “Homelessness” as defined by the U.S. Department of Housing and Urban Development (HUD) has recently been updated. The following list includes the updated descriptions for what constitutes “homelessness” and explains how the definition from HUD changed:

- People who are living in a place not meant for human habitation, in emergency shelter, in transitional housing, or are exiting an institution where they temporarily resided. The only significant change from existing practice is that people will be considered homeless if they are exiting an institution where they resided for up to 90 days (it was previously 30 days), and were in shelter or a place not meant for human habitation immediately prior to entering that institution.
- People who are losing their primary nighttime residence, which may include a motel or hotel or a doubled-up situation, within 14 days and lack resources or support networks to remain in housing. HUD had previously allowed people who were being displaced within 7 days to be considered homeless. The proposed regulation also describes specific documentation requirements for this category.
- Families with children or unaccompanied youth who are unstably housed and likely to continue in that state. This is a new category of homelessness that applies to families with children or unaccompanied youth who have not had a lease or ownership interest in a housing unit in the last 60 or more days, have had two or more moves in the last 60 days, and who are likely to continue to be unstably housed because of disability or multiple barriers to employment.
- People who are fleeing or attempting to flee domestic violence, have no other residence, and lack the resources or support networks to obtain other permanent housing. This category is similar to the current practice regarding people who are fleeing domestic violence.

The HUD definition does not include the following: persons living in substandard housing (unless it has been officially condemned); persons living in overcrowded housing (for example, doubled up with others); persons being discharged from mental health facilities (unless the person was homeless when entering and is considered to be homeless at discharge); or persons who may be at risk of homelessness (for example, living temporarily with family or friends.)

Table 2-27 below displays data from the Los Angeles County Point in Time Count. The Count gathers data on the homeless population in the County as well as in all jurisdictions within the County. According to the data from 2017 to 2018 Arcadia experienced a slight drop in the homeless population, then a significant increase through 2020. Overall, Arcadia’s homeless population was higher than nearby jurisdictions such



CITY OF ARCADIA 6TH CYCLE Housing Element Update

as Monrovia and Pasadena (77 and 27 persons respectively). However, Arcadia did have a lower amount than El Monte. Overall, Arcadia has a moderate number of homeless individuals when compared to neighboring jurisdictions.

Table 2-27: Homelessness in Arcadia and Surrounding Cities

Jurisdiction	2017	2018	Count Change	2019	2020	Count Change
Monrovia	42	69	27	80	77	-3
Pasadena	575	677	102	542	527	15
Arcadia	17	15	-2	77	106	29
El Monte	240	517	277	428	433	5
Los Angeles County	45,979	45,039	-940	49,521	54,291	4,770

Source: Los Angeles Point in Time Count, 2017, 2018, 2019, 2020.
Source for Homelessness in Pasadena: Pasadena Partnership. Pasadena Homelessness Count 2020. Available at https://pasadenapartnership.org/wp-content/uploads/2020/06/Pasadena-Homeless-Count_2020-FINAL.pdf. Accessed on December 20, 2021.

The data in **Table 2-28** displays data for the homeless population in Arcadia and surrounding cities as compared to the County of Los Angeles. Of the total homeless population in the County (54,291) the 106 in Arcadia make up about 0.2 percent. Similarly, Monrovia, El Monte, and Pasadena made up less than one percent of the County's homeless population. Therefore, it can be determined that homelessness is not high in the area.

Table 2-28: Homelessness in Arcadia and Surrounding Cities

Jurisdiction	2020	% of County
Monrovia	77	0.14%
Pasadena*	27	0.02%
Arcadia	106	0.20%
El Monte	433	0.80%
Los Angeles County	54,291	100%

Source: Los Angeles County Point in Time Count, accessed on March 2021
*Data is for East and South Pasadena Combined

5. Housing Stock Characteristics

The characteristics of the housing stock, including growth, type, availability and tenure, age and condition, housing costs, and affordability are important in determining the housing needs for the community. This



CITY OF ARCADIA 6TH CYCLE Housing Element Update

section details the housing stock characteristics of Arcadia to identify how well the current housing stock meets the needs of its current and future residents.

A. Housing Growth

As a built-out community, Arcadia experienced modest housing stock growth from 2010 to 2019. **Table 2-29** below displays American Community Survey data from 2010 to 2019 showing housing unit growth over the nine-year period.

In 2010, the City had an estimated 19,488 housing units, which steadily increased over nine years to an estimated 21,386, an overall percent growth of 1.04 percent. Nearby jurisdictions experienced moderately the same increases in housing unit growth. For example, from 2010 to 2015 Arcadia experienced the highest growth in housing units (8.61 percent) when compared to neighboring jurisdictions (which saw anywhere from -3.45 percent growth to 2.86 percent growth in units). From 2015 to 2019, only Monrovia (-1.33 percent) and El Monte (-5.47 percent) saw less housing unit growth than Arcadia (1.04 percent).

Table 2-29: Housing Unit Growth (Growth Trends)					
Jurisdiction	2010	2015	2019	Percent Change 2010 to 2015	Percent Change 2015 to 2019
Monrovia	14,444	13,946	13,761	-3.45%	-1.33%
Pasadena	57,188	58,823	61,572	2.86%	4.67%
Arcadia	19,488	21,165	21,386	8.61%	1.04%
El Monte	28,810	33,029	31,223	14.64%	-5.47%
Los Angeles County	3,425,736	3,476,718	3,542,800	1.49%	1.90%
Source: American Community Survey, 5-Year Estimates, 2010, 2015, and 2019.					

B. Housing Type

Arcadia's housing stock primarily consists of single-family housing units, which comprise nearly 60.27 percent of all housing units. The majority of the single-family housing available in Arcadia is detached housing, compared to 8.75 percent attached (which includes townhomes and condos). The housing stock may gradually become more diverse as housing needs in the City change throughout the years. Currently about 31 percent of all housing is multi-family, and under one percent are mobile homes. Overall, the City of Arcadia's housing stock makeup is similar to the County of Los Angeles, where about 54.91 percent of all housing is single-family, about 43.5 percent is multi-family and about 1.61 percent are mobile homes.

Table 2-30: Total Housing Units by Type								
Jurisdiction	Single- Family Detached		Single-Family Attached		Multi-Family		Mobile Homes	
	Count	Percent	Count	Percent	Count	Percent	Count	Percent
Arcadia	12,890	60.27%	1,871	8.75%	6,615	31.0%	10	0.05%



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Los Angeles County	1,722,121	48.61%	223,134	6.30	1,537,818	43.5%	57,197	1.61%
Source: American Community Survey, 5-Year Estimates, 2019.								

C. Housing Availability and Tenure

Housing tenure and vacancy rates generally influence the supply and cost of housing. Housing tenure defines if a unit is owner-occupied or renter-occupied. The tenure characteristics in a community can indicate several aspects of the housing market, such as affordability, household stability, and availability of unit types, among others. In many communities, tenure distribution generally correlates with household income, composition and age of the householder.

In 2019, the majority of single-family housing was owner-occupied, shown below in **Table 2-31**. When broken down by housing type, the data shows that majority of renters live in multi-family housing. The lack of renters in single family homes, both attached and detached, may be a correlation to housing affordability or size of households. It is common for renters to live in multi-family units, as renters often include nonfamily households such as roommates.

Table 2-31: Occupied Housing Units by Type and Tenure (in Percent)

Tenure	Single- Family Detached		Single-Family Attached		Multi-Family		Mobile Homes		Total Housing Units
Owner Occupied	9,453 units	81.4%	1,145 units	9.9%	1,001 units	8.6%	10 units	0.1%	11,609 units
Renter Occupied	2,356 units	29.8%	595 units	7.5%	4,960 units	62.8%	0 units	0.0%	7,911 units
Source: American Community Survey, 5-Year Estimates, 2019.									

As shown in **Table 2-32**, owners had a slightly larger average household size than renters in Arcadia, 3.01 to 2.85 respectively. Neighboring jurisdictions showed unsimilar trends with Monrovia, Pasadena, El Monte and Los Angeles County estimating larger average renter households than owner households. All municipalities listed except for Pasadena had a larger average owner household size than renter household size.

Table 2-32: Average Household Size by Tenure

Jurisdiction	Owner Occupied Households (% of Total Households)	Average Owner Household Size	Renter Occupied Households (% of Total Households)	Average Renter Household Size
Monrovia	46.8%	2.56	53.2%	2.44
Pasadena	42.0%	2.77	58.0%	2.89



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Arcadia	59.5%	3.01	40.5%	2.85
El Monte	40.0%	3.89	60.0%	3.77
Los Angeles County	45.8%	3.17	54.2%	2.83
Source: American Community Survey, 5-Year Estimates, 2019				


D. Vacancy Rates

Vacancy rates are an important housing indicator because they indicate the degree of housing choice available in a community. High vacancy rates usually indicate low demand and/or high supply conditions in the housing market. Too high of a vacancy rate can be difficult for owners trying to sell or rent. Low vacancy rates usually indicate high demand and/or low supply conditions in the housing market. Too low of a vacancy rate can force prices up, making it more difficult for lower and moderate income households to find housing. Vacancy rates of between two to three percent are usually considered healthy for ownership housing, and rates of five to six percent are usually considered healthy for rental housing. However, vacancy rates are not the sole indicator of market conditions. They must be viewed in the context of all the characteristics of the local and regional market. **Figure 2-7** shows the overall homeowner vacancy rate and renter vacancy rate in Arcadia, the County and nearby jurisdictions. According to the ACS data, in 2019, Monrovia had the highest rental vacancy rate at five percent. The City of Arcadia had a four percent rental vacancy rate, lower than Monrovia, and higher than Pasadena, El Monte and Los Angeles County. While the rental vacancy rate averages are considered healthy, the homeowner vacancy rates were all low, with Pasadena's being the highest at two percent.

Figure 2-7: Homeowner and Renter Vacancy Rates, 2019



CITY OF ARCADIA 6TH CYCLE Housing Element Update



Source: American Community Survey, 5-Year Estimates, 2019.

Table 2-33 below displays the breakdown of type of vacant units in Arcadia. For rent units have the highest count of vacancy at 335 units, meaning that many of the vacant homes in Arcadia are on the market, and listed for residents looking to rent. There were 100 rented but unoccupied units in 2019 and 100 sold but unoccupied units. In addition, there were zero units vacant for migrant workers and 182 units available for sale. Additionally, there were only 277 units vacant for seasonal, recreational, or occasional use.

Table 2-33: Vacant Housing Units by Type, 2019

Type of Housing	Estimate
For rent	335
Rented, not occupied	100
For sale only	182
Sold, not occupied	100
For seasonal, recreational or occasional use	277
For migrant workers	0
Other vacant	872
Total	1,866

Source: American Community Survey, 5-Year Estimates, 2019.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

E. Housing Age and Condition


Housing age can be an important indicator of housing condition within a community. For example, housing that is over 30 years old is typically in need of some major rehabilitation, such as a new roof, foundation, plumbing, etc. Many federal and state programs also use the age of housing as one factor in determining housing rehabilitation needs.

Figure 2-8 displays housing stock age data in the City of Arcadia. According to the 2019 ACS, Arcadia had a large growth in housing development from 1950 to 1959. The majority of Arcadia's housing was built between the years 1939 and 1969, about 60.01 percent. Overall, Arcadia's housing stock is primarily older, meaning that the cost of updates and maintenance could be high for residents. However, the figure does show a slowing in housing production from 2000 on.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 2-8: Housing Stock Age in Arcadia, 2019



Source: American Community Survey, 5-Year Estimates, 2019.

F. Housing Costs and Affordability

Housing costs reflect the supply and demand of housing in a community. This section summarizes the cost and affordability of the housing stock to Arcadia's residents. **Table 2-34** displays data for the median home value in Arcadia, the County of Los Angeles, and surrounding jurisdictions. In 2019, the ACS estimated that the median value of a home in Los Angeles County was \$538,200. In Arcadia, the same year, the median value of a home was \$1,097,600. Overall, each of Arcadia's neighboring jurisdictions had a median home value higher than the County's with the exception of El Monte.

Table 2-34: Median Home Value by Community, 2019

Jurisdiction	Median Home Value
Monrovia	\$663,400
Pasadena	\$785,700
Arcadia	\$1,097,600
El Monte	\$454,900
Los Angeles County	\$583,200

Source: American Community Survey, 5-Year Estimates, 2019.

Table 2-35 shows that rent for a two bedroom unit in Arcadia experienced a two percent increase from \$2,161 to \$2,202 from 2018 to 2021. Three bedroom rentals saw the highest percent change from 2018 to



CITY OF ARCADIA 6TH CYCLE Housing Element Update

2021 (9 percent), increasing from \$3,137 to \$3,440 while 4 bedroom rentals experienced a one percent decrease in cost (\$4,090 to \$4,060).

Table 2-35: Average Monthly Rental Rates

Unit Type	January 2018 Average Monthly Rent	January 2019 Average Monthly Rent	January 2020 Average Monthly Rent	January 2021 Average Monthly Rent	Percent Change from 2018 to 2021
1 Bedroom	\$2,622	\$1,521	\$1,742	\$1,666	-57%
2 bedrooms	\$2,161	\$2,237	\$2,280	\$2,202	2%
3 Bedrooms	\$3,137	\$3,072	\$3,187	\$3,440	9%
4+ Bedrooms	\$4,090	\$4,100	\$3,913	\$4,060	-1%
Source: Zumper, Arcadia Rentals Zumper Rent Index, accessed March 2021.					
*Percent Change from 2019 to 2019, 2020 rental data not available.					

Housing affordability can be inferred by comparing the cost of renting or owning a home in the City with the maximum affordable housing costs for households at different income levels. Taken together, this information can generally show who can afford what size and type of housing and indicate the type of households most likely to experience overcrowding and overpayment.

The Federal Department of Housing and Urban Development (HUD) conducts annual household income surveys nationwide to determine a household's eligibility for federal housing assistance. Based on this survey, the California Department of Housing and Community Development (HCD) developed income limits, based on the Area Median Income (AMI), which can be used to determine the maximum price that could be affordable to households in the upper range of their respective income category. Households in the lower end of each category can afford less by comparison than those at the upper end. The maximum affordable home and rental prices for residents in Los Angeles County are shown in **Table 2-36**.

The data shows the maximum amount that a household can pay for housing each month without incurring a cost burden (overpayment). This amount can be compared to current housing asking prices (**Table 2-36**) and market rental rates (**Table 2-37**) to determine what types of housing opportunities a household can afford.

Extremely Low income Households

Extremely low income households earn less than 30 percent of the County AMI – up to \$24,850 for a one-person household and up to \$38,300 for a five-person household in 2021. Extremely low income households cannot afford market-rate rental or ownership housing in Arcadia without assuming a substantial cost burden.

Very Low income Households

Very low income households earn between 31 percent and 50 percent of the County AMI – up to \$41,400 for a one-person household and up to \$63,850 for a five-person household in 2021. A very low income household can generally afford homes priced between \$158,600 and \$225,700, adjusting for household size. A very low income household at the maximum income limit can afford to pay approximately \$878 to \$1,268 in monthly rent, depending on household size. Given the cost of housing in Arcadia, persons or households of very low income could not afford to rent or purchase a home in the City.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Low income Households

Low income households earn between 51 percent and 80 percent of the County's AMI - up to \$66,250 for a one-person household and up to \$ 102,200 for a five-person household in 2021. The affordable home price for a low income household at the maximum income limit ranges from \$274,300 to \$404,300. Ownership housing would not be affordable to low income households. A one-person low income household could afford to pay up to \$1,499 in rent per month and a five-person low income household could afford to pay as much as \$2,227. Low income households in Arcadia would not be able to find adequately sized affordable apartment units.

Moderate income Households

Persons and households of moderate income earn between 81 percent and 120 percent of the County's AMI – up to \$ 103,700 for a five-person household in 2021. The maximum affordable home price for a moderate income household is \$278,800 for a one-person household and \$411,400.00 for a five-person family. Moderate income households in Arcadia would not be able to purchase a home in the City. The maximum affordable rent payment for moderate income households is between \$1,523 and \$2,265 per month. Appropriately sized market-rate rental housing is generally affordable to households in this income group.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-36: Affordable Monthly Housing Cost for Renters

Annual Income		Rent	Utilities ¹	Total Affordable Monthly Housing Cost
Extremely Low income (30% of AMI)				
1-Person	\$24,850	\$464	\$157	\$621
2-Person	\$28,400	\$518	\$192	\$710
3-Person	\$31,950	\$564	\$235	\$799
4-Person	\$35,450	\$601	\$285	\$886
5-Person	\$38,300	\$630	\$328	\$958
Very Low income (50% of AMI)				
1-Person	\$41,400	\$878	\$157	\$1,035
2-Person	\$47,300	\$991	\$192	\$1,183
3-Person	\$53,200	\$1,095	\$235	\$1,330
4-Person	\$59,100	\$1,193	\$285	\$1,478
5-Person	\$63,850	\$1,268	\$328	\$1,596
Low income (80% AMI)				
1-Person	\$66,250	\$1,499	\$157	\$1,656
2-Person	\$75,700	\$1,701	\$192	\$1,893
3-Person	\$85,150	\$1,894	\$235	\$2,129
4-Person	\$94,600	\$2,080	\$285	\$2,365
5-Person	\$102,200	\$2,227	\$328	\$2,555
Moderate Income (120% AMI)				
1-Person	\$67,200	\$1,523	\$157	\$1,680
2-Person	\$76,800	\$1,728	\$192	\$1,920
3-Person	\$86,400	\$1,925	\$235	\$2,160
4-Person	\$96,000	\$2,115	\$285	\$2,400
5-Person	\$103,700	\$2,265	\$328	\$2,593
Source: Housing Authority County of Los Angeles, Allowances for Tenant-Furnished Utilities and Other Services Report and California Department of Housing and Community Development, 2021 Income Limits and Kimley Horn and Associates Assumptions: 2020 HCD income limits; 30% gross household income as affordable housing cost; 15% of monthly affordable cost for taxes and insurance; 10% down payment; and 4.5% interest rate for a 30-year fixed-rate mortgage loan. Utilities based on Los Angeles County Utility Allowance. ¹Utilities includes basic electric, water, sewer/trash, refrigerator, and stove.				



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 2-37: Affordable Housing Costs

Annual Income		Mortgage	Utilities ¹	Tax and Insurance	Total Affordable Monthly Housing Cost	Affordable Purchase Price
Extremely Low income (30% of AMI)						
1-Person	\$24,850	\$371	\$157	\$93	\$621	\$81,400
2-Person	\$28,400	\$412	\$192	\$107	\$710	\$90,400
3-Person	\$31,950	\$444	\$235	\$120	\$799	\$97,500
4-Person	\$35,450	\$468	\$285	\$133	\$886	\$102,700
5-Person	\$38,300	\$486	\$328	\$144	\$958	\$106,600
Very Low Income (50% of AMI)						
1-Person	\$41,400	\$723	\$157	\$155	\$1,035	\$158,600
2-Person	\$47,300	\$813	\$192	\$177	\$1,183	\$178,200
3-Person	\$53,200	\$896	\$235	\$200	\$1,330	\$196,600
4-Person	\$59,100	\$971	\$285	\$222	\$1,478	\$231,000
5-Person	\$63,850	\$1,029	\$328	\$239	\$1,596	\$225,700
Low income (80% AMI)						
1-Person	\$66,250	\$1,251	\$157	\$248	\$1,656	\$274,300
2-Person	\$75,700	\$1,417	\$192	\$284	\$1,893	\$310,800
3-Person	\$85,150	\$1,574	\$235	\$319	\$2,129	\$345,200
4-Person	\$94,600	\$1,725	\$285	\$355	\$2,365	\$378,200
5-Person	\$102,200	\$1,844	\$328	\$383	\$2,555	\$404,300
Moderate Income (120% AMI)						
1-Person	\$67,200	\$1,271	\$157	\$252	\$1,680	\$278,800
2-Person	\$76,800	\$1,440	\$192	\$288	\$1,920	\$315,900
3-Person	\$86,400	\$1,601	\$235	\$324	\$2,160	\$351,000
4-Person	\$96,000	\$1,755	\$285	\$360	\$2,400	\$384,900
5-Person	\$103,700	\$1,876	\$328	\$389	\$2,593	\$411,400

Source: Housing Authority County of Los Angeles, Allowances for Tenant-Furnished Utilities and Other Services Report and California Department of Housing and Community Development, 2020 Income Limits and Kimley Horn and Associates Assumptions: 2020 HCD income limits; 30% gross household income as affordable housing cost; 15% of monthly affordable cost for taxes and insurance; 10% down payment; and 4.5% interest rate for a 30-year fixed-rate mortgage loan. Utilities based on Los Angeles County Utility Allowance.

¹ Utilities includes heating, cooking, water heating, water, sewer, trash collection, microwave, and refrigerator. All utilities are assuming electric as averaged on the County of Los Angeles Utility Allowance Schedule Utilities are based on Single Family Unit Size.



CITY OF
ARCADIA

Technical Background Report Section 3

Housing Constraints, Resources, and Affirmatively Furthering Fair Housing (AFFH)





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Section 3: Housing Constraints, Resources, and Affirmatively Furthering Fair Housing (AFFH)

A variety of constraints may affect the provision and opportunity for adequate and affordable housing in the City of Arcadia. Housing constraints consist of both governmental constraints, including but not limited to development standards and building codes, land use controls, and permitting processes; as well as nongovernmental or market constraints, including but not limited to land costs, construction costs, and availability of finances. Combined, these factors create barriers to availability and affordability of new housing, especially for lower and moderate income households.

HCD requires that these constraints be evaluated as part of the Housing Element in order to understand barriers to housing and plan for the implementation of fair housing measures. This analysis is an important step in evaluating potential housing stock that can be allocated to all housing needs within the City. Factors that may constrain affordable housing in Arcadia will be analyzed in this chapter.

1. Nongovernmental Constraints

Nongovernmental constraints may largely affect the cost of housing in the City of Arcadia and can produce barriers to housing production and affordability. These constraints include the availability and cost of land for residential development, the demand for housing, financing and lending, construction costs, and the availability of labor, which can make it expensive for developers to build any housing, and especially affordable housing. The following highlights the primary market factors that affect the production of housing in Arcadia.

A. Land Costs and Construction Costs

Construction costs vary widely according to the type of development, with multi-family housing generally less expensive to construct than single-family homes. However, there is variation within each construction type, depending on the size of the unit and the number and quality of amenities provided. An indicator of construction costs is Building Valuation Data compiled by the International Code Council (ICC). The International Code Council was established in 1994 with the goal of developing a single set of national model construction codes, known as the International Codes, or I-Codes. The ICC updates the estimated cost of construction at six-month intervals and provides estimates for the average cost of labor and materials for typical Type VA wood-frame housing. Estimates are based on “good-quality” construction, providing for materials and fixtures well above the minimum required by state and local building codes.

In February 2021, the ICC estimated that the average per square-foot cost for good-quality housing was approximately \$125.18 for multi-family housing, \$138.79 for single-family homes, and \$156.95 for residential care/assisted living facilities. Construction costs for custom homes and units with extra amenities, run even higher. Construction costs are also dependent upon materials used and building height, as well as regulations set by the City’s adopted Building Code. For example, according to the ICC, an accessory dwelling unit (ADU) or converting a garage using a Type VB wood framed unit would cost about



CITY OF ARCADIA 6TH CYCLE Housing Element Update

\$130.58 per square foot. Although construction costs are a significant portion of the overall development cost, they are consistent throughout the region.¹

Land costs pose a significant constraint to the development of affordable and middle income housing and represent a significant cost component in residential development. Land costs may vary depending on whether the site is vacant or has an existing use that must be removed. Similarly, site constraints such as environmental issues (e.g. soil stability, seismic hazards, flood risks) can also be factored into the cost of land. A May 2021 web search for lots for sale in the City of Arcadia returned 6 lots for sale ranging drastically in size and cost based on location.² Lots for sale outside of the City's primary center for housing and commercial business are not considered in this analysis as well as lots zoned for commercial use, as they will not be representative of size or cost of land which has been developed for residential use historically. The cost of vacant lots currently for sale near existing development in Arcadia, ranges from \$1.15 million for 9,855 square feet south of Interstate 210, \$2.29 million for 0.423 acres southwest of Interstate 210, to \$3.48 million for 1.02 acres near the southwestern edge of the city. Overall, the estimated average cost of land in the City is about \$101.67 per square foot. The cost of land in the City of Arcadia is considered expensive, selectively accessible, and can be considered a barrier or constraint to the potential development of housing.

B. Availability of Financing

The availability of financing in a community depends on a number of factors, including the type of lending institutions active in a community, lending practices, rates and fees charged, laws and regulations governing financial institutions, and equal access to such loans. Additionally, availability of financing affects a person's ability to purchase or improve a home. Under the Home Mortgage Disclosure Act (HMDA), lending institutions are required to disclose information on the disposition of loan applications and the income, gender, and race of loan applicants. The primary concern in a review of lending activity is to determine whether home financing is available to all residents of a community. The data presented in this section include the disposition of loan applications submitted to financial institutions for home purchase, home improvement, and refinancing in the Los Angeles-Long Beach-Glendale Metropolitan Statistical Area/Metropolitan Division (MSA/MD).

Table 3-1 below displays the disposition of loan applications for the Los Angeles-Long Beach-Glendale MSA/MD per the 2019 Home Mortgage Disclosure Act report. According to the data, applicants in the 120% MSA/MD median income or more had the highest rates of loans approved. Of that income category, applicants who reported as white ethnicity had the highest percentage of approval and number of applications. Applicants in the less than 50% of the MSA/MD median income categories showed higher percentages of denied loans than loans originated. According to the data, applicants who reported as White ethnicity were, on average, more likely to be approved for a loan than another race or ethnicity.³

Given the relatively high rates of approval for home purchase, improvement, and refinance loans, home financing is generally available and not considered to be a significant constraint to the provision and maintenance of housing in Arcadia.

¹ International Code Council. (2021). Building Valuation Data. Available at <https://www.iccsafe.org/products-and-services/fi-codes/code-development-process/building-valuation-data/>.

² Zillow. [Arcadia CA Real Estate & Homes for Sale](https://www.zillow.com/homes/Arcadia,-CA_rb/). Available at https://www.zillow.com/homes/Arcadia,-CA_rb/. Accessed on August 27, 2021.

³ FFIEC- MSA/MD Aggregate Reports. (2019). Disposition of applications by income, race, and ethnicity of applicant. <https://ffiec.cfbp.gov/data-publication/aggregate-reports/2019/CA/31084/5>



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-1: Disposition of Loan Applications by Race/Ethnicity – Los Angeles-Long Beach-Glendale MSA/MD (2019)

Applications by Race/Ethnicity	Percent Approved	Percent Denied	Percent Other	Total (Count)
LESS THAN 50% OF MSA/MD MEDIAN				
American Indian and Alaska Native	24.16%	57.30%	19.66%	178
Asian	36.54%	42.13%	23.50%	1,932
Black or African American	41.98%	28.82%	31.98%	2,120
Native Hawaiian or other Pacific Islander	20.33%	67.03%	14.29%	182
White	44.14%	30.93%	27.22%	11,384
Hispanic or Latino	39.00%	36.23%	27.28%	6,559
50-79% OF MSA/MD MEDIAN				
American Indian and Alaska Native	36.97%	43.28%	22.27%	238
Asian	44.31%	34.08%	27.98%	2,873
Black or African American	42.75%	32.23%	29.11%	2,367
Native Hawaiian or other Pacific Islander	22.83%	62.20%	17.32%	254
White	48.99%	28.31%	27.75%	14,902
Hispanic or Latino	44.63%	32.50%	27.81%	10,611
80-99% OF MSA/MD MEDIAN				
American Indian and Alaska Native	41.44%	33.33%	27.03%	111
Asian	51.15%	27.37%	27.37%	1611
Black or African American	47.33%	27.31%	28.91%	1124
Native Hawaiian or other Pacific Islander	35.48%	47.31%	20.43%	93
White	53.61%	23.41%	27.73%	6,887
Hispanic or Latino	50.10%	26.66%	27.42%	4,974
100-119% OF MSA/MD MEDIAN				
American Indian and Alaska Native	42.05%	32.10%	29.26%	352
Asian	60.54%	19.94%	25.90%	5,869
Black or African American	49.93%	23.72%	30.51%	3,579
Native Hawaiian or other Pacific Islander	40.89%	39.86%	21.65%	291
White	60.13%	17.88%	27.40%	25,143
Hispanic or Latino	56.43%	20.69%	27.80%	16,541



CITY OF ARCADIA 6TH CYCLE Housing Element Update

120% OR MORE OF MSA/MD MEDIAN				
American Indian and Alaska Native	48.91%	23.88%	30.08%	871
Asian	62.94%	14.28%	27.54%	35,764
Black or African American	55.04%	19.47%	29.58%	11,611
Native Hawaiian or other Pacific Islander	54.18%	23.29%	27.19%	1052
White	64.87%	13.46%	25.98%	135,203
Hispanic or Latino	60.42%	16.47%	27.46%	42,722
Source: Consumer Financial Protection Bureau, Disposition of loan applications, by Ethnicity/Race of applicant, 2019.				



CITY OF ARCADIA 6TH CYCLE Housing Element Update

C. Economic Constraints

Market forces on the economy and the subsequent trickle-down effects on the construction industry can act as a barrier to housing construction and especially to affordable housing construction. It is estimated that housing price growth will continue in the city and the region for the foreseeable future. Moving into 2020, the economy was growing, California was experiencing a 1.6 percent growth in jobs from 2019 and experiencing all-time lows for unemployment rates. However, with the current COVID-19 pandemic, employment rates have been unstable. In May of 2020, unemployment within California increased to 15.6 percent. As of May 2021, the State's unemployment rate has declined to 7.9 percent.⁴

A 2021 California Association of Realtors (CAR) report found that homes on the market in Los Angeles County experienced a 25.1 percent year to year increase and cost an average of \$707,050 in April 2021; approximately \$42,950 lower than the Southern California median home price in the same month (\$750,000).⁵ According to the CAR First Time Buyer Housing Affordability Index, for 2021 the median value of a home in Los Angeles County was \$580,010 with monthly payments (including taxes and insurance) of \$2,830, requiring a minimum qualifying income of \$84,900.⁶ Homes and cost of living in the City of Arcadia was reported higher than the State median housing and living costs, almost double.⁷ According to May 2021 data from Zillow, the median cost of a home is \$1,131,169. Home values in the City have gone up 8.4% over the past year.⁸

2. Governmental Constraints

In addition to market constraints, local policies and regulations also affect the price and availability of housing and the provision of affordable housing. For example, State and Federal regulations affect the availability of land for housing and the cost of housing production, making it difficult to meet the demand for affordable housing and limiting supply in a region. Regulations related to environmental protection, building codes, and other topics have significant, often adverse, impacts on housing cost and availability.

While the City of Arcadia has no control over State and Federal Laws that affect housing, local laws including land use controls, site improvement requirements, fees and exactions, permit processing procedures, and other factors can constrain the maintenance, development, and improvement of housing or create barriers to housing.

A. Land Use Controls

Cities in California are required by Law to prepare a comprehensive, long term General Plan to guide future development. The Land Use and Community Design Element of the General Plan establishes permitted

⁴ California Employment Development Department. California unemployment rate improves to 7.9% in May 2021. (2021). Available at <https://www.edd.ca.gov/newsroom/unemployment-may-2021.htm>.

⁵ California Association of Realtors (CAR). (2021). April home sales and price report. Available at <https://www.car.org/aboutus/mediacenter/newsreleases/2021releases/apr2021sales>.

⁶ CAR. Housing Affordability Index- First-time Buyer. Available at <https://www.car.org/marketdata/data/ftbhaj>. Accessed on August 27, 2021.

⁷ Best Places. Cost of Living in Arcadia. Available at https://www.bestplaces.net/cost_of_living/city/california/arcadia. Accessed on August 27, 2021.

⁸ Zillow. (2021). Arcadia Home Values. Available at <https://www.zillow.com/arcadia-ca/home-values/>.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

land uses and development density throughout the City of Arcadia.⁹ The following lists the land uses that permit residential developments and the allowable densities:

- **Residential Estates (RE)** (up to 2 du/ac) – The Residential Estates designation accommodates low-density and single-family residential neighborhoods. Permitted uses include single-family residences on a single lot, private tennis courts and similar facilities.
- **Very Low Density Residential (VLDR)** (up to 4 du/ac) – The Very Low Density Residential designation accommodates low-density single-family residential neighborhoods. Permitted uses include single-family residences on a single lot and private tennis courts and similar facilities.
- **Low Density Residential (LDR)** (up to 6 du/ac) – The Low Density Residential designation accommodates low-density single-family residential neighborhoods. Permitted uses are limited to single-family residences on a single lot.
- **Medium Density Residential (MDR)** (6 to 12 du/ac) – The Medium Density Residential designation accommodates varied housing types and sizes within a suburban neighborhood context. Permitted residential uses include detached and attached residences with private and/or shared yards and open space areas.
- **High Density Residential (HDR)** (12 to 30 du/ac) – The High Density Residential designation accommodates higher-density attached housing types for both renter and owner households within a neighborhood context. Such housing types generally are located near transit stops, along arterials and transit corridors, and within easy walking distance of shops and services.
- **Commercial (C)** (1.0 FAR and 30 to 80 du/ac) – The Commercial designation also allows a Residential Flex Overlay that allows residential development up to 30 du/acre without the need for a commercial component like mixed use zones. In addition, to provide the residential population that is required to support the uses in the downtown and around the Metro Gold Line transit station, residential uses in a mixed-use development are permitted above ground floor commercial or adjacent to a commercial use.
- **Horse Racing (HR)** (Maximum FAR – N/A) – The Horse Racing designation provides for the continued operation of the Santa Anita Park race track for horse racing and related activities and special events. Seasonal housing for employees is permitted as an ancillary use per Municipal Code standards.
- **Mixed Use (MU)** (Maximum FAR – 1.0, up to 30 du/ac) – The Mixed Use designation provides opportunities for commercial and residential mixed-use development that takes advantage of easy access to transit and proximity to employment centers, and that provide complementary mixes of uses that support and encourage pedestrian activity. Residential uses in a mixed-use development are permitted above ground floor commercial or adjacent to a commercial use. Mixed commercial/office and residential tenancies and stand-alone commercial or office uses are allowed. However, exclusively residential buildings are not. The FAR maximum is applicable only to nonresidential component of a development.
- **Downtown Mixed Use (DMU)** (Maximum FAR – 1.0, up to 80 du/ac) – The Downtown Mixed Use designation provides opportunities for complementary service and retail commercial businesses, professional offices, and residential uses to locate within the City's downtown. Residential uses in a mixed-use development are permitted above ground floor commercial or adjacent to a commercial use. However, exclusively residential buildings are not allowed. A specific plan or zone change for the Downtown area will contain detailed development standards, infrastructure

⁹City of Arcadia. (2010). Land Use and Community Design Element. Available at <https://www.arcadiaca.gov/Shape%20Arcadia/Development%20Services/general%20plan/Land%20Use%20Element%20Update%20Final.pdf> ., pg. 10



CITY OF ARCADIA 6TH CYCLE Housing Element Update

requirements, land use regulations, and implementation measures for coordinated development. The FAR maximum is applicable only to nonresidential component of a development.

State Density Bonus Law¹⁰

In accordance with State Law – Government Code Section 65915 – a housing development may increase the number of units above the maximum permitted and/or receive reductions in development standards in exchange for reserving units for very low, low income, and/or moderate income households or for seniors. These units must be restricted to their level of affordable for at least 55 years. A density bonus is applicable to projects which include at least 5 units and at least one of the following:

- 5% units restricted to very low income households;
- 10% units restricted to low income or moderate income households;
- 10% units restricted for transitional foster youth, disables veterans, or homeless;
- 20% units for low income student housing;
- A senior housing project;
- An age-restricted mobile home park; and/or
- Projects which include a childcare facility.

The City of Arcadia's municipal code states that a density bonus and applicable concessions are granted if an applicant for a housing development seeks and agrees to construct a development that contains low income, very-low income, moderate income, and/or senior housing units, as such outlined in the Government Code Section 65915(b)1. The amount of a density bonus and the extent of other incentives allowed will be determined by the Council in conjunction with the Government Code Section 65915. An additional density bonus incentive is granted if an applicant proposed to construct a housing development includes a childcare facility located on the premises of, as part of or adjacent to the project. If a density bonus and/or other incentives cannot be accommodated on a site due to strict compliance with the provisions of the City of Arcadia's Development Code, the Council may modify or waive other development standards as necessary to accommodate all bonus units and other incentives to which the development is entitled.

Until 2021, under Government Code Section 65915, known as the Density Bonus Law, the maximum bonus was 35%. California state law AB 2345 states that all jurisdictions in California are required to process projects proposing up to 50% additional density as long as those projects provide the additional Below Market Rate units (BMR) in the "base" portion of the project, unless the locality already allows a bonus above 35%. The bill also lowered the BMR thresholds for concessions and incentives for projects with low income BMRs. As of 2021, Government Code Section 65915 authorizes an applicant to receive 2 incentives or concessions for projects that include at least 17% of the total units for lower income households, at least 10% of the total units for very low income households, or at least 20% for persons or families of moderate income in a common interest development. It also allows an applicant to receive 3 incentives or concessions for projects that include at least 24% of the total units for lower income households, at least 15% of the total units for very low income households, or at least 30% for persons or families of moderate income in a common interest development.

¹⁰Municode. Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV3RE_APALZOITPLGEDEST_S9103.15DEBOAFSEHO_9103.15.060FI. Accessed on August 27, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

The City's Density Bonus program is determined in compliance with Government Code Section 65915, however, does not reflect AB 2345 which requires an allowance of up to 50% when the appropriate base BMR is proposed.¹¹ The City of Arcadia has included a program in Chapter 10: Implementation Plan to evaluate and update the City's Municipal Code in compliance with state legislation. It is the City's goal and intention to remain up to date with most recent Density Bonus legislation throughout the 6th cycle as it applies to Arcadia.

B. Residential Development Standards¹²

The City of Arcadia's Municipal Code establishes residential zoning districts that permit a variety of developments and land uses in accordance with the General Plan Land Use Element. **Table 3-2** provides the development standards established for each zoning district to guide appropriate development. The development standards include minimum lot size requirements, building setbacks, and lot coverage.

- **Residential Mountainous Zone (R-M)** – The R-M zone is intended to provide areas for detached single-family dwelling units on estate-type lots in the hillside and valley areas of the City and accessory uses compatible with the residential use of the zone. This zone implements the General Plan Residential Estates designation.
- **Very Low Density Residential Zone (R-0)** – The R-0 zone is intended to provide areas for detached single-family dwelling units on large lots and accessory uses compatible with the residential use of the zone. This zone implements the General Plan Residential Estates, Very Low Density Residential, and Low Density Residential designations.
- **Low Density Residential Zone (R-1)** – The R-1 zone is intended to provide areas for detached single-family dwelling units and accessory uses compatible with the residential use of the zone. This zone implements the General Plan Very Low Density Residential and Low Density Residential designations.
- **Medium Density Residential Zone (R-2)** - The R-2 zone is intended to provide areas for a variety of dwelling types and accessory uses compatible with the residential use of the zone. Types of dwelling units include attached or detached single-unit and multi-unit homes and duplexes at a density of six to 12 dwelling units per acre. This zone implements the General Plan Medium Density Residential designation.
- **High Density Residential Zone (R-3)** – The R-3 zone is intended to provide areas for a variety of medium- to high-density residential development and accessory uses compatible with the residential use of the zone. Types of dwelling units include single-unit attached, townhomes, condominiums, and apartment structures at a density of 12 to 30 units per acre. This zone implements the General Plan High Density Residential designation.
- **Restricted High Density Residential Zone (R-3-R)** – The R-3-R zone is intended to provide areas for medium to high-density residential development at a density of 12 to 30 units per acre but restricted to one story in height. Accessory uses compatible with the residential use of the zone are also permitted. This zone implements the General Plan High Density Residential designation.

¹¹ Municode, Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV3REA_PALZOITPLGEDEST_S9103.15DEBOAFSEHO_9103.15.020DEBO. Accessed on August 27, 2021.

¹² Municode, Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV2ZOALUSDEST_S9102.01REZO. Accessed on August 27, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-2: Development Standards

Development Feature	Zoning Designation								
	R-M	R-O	R-1	R-2	R-3-R	R-3	CBD	MU	DMU
Lot Standards									
Minimum Lot Area (SF)	15,000	R-0-30,000: 30,000 R-0-22,000: 22,000 R-0-15,000: 15,000 R-0-12,500: 12,500	R-1-15,000: 15,000 R-1-10,000: 10,000 R-1-7,500: 7,500	7,500	10,000	10,000	5,000	5,000	10,000
Minimum Lot Width									
At Front Property Line	100 ft; 44 ft for cul-de-sac lots	100 ft; 57 ft for cul-de-sac lots	75 ft; 44 ft for cul-de-sac lots	75 ft; 44 ft for cul-de-sac lots; 85 ft if reversed corner lot	100 ft	100 ft; 57 ft for cul-de-sac lots; 85 ft if reversed corner lot	-	-	-
At Front Setback Line	75 ft	100 ft; 85 ft on reverse corner lots	75 ft	75 ft; 85 ft if reversed corner lot	100 ft; 85 ft if reversed corner lot	100 ft; 85 ft if reversed corner lot	-	-	-
Minimum Lot Depth	100 ft	100 ft	100 ft	100 ft	100 ft	100 ft	-	-	-
Structure Form and Location Standards									
Minimum Density (du/Acre)	1 unit per lot	1 unit per lot	1 unit per lot	2 units per lot	None	1 unit per 2,200 sf of lot area	-	-	-



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-2: Development Standards

Table 3-2: Development Standards									
Development Feature	Zoning Designation								
	R-M	R-O	R-1	R-2	R-3-R	R-3	CBD	MU	DMU
Maximum Density (du/Acre)	1 unit per lot	1 unit per lot	1 unit per lot	1 unit per 3,750 sf of lot area	1 unit per 1,450 sf of lot area	1 unit per 1,450 sf of lot area	80 units per acre	30 units per acres	80 unit per acre
Minimum Setbacks									
Front	25 ft	35 ft	25 ft	25 ft	25 ft	25 ft	0 ft (10 ft maximum)	0 ft (10 ft maximum)	0 ft (10 ft maximum)
Side (Interior)	First or Single Story			10 ft	10 ft	10 ft	Abutting nonresidential or mixed-use zone		
	10 ft or 10% of lot width, whichever is greater, not exceeding 15 ft	10 ft or 10% of the lot width, whichever is greater	5 ft or 10% of the lot width, whichever is greater				0 ft	0 ft	0 ft
	Second Story						Abutting residential zone		
	15 ft or 20% of the lot width, whichever is greater	15 ft or 20% of the lot width, whichever is greater	10 ft or 20% of the lot width, whichever is greater				10 ft	10 ft	10 ft
							Side (Street side)		
							0 ft (10 ft max)	0 ft (10 ft max)	0 ft (10 ft max)
Corner (Street Side)	First or Single Story			25 ft	25 ft	25 ft	-	-	-
	20 ft	20 ft	20 ft						
	Second Story								
	20 ft	20 ft	20 ft						
Reverse Corner (Street Side)	First or Single Story			25 ft	25 ft	25 ft	-	-	-
	20 ft	25 ft	25 ft						
	Second Story								
	20 ft	25 ft	25 ft						



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-2: Development Standards

Table 3-2: Development Standards									
Development Feature	Zoning Designation								
	R-M	R-O	R-1	R-2	R-3-R	R-3	CBD	MU	DMU
Rear	First or Single Story			10 ft	10 ft	10 ft	Abutting Nonresidential or Downtown Zone		
	25 ft	35 ft	25 ft				0 ft	0 ft	0 ft
	Second Story						Abutting Residential Zone		
	35 ft	35 ft	35 ft				20 ft	15 ft	15 ft
Maximum Height	16 ft and cannot exceed the maximum height of dwelling	16 ft and cannot exceed the maximum height of dwelling	16 ft and cannot exceed the maximum height of dwellings	30 ft	18 ft	30 ft*	60 ft	40 ft	60 ft
Maximum Number of Stores	2 stories	2 stories	2 stories	-	-	3 stories	-	-	-
Notes: *- The Code allows up to 33 feet to accommodate ridge heights of roofs.									



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Landscaping Requirements¹³

The City of Arcadia Municipal Code requires landscaping of residential sites to include elements such as lawn, trees, and shrubs and for these elements to be maintained in a neat and orderly manner.

Zones R-M, R-0, and R-1:

- The front and street-side areas shall be landscaped with lawn, trees, shrubs, or other plant materials, and shall be permanently maintained in a neat and orderly manner.
- Hardscape materials, inclusive of driveways and pedestrian walkways but not including artificial turf, shall not cover more than 40 percent of the required front setback or street side.

Zones R-M:

- All cut or fill slopes exceeding six feet six inches in vertical height between two or more contiguous lots shall be planted with adequate plant material to protect the slope against erosion. The planting shall cover the bank within two years from the time of planting. The permittee, owner, or developer shall water the planted slopes at sufficient time intervals to promote growth.

Zones R-2, R-3, and R-3-R:

- The front and street-side areas shall be landscaped with lawn, trees, shrubs, or other plant materials, and shall be permanently maintained in a neat and orderly manners
- Hardscape materials, inclusive of driveways and pedestrian walkways but not including artificial turf, shall not cover more than 40 percent of the required front setback or street side.

Site Coverage and FAR¹⁴

The City of Arcadia defines Floor Area Ratio (FAR) as:

Residential Floor Area Ratio: The floor area ratio shall be the numerical value obtained by dividing the aboveground floor area of any building(s) located on a lot by the net area of the lot.

Non-Residential Floor Area Ratio: The floor area ratio shall be the numerical value obtained by dividing the non-residential floor area of any building(s) located on a lot by the net area of the lot.

Minimum Unit Sizes

The City of Arcadia does not have minimum unit sizes. The lack of restrictions on unit sizes creates an opportunity for increased density in housing within the City which has less vacant land to accommodate housing. No restrictions on unit sizes in addition to zoning for higher intensity uses could allow for a higher number of smaller units such as micro-units.

Maximum Building Heights¹⁵

According to Division 2 of the City of Arcadia's Municipal Code, building structures may not exceed the height limit established by the lot's zone. The maximum building height in R-M, R-0 and R-1 is 25-30 ft depending on the width of the lot. R-2 and R-3 both have a maximum building height of 30 ft, or 33 ft with

¹³ Municode, Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV3REAPALZOITPLGEDEST_S9103.09LA. Accessed on August 27, 2021.

¹⁴ Municode, Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV3REAPALZOITPLGEDEST_S9103.01SIPLGEDEST. Accessed on August 27, 2021.

¹⁵ Municode, Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV3REAPALZOITPLGEDEST_S9103.01SIPLGEDEST_9103.01.050HEMEEX. Accessed on August 27, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

a pitched roof, while R-3-R has a maximum building height of 18 ft. In comparison to surrounding communities, the City of Arcadia has extensive building height regulations that are described below:

Height Measurement

- **Structure Height.** Structure height is measured from the base to the highest point of the building—excluding the chimney.
- **Structure Height on Slopes with 20 Percent Grade.** Structures on slopes with 20 percent or greater grade are measure from the adjacent existing grade to the highest point of the building – excluding chimneys.
- **Porch Height.** Porch height is measured from the finished grade to the uppermost points of the railing, cornices, and other features. For recessed porches, height is measure to the uppermost point of the opening.
- **Height Regulations by Lot Width.** Some maximum building heights will vary based on the width of the lot. The lot width for determining height shall be measured from the front property line or at the required front setback line, whichever is greater.

Exceptions to Height Limits in All Zones

Maximum building heights in these areas do not apply to flagpoles and antennas. Height guidelines for these features are provided by §9103.01.050 of the City’s zoning code.

Three-Story Projects

In 2016, the City changed the regulations in the R-2 and R-3 Zones (multi-family) and eliminated the number of stories within 30-foot height requirement to encourage higher-quality designs, to allow more units, and to align with the General Plan Goal LU-4 - “Promote high-quality and attractive multi-family residential neighborhoods that provide ownership and rental opportunities for people in all stages of life.”

The Development Code currently allows development up to 30 feet in height or 33 feet in height if the proposed project has a pitched roof. Since this requirement has been in place, the City has approved 11 three-story developments under the existing regulations.

Parking Standards¹⁶

Off-street parking for residential uses is defined by the City of Arcadia in **Table 3-3**. These standards are considered the minimum required to preserve the public health, safety, and welfare of the community. An increase or decrease in the parking requirements may be determined by the Review Authority in particular circumstances where these requirements are inadequate for a specific project. These cases are determined through a parking study as outlined in Article IX, Chapter 1, Division 3, Section 9103.07.

Table 3-3: Off-Street Parking Requirements for Residential Uses	
Land Use	Minimum Parking Spaces Required
Single-Family Housing	• 2 spaces per dwelling unit in a garage for units less than 5,000 square feet in size with up to 4 bedrooms.
	• 3 spaces per dwelling unit in a garage for units 5,001 square feet or more in size and/or with 5 or more bedrooms.

¹⁶ Municode, Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DE_CO_DIV3REAPALZOITPLGEDEST_S9103.07OREPALO. Accessed on August 27, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-3: Off-Street Parking Requirements for Residential Uses

Land Use	Minimum Parking Spaces Required	
Accessory Dwelling Unit	One on-site parking space (covered or uncovered)² Refer to Section 92102.01.080 for additional standards.	
Multi-Family Dwellings and Other Attached Dwellings	R-2, R-3, and the R-3-R Zones	2 covered spaces per unit 1 guest parking space per each 2 units
Mixed Use Units	1 space per studio 1.5 spaces per unit and 1 guest space for every 3 units	
Live/Work Units	1 space per unit and 1 space per 1,000 square feet of nonresidential floor area	
Senior Housing (when restricted to age 62 and older)	- For senior affordable apartment housing: 1 space per unit, and 1 guest space for every 4 units for assisted living facilities: 1.5 spaces per unit - For senior market rate housing: 2 spaces per unit	
Notes: (1) A tandem parking space may be allowed to satisfy the third required, or any non-required, parking space, subject to Design Review approval (2) Parking standards shall not be imposed on an accessory dwelling unit in any of the following circumstances: a. The accessory dwelling unit is located within one-half mile of public transit. b. The accessory dwelling unit is located within an architecturally and historically significant historic district. c. The accessory dwelling unit is part of the existing primary residence or an existing accessory structure. d. When on-street parking permits are required but not offered to the occupant of the accessory dwelling unit. e. When there is a car sharing vehicle located within one block of the accessory dwelling unit.		

The parking requirements for the City of Arcadia are similar to the requirements set by a neighboring jurisdiction, the City of Sierra Madre. Both cities require two parking spaces per dwelling unit for single family housing zones. Furthermore, for multi-family housing, both cities require two covered spaces per unit and one guest parking space per two units. From these similarities, it should be reasonable to consider Arcadia's parking requirements as practical and meeting the needs of its residents and guests.

However, parking requirements could be viewed as a constraint to providing fair housing. By requiring parking spaces based on unit amount or the size of a unit, housing development is restricted. Less housing development takes place overall since space must be left to accommodate parking. Parking permit programs through residential developments and neighborhoods could also be considered a constraint on fair housing. Since these parking permits could present a financial burden for those who are required to use them, low-income families could be deterred from living in areas where they are required. The City will continue to monitor fees in order to ensure they do not become a constraint.

Definition of a Family



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Per Arcadia Municipal Code §9109.01.070, a family is defined as a group of persons, whether related or unrelated, who live together in a non-transient and interactive manner, including the joint use of common areas of the premises which they occupy and sharing household activities and responsibility such as meals, chores and expenses. Notwithstanding the foregoing, any group of persons required to be considered as a "family" for zoning purposes pursuant to California Health & Safety Code Sections 1267.8, 1566.3, 1568.0831, 1569.85, 11834.23, or any other state law shall be deemed to be a family for purposes of this code.

C. Homeowners Association Areas

The City of Arcadia Municipal Code has established different developmental standards for Homeowners Association Areas within single-family residential zones R-M, R-0, and R-1. The documented Homeowners Associations within the code include the Santa Anita Village, Highland Oaks, Upper Rancho, Lower Rancho, and Santa Anita Oaks HOAs. Their allowable Floor Area Ratios (FARs) are documented in Table 3-4. Table 3-5 documents other applicable development standards such as minimum setbacks, maximum lot coverages, maximum number of stories, and more, for homeowner association areas.

~~The City of Arcadia Municipal Code has established different developmental standards for Homeowners Association Areas within single-family residential zones R-M, R-0, and R-1. The documented Homeowners Associations within the code include the Santa Anita Village, Highland Oaks, Upper Rancho, Lower Rancho, and Santa Anita Oaks HOAs. Their allowable Floor Area Ratios (FARs) are documented in Table 3-4. Table 3-5 documents other applicable development standards such as minimum setbacks, maximum lot coverages, maximum number of stories, and more, for homeowner association areas.~~

Table 3-4: Floor Area Ratio Standards for Homeowners Association Areas

Single-Family Residential Zones (R-M, R-0, and R-1)

Maximum Floor Area in Specific Homeowners Association Areas	
HOA and Lot Size	Floor Area Ratio
Santa Anita Village and Highland Oaks HOAs	
Less than 10,000 sf	35% of lot area
10,001 – 15,000	3,500 sq ft plus 25% of lot area over 10,000 sq ft
15,001 – 20,000	4,750 sq ft plus 10% of lot area over 15,000 sq ft
20,001 – 30,000	5,250 sq ft plus 10% of lot area over 20,000 sq ft
30,000 +	6,250 sq ft plus 10% of lot area over 30,000 sq ft
Upper Rancho HOA	
Less than 10,000 sf	45% of lot area
10,001 – 15,000	4,500 sq ft plus 40% of lot area over 10,000 sq ft
15,001 – 20,000	6,500 sq ft plus 30% of lot area over 15,000 sq ft
20,001 – 30,000	8,000 sq ft plus 25% of lot area over 20,000 sq ft
30,000 +	13,000 sq ft plus 32% of lot area over 40,000 sq ft
Lower Rancho and Santa Anita Oaks HOA	
Less than 10,000 sf	37% of lot area
10,001 – 15,000	3,700 sq ft plus 37% of lot area over 10,000 sq ft
15,001 – 20,000	5,500 sq ft plus 20% of lot area over 15,000 sq ft
20,001 – 30,000	6,550 sq ft plus 20% of lot area over 20,000 sq ft



CITY OF ARCADIA 6TH CYCLE Housing Element Update

~~The City of Arcadia Municipal Code has established different developmental standards for Homeowners Association Areas within single family residential zones R-M, R-O, and R-1. The documented Homeowners Associations within the code include the Santa Anita Village, Highland Oaks, Upper Rancho, Lower Rancho, and Santa Anita Oaks HOAs. Their allowable Floor Area Ratios (FARs) are documented in Table 3-4. Table 3-5 documents other applicable development standards such as minimum setbacks, maximum lot coverages, maximum number of stories, and more, for homeowner association areas.~~

Table 3-4: Floor Area Ratio Standards for Homeowners Association Areas

Single-Family Residential Zones (R-M, R-O, and R-1)

Maximum Floor Area in Specific Homeowners Association Areas

30,000 +	8,550 sq ft plus 15% of lot area over 30,000 sq ft
Incentive for One-Story Homes in all HOA Areas	
3% of the lot area in additional floor area	



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-5: Additional Development Standards for Homeowners Association Areas

Single-Family Residential Zones (R-M, R-0, R-1)

Development Feature	Zoning Designation				
	Santa Anita Village (R-1)	Highlands (R-M and R-1)	Lower Rancho (R-0)	Santa Anita Oaks (R-0)	Upper Rancho (R-0)
Minimum Setbacks					
Front	25 ft	25 ft	35 ft	65 ft Exceptions: Tract 13544 and 11013 shall be a minimum of 55 ft and Tract 14565 shall be a minimum of 50 ft	50 ft
Side – first or single story					
Interior	5 ft or 10% of the lot width, whichever is greater	R-M: 10 ft or 10% of lot width, whatever is greater but not to exceed 15 ft as a required setback R-1: 6 ft or 10% of the lot width, whichever is greater	10 ft or 10% of the lot width, whichever is greater	10 ft or 10% of the lot width, whichever is greater	15 ft
Corner (street side)	20 ft	20 ft	20 ft	20 ft	20 ft
Reverse Corner (street side)	25 ft	R-M: 20 ft R-1: 25 ft	25 ft	25 ft	25 ft



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-5: Additional Development Standards for Homeowners Association Areas

Single-Family Residential Zones (R-M, R-0, R-1)

Development Feature	Zoning Designation				
	Santa Anita Village (R-1)	Highlands (R-M and R-1)	Lower Rancho (R-0)	Santa Anita Oaks (R-0)	Upper Rancho (R-0)
Side – second story					
<i>Interior</i>	10 ft or 20% of the lot width, whichever is greater	R-M: 15 ft or 20% of lot width, whatever is greater R-1: 10 ft or 20% of the lot width, whichever is greater	15 ft or 20% of the lot width, whichever is greater	15 ft or 20% of the lot width, whichever is greater	15 ft or 20% of the lot width, whichever is greater
<i>Corner (street side)</i>	20 ft	20 ft	20 ft	20 ft	20 ft
<i>Reverse Corner (street side)</i>	25 ft	R-M: 20ft R-1: 25ft	35 ft	35 ft	35 ft
Rear					
First or single story	25 ft	25 ft	35 ft	35 ft	40 ft
Second Story	35 ft	35 ft	35 ft	35 ft	35 ft
Maximum Lot Coverage					
1-story dwellings	45%	45%	45%	45%	45%
2-story dwellings	35%	35%	35%	35%	35%
Maximum number of stories	2 stories	2 stories	2 stories	2 stories	2 stories
Maximum Street-Facing Porch Height	14 ft	14 ft	14 ft	14 ft	14 ft
Encroachment Plane					
Front Property Line	30 degrees	R-M: 40 degrees R-1: 30 degrees	30 degrees	30 degrees	30 degrees
Interior Rear and/or Interior Side	N/A	N/A	N/A	N/A	N/A



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-5: Additional Development Standards for Homeowners Association Areas

Single-Family Residential Zones (R-M, R-0, R-1)

Development Feature	Zoning Designation				
	Santa Anita Village (R-1)	Highlands (R-M and R-1)	Lower Rancho (R-0)	Santa Anita Oaks (R-0)	Upper Rancho (R-0)
Corner Street Side Property Line	40 degrees	40 degrees	40 degrees	40 degrees	40 degrees
Maximum Height	25 ft	R-M: 25 ft for lots less than 71-foot lot width; an additional 1 ft in height for every additional 1 ft in lot width up to 75 ft lot (30 ft height) 80-85 ft lot width: 31 ft, 85'-1"-90 ft lot width: 32 ft, 90'-1"- 95 ft lot width: 33 ft, 95'-1"-100 ft lot width: 34ft, 100'-1" + ft lot width: 35 ft R-1: Less than 75 ft lot width: 25 ft, 75'-94 ft lot width: 27ft, 94'-1"-114 ft lot width: 29ft, 114'-1" ft lot or larger width: 30 ft	25 ft for lots less than 75-foot lot width 30 ft for lots with 75-foot width or greater	25 ft for lots less than 75-foot lot width 30 ft for lots with 75-foot width or greater	25 ft for lots less than 75-foot lot width 30 ft for lots with 75-foot width or greater

Notes:

1. In cases where the underlying zoning's Development Standard is greater than the requirements stated in Table 2-2, Additional Development Standards for Homeowners Association Areas Single-family Residential Zones (R-M, R-0, R-1), the underlying zoning shall be used unless an exception is specifically identified.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

D. Growth Management Measures

Growth management measures are techniques used by a government to regulate the rate, amount, and type of development. Growth management measures allow cities to grow responsibly and orderly, however, if overly restrictive, they can produce constraints to the development of housing, including accessible and affordable housing. There are currently no growth management measures in Arcadia.

E. Specific Plans

The purpose of a Specific Plan is to implement the goals and objectives of a city's General Plan in a more focused and detailed manner that is area and project specific. The Specific Plan process promotes consistency and an enhanced aesthetic level throughout the identified project area. Specific Plans contain their own development standards and requirements that may be more restrictive than those defined for the City as a whole.

Seabiscuit Pacific Specific Plan – Le Meridien Hotel and Mixed Use Project (SP-SP)¹⁷

The Seabiscuit Pacific Specific Plan consists of a 6.15-acre mixed-use project, consisting of a 234-unit Marriott Full Service Hotel and 8-story mixed-use residential site with 96 dwelling units. The project proposed 595 total parking spaces on surface and parking garage settings. According to Section 1.3 of the Specific Plan, the Seabiscuit Pacifica Specific Plan was developed with the overall framework of the City of Arcadia's development standards, except for a few guidelines, customized for the specific plan. It should be noted that if not mentioned in the following guidelines, the City of Arcadia's development standards should prevail:

- Height Limit
- Buildings in Zone H may exceed the height defined by its zone, yet shall not exceed:
 - Zone H4 - Four stories or forty-five feet
 - Zone H5 - Five stories or fifty-five feet
 - Zone H6 - Six stories or sixty-five feet
 - Zone H7 - Seven stories or seventy-five feet
 - Zone H8 - Eight stories or ninety-five feet

Landscaping

- There are many new trees, shrubs, and ground covers that have been planted to enhance the aesthetics of the site. The project landscaping plans attempted to preserve the existing mature trees onsite to the extent feasible, based on the tree assessment.

Signs

- Typical directional and room designation signage conform with City of Arcadia code requirements.

F. Variety of Housing Types Permitted

California Housing Element Law mandates that jurisdictions must make sites available through zoning and development standards to promote the development of a variety of housing types for all socioeconomic levels

¹⁷ Seabiscuit Pacifica Specific Plans. (2018). Available on https://www.arcadiaca.gov/Shape%20Arcadia/Development%20Services/specific%20plans/3.FinalAmendedSPSP_62018.pdf.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

of the population. Housing types include single-family homes, multi-family housing, accessory dwelling units, factory-built homes, mobile-homes, employee and agricultural work housing, transitional and supportive housing, single-room occupancy (SROs), and housing for persons with disabilities. **Table 3-6** shows the various housing types permitted throughout the City of Arcadia.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-6: Housing Types Permitted in Arcadia

Land Uses																			
Housing Types	Residential						Commercial			Industrial	Downtown Zones					Special Purpose Zones			
	R-M	R-0	R-1	R-2	R-3	R-3R	C-O	C-G	C-R	M-1	CBD	MU	DMU	C-M	PF	OS-OR	OS-RP	RR	S-1
Single-Family	P	P	P	P	P	-	NA	NA	NA	NA	-	-	P	-	NA	NA	NA	NA	NA
Multi-Family	-	-	-	P	P	P	NA	NA	NA	NA	M	M	M	-	NA	NA	NA	NA	NA
Two-Family Dwelling	-	-	-	P	P	P	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Accessory Dwelling Unit	A	A	A	A	A	A	NA	NA	NA	NA	A	A	A	-	NA	NA	NA	NA	NA
Junior Accessory Dwelling Unit	A	A	A	-	-	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Residential Care Facility - Six or fewer persons	P	P	P	P	P	P	NA	NA	NA	NA	-	-	P	P	NA	NA	NA	NA	NA
Residential Care Facilities - Seven or More Persons	NA	NA	NA	NA	NA	NA	C	C	-	-	NA	NA	NA	NA	NA	NA	NA	NA	NA



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Supportive Housing - Housing Type	-	-	-	P	P	P	NA	NA	NA	NA	M (UF)	M (UF)	M (UF)	-	NA	NA	NA	NA	NA
Supportive Housing - Residential Care Facility Small Type	P	P	P	P	P	P	NA	NA	NA	NA	-	-	C	C	NA	NA	NA	NA	NA
Supportive Housing - Residential Care Facility Large Type	NA	NA	NA	NA	NA	NA	C	C	-	-	NA	NA	NA	NA	NA	NA	NA	NA	NA
Transitional Housing - Housing Type	-	-	-	P	P	P	NA	NA	NA	NA	M (UF)	M (UF)	M (UF)	-	NA	NA	NA	NA	NA
Transitional Housing - Residential Care Facility Small Type	P	P	P	P	P	P	NA	NA	NA	NA	-	-	-	C	NA	NA	NA	NA	NA
Transitional Housing - Residential Care Facility Large Type	NA	NA	NA	NA	NA	NA	C	C	-	-	NA	NA	NA	NA	NA	NA	NA	NA	NA
Boarding House	-	-	-	-	-	-	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Emergency Shelter	NA	NA	NA	NA	NA	NA	-	-	-	P	NA	NA	NA	NA	NA	NA	NA	NA	NA
Hotel and Motel	NA	NA	NA	NA	NA	NA	-	C	-	-	C	C	C	C	NA	NA	NA	NA	NA
Live/Work Unit	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M	M	M	-	NA	NA	NA	NA	NA

Notes:

P – Permitted

A – Permitted as an Accessory Use

M – Minor Use Permit Required

C – Conditional Use Permit Required

(UF)- Uses are Permitted on Upper Floor only

NA- No Information

Source: City of Arcadia Municipal Code, Division 2: Zones, Allowable Uses, and Development Standards



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Single-Family Dwelling

Single-Family Dwellings are defined by the City of Arcadia's Zoning Code as a detached structures containing no more than one dwelling unit which, regardless of form of ownership, is designed and/or used to house not more than one household. Single-Family Dwellings are permitted in the R-M, R-0, R-1, R-2, R-3 residential zones.

Multi-Family Dwelling

Multi-Family Dwellings are defined by the City of Arcadia's Zoning Code as a structure or portion thereof containing three or more dwelling units designed for the independent occupancy of three or more households. Multi-Family Dwellings are permitted in the R-3 and R-3-R residential zones and can be permitted in downtown zones CBD, MU and DMU with a minor use permit.

Two-Family Dwelling

Two-Family Dwellings are defined by the City of Arcadia's Zoning Code as a building containing two complete dwelling units designed for the independent occupancy of two households. Two-Family Dwellings are permitted in residential zones R-2, R-3, and R-3-R.

Accessory Dwelling Unit

Accessory Dwelling Units are defined by the City of Arcadia's Zoning Code as an attached or detached unit which provides complete, independent living facilities for one or more persons, including permanent provisions for living, sleeping, eating, cooking, and sanitation on the same parcel as an existing qualified primary dwelling unit as situated and is no larger than 850 square feet for one bedroom or 1,000 square feet for two bedrooms. Accessory Dwelling Units are permitted as an accessory use in R-M, R-0, R-1, R-2, R-3, R-3-R residential zones as well as CBD, MU and DMU zones.

Junior Accessory Dwelling Unit

Junior Accessory Dwelling Units are defined by the City of Arcadia's Zoning Code as an accessory dwelling unit that is contained entirely within an existing or proposed single family structure and is not more than 500 square feet in area, which provides independent living facilities, including provisions for cooking and either separate or shared sanitation on the same parcel as an existing qualified primary dwelling unit is situated.

Residential Care Facility- Small and Large

A Residential Care Facility is defined by the City of Arcadia's Zoning Code as any facility, place, or building which is maintained and operated to provide 24-hour care of persons in need of personal services, supervision, or assistance essential for sustaining the activities of daily living or for the protection of the individual. The Housing type, Residential Care Facility, is defined as one residence that operates as a group living facility, where the residents share a common living area and kitchen. Residential Care facilities with six or fewer residents (small), excluding staff, is permitted in R-M, R-0, R-1, R-2, R-3, and R-3-R residential zones. Residential Care Facilities with more than seven persons (large), excluding staff, is permitted with a conditional use permit in C-O and C-G commercial zones.

Supportive Housing – Housing Type, Small, and Large

The term Supportive Housing (per California Government Code Section 65582[f], as may be amended) shall mean a dwelling unit occupied by a target population, with no limit on length of stay, that is linked to on-site or off-site services that assist the supportive housing resident(s) in retaining the housing, improving their health status, and maximizing their ability to live and, when possible, work in the community. A target population means



CITY OF ARCADIA 6TH CYCLE Housing Element Update

persons with low incomes having one or more disabilities, including mental illness, HIV or AIDS, substance abuse, or other chronic health conditions, or individuals eligible for services provided under the Lanterman Developmental Disabilities Services Act (Welfare and Institutions [W&I] Code Section 4500) and may include—among other populations—adults, emancipated youth, families, families with children, elderly persons, young adults aging out of the foster care system, individuals exiting from institutional settings, veterans, and homeless people. Supportive housing may be designed as a residential group living facility or as a regular residential use and includes the following:

Supportive Housing - Housing Type is defined as two or more dwelling units on one parcel, where each unit functions as a single housekeeping unit and no on-site social services are provided.

Supportive Housing - Residential Care Facility Small Type is defined as one residential facility on a parcel with six residents or fewer (including minor children), excluding staff, that operates as a group living facility, where the residents share a common living area and a kitchen.

Supportive Housing - Residential Care Facility Large Type is defined as a residential facility with seven or more residents that operates as a group living facility where the residents share a common living area and a kitchen.

Supportive Housing (Housing Type) is permitted in CMD, MU, DMU with a minor use permit for upper floors only. Supportive Housing with six or fewer residents (small), excluding staff, is permitted in R-M, R-0, R-1, R-2, R-3, and R-3-R residential zones. Supportive Housing with more than seven persons (large), excluding staff, is permitted with a conditional use permit in C-O and C-G commercial zones.

The City will update its Municipal Code to align with AB 2162 (Supportive Housing Streamlined Approvals) as outlined in Program 5-24.

Transitional Housing – Housing Type, Small, and Large

The term Transitional Housing (per California Government Code Section 65582[h], as may be amended) shall mean buildings configured as rental housing developments, but operated under program requirements that require the termination of assistance and recirculating of the assisted unit to another eligible program recipient at a predetermined future point in time that shall be no less than six months from the beginning of assistance. Transitional housing may be designed as a residential group living facility or as a regular residential use and includes the following:

Transitional Housing - Housing Type is defined as two or more dwelling units on one parcel, where each unit functions as a single housekeeping unit and no on-site social services are provided.

Transitional Housing - Residential Care Facility Small Type is defined as one residential facility on a parcel with six residents or fewer (including minor children), excluding staff, that operates as a group living facility, where the residents share a common living area and a kitchen.

Transitional Housing - Residential Care Facility Large Type is defined as a residential facility with seven or more residents that operates as a group living facility where the residents share a common living area and a kitchen.

Transitional Housing (Housing Type) is permitted in CMD, MU, DMU with a minor use permit for upper floors only. Transitional Housing with six or fewer residents (small), excluding staff, is permitted in R-M, R-0, R-1, R-2, R-3, and R-3-R residential zones as well as C-M commercial zone. Transitional Housing with more than



CITY OF ARCADIA 6TH CYCLE Housing Element Update

seven persons (large), excluding staff, is permitted with a conditional use permit in the C-O and C-G commercial zones.

The City will update its Municipal Code to align with the Emergency and Transitional Housing Act of 2019 as outlined in Program 5-24.

Boarding House

Boarding Houses are defined by the City of Arcadia's Zoning Code as a residence or dwelling, other than a motel or hotel, wherein two or more rooms, with or without cooking facilities in the rooms and/or for groups, are rented to individuals, persons or groups under separate rental agreements or leases, either written or oral, whether or not an owner, agent or rental manager is in residence. Boarding houses are not permitted in residential zones.

Emergency Shelter

Emergency Shelter is defined by the City of Arcadia's Zoning Code as housing with minimal supportive services for homeless persons that is limited to an occupancy time of six months or less. Emergency Shelter cannot be denied because of a person's inability to pay.

The City permits emergency shelters by-right without a discretionary approval process in the Light Industrial (M-1) zone. Emergency shelters are subject to the same development standards as an industrial building. The M-1 zone encompasses approximately 118 acres of land in the southernmost part of the City. It is mostly made up of large parcels with existing uses that are older and underutilized, including many warehousing uses. Such uses can be converted to accommodate emergency shelter use. Properties in the M - 1 zone are also located close to or along major arterials and thus easily accessible to transit and other services.

The existing management standards and use standards and can be found in Section 9104.02.140 of the City's Development. Emergency shelters are required to have onsite management and onsite security during all hours of operation. Emergency shelters are not allowed to have designated exterior waiting areas or client intake areas.

The City has committed to Program 5-24 to comply with the Emergency and Transitional Housing Act of 2019. Adoption of this program would change parking requirements for emergency shelters to only account for staff parking. By doing this, planning for emergency shelters and finding the space for them will be more efficient and therefore more effective if an emergency shelter is needed.

Hotel and Motel

Hotel is defined by the City of Arcadia's Zoning code as a commercial establishment offering overnight visitor accommodations, but not providing room rentals on an hourly basis. Motel is defined by the Zoning Code as a lodging establishment typically featuring a series of rooms whose entrances are immediately adjacent to a parking lot. Hotel and Motel is permitted with a conditional use permit in C-G, CBD, MU, DMU and C-M zones.

Live/Work Unit

A Live/Work unit is defined as a unit that combines a work space and incidental residential occupancy for use by a single household. The working space is reserved for and regularly used by one or more occupants of the unit. Living space includes, but is not limited to, a sleeping area, a food preparation area with reasonable work space, and a full bathroom including bathing and sanitary facilities which satisfy the provisions of applicable codes. Live/Work Units are permitted in the CBD, MU and DMU zones with a minor use permit.

Single-Room Occupancy

A Single-Room Occupancy (SRO) is defined as a building or buildings constructed or converted for residential living consisting of one-room dwelling units, where each unit is occupied by a single individual or two persons



CITY OF ARCADIA 6TH CYCLE Housing Element Update

living together as a domestic unit, and where the living and sleeping spaces are combined. A unit that contains both a bathroom and kitchen shall be considered a studio unit and not a Single-Room Occupancy. Single-Room Occupancies are permitted in all multi-family residential zones (R-2, R-3 and R-3-R) either through supportive housing, transitional housing, or residential care facility. SROs are permitted as a stand-alone use.

Employee Housing

Employee housing is permitted in the Special Use Zone for the Santa Anita Racetrack (S-1). While the City is compliant with the Employee Housing Act, the City does not have a definition of Employee Housing in its Municipal Code and has committed to Program 5-24 to add a definition of Employee Housing that is compliant with State Law.

Mobile Homes

Mobile homes may be used as temporary workspaces in construction spaces and for short term use up to 12 months. Mobile homes are not permitted for long term use as housing or workspaces.

Manufactured Homes

Manufactured homes are defined as a structure either wholly or mainly manufactured at an off-site location and is assembled on site on a permanent foundation with permanent service connections. The definition does not include a mobile home, mobile accessory structure, or an automobile trailer or recreational vehicle. Manufactured homes are permitted in the City of Arcadia as a temporary accessory use.

Short Term Rentals and Unoccupied Housing

The City of Arcadia's Short Term Rental Ordinance prohibits short term rentals allowing for more housing supply for Arcadia residents. Additionally, the City of Arcadia maintains an unoccupied housing registry. The unoccupied housing registry requires that owners of unoccupied homes pay a fee and register their homes as unoccupied. The annual fee for an unoccupied home is \$1,492 annually.¹⁸ This is not considered a constraint to fair housing as the fee provides an incentive to keep housing occupied to the extent that owners can.

G. Housing for Persons with Disabilities

Both the Federal Fair Housing Amendment Act (FHAA) and the California Fair Employment and Housing Act direct require governments to make reasonable accommodations (that is, modifications or exceptions) in their zoning laws and other land use regulations to afford disabled persons an equal opportunity to access housing. State law also requires cities to analyze potential and actual constraints to the development, maintenance, and improvement of housing for persons with disabilities.

The Housing Element Update must also include programs that remove constraints or provide reasonable accommodations for housing designed for persons with disabilities. The analysis of constraints must touch upon each of three general categories: 1) zoning/land use; 2) permit and processing procedures; and 3) building codes and other factors, including design, location and discrimination, which could limit the availability of housing for disabled persons.

¹⁸ City of Arcadia, Unoccupied Housing Fee, available at https://www.arcadiaca.gov/shape/development_services_department/neighborhood_services/code_services_enforcement/unoccupied_residences_registration.php.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Reasonable Accommodation¹⁹

Reasonable accommodation in the land use and zoning context means providing individuals with disabilities or developers of housing for people with disabilities, flexibility in the application of land use and zoning and building regulations, policies, practices and procedures, or even waiving certain requirements, when it is necessary to eliminate barriers to housing opportunities. For example, it may be reasonable to accommodate requests from persons with disabilities to waive a setback requirement or other standard of the Zoning Code to ensure that homes are accessible for the mobility impaired. Whether a particular modification is reasonable depends on the circumstances.

The City of Arcadia's Municipal Code defines an individual with a disability as a person who has a physical or mental impairment that limits or substantially limits one or more major life activities, anyone who is regarded as having this type of impairment, or anyone who has a record of this type of impairment. These individuals are protected under the Federal Fair Housing Act and the California Fair Employment and Housing Act (the Acts). The Code specifies that reasonable accommodation must be granted if all of the following findings are made:

- The housing, which is the subject of the request, will be used by individual disabled as defined under the Acts.
- The requested reasonable accommodation is necessary to make specific housing available to an individual with a disability under the Acts.
- The requested reasonable accommodation would not impose an undue financial or administrative burden on the city.
- The requested reasonable accommodation would not require a fundamental alteration in the nature of a city program or law, including, but not limited to, land use and zoning.
- The requested reasonable accommodation would not adversely impact surrounding properties or uses.
- There are no reasonable alternatives that would provide an equivalent level of benefit without requiring a modification or exception to the city's applicable rules, standards and practices.

To be considered for a reasonable accommodation, the Development Services Director must approve or conditionally approve an application, followed by a ten-day public notice to adjacent property owners. The decision may be appealed to the Planning Commission for review. An application for reasonable accommodation must include all of the following:

- Certification and documentation that the applicant is a person with disability or representing a person(s) with disability.
- The name and address of the person requesting reasonable accommodation.
- The name and address of the property owner(s).
- A description and diagram depicting the reasonable accommodation requested by the applicant.
- An explanation of how the requested accommodation is necessary to provide the person(s) with disability equal opportunity to use and enjoy the residence.
- The director may request additional information from the applicant if the application does not provide sufficient information to make the findings required in Section E.

¹⁹ Municode. Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV7PEP_RPR_S9107.17REAC. Accessed on August 27, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

- Fee as established through the city's fee schedule, if the project requires another discretionary permit, the fee(s) for all other discretionary permits shall be paid.
- If an individual needs assistance in making the request for reasonable accommodation, the city will provide assistance to ensure the process is accessible.

In the past year, the City received 6 applications for reasonable accommodations. 3 of the applications were approved and 3 were closed because the applicant decided not to pursue the project. The City will implement Program 5-31: Fair Housing to further reduce barriers to provide reasonable accommodations.

H. Development Fees

Residential developers are subject to a variety of permitting, development, and impact fees in order to access services and facilities as allowed by State law. The additional cost to develop, maintain, and improve housing due to development fees result in increased housing unit cost, and therefore is generally considered a constraint to housing development. However, fees are necessary to provide planning and public services in Arcadia.

The location of projects and housing type result in varying degrees of development fees. The presumed total cost of development is also contingent on the project meeting city policies and regulations and the circumstances involved in a particular development project application. **Table 3-7** provides the planning processing fees, **Table 3-8** provides the permit processing fees, and Error! Reference source not found. provides development impact fees for the City. Planning processing, permit processing, and development impact fees are available on the City's website.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-7: Planning and Land Use Fees

Fee Type		Fee
Site Plan and Design Reviews (<u>Multiple Family</u>)	New, Up to 20 Dwelling Units	\$2,750
	Amendment, Up to 20 Dwelling Units	\$1,610
	New, 21+ Dwelling Units	\$6,821
	Amendment, 21+ Dwelling Units	\$2,391
	Remodel/Addition	\$1,618
Site Plan and Design Reviews (<u>Single Family</u>)	New	\$2,245
	New — Amendment	\$1,059
	Remodel/Addition	\$1,131
	Remodel/Addition - Amendment	\$507
Historic Preservation	Designation of a Local Landmark	\$1,890
	Designation of a Historic District	\$2,625
	Mills Act Contract Application	\$1,050
	Certificate of Appropriateness (Major)	\$1,680
	Certificate of Appropriateness (Minor)	\$945
Certificate of Demolition	Director's Review	\$187
	Referred to Planning Commission	\$1,260 (plus CEQA Fees)
	Appeal	\$630
Conditional Use Permit	New	\$2,934
	Amendment	\$1,940
	Extension	\$133
	Appeal	\$630
Minor Use Permit	New	\$1,410
	Amendment	\$721
	Appeal	\$630
Variance	New	\$2,564
	Amendment	\$1,748



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-7: Planning and Land Use Fees

Fee Type		Fee
	Appeal	\$630
Administrative Modifications	Minor Director's Review	\$626
	Major Director's Review	\$1,112
	Reasonable Accommodation	\$1,260
	Commission's Review	\$2,330
	Appeal	\$630
	Extension	\$187
Reasonable Accommodation		\$1,260
Home Occupation Permits*	Administrative	\$40
	Hearing	\$263
Determination of Use		\$1,927
Specific Plan	Application	\$8,892
	Amendment	\$4,771
General Plan Amendment		\$7,303
Text Amendment		\$4,900
Zone Change		\$6,783
Planned Developments		\$7,828
Subdivisions	Lot Line Adjustment w/Certificate of Compliance	\$1,770
	Tentative or Vesting Tentative Parcel Map	\$1,276
	Tentative or Vesting Tentative Tract Map for Family Lots (+\$30 for each lot above 5)	\$2,360
	Tentative or Vesting Tentative Tract Map for Condominiums	\$1,359
	Appeal	\$630
	Extension	\$257
	Final Map	\$1,634
	Parcel Map Waiver	\$762



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-7: Planning and Land Use Fees

Fee Type		Fee
	Amendment to an Approved Tentative Map and/or conditions and/or conditions	\$1,022
	Lot Mergers	\$1,354
	Certificate of Compliance	\$838
Environmental Review (CEQA)	Initial Study - Negative Declaration/Mitigated Neg. Dec.	\$1,575
	Environmental Impact Report (EIR)	At Cost
	LA County Clerk Posting/Processing	\$75
CA Dept. of Fish & Wildlife Filing with NOD	Negative Declarations (ND & MND)	\$2,480.25
	Environmental Impact Report (EIR) Environmental Document per a Certified Regulatory Program (CRP)	\$3,445.25
	Environmental Document per a Certified Regulatory Program (CRP)	\$1,721.25
Temporary Use Permit*	Application	\$574
	Council Review	\$1,437
Zoning Clearance		\$285
Development Agreement		At Cost
Development Agreement Amendment		At Cost
Development Agreement Periodic Review		\$1,034
Covenant Preparation		\$327
General Plan Document*		\$75
General Plan Land Use Map*	27 x 35 map	\$25
	11 x 17 map	\$2
Zoning Map*	27 x 35 Map	\$25
	11x 17 Map	\$2
Accessory Dwelling Unit	Zoning Clearance	\$285
	Covenant	\$327



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-7: Planning and Land Use Fees

Fee Type	Fee
Source: City of Arcadia. (2021). Planning Fees. Available at https://cms9files.revize.com/arcadia/Shape%20Arcadia/Development%20Services/planning/Planning%20Fees%20(with%205%20percent%20ROUNDED)%207-1-21.pdf Note: - All fees include a 5% General Plan Update fee except for those marked with an asterisk (*). - All fees are the same for multiple family and single family unless otherwise indicated.	

Table 3-8: Permit Processing Fees

Valuation	Fee
\$1.00 to \$500	\$40.65
\$501 to \$2,000	\$40.65 for the first \$500.00 plus \$4.20 for each additional \$100.00 or fraction thereof, to and including \$2,000.00
\$2,001 to \$25,000	\$103.65 for the first \$2,000.00 plus \$16.70 for each additional \$1,000.00 or fraction thereof, to and including \$25,000.00
\$25,001 to \$50,000	\$487.75 for the first \$25,000.00 plus \$12.75 for each additional \$1,000.00 or fraction thereof, to and including \$50,000.00
\$50,001 to \$100,000	\$806.50 for the first \$50,000.00 plus \$8.35 for each additional \$1,000.00 or fraction thereof, to and including \$100,000.00
\$100,001 and up	\$1,224.00 for the first \$100,000.00 plus \$6.90 for each additional \$1,000.00 or fraction thereof.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3- 9: Development Impact Fees

Fee Type	Planning Fee ¹	Building Fees
Single-family Detached	\$2,245	\$2.85 per SF
School Fees (Residential)		\$4.08 per SF
Single Family/Condo/Townhome		\$1,983 per unit
Multi-family (up to 20 units)	\$2,750	\$3.73 per SF
Multi-family (21 or more units)	\$6,821	\$3.73 per SF
School Fees (Residential)		\$4.08 per SF
Apartment		\$1,229 per SF
Condo/Townhome		\$1,983 per SF
Assisted Living		\$343 per unit
Notes:		
¹ These fees can be partially waived for affordable units		

The development fees associated with each project is dependent on the housing type, density, intensity of use, and location. In addition to these direct fees, the total cost of development is contingent on the project meeting the City's policies and standards, as well as the project applicant submitting necessary documents and plans in a timely manner.

The development fees associated with each project is dependent on the housing type, density, intensity of use, and location. In addition to these direct fees, the total cost of development is contingent on the project meeting the City's policies and standards, as well as the project applicant submitting necessary documents and plans in a timely manner.

The estimated total development and impact fees for a typical single-family residential project, assuming it is not part of a subdivision and is consistent with existing city policies and regulations, can range from \$23,063.66 to \$27,193.91. Estimated total development and impact fees for a typical multi-family residential project with ten units, assuming it is consistent with existing city policies and regulations range from \$196,978.06 to \$201,108.31. See **Table 3-10** and **Table 3-11** for a cost breakdown.

These estimates are illustrative in nature and that actual costs are contingent upon unique circumstance inherent in individual development project applications. Considering the cost of land in Arcadia, and the International Code Council (ICC) estimates for cost of labor and materials, the combined costs of permits and fees range from approximately 2.19% percent to 2.2% percent of the direct cost of development for a single-family residential project and 1.7% percent to 2% percent for a multi-family residential project. Direct costs do not include, landscaping, connection fees, on/off-site improvements, shell construction or amenities, therefore the percentage of development and impact fees charged by the City may be smaller if all direct and indirect costs are included.

Table 3-10: Land and Construction Costs

Single Family	Multi-Family
Land Cost (9,000 sf lot) ¹ : \$915,030	Land Cost (43,560 sf lot): \$4,428,745.20
Construction Cost (3,000 sf structure) ² : \$416,370	Construction Cost (2 story – 34,848 sf structure) ³ : \$4,362,272.60
Total Cost	
\$1,331,400	\$8,791,017.80



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Notes:

- 1- Land Cost: \$101.76 sq.ft. average land value
- 2- Construction Cost: \$138.79/sf for single-family
- 3- Construction Cost: \$125.18/sf for multi-family

Table 3-11: Total Development and Impact Fees Cost Breakdown

Single Family		Multi-Family	
Low Estimate	\$23,063.66	Low Estimate	\$196,978.06
Site Plan (New)	\$2,245	Site Plan (New)	\$2,750
Home Occupation Permits	\$303	Home Occupation Permits	\$303
Permit Processing Fees for \$100,001 and Up	\$9,720.66	Permit Processing Fees for \$100,001 and Up	\$61,192.02
School Fees (Single Family Detached)	\$10,795 (Including Planning Fee)	School Fees (Multi-Family up to 20 units)	\$132,733.04 (Including Planning Fee)
High (+CEQA) Estimate	\$27,193.91	High (+CEQA) Estimate	\$201,108.31
Site Plan (New)	\$2,245	Site Plan (New)	\$2,750
Home Occupation Permits	\$303	Home Occupation Permits	\$303
Permit Processing Fees for \$100,001 and Up	\$9,720.66	Permit Processing Fees for \$100,001 and Up	\$61,192.02
School Fees (Single Family Detached)	\$10,795 (Including Planning Fee)	School Fees (Multi-Family up to 20 units)	\$132,733.04 (Including Planning Fee)
Environmental Review (Initial Study)	\$1,575	Environmental Review (Initial Study)	\$1,575
LA County Clerk Processing	\$75	LA County Clerk Processing	\$75
CA Dept of Fish and Wildlife Filing with NOD (Negative Declarations)	\$2,480.25	CA Dept of Fish and Wildlife Filing with NOD (Negative Declarations)	\$2,480.25

Table 3- 12: Percent of total Direct (Available) Costs:

Single Family		Multi-Family	
Low	1.7%	Low	2.19%
High	2%	High	2.2%

When compared to development fees from surrounding jurisdictions, the City of Arcadia's fees are higher in comparison. For example, a permit that has a value between \$1.00 and \$500.00 requires a fee of \$37.85



CITY OF ARCADIA 6TH CYCLE Housing Element Update

in Monrovia²⁰, \$29.00 in Pasadena²¹, and \$40.65 in Arcadia. While the fees appear high, they would only make up approximately 2 percent of total costs to building in Arcadia. Therefore, they are not a constraint.

I. On-/Off-Site Improvements

Site improvements in the City consist of those typically associated with development for on-site improvements (improvements within the lot or property boundaries specific to the project or development), and off-site improvements which are required as a result of a development or project such as streets, sidewalks, water and sewer, drainage, curbs and gutters, street signs, park dedications, utility easements, and landscaping. Additional requirements for improvement implementation can be found in the Arcadia Municipal Code (AMC) § 9105.09. Per the municipal code, improvements are required to be installed or agreed upon by a subdivider as a condition precedent to filing a final map or parcel map. While these improvements are necessary to ensure that new housing meets the local jurisdiction's development goals, the cost of these requirements can represent a significant share of the cost of producing new housing. All improvements shall be constructed in compliance with the standards approved by the City Engineer. Requiring improvements may inflict the sale or rental price of housing.

Because residential development cannot take place without the addition of adequate infrastructure, site improvement requirements are considered a regular component of development of housing within the City. The majority of cost associated with on- and off-site improvements is reimbursed to the City in the form of Development Impact Fees as these improvements would impact public facilities such as water and sewer lines. The City of Arcadia requires that subdivisions of four or fewer or five or more lots shall provide improvements such as full width grading, full height Portland cement concrete curbs and gutters, full width roadway paving, installation of incidental drainage facilities, street signs, sidewalks, streetlights on public streets, and any other improvements for traffic and drainage needs as are required for the appropriate development of the division of land. These improvements are necessary for the safety and well-being of residents. Since they are necessary, they would not be a constraint to housing development.

Building Codes and Enforcement

The City has adopted the 2019 California Building Code as the basis of its building code, including the ancillary information within the tables, attachments, addendums, and footnotes per AMC Article VIII. This would include the California Administrative Code, Building Code, Residential Code, Electrical Code, Mechanical Code, Plumbing Code, Energy Code, Historical Building Code, Fire Code, Existing Building Code, Green Building Standards Code, and California Referenced Standards Code. The adopted California Building Code therefore ensures a consistent development standard that would be promoted throughout the State. The 2019 California Building Standards Code is the newest edition with an effective date of January 1, 2020. The City has amended the Building Code. Some amendments include further regulating the slopes into subterranean parking, acoustic requirements, and not allowing mechanical or plumbing infrastructure to run between share walls in condominiums. These amendments would not put a constrain on housing development as they do not relate to the provision of housing nor the affordability of housing units.

²⁰ City of Monrovia. 2021. Schedule of Fees & Charges- Fiscal Year 2021-2022. Available at <https://www.cityofmonrovia.org/home/showpublisheddocument/26154/637641916081730000>.

²¹ City of Pasadena. 2021. *General Fee Schedule Update*. Pg. 8. Available at <https://www.cityofpasadena.net/finance/wp-content/uploads/sites/27/FY-2022-Adopted-General-Fee-Schedule.pdf?v=1631111377237>.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

In partnership with the people of Arcadia, the Code Services Division monitors and enforces the ordinances in the Arcadia Municipal Code adopted by the Arcadia City Council to help maintain and promote a healthy, safe, and pleasant environment for everyone to live, work, and play. The Code Enforcement program in Arcadia is designed to keep housing safe and protect the general welfare of the community and is a complaint-based system. Like most small cities, Arcadia does not have a large code services staff and thus is not proactive when it comes to evaluating properties throughout the City for code violations. From 2018 through 2021, Code Enforcement staff indicated that there were 4,419 ~~property maintenance~~ code enforcement cases opened in Arcadia. An “opened” case simply refers to an issue raised on a property that must be reviewed or investigated. This does not mean there was any specific follow up, just that a case was opened for review. Of these opened cases, approximately 2,367 of the cases were related to “Property Maintenance”, is a very broad category of issues that includes everything from landscaping issues, to trash cans being left out, to junk and debris, to parking issues. Far and away the two most common complaints in Arcadia when it comes to property maintenance are landscaping problems and trash cans being left out too long.

The vast majority of these Code enforcement cases are simply notices of violation designed to inform property owners or renters of some type of issue. These are not citations, nor do they carry any monetary penalty. Further, a very small minority of these cases ripen into citations that are related to building maintenance or substandard housing conditions (only 151 of these during this four-year period). The majority of cases are aesthetic in nature and are dealt with before any penalties or citations are pursued. The Code enforcement philosophy in Arcadia is to find solutions rather than lead with citations, and in some cases, the Code Enforcement staff will refer a situation of someone in need to the County Health Department, Building and Safety Division, or to the City’s CDBG funded Home Improvement Program for assistance. There is a desire to help individuals stay in their homes. For all of these reasons, there are no policies that would hinder the production of housing units or the elimination of units, nor any code enforcement policies that would hinder affordability.

Local Processing and Permit Procedures²²

Depending on the magnitude and complexity of the development proposal, the time that elapses from application submittal to project approval may vary considerably. Factors that can affect the length of development review on a proposed project include the completeness of the development application and the responsiveness of developers to staff comments and requests for information. Approval times are substantially lengthened for projects that are not exempt from the California Environmental Quality Act (CEQA), require zoning or general plan amendments, or encounter community opposition.

Applicants for all permits or reviews are recommended to request a preapplication conference with the respective department to: confirm City requirements as they apply to the proposed project; discuss the City’s review process, possible project alternatives or revisions; and identify information and materials the City will require with the application, and any necessary technical studies and information relating to the environmental review of the project.

All plans are first reviewed by City Staff for completeness before it is accepted and officially filed. Once an application is accepted as complete, City Staff may require the applicant to submit additional information needed for the environmental review of the project in compliance with the California Environmental Quality

²² Municode. Arcadia, CA. Available at https://library.municode.com/ca/arcadia/codes/code_of_ordinances?nodeId=ARTIXDIUSLA_CH1DECO_DIV7PEP_RPR_S9107.03APPRPR_9107.03.020APSU. Accessed on August 27, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Act (CEQA) prior to the review by the appropriate authority. Various applications may also require public notice and a public hearing. Division 7, Section 9107.03 of Arcadia's Code of Ordinances provides the standards and procedures for submitting and obtaining permits. **Table 3-13** identifies the appropriate review authority for each planning permit application.

Table 3-13: Designated Authority for Permits and Appeals			
Type of Action	Role of Review Authority ¹		
	Director	Commission	Council
Legislative Action			
Development Agreements and Amendments	R	R	D
Development Code Amendments	R	R	D
General Plan Amendments	R	R	D
Specific Plans and Amendments	R	R	D
Zoning Map Amendments	R	R	D
Planning Permits and Approvals and Administrative Actions			
Administrative Modifications	See Table 7-2 in Section 9107.05		
Certificates of Demolition	D	A	A
Conditional Use Permits	R	D	A
Home Occupation Permits	D	A	A
Interpretations	D	A	A
Minor Use Permits	D	A	A
Planned Developments	D	D	A
Reasonable Accommodations	D	A	A
Sign Permits	D	A	A
Site Plan and Design Review	D	D/A	A
Site Plan and Design Review (HOA Areas)	D	A	A
Temporary Use Permits	D	A	A
Tree Encroachment, Preservation, and Removal	See Section 9110.01 for specific thresholds		
Variances	R	D	A
Zoning Clearances	I	A	A
Zoning Clearances (ADU)	I	A	A
<i>R = Review Authority makes a recommendation to a higher decision-making body</i> <i>D = Decision made by Reviewing Authority</i>			



CITY OF ARCADIA 6TH CYCLE Housing Element Update

I = Decision after Confirmed Compliance

A = Reviewing Authority may consider and decide upon appeal

Typically housing development processing is dependent on whether or not a tentative parcel or tract map is required. Without a tentative parcel or tract map, the timeline between receiving project approval and the submittal of an application for building permits could range from six to eight months, while processing for projects that require them could last anywhere from ten to twelve months.

Once a housing development is approved, a variety of factors determine the length of time it takes to apply for building permits. The average length of time between receiving approval for a housing development and submittal of an application for building permits is not under the City's control because once a project is approved, it is up to the applicant to decide when they will apply for building permits. Factors such as the cost and availability of material and labor may determine the length of time before developers apply for building permits. Some developers also delay pulling building permits due to financing issues. While it is generally difficult to accurately estimate the average length of time between receiving approval for a housing development and submittal of an application for building permits due to the unique nature and circumstances of individual developments, the City typically processes a single family project approval within three months and a building permit requires within another three months. For a multifamily project, the design review and parcel or tract map takes approximately four months. However, under the SB 330 process, a multifamily project permit processing time would be reduced to less than a month for design review. If the multifamily project is subject to a parcel or tract map, the process is typically 3 months. Multifamily building permits are typically processed an additional 3 months after the parcel or tract map.

Smaller projects such as re-roofing, solar panels, ADUs less than 800 square feet, and Junior ADUs require ministerial review. This process is typically shorter. Projects that require conditional use permits typically take three to four months to process and prepare all necessary documents for public hearing. The approval body is the Planning Commission, and the Planning Commission's decision is appealable to the City Council.

Projects requiring a Minor Use Permit are approved directly by the Director and a public hearing is held if it is requested in writing by an interested person. A minor use permit is typically processed in one to one and a half months depending on the request. The processing time includes a 14-day noticing period. The minor use permit is administratively approved by a Planner.

Zone changes and General Plan Amendments typically take six to nine because of the environmental review process. Zone changes and General Plan Amendments are analyzed to evaluate all the potential impacts the zone change may have to the environment, notifying the property owners if more than one parcel is involved, and preparing all the necessary documents and staff reports for the public hearings to both Planning Commission and City Council. The Planning Commission would forward a recommendation to the City Council, and the City Council is the final approval body.

Permit Processing

The Code states that requests for permits, licenses, appeals, amendments, approvals, and other discretionary actions required or allowed require that a city application form filled out in its entirety be submitted to the department. In addition, other materials, reports, dimensioned plans, or other information required to take an action on the application, and application check list, must be submitted with the application. The application checklist of required items for each type of application is available as a handout at the department.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Applications must be determined complete by the director before they are processed, as outlined in the municipal code, a complete application consists of the following:

- The application form with all applicable information included on, or attached to, the form;
- Other information or forms required for implementation of the California Environmental Quality Act (CEQA) in compliance with city and state guidelines for the implementation of CEQA;
- A statement indicating that the applicant is the owner of the property or is the legal representative of the property owner(s);
- If the application requires a public hearing, a list of the names and addresses of all owners of the property in compliance with Division 8, Section 9108.13 (Public Hearings) of the Municipal Code;
- Payment in full of the required fees and/or deposit for processing the application, in compliance with the council's fee resolution (Fees outlined above);
- Other information required by the director; and
- An application for variance shall include evidence to substantiate the basis for approval, in compliance with Division 7, 9107.25.050 (Findings and Decision).

Site Plan and Design Review

Division 7, Section 9107.19 of Arcadia's Municipal Code outlines the process for site plan and design review of development projects, which are intended to protect the integrity and character of the residential, commercial, and industrial areas of the city, consistent with the general plan. Site plan and design review are required to be approved before construction any structure, or relocate, rebuild, or significantly enlarge or modify any existing structure or site begins. There are three levels of review that a site plan may go through to get approved:

- Director review with no public notice;
- Director review with public notice; and
- Commission meeting with required public notice and hearing; and

The power to recommend, decide and appeal the project is dependent on the scope of the proposed project. More minor projects could be decided through first director review, while more involved projects would be decided through the planning commission.

A Development Plan Permit is required under the following conditions:

- New single-family residences;
- Minor first floor single-family residential additions and detached accessory structures;
- Second story additions to existing residences;
- All development located on hillsides having a natural slope gradient of 20 percent or greater;
- Multifamily residential construction;
- Any addition or change in the number of multifamily units;
- As may otherwise be required by Table 7-3 in Section 9107.19.

At the time of application submittal a review of configuration, design, location, and impact of the proposed use is conducted by comparing the use to established standards and design guidelines. This review determines whether the permit should be approved by weighing the public need for and the benefits to be



CITY OF ARCADIA 6TH CYCLE Housing Element Update

derived from the use against the impacts it may cause. Below is a table describing the estimated timeline of Site Plan and Design Review based on project characteristics:

Table 3-14: Processing Timelines and Approvals by Project Type		
Project Type	Duration of Process	Approval Details
Site Plan and Design Review: Single-Family Residence	Three months	Approved administratively by a Planner. There is a 10-day appeal period and the Planner's decision is appealable to the Planning Commission.
Site Plan and Design Review: Multi-family Development (without any affordable units)	Three to four months*	The approval body is the Planning Commission for the project, and the City Council if the final map involves a dedication. For a final map without a dedication, it can be approved administratively by the City Engineer.
Site Plan and Design Review: Commercial/Industrial Development (20,000 square feet or less)	Three months	Approved administratively by a Planner. There is a 10-day appeal period and the Planner's decision is appealable to the Planning Commission.
Site Plan and Design Review: Commercial/Industrial Development (20,001 square feet or more)	Three to four months	The approval body is the Planning Commission. There is a 10-day appeal period and the Commission's decision is appealable to the City Council.
Site Plan, Design Review, and Minor Use Permit: Mixed-Use Development	Four to five months (no CEQA)** Six to nine months (with CEQA)	Most mixed-use development can be approved administratively by a Planner, unless the project includes a map, dedication, and/or density bonus then it is subject to the Planning Commission's review and approval. If the project involves a density bonus, then the Planning Commission will make a recommendation to the City Council for final review.
Tract Map Approval	Four to five months	The approval body is the Planning Commission for the tentative tract map, and the City Council for the final tract map.
Parcel Map Approval	Four to five months	The approval body is the Planning Commission for the tentative parcel map. As for the



CITY OF ARCADIA 6TH CYCLE Housing Element Update

		final parcel map it is approved by the City Engineer. If there is a dedication, then it is approved by the City Council.
Initial Study (IS)	Six to nine months	-
Environmental Impact Report (EIR)	Twelve months	Depending on the project, the approval body could be either the Planning Commission or City Council.
Notes: *- dependent on whether a tentative parcel or tract map is required. **- dependent on whether or not the project is exempt from California Environmental Quality act (CEQA)		

The City's timeline for the design review process is not considered a constraint. Additionally, the City does not have standard subjective conditions within its design review process. While the Design Review process is not identified as a constraint, **Program 5-35** along with **Program 5-3** will continue to ensure that the design review process remains objective and is conducive to the development of housing within the City.

Developed Densities

Based on the development trends historically, most development projects develop close to maximum allowable densities and the City has not received requests to develop below standard densities for the underlying zoning.

Table 3-15: Example Development Densities within the City

Project Address	Development Density	Existing Maximum Density
57 Wheeler Avenue ¹	48	50
117-129 E. Huntington Drive & 124-134 Wheeler Avenue	80	80
150 North Santa Anita Avenue	146	80
122-128 E. Live Oak	30	30
56 East Duarte	22	30
314 East Live Oak	37	30
17 Las Tunas Dr	42	30
656 W. Huntington Dr	20	30
968 - 998 Arcadia Ave	34	30
736 – 738 Camino Real Ave	20	30
825 Arcadia Ave	20	30
415 California St	29	30
627 - 633 Fairview Ave	21	30
901 W. Duarte Rd	19	30
¹ At the time of this development, the DMU zone allowed a maximum density of 50 du/acre		

H. Senate Bill 35

California Senate Bill 35 (SB 35), codified at Government Code Section 65913.41, was signed on September 29, 2017 and became effective January 1, 2018. SB 35 will automatically sunset on January 1, 2026 (Section 65913.4(m)). The intent of SB 35 is to expedite and facilitate construction of affordable



CITY OF ARCADIA 6TH CYCLE Housing Element Update

housing. SB 35 applies to cities and counties that have not made sufficient progress toward meeting their affordable housing goals for above moderate- and lower income levels as mandated by the State. In an effort to meet the affordable housing goals, SB 35 requires cities and counties to streamline the review and approval of certain qualifying affordable housing projects through a ministerial process.

When a jurisdiction has made insufficient progress toward their Above Moderate income RHNA and/or have not submitted the latest Housing Element Annual Progress Report (2018) it is subject to the streamlined ministerial approval process (SB 35 (Chapter 366, Statutes of 2017) streamlining) for proposed developments with at least 10 percent affordability.²³ All projects which propose at least 10 percent affordable units within Arcadia are eligible for ministerial approval under SB 35 as determined by the SB 35 Statewide Determination Summary. To be eligible for SB 35 approval, sites must meet a long list of criteria, including:

- A multifamily housing development (at least two residential units) in an urbanized area;
- Located where 75% of the perimeter of the site is developed;
- Zoned or designated by the general plan for residential or mixed use residential;
- In a location where the locality's share of regional housing needs have not be satisfied by building permits previously issued;
- One that includes affordable housing in accordance with SB 35 requirements;
- Consistent with the local government's objective zoning and design review standards; and
- Willing to pay construction workers the state-determined "prevailing wage."

A project does not qualify for SB 35 streamline processing if:

- A coastal zone, conservation lands, or habitat for protected species;
- Prime farmland or farmland of statewide importance;
- Wetlands or lands under conservation easement;
- A very high fire hazard severity zone;
- Hazardous waste site;
- Earthquake fault zone;
- Flood plain or floodway;
- A site with existing multi-family housing that has been occupied by tenants in the last ten years or is subject to rent control; or
- A site with existing affordable housing.

I. Infrastructure Constraints

Another factor that could constrain new residential construction is the requirement and cost to provide adequate infrastructure (major and local streets; water and sewer lines; and street lighting) needed to serve new residential development. In most cases, where new infrastructure is required, it is funded by the developer and then dedicated to the City, which is then responsible for its maintenance. Because the cost of these facilities is generally borne by developers, it increases the cost of new construction, with much of that increased cost often "passed on" in as part of home rental or sales rates.

²³ HCD. (2021). Streamline Ministerial Approval Process. Available at <https://www.hcd.ca.gov/community-development/accountability-enforcement/docs/sb35determinationsummary10012020.pdf>.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Dry Utilities

Electricity

Southern California Edison (SCE) delivers electricity purchased by the Clean Power Alliance (CPA) to Arcadia. According to the California Energy Commission, SCE consumed approximately 80,912 million kilowatts per hour (kWh) of electricity in 2019. SCE continues to provide energy to the state of California through a series of methods including oil and natural gas, renewable energy resources and alternative diverse supplied. SCE is responsible for delivering electricity to all existing and future development in Arcadia.

Natural Gas

The Southern California Gas Company (SCGC) provides natural gas service to Arcadia and is the nation's largest natural gas utility provider with more than to 21.8 million consumers across 24,000 square miles throughout Central and Southern California. As a public utility, SCGC is under the jurisdiction of the California Public Utilities Commission (CPUC) which regulates natural gas rates and natural gas services, including in state transportation over the utilities' transmission and distribution pipelines system, storage, procurement, metering, and billing. Most of California's natural gas supply comes from out of the state. SCGC is responsible for providing service to residential, industrial, and commercial customers in Arcadia.

Water Supply and Wastewater Capacity

Water Supply

Water supply in Arcadia comes from groundwater from the Main San Gabriel Basin and the Raymond Basin and from treated surface water from the Metropolitan Water District of Southern California (MWD). The City owns and operates its own water distribution system maintained by the Public Works Service Department

According to the Hydrology Chapter of Arcadia's General Plan EIR, the Main San Gabriel basin encompasses the largest land area within Arcadia. Several areas within the City, primarily at the surrounding boundaries, are served by small private water agencies. The Sunny Slope Water Company, East Pasadena Water Company, and California-American Water Company serve areas along the western City boundary while the Southern California Water Company serves residents along the south and east boundaries.

Water Demand and Supply Reliability²⁴

The City of Arcadia is supplied water by three different water sources, below is an analysis of current and future supply reliability for each source.

Upper San Gabriel Valley Municipal Water District

The Upper San Gabriel Valley Municipal Water District (Upper District) is a special district organized and operated pursuant to the California Water Code and serves the greater San Gabriel Valley area, including the Cities of Arcadia, El Monte, and Baldwin Park. While the City can purchase water from the Upper District, the City's collective groundwater supplies are sufficient to meet water demands and treated imported water is only considered as an emergency water supply source.

Raymond Basin

²⁴ City of Arcadia. (2015). Urban Water Management Plan. <https://www.arcadiaca.gov/Shape%20Arcadia/Public%20Works%20Services%20Department/Water%20&%20Sewer%20Services/Urban%20Water%20Management%20Plan.pdf>, pg. 100 – 103.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Raymond Basin's management is based upon the Raymond Basin Judgement. The City is a party to the Judgement and has established the right to 3,803.6 acre-feet of water annually.

Main Basin

Main Basin's management is based upon Watermaster services under two Court Judgements. The City is a defendant and participates in the management of Main Basin. Main Basin operates under a cyclical model. The model does not restrict the quantity of water parties can take, rather it provides a means for replacing water that had been extracted in access that year. An Operating Safe Yield is established annually then each party is allocated a portion.

As a result of the Main Basin and Raymond Basin management and the demonstrated ability for the groundwater basin water level to recover, the City does not experience water supply constraints or deficiencies to its existing collective portfolio of water supplies. According to Arcadia's 2015 Urban Water Management Plan, the current water sources are projected to be able to meet water demands over the next 20 under all projected yearly conditions.

Wastewater Capacity

The City of Arcadia's local wastewater collection is managed by the Arcadia Public Works Services Department, Utilities Section. The wastewater generated in Arcadia flows into regional trunk lines operated by the County Sanitation Districts of Los Angeles. The Sanitation Districts manage a joint sewer outfall system that conveys collected wastewater to treatment plants located in Whittier. Since new development activity has the potential to result in increased wastewater flows, the City is continuing to monitor and plan for system enhancements as needed.

Fire and Emergency Services²⁵

Fire Prevention

The Arcadia Fire Department provides prevention and emergency response services to fires, search and rescue, disaster situations, and medical emergencies. The Department's fire fleet consists of 21 vehicles and two trailers located throughout the community. The average response time of the Arcadia Fire Department is four to five minutes. **Table 3-16** below identifies the Fire Department's activities for April 2021, which represents a "typical" month of calls.

The City anticipates that the Arcadia Fire Department will be able to serve future housing units, as designated by the 2021-2029 RHNA allocation.

Table 3-16: Arcadia Fire and Rescue Activity Report for April 2021	
Service Type	Total Monthly Occurrence
Fire	6
Rescue & Emergency Medical Service	254
Hazardous Condition (No Fire)	5
Service Call/Public Assistance	22
Good Intent Call	33

²⁵ City of Arcadia. (2010). General Plan: Safety Element. <https://www.arcadiaca.gov/Shape%20Arcadia/Development%20Services/general%20plan/Safety.pdf>, pg. 8-29.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-16: Arcadia Fire and Rescue Activity Report for April 2021

Service Type	Total Monthly Occurrence
False Alarm/False Call	38
Special Incident/Other	3
Overpressure Rupture/Explosion/Overheat	0
Sever Weather/Natural Disaster	2
Total Incidents	363
<i>Source: City of Arcadia Fire Department, Fire Department Weekly Report, compiled for April 2021.</i>	

Emergency Medical Services (EMS)

Arcadia's Emergency Medical Services responds to medical and trauma emergencies to initiate medical care to patients suffering from illness or injuries. Emergency medical and rescue services make up the majority of annual response incidents. As a result, Arcadia established a Paramedic Membership Program to minimize the cost to the community for emergency response as emergency medical and rescue services represents the majority of the City's incidents. The program allows enrollees to voluntarily pay a nominal membership to protect its members from out-of-pocket expenses for emergency paramedic and ambulance transport services provided within Arcadia. Since the program's inception, members have saved over one million dollars on emergency paramedic and ambulance services.

Police Services

The City of Arcadia Police Department is dedicated to providing the highest quality police service to enhance community safety, protect life and property and reduce crime. The Department is committed to working with the community to improve the quality of life throughout the community.

The Arcadia Police Department is made up of an Operations Division and Administration Division. The Operations Division is made up of a Patrol including Officers and Watch Commanders, S.W.A.T., Force Training Unit and Field Training Officers, a Reserve Officer Program, and the Traffic Enforcement Bureau. The Administrative Division includes Investigation (Detective Bureau), Crime Analysis, Laboratory/Property and Evidence, Records Bureau, Jail Operations, Dispatch, Community Affairs, and other trainings and programs.

L. Environmental Constraints

The City of Arcadia is located south of the Angeles National Forest and adjacent to the San Gabriel Mountains which exposes the City to several environmental conditions that affect how housing can be used and developed. The development of housing in the City is susceptible to several potential environmental constraints including geologic and seismic hazards, flooding, and fire hazards, all of which are detailed below.

Geologic and Seismic Hazards

According to the City of Arcadia's Safety Element and Section 4.6 of the General Plan EIR, Arcadia is located at the boundary between the Peninsular Ranges and the Transverse ranges. The San Gabriel Mountains adjacent to Arcadia are a part of the Transverse Ranges and are expressions of extensive faulting and movement of the plates that comprise the Earth's surface, with local tectonic activity pushing the mountains upward at rate of up to two centimeters per year. The San Gabriel Mountains' steep slopes



CITY OF ARCADIA 6TH CYCLE Housing Element Update

historically caused massive volumes of rocks and debris to flow down into the San Gabriel Valley during periods of heavy rain, creating the rocky alluvial soils that underlie Arcadia.

Seismic Hazards

The City of Arcadia, like the rest of southern California, is located within a seismically active region. Faults and earthquakes present direct hazards from fault rupture and ground shaking as well as indirect hazards, described below.

Faults

There are five faults or groundwater barriers that may be faults that underlie Arcadia:

- Raymond Fault
- Sierra Madre Fault Zone and Associated Groundwater Barriers
- Puente Hills (blind thrust)
- Upper Elysian Park (blind thrust)
- Eaton Wash groundwater barrier

From these five faults, the two potentially active faults that pass directly through Arcadia are the Sierra Madre and Raymond faults. In addition to these local faults, 20 faults have been identified within a 35-mile radius of City Hall. If any of the faults within the 35-mile radius were to achieve their maximum earthquake potential, the following faults represent the faults with the most potential for causing damage to the City due to ground shaking:

- Raymond Fault
- Sierra Madre Fault Zone and Associated Groundwater Barriers
- Puente Hills (blind thrust)
- Upper Elysian Park (blind thrust)
- Clamshell-Sawpit
- Verdugo Fault

Flooding

Similar to most of Southern California, Arcadia is subject to unpredictable seasonal rainfall. Every few years, the region is subjected to intense and sustained rainfall which could result in localized flooding. The Los Angeles County Department of Public Works has constructed regional flood and debris control facilities throughout the region, including Arcadia. Due to the combination of the regional and local storm drain system, no areas in Arcadia lie within a 100-year floodplain.

Fire Hazards

Wildland Fires

A wildland fire is an uncontrolled fire spreading through vegetative fuels that may expose or consume structures. Although not located in a wilderness area, the threat of a wildland fire in or near Arcadia is high due to the topography and vegetation in northern Arcadia, the threat of fire to hillside developments of the San Gabriel Mountains is of real concern. The City has targeted high risk areas and implemented fire mitigation strategies and policies for new development to keep the area clear of possible fire fuels and to provide emergency access.

Urban Fires



CITY OF ARCADIA 6TH CYCLE Housing Element Update

According to the City's Safety Element of the General Plan, urban fires accounted for less than four percent of the City's total incident responses in 2007, however the damage to residential structures were estimated at \$1.5 million. The Fire Department is focused on fire prevention and education to keep incident levels and damage low.

Mitigating Environmental Conditions

The proposed candidate housing sites (see Appendix A) have been chosen in a way that best mitigates environmental constraints. Sites in areas that were deemed at higher risk to fires, flooding, and seismic hazards were avoided in the selection process. Even with a conscious effort to avoid hazardous environmental conditions, there is still potential to be affected. Future housing development facilitated by the Housing Element Update will be subject to environmental review by the discretion of the City and other responsible agencies. The review process would further ensure that negative impact to the environment and environmental factors that could threaten residents are mitigated.

3. Affirmatively Furthering Fair Housing (AFFH)

Beginning January 1, 2019, AB 686 established new requirements for all California jurisdictions to ensure that local laws, programs, and activities affirmatively further fair housing. All Housing Elements due on or after January 1, 2021 must contain an Assessment of Fair Housing (AFH) consistent with the core elements of the analysis required by the federal Affirmatively Further Fair Housing Final Rule of July 16, 2015.

Fair housing is a condition in which individuals of similar income levels in the same housing market have like ranges of choice available to them regardless of race, color, ancestry, national origin, age, religion, sex, disability, marital status, familial status, source of income, sexual orientation, or any other arbitrary factor. Under State law, affirmatively further fair housing means "taking meaningful actions, in addition to combatting discrimination, that overcome patterns of segregation and foster inclusive communities free from barriers that restrict access to opportunity based on protected characteristics."

The Analysis of Fair Housing (AFH), prepared for the County of Los Angeles, examines local housing conditions, economics, policies and practices in order to ensure that housing choices and opportunities for all residents are available in an environment free from discrimination. The AFH assembles fair housing information, identifies any existing impediments that limit housing choice, and proposes actions to mitigate those impediments. The Regional AFH examines fair housing issues in the County's unincorporated areas and cooperating cities from 2019 to 2024, it includes additional fair housing issues and data for the City of Arcadia.²⁶

A. Needs Assessment

The AFH contains a Countywide analysis of demographic, housing, and specifically fair housing issues in the City of Arcadia. The City's demographic and income profile, household and housing characteristics, housing cost and availability, and special needs populations were discussed in previous **Section 2: Community Profile**.

Countywide AFH Outreach FY 2017

²⁶ 2017 Assessment of Fair Housing for the Community Development Commission and Housing Authority of the County of Los Angeles. Retrieved <http://file.lacounty.gov/SDSInter/bos/supdocs/116559.pdf>



CITY OF ARCADIA 6TH CYCLE Housing Element Update

As part of the Regional Analysis for the County, a series of regional discussion groups, Resident Advisory Board Meetings, community input meetings, and the 2017 Resident Fair Housing Survey were conducted.

Additionally, the County released a “2017 Fair Housing Survey” to residents in 2017. A total of 6,290 responses were received and it focused on displacement, perceived safety, rental increases, and discrimination. The survey was published in English, Russian, Armenian, Tagalog, Korean, Chinese, and Spanish and accessible through the City and County’s websites as well as through community meetings and mailings.

In addition, a Fair Housing Stakeholder Survey was conducted from January through April 2017 and collected a total of 108 responses. The Stakeholder survey focused on Fair Housing in the County, State and Federal Law, Fair Housing activities in the County and City of LA, Fair Housing in the public and private sectors. In addition, a separate Los Angeles County Planning and Zoning Survey was released from January through March 2017. The Survey presented 35 questions and elicited 49 responses.

No further fair housing outreach has been conducted by the City.

2021 – 2029 Housing Element Update Outreach

As part of the 2021-2029 Housing Element Update, the City conducted extensive public outreach activities beginning in March of 2021. These outreach efforts included Community Workshops, an online community survey, digital media and engagement, and noticed Public Hearings. All project materials, including summaries from community workshops and the draft public review document are available on the City’s website: <https://www.ArcadiaCA.gov/housing>. In addition to digital media and engagement, the City also utilized utility mailers to reach a broader group of the population.

The City has also conducted targeted outreach to the recipients of the CDBG Home Improvements Program – a program that serves lower-income individuals, residents at Naomi Gardens – an affordable housing complex, Assistance League of America, Foothill Unity Center, and Habitat for Humanity. The City engaged these various organizations to ensure that information regarding the Housing Element Update reached low-to moderate-income households and to allow these organizations an opportunity to comment on the various drafts released through the City’s Housing Element webpage.

The City also conducted additional outreach to the Arcadia Downtown Improvement Association, Arcadia Association of Realtors, Chamber of Commerce, HOA Board and ARB Chairs, Arcadia Chinese Association, and the Planning Commission. In addition, the City mailed letters to the Property Manager at Naomi Gardens, Habitat for Humanity, Foothill Unity Center and Assistance League of Arcadia, and individuals who subscribed to the Housing Element interested parties list which consists of 84 individuals.

A detailed overview of all outreach efforts is provided in **Appendix B: Community Engagement Summary** of this Housing Element.

Outreach for Persons Experiencing Homelessness

From November to December 2021, the City of Arcadia implemented a comprehensive census of Arcadia’s unhoused individuals. Teams consisting of staff from the Recreation and Community Services Department, Fire Department, and Police Department deployed to cover all 26 census tracts in Arcadia. Participation in the census was optional and those who did not wish to partake were simply counted. Over the two month period, census teams encountered 79 individuals experiencing homelessness within the City and 55 individuals participated in the survey. The census consisted of 33 questions. Information for homeless services was offered and distributed to all individuals experiencing homelessness.

Responses were collected in a survey data base and locations were manually noted and converted into geographic coordinates. Duplicate entries of individuals were removed by comparing names and age ranges. All responses are self-attestations.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

The report was presented to the City Council at their meeting of March 15, 2022. The City Council adopted the report and agreed to the following action items:

- Utilize PLHA funding to fund and support additional case workers from Union Station to connect homeless individuals to services. The City currently has one case worker and this funding will secure at least two additional case workers.
- Study the possibility of providing a shelter or tiny homes within the City or local region in several select areas.
- Provide additional information and mailers to all City residents on Homeless Diversion programs and our existing Homeless Diversion Program to keep people in their homes.

Compliance with State and Local Fair Housing Laws

Table 3-17: Compliance with State and Local Fair Housing Laws	
Law	Compliance
California Fair Employment and Housing Act (FEHA) establishes protections for employees against discrimination, retaliation and harassment in employment. All employment provisions of the FEHA anti-discrimination provisions apply to all employers with five or more full-time or part-time employees. In addition, the FEHA's anti-harassment provisions apply to all employers with only one or more employees.	Compliant.
Government Code section 65008 covers actions of a city, county, city and county, or other local government agency, and makes those actions null and void if the action denies an individual or group of individuals the enjoyment of residence, landownership, tenancy, or other land use in the state because of membership in a protected class, the method of financing, and/or the intended occupancy.	Compliant.
Government Code section 8899.50 requires all public agencies to administer programs and activities relating to housing and community development in a manner to affirmatively further fair housing and avoid any action that is materially inconsistent with its obligation to affirmatively further fair housing.	Compliant.
Government Code section 11135 et seq. requires full and equal access to all programs and activities operated, administered, or funded with financial assistance from the state, regardless of one's membership or perceived membership in a protected class.	Compliant. The City of Arcadia contracts with the Housing Rights Center to provide resources and workshops to increase fair housing resource awareness within the City.
Density Bonus Law (Gov. Code § 65915.)	Compliant. The City of Arcadia has a process for approving and implementing the Density Bonus Law has included a program to ensure compliance with the State Density Bonus Law.
Housing Accountability Act (Gov. Code §65589.5.) establishes limitations to a local	Compliant. The City of Arcadia is currently updating the City's Housing Element in order to



CITY OF ARCADIA 6TH CYCLE Housing Element Update

government's ability to deny, reduce the density of, or make infeasible housing development projects, emergency shelters, or farmworker housing that are consistent with objective local development standards and contribute to meeting housing need.	maintain compliance with the Housing Accountability Act that requires jurisdictions in the State to have an adopted housing element that successfully reaches their allocated housing goal. The City currently has adopted the 5 th Cycle Housing Element.
No-Net-Loss (Gov. Code § 65863) ensures development opportunities remain available throughout the planning period to accommodate a jurisdiction's regional housing need allocation (RHNA), especially for lower- and moderate-income households.	Compliant. The City of Arcadia is currently updating the City's Housing Element to maintain compliance with the No-Net-Loss (Gov. Code § 65863). The Element ensures the City would create positive net units. See Appendix A for more information.
Least Cost Zoning Law (Gov. Code § 65913.1) requires local agencies to designate and zone sufficient vacant land for residential use with "appropriate standards" to meet the housing needs of all segments of the population, including low and moderate income housing, as identified in the housing element.	Compliant. The City of Arcadia is currently updating the City's Housing Element to maintain compliance. The City of Arcadia has does not have a sufficient amount of vacant land that meets the "appropriate standards" for residential use.
Excessive Subdivision Standards (Gov. Code § 65913.2)	Compliant. The City of Arcadia is currently in compliance with the Excessive Subdivision Standard that prohibits the creation of laws and regulations that impose excessive standards on housing developments and utilities.
Limits on growth controls (Gov. Code § 65302.8.) ensures that if a county or city, including a charter city, adopts or amends a mandatory general plan element which operates to limit the number of housing units which may be constructed on an annual basis, such adoption or amendment shall contain findings which justify reducing the housing opportunities of the region.	Compliant. The City of Arcadia has not adopted any growth controls which limit the number of housing units that may be constructed on an annual basis.
Housing Element Law (Gov. Code, § 65583, esp. subds. (c)(5), (c)(10).) promotes and affirmatively furthers fair housing opportunities and promote housing throughout the community or communities for all persons regardless of race, religion, sex, marital status, ancestry, national origin, color, familial status, or disability, and other characteristics protected by the California Fair Employment and Housing Act (Part 2.8 (commencing with Section 12900) of Division 3 of Title 2), Section 65008, and any other state and federal fair housing and planning law.	Compliant. The City of Arcadia is currently updating the City's Housing Element to identify constraints to Fair Housing and Programs to affirmatively further Fair Housing opportunities.

Enforcement and Outreach

The City of Arcadia does not have their own housing authority and is served by the Los Angeles County Development Authority (LACDA). In the 2020-2021 FY, the Los Angeles County Development Authority issued approximately 772 housing vouchers to families in the County. In addition, LACDA funded 23 affordable housing developments that totaled 1,484 additional affordable housing units and allocated approximately \$150.1 million into affordable housing repair, maintenance, and development.²



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Los Angeles County jurisdictions are served by a variety of regional and local fair housing service providers, that investigate and resolve discrimination complaints, conduct discrimination auditing and testing, and education and outreach, including the dissemination of fair housing information such as written material, workshops, and seminars. These service providers also provide landlord/tenant counseling, which is another fair housing service that involves informing landlords and tenants of their rights and responsibilities under fair housing law and other consumer protection regulations, as well as mediating disputes between tenants and landlords. While the City of Arcadia does not have its own housing authority, it is served by the following fair housing organizations:

- Housing Rights Center (HRC)
- Legal Aid Foundation of Los Angeles (LAFLA)

LAFLA offers residents of Los Angeles County fair housing legal services. In 2020, more than 100,000 Los Angeles County residents received legal counsel through LAFLA. ¹

The City uses their Community Development Block Grant (CDBG) program to provide outreach for home improvements through the HRC. The HRC is the nation's largest non-profit civil rights organization dedicated to securing and promoting Fair Housing. HRC actively supports and promotes freedom of residence through education, advocacy, and litigation, to the end that all persons have the opportunity to secure the housing they desire and can afford, without regard to their race, color, religion, gender, sexual orientation, national origin, familial status, marital status, disability, ancestry, source of income or other characteristics protected by law.

The HRC distributes fair housing resources, offers in-person housing counseling for tenants and landlords, and has recently launched 'Project Place' that outlines the process of applying, finding and living in affordable housing in Los Angeles County.

In recent years, the HRC has performed the following in the region:

- Housing Counseling
- Discrimination Investigation & Disability Accommodations
- Community Workshops and Events
- Monthly Rental Listings

The City provides fair housing information regularly through code enforcement efforts and responses to housing questions. The City of Arcadia is committed to mitigating fair housing issues and discrimination in the community and increasing fair housing access and opportunity. Information is offered in English, Spanish and Chinese. All fair housing outreach is conducted by HRC and is not disseminated by the City.

(HUD) maintains a record of all housing discrimination complaints filed in local jurisdictions. These grievances can be filed on the basis of race, color, national origin, sex, disability, religion, familial status and retaliation. From January 1, 2006 to June 30, 2020, 130 fair housing complaints in Los Angeles County were filed with HUD.

FHEO Inquires by City (HUD, 2013-2021)

Figure 3-1 depicts Fair Housing Inquiries (FHEO) in the City of Arcadia from 2013 through 2021. It should be noted that inquiries are not official cases. Inquiries may have been dropped by the resident for a number



CITY OF ARCADIA 6TH CYCLE Housing Element Update

of reasons, and there is value to identify concerns that residents have about possible discrimination through the analysis of SED inquiries.

In the City of Arcadia, there were a total of 18 inquiries made over eight years, or 0.31 inquiries per one-thousand people. Of the 18, 11 were never followed up with. When inquiries are made, they are categorized into different protected classes such as disability, race, and religion among others. HUD reported one inquiry related to disability, three related to race, two related to familial status, and two related to national origin. Some inquiries may be classified in multiple protected groups.


In comparison to surrounding jurisdictions, Arcadia's inquiries per one-thousand people is higher than cities such as Sierra Madre (0.27 per one-thousand), El Monte (0.15 per one-thousand), and Temple City (0.03 per one-thousand). Surrounding cities generally fall under <0.5 inquiries per one-thousand people with exceptions for cities such as Irwindale (0.69 per one-thousand). Overall, the City of Arcadia has a relatively low amount of inquiries.

The City has not taken any enforcement actions or had any lawsuits as they relate to fair housing and have determined that there is no significant impact.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-1: FHEO Inquiries by City (HUD, 2013-2021)



Source: HUD, 2013-2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

County of Los Angeles: FHEO Cases- Total 2021


Figure 3-2 depicts the amount of Title VIII fair housing cases filed by FHEO from January 1, 2006 through June 30, 2020 in Los Angeles County. Cases are categorized into protected classes. Some of the classes such as race are more specifically broken down (i.e. Race- Asian). It should be noted that one case may fall into multiple protected classes.

In the 14 year data collection period, a total of 130 Title VIII fair housing cases have been filed. Of the 130, approximately 27 cases identified a racial bias as a barrier to fair housing, 86 identify a disability bias, and 9 identify a familial status bias. The majority of cases, approximately 66 percent, had identified a disability bias as a barrier to fair housing. Surrounding counties such as Ventura, San Bernardino, and Orange County also reflected this pattern.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-2: FHEO Cases by Population (HUD, 2006-2020)





CITY OF ARCADIA 6TH CYCLE Housing Element Update

B. Fair Housing Issues

With the legal framework of federal and state laws based on the guidance provided by the HUD Fair Housing Planning Guide, impediments to fair housing choice can be defined as:

- Any actions, omissions, or decisions taken because of race, color, ancestry, national origin, age, religion, sex, disability, marital status, familial status, source of income, sexual orientation, or any other arbitrary factor which restrict housing choices or the availability of housing choices; or
- Any actions, omissions, or decisions which have the effect of restricting housing choices or the availability of housing choices on the basis of age, race, color, ancestry, national origin, age, religion, sex, disability, marital status, familial status, source of income, sexual orientation or any other arbitrary factor.

Through the outreach efforts and Countywide Analysis of Impediments conducted in 2018, the County identified the following fair housing impediments:²⁷

- Barriers to mobility
- Lack of affordable housing in a range of sizes
- Lack of sufficient accessible housing in a range of unit sizes
- Lack of sufficient publicly supported housing for persons with HIV/AIDS
- Land use and planning decisions restrict fair housing choice for persons with disabilities and affordable housing in general
- Presence of lead poisoning exposure
- Significant disparities in the proportion of members of protected classes experiencing substandard housing when compared to the total population
- Noise Pollution due to plan traffic from Los Angeles International Airport
- Poor land use and zoning situating sources of pollution and environmental hazards near housing
- Access to quality healthcare
- Food insecurity – access to healthy and nutritional food options
- Location and access to local businesses, especially in economically depressed areas
- Lack of information on affordable housing
- Increasing measures of segregation
- Discrimination in private rental and homes sales markets
- Access to financial services
- Lack of coordination with other Planning Processes and Programs to addressing contributing factors

C. Lending Patterns

Availability of financing affects a person's ability to purchase or improve a home. The analysis of the lending patterns and practices within a community or city help to identify persons who regularly experience disproportionate roadblocks to home ownership. **Table 3-18** below identifies the lending patterns by race

²⁷ County of Los Angeles. (2018). Analysis of Impediments. Available https://www.lacda.org/docs/librariesprovider25/community-development-programs/cdbgp/plans-and-reports/analysis-of-impediments/executive-summary---english.pdf?sfvrsn=20d667bc_2.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

and ethnicity, as well as income category for the Los Angeles-Long Beach-Glendale Metropolitan Statistical Area (MSA). According to the data, low income applicants (less than 50 percent of the MSA/MD median income) are more likely to have a loan application denied, the highest rates of denial were among Native Hawaiian/Pacific Islander (67 percent) and American Indian and Alaska Natives (58.3 percent). Across all income categories, applicants who identified as White had the highest rates of loan approvals, followed by applicants who identified as Hispanic or Latino.

Table 3-18: Disposition of Loan Applications by Race/Ethnicity – Los Angeles-Long Beach-Glendale MSA/MD

Applications by Race/Ethnicity	Percent Approved	Percent Denied	Percent Other	Total (Count)
LESS THAN 50% OF MSA/MD MEDIAN				
American Indian and Alaska Native	24.16%	57.30%	19.66%	178
Asian	36.54%	42.13%	23.50%	1,932
Black or African American	41.98%	28.82%	31.98%	2,120
Native Hawaiian or other Pacific Islander	20.33%	67.03%	14.29%	182
White	44.14%	30.93%	27.22%	11,384
Hispanic or Latino	39.00%	36.23%	27.28%	6,559
50-79% OF MSA/MD MEDIAN				
American Indian and Alaska Native	36.97%	43.28%	22.27%	238
Asian	44.31%	34.08%	27.98%	2,873
Black or African American	42.75%	32.23%	29.11%	2,367
Native Hawaiian or other Pacific Islander	22.83%	62.20%	17.32%	254
White	48.99%	28.31%	27.75%	14,902
Hispanic or Latino	44.63%	32.50%	27.81%	10,611
80-99% OF MSA/MD MEDIAN				
American Indian and Alaska Native	41.44%	33.33%	27.03%	111
Asian	51.15%	27.37%	27.37%	1611
Black or African American	47.33%	27.31%	28.91%	1124
Native Hawaiian or other Pacific Islander	35.48%	47.31%	20.43%	93
White	53.61%	23.41%	27.73%	6,887
Hispanic or Latino	50.10%	26.66%	27.42%	4,974
100-119% OF MSA/MD MEDIAN				
American Indian and Alaska Native	42.05%	32.10%	29.26%	352
Asian	60.54%	19.94%	25.90%	5,869
Black or African American	49.93%	23.72%	30.51%	3,579
Native Hawaiian or other Pacific Islander	40.89%	39.86%	21.65%	291
White	60.13%	17.88%	27.40%	25,143
Hispanic or Latino	56.43%	20.69%	27.80%	16,541
120% OR MORE OF MSA/MD MEDIAN				
American Indian and Alaska Native	48.91%	23.88%	30.08%	871
Asian	62.94%	14.28%	27.54%	35,764



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-18: Disposition of Loan Applications by Race/Ethnicity – Los Angeles-Long Beach-Glendale MSA/MD

Applications by Race/Ethnicity	Percent Approved	Percent Denied	Percent Other	Total (Count)
Black or African American	55.04%	19.47%	29.58%	11,611
Native Hawaiian or other Pacific Islander	54.18%	23.29%	27.19%	1052
White	64.87%	13.46%	25.98%	135,203
Hispanic or Latino	60.42%	16.47%	27.46%	42,722
<i>Source: Consumer Financial Protection Bureau, Disposition of loan applications, by Ethnicity/Race of applicant, 2019.</i>				

D. Hate Crimes

Hate crimes are violent acts against people, property, or organizations because of the group to which they belong or identify with. The Federal Fair Housing Act makes it illegal to threaten, harass, intimidate, or act violently toward a person who has exercised their right to free housing choice. In Los Angeles County there were a total of 103 reported hate crimes between 2014 and 2019, 15 of which were reported in 2019. However, no hate crimes were reported in the City of Arcadia.

E. Analysis of Federal, State, and Local Data and Knowledge

Summary of Local Knowledge Analysis

As part of the Housing Element, the City considers protected classes (such as race, ethnicity, income, etc.) and opportunity indicators as key factors in fair housing. Federal, State, and local data provide regional context, background information, and supportive data which helps the City to understand fair housing issues and to identify key fair housing factors for Arcadia. The section below uses available data to identify key trends and local contributing factors for fair housing. Key themes for each category of analysis are summarized in each section.

Integration and Segregation Patterns and Trends

Dissimilarity Index

The dissimilarity index is the most commonly used measure of segregation between two groups, reflecting their relative distributions across neighborhoods (as defined by census tracts). The index represents the percentage of the minority group that would have to move to new neighborhoods to achieve perfect integration of that group. An index score can range in value from 0 percent indicating complete integration, to 100 percent, indicating complete segregation. An index number above 60 is considered to show high dissimilarity and a segregated community.

It is important to note that segregation is a complex topic, difficult to generalize, and is influenced by many factors. Individual choices can be a cause of segregation, with some residents choosing to live among people of their own race or ethnic group. For instance, recent immigrants often depend on nearby relatives, friends, and ethnic institutions to help them adjust to a new country. Alternatively, when White residents leave neighborhoods that become more diverse, those neighborhoods can become segregated. Other factors, including housing market dynamics, availability of lending to different ethnic groups, availability of affordable housing, and discrimination can also cause residential segregation.

Figure 3-3 shows the dissimilarity between each of the identified race and ethnic groups in Arcadia and the Los Angeles-Long Beach metropolitan area's White populations. The higher scores indicate higher levels of segregation among those race and ethnic group. The Asian population within Arcadia make up the



CITY OF ARCADIA 6TH CYCLE Housing Element Update

majority of the City's population at approximately 61.6 percent according to 2019 American Community Survey (ACS) estimates, therefore the Asian population has the lowest dissimilarity since the population is more evenly integrated into the community than other racial groups.


The race and ethnic groups with the highest scores were Native Hawaiian (63.4) and American Indian (40.2). These scores correlate directly with the percentage of people within that racial or ethnic group that would need to move into a predominately White census tract in order to achieve a more integrated community. For instance, 63.4 percent of the Native Hawaiian population would need to move into predominately White census tract areas to achieve "perfect" integration or 40.2 percent of the American Indian population would need to move into the predominantly White census tract areas for perfect integration. While a score of 60 or higher typically indicates a segregated area, if a group's population is less than 1,000, the dissimilarity index may be high even if the group's members are evenly distributed throughout the area. It is important to note that the Native Hawaiian population includes a total of 29 people and the American Indian population is a total of 65 persons out of Arcadia's total population of 53,054.

The Los Angeles-Long Beach metro area is predominantly White (54.4 percent of the total population), while Arcadia's White population only makes up approximately 30.7 percent of the City's total population. Arcadia's racial and ethnic groups are more evenly spread out than the Los Angeles-Long Beach metropolitan area, and therefore the figure shows that Arcadia has lower dissimilarity in every racial and ethnic category than the metro area.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-3: Dissimilarity Index with Whites, City of Arcadia



Source: Census Scope. Available at https://www.censusscope.org/us/s6/p2462/chart_dissimilarity.html. Accessed on November 10, 2021.

Predominant Racial and Ethnic Groups

A predominant population is a racial or ethnic group that makes up a main proportion of the population. Predominant populations are important to identify for a number of reasons when assessing fair housing constraints. Populations made up of predominantly people of color have been shown to be underserved at a higher rate than predominantly White communities according to the National Equity Atlas, so it is important that these communities are identified and prioritized.²⁸

²⁸ National Equity Atlas.(2019). Neighborhood Poverty. Available at https://nationalequityatlas.org/indicators/Neighborhood_poverty#/.




CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-4 display pockets of predominantly Asian populations throughout the census tracts in Arcadia. Northern Arcadia has lower proportions of Asian residents when compared to central and eastern Arcadia. Communities to the southwest of the City are predominantly Asian. Additionally, there are large predominantly Asian communities to the southeast of Arcadia in cities such as Chino Hills and Diamond Bar. Compared to the rest of the Los Angeles-Long Beach Metropolitan Statistical Area, Arcadia and these communities have higher proportions of Asian populations.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-4: Asian Population by Region (U.S. Census Bureau's SF1 and TIGER data sets for 2010)



Source: U.S. Census Bureau's SF1 and TIGER data sets for 2010



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Low Income Community Segregation

Income segregation is another common type of segregation that can occur when federal, state, and local subsidized programs fail to construct affordable housing in high-resource neighborhoods. Neighborhoods with lower median incomes tend to have less resources, poorer school districts, and higher rates of health issues related to their environments. In this analysis, persons identified as low and moderate income are determined based on the area's median income.


Figure 3-5 shows a map of Arcadia's concentration of low and moderate income communities. The areas portrayed in darker shades represents a higher concentration of low to moderate incomes. The northern block groups of the City had a lower proportion of people in the low to moderate income brackets, indicating that residents of this part of the City had relatively high incomes. The southern blocks appeared to have more people that were identified within the low to moderate income groups, however the concentration rarely exceeds more than 50 percent of people. There are two census tracts (Census Tract 4307.24 and 4325.00) that have a concentration of approximately 55.8 and 57.5 percent of people with low to moderate incomes, which is the highest proportion of low to moderate income populations in the City.

Outside of the City limits, jurisdictions to the south typically had higher concentrations of low to moderate income residents. For example, towards the southeast edge of the City, there is a higher concentration (75 to 100 percent) of people within the Santa Fe Dam Open Space Area fall in the low to moderate income group. Overall, tract groups within Arcadia were mostly composed of lower concentrations of people (25 to 50 percent) that made low to moderate incomes, indicating that Arcadia residents had incomes that were relatively high when compared to surrounding areas with the exception of tract 4307.24. Compared to the rest of the region, Arcadia has a low concentration of low to moderate income households. Most communities to the south of the City, such as the City of Los Angeles, have denser populations of low to moderated income households. Overall, Arcadia is made up of relatively high incomes compared to communities to the south and east.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-5: Low to Medium Income Population Tract in Arcadia (ACS, 2015)




Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2015



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-6: Low to Medium Income Population Tract in the Region (ACS, 2015)



Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2015



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Familial Status: Single Parent, Female Headed Households

Single parent, female headed households are of special interest not only because of their unique family structure, but it has been demonstrated that these households have significantly less access to economic stability, home stability, and crucial resources. ²⁹ **Figure 3-7** displays the concentration of single parent, female headed households with children in Arcadia and the surrounding region. Arcadia and communities immediately surrounding the City, are typically characterized by less than 20 percent of children living in a single parent, female headed household. There are two Census tracts (Census Tract 4307.23 and Census Tract 4307.24) in Arcadia that show higher proportions of children in single parent, female headed households. Both census tracts show that approximately 20 to 40 percent of children live in single parent, female headed households. As shown in

Figure 3-5 above, Census Tract 4307.24 has the second highest proportion of low to moderate income earning residents in the City.


Regionally, Arcadia and communities to the north of the City have lower proportions of census tracts with high concentrations of single mothers. Single mothers are generally lower income than their single father counterparts and are more likely to live in lower income neighborhoods since housing is more affordable. To the northwest, there are higher concentrations of children living with single mothers in communities near Altadena and Pasadena. Communities to the southwest and southeast such as the City of Los Angeles, El Monte and Temple City have higher concentrations of single mothers with children. These communities are also generally lower income compared to Arcadia as seen above. Overall, Arcadia has a low proportion of single mothers with children within the City.

²⁹ Mather, Marc PhD. (2010). U.S. Children in Single-Mother Families. Available at <https://www.prb.org/wp-content/uploads/2010/05/05152010-single-motherfamilies.pdf>.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-7: Concentration of Children in Single Parent, Female Headed Households in Arcadia (ACS, 2019)




Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-8: Concentration of Children in Single Parent, Female Headed Households in the Region (ACS, 2019)



Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019



CITY OF ARCADIA 6TH CYCLE Housing Element Update


Figure 3-10 below displays the proportions of local populations that have disability. The City of Arcadia generally has a low proportion of the population with a disability (less than 10 percent in most tracts). There are four census tracts that have higher proportions (approximately 10 to 20 percent) of persons with disabilities—Census Tract 4307.21, 4313, 4318, and 4325. Of these tracts, Census Tract 4325 is also characterized as one of the two census tracts in Arcadia that has a higher proportion of people that earn low to moderate incomes.

Figure 3-9 and **Figure 3-10** show the differences in disabled population densities in the early 2010s and more recent years (2019). It appears that over time, the concentration of people with disabilities increased specially in central and southern Arcadia. **Figure 3-11** and **Figure 3-12** show this change over time in a regional context. It appears that the region experienced an overall increase in census tracts that had higher proportions of people with disabilities over time. In the 2010-2014 map, Arcadia has does not have a particularly dense population of people with disabilities, however as mentioned, central and southern Arcadia experienced an increase in density of persons with disabilities by 2019. Compared to the greater region, Arcadia has a moderate level of persons with disabilities and while the density of persons with disabilities increased, Arcadia still has a lower density of persons with disabilities. Communities such as Sierra Madre and Kinneloa Mesa have higher proportions of persons with disabilities, but the largest population appears in to the southwest and southeast in communities like Los Angeles, West Covina, and Montebello. These communities have historically had higher densities of persons with disabilities.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-9: Disability Population in Arcadia (ACS, 2010-2014)



Legend

--- City Boundary

Population with a Disability (Tract) - ACS (2010-2014)

Percent of Population with a Disability




Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2010-2014



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-10: Disability Population in Arcadia (ACS, 2019)




Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-11: Disability Population in the Region (ACS, 2010-2014)




Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2010-2014



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-12: Disability Population in the Region (ACS, 2019)




Legend

--- City Boundary

Population with a Disability (Tract) - ACS (2015-2019)

Percent of Population with a Disability





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019 Summary of Segregation and Integration Factors

The intent of the segregation and integration portion of the AFFH is meant to inform future policy and actions that the City can take to reduce segregation and increase integration of protected groups. The analysis has identified the following as possible constraints to providing fair housing:

- While Arcadia is generally an affluent community, residents in the southern portion of the City are more likely to make a low to moderate income when compared to those that live in the northern part of the City. This may indicate a lack of affordable housing in the northern portions of the City, which hinders further integration of lower income families throughout the community.
- Census Tracts 4307.23 and 4307.24 have a higher concentration of single parent, female headed households with children, suggesting that there is some sort of barrier, whether it be financial or social, that prevents these families from integrating into the broader community.
- Persons with disabilities tend to live in the southern portion of Arcadia, suggesting that there may be a fair housing barrier or social barrier that is preventing these communities from integrating further into the community.

Racially or Ethnically Concentrated Areas of Poverty (R/ECAP)

To assist communities in identifying racially/ethnically concentrated areas of poverty (R/ECAPs), HUD has developed a census-tract based definition of R/ECAPs. The definition involves a racial/ethnic concentration threshold and a poverty test. The racial/ethnic concentration threshold is straightforward: R/ECAPs must have a non-white population of 50 percent or more. Regarding the poverty threshold, Wilson (1980) defines neighborhoods of extreme poverty as census tracts with 40 percent or more of individuals living at or below the poverty line. Because overall poverty levels are substantially lower in many parts of the country, HUD supplements this with an alternate criterion. Thus, a neighborhood can be a R/ECAP if it has a poverty rate that exceeds 40% or is three or more times the average tract poverty rate for the metropolitan area, whichever threshold is lower.

Location of residence can have a substantial effect on mental and physical health, education opportunities, economic opportunities. Urban areas that are more residentially segregated by race and income tend to have lower levels of upward economic mobility than other areas. Research has found that racial inequality is thus amplified by residential segregation. However, these areas may also provide different opportunities, such as ethnic enclaves providing proximity to centers of cultural significance, or business, social networks and communities to help immigrants preserve cultural identity and establish themselves in new places. Overall, it is important to study and identify these areas in order to understand patterns of segregation and poverty in a City.

Figure 3-13 below displays the R/ECAP analysis of Arcadia and immediately surrounding communities. The HUD data available does not provide information specific to the City of Arcadia, thus a broader more regional approach was taken, as shown in the map. The figure shows there are no pockets of racially or ethnically concentrated areas of poverty within Arcadia. However, there is a R/ECAP in El Monte, south of Arcadia. While the City has no R/ECAP areas, there are still concentrated areas of poverty in surrounding communities; therefore, the City is committed to increasing housing mobility opportunities for persons outside the City or in Los Angeles County as a whole. **Chapter 10: Implementation Plan** of this Housing Element outlines housing opportunity, affordable housing, and fair housing strategies to increase opportunities to all households.

Figure 3-14 below identifies low poverty index with race/ethnicity and R/ECAPs in Arcadia, and the overall Northeast Los Angeles County region. The low poverty index captures the depth and intensity of poverty in



CITY OF ARCADIA 6TH CYCLE Housing Element Update


a given neighborhood. The index uses both family poverty rates and public assistance receipt, in the form of cash-welfare, such as Temporary Assistance for Needy Families (TANF). The poverty rate and public assistance for neighborhoods are determined at the census tract level, and the higher the score, the less exposure to poverty in a neighborhood. The map identifies the R/ECAP and a few surrounding neighborhoods, to the south and southwest. The figure identifies R/ECAP areas (outlined in red) concentrated in the City of Los Angeles.

The map also shows that there are R/ECAPs in areas bordering the Angeles National Forest and in Central Los Angeles near Downtown. Overall, the City of Arcadia is a high income area. The City should consider the impact of high cost of housing and higher annual incomes on lower income households. The current financial circumstance combined with the recent housing boom can create displacement through economic pressures, where lower income households need to look for affordable housing outside of the City.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-13: Local R/ECAP Analysis (HUD 2009-2013, TCAC 2021)



Legend

- City Boundary
- TCAC Area of High Segregation and Poverty 2021 (Tract)

Racially or Ethnically Concentrated Areas of Poverty (R/ECAPs) - (HUD, 2009 - 2013)

- 0 - Not a R/ECAP
- 1 - R/ECAP Area



0 0.75 1.5 Miles



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Source: HUD, 2009-2013, TCAC, 2021


R/ECAPs Over Time

Over time, R/ECAPs can move or expand into new areas. **Figure 3-14** below shows R/ECAPs in the Los Angeles region from 2009-2013. Compared to **Figure 3-13** above, there are fewer R/ECAPs in the region overall. It appears that over time, central and northern Los Angeles have seen an influx in R/ECAPs. This suggests possible increases of segregation between communities based on race, income, and other protected characteristics over time. Although there are not and have not been R/ECAPs within Arcadia in recent years, the City should consider the impact of high cost of housing and higher annual incomes on lower income households regionally.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-14: Regional R/ECAP Analysis (HUD 2009-2013, TCAC 2021)



Source: HUD, 2009-2013, TCAC, 2021



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Summary of R/ECAP

Racially and Ethnically Concentrated Areas of Poverty (R/ECAPs) are geographic areas with significant concentrations of poverty and minority populations. While there are no R/ECAPs within the City of Arcadia, ~~the~~ the number of R/ECAPs have been increasing in the Los Angeles Metropolitan Area over time. An absence of R/ECAPs does not confirm the presence of rich, predominantly White areas nor does it confirm that there is an absence of ~~low-income~~ low-income areas within the ~~City~~ city. -Identifying R/ECAPS facilitates an understanding of entrenched patterns of segregation and poverty due to the legacy effects of historically racist and discriminatory housing laws. Racially or Ethnically Concentrated Areas of Poverty have long been analyzed and reviewed as a contributing factor to segregation.

Racially Concentrated Areas of Affluence (RCAs)

Racially Concentrated Areas of Affluence (RCAs) are defined by the HUD as communities with a large proportion of affluent and non-Hispanic White residents. ~~Racially or Ethnically Concentrated Areas of Poverty have long been analyzed and reviewed as a contributing factor to segregation. However, patterns~~ Patterns of segregation in the United States show that of all racial groups, Whites are the most severely segregated.³⁰ Research done by the HUD also identifies segregation of affluence to be greater than the segregation of poverty. Racial and economic segregation can have significant effects on respective communities, including but not limited to, socioeconomic disparities, educational experiences and benefits, exposure to environmental conditions and crime, and access to public goods and services.

Data used in the analysis of Racially Concentrated Areas of Affluence (RCAA) is from the 2012-2016 American Community Survey and measured at the census tract level. The definition for an RCAA is a census tract in which 80 percent or more of the population is White and has a median income of at least \$125,000. The nationwide RCAA analysis identifies the following:

- RCAA tracts have more than twice the median household income of the average tract in their metro area.
- Poverty rates in RCAAs are significantly lower and are, on average about 20 percent of a typical tract.
- RCAAs tracts are more income homogenous than R/ECAPs.
- The average RCAA is about 57 percent affluent, whereas the average R/ECAP had a poverty rate of 48 percent.
- The typical RCAA tract has a rate of affluence 3.2 times that of a typical tract, whereas R/ECAPs on average had a poverty rate 3.2 times that of a typical tract

~~Overall, RCAAs may represent a public policy issue to the extent that they have been created and maintained through exclusionary and discriminatory land use and development practices. Postwar patterns of suburbanization in many metropolitan areas were characterized by White communities erecting barriers to affordable housing and engaging in racially exclusionary practices.~~³¹ To identify these areas in Arcadia, this analysis examines census tracts with a population that is at of at least 50 percent White with a median income over \$100,000. ~~While none~~ None of Arcadia's census tracts have a population greater than 50 percent White, but the ~~City~~ city has one census tract with a median income over \$100,000. **Figure 3-15**

³⁰ Racially Concentrated Areas of Affluence: A Preliminary Investigation. University of Minnesota. Edwards Goets, Damiano, Williams. 2019.

³¹ ~~Ibid.~~



CITY OF ARCADIA 6TH CYCLE Housing Element Update

below shows that there are no census tracts in Arcadia that meets both the income and race threshold for the tract to be considered an RCAA.

While there are no Racially Concentrated Areas of Affluence within the City of Arcadia, there is a concentrated area of affluence just outside the north border of Arcadia in the northern portion of the City. ~~These communities~~ The areas to the north meet both the racial and economic criteria to be considered RCAAs. Although these areas are not within the ~~City~~ city, the northern portion of Arcadia could reflect a transitional al ~~area~~ where the ~~as the~~ concentration of the Asian community is ~~lower~~ lower than the rest of city, and the portion of white residents ~~increases~~ is higher. This transition area of northern Arcadia may face different issues than the rest of the city with housing availability and affordability because an RCAA is located just outside the northern boundary. ~~No lower income housing sites have been identified in this area due to potential fire hazards in the hillsides that pose safety hazard.~~

~~Regionally, the~~ Communities only potential RCAAs nearby are those to the north. ~~Communities~~ to the south of Arcadia are primarily Non-White and typically have lower median incomes. While Arcadia is a generally affluent ~~area, the~~ area, the high proportion of Non-White residents prevents it from being identified as an RCAA by HCD's definition.

~~While the City of Arcadia does not have any RCAAs, there are a number of Census Tracts north of the City that have been identified as RCAAs. Table 3-19 below shows the local (Arcadia) and regional (Los Angeles County) for context for the median household incomes of white residents. The City is aware of the RCAA to the north, but has not proposed affordable housing in the north due to the fact that the Northern portion of the City is listed as a Very High Fire Hazard Severity Zone and is not suitable for higher density affordable housing.~~

Table 3-19: RCAAs – Median Household Income by Race, Arcadia and Los Angeles

<u>Race</u>	<u>County</u>		<u>Los Angeles County</u>	
	<u>Arcadia</u>			
	<u>Median Income</u>	<u>Population</u>	<u>Median Income</u>	<u>Median Income</u>
<u>White</u>	<u>\$86,581</u>	<u>33.6%</u>	<u>\$75,422¹</u>	<u>51.3%</u>
<u>All Households</u>	<u>\$93,574</u>	<u>--</u>	<u>\$68,044</u>	<u>--</u>


Notes: 1. Median income in the past 12 months (in 2019 inflation-adjusted dollars)

Source: American Community Survey, 5-Year Estimates, 2019.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-15: RCAA in Arcadia (U.S. Census Bureau's SF1 and TIGER data sets for 2010, ACS 2019)




Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019, [U.S. Census Bureau's SF1 and TIGER data sets for 2010](#) [AFFH Data Viewer](#)



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-16: RCAA in Arcadia (U.S. Census Bureau's SF1 and TIGER data sets for 2010, ACS 2019)



Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019, [U.S. Census Bureau's SF1 and TIGER data sets for 2010](#) [AFFH Data Viewer](#)



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Disparities in Access to Opportunity

The UC Davis Center for Regional Change and Rabobank partnered to develop the Regional Opportunity Index (ROI) intended to help communities understand local social and economic opportunities. The goal of the ROI is to help target resources and policies toward people and places with the greatest need to foster thriving communities. The ROI incorporates both “people” and “place” components, integrating economic, infrastructure, environmental, and social indicators into a comprehensive assessment of the factors driving opportunity.

The ROI: People is a relative measure of people’s assets in education, the economy, housing, mobility/transportation, health/environment, and civic life as follows:

- **Education Opportunity:** Assesses people’s relative success in gaining educational assets, in the form of a higher education, elementary school achievement, and regular elementary school attendance.
- **Economic Opportunity:** Measures the relative economic well-being of the people in a community, in the form of employment and income level.
- **Housing Opportunity:** Measures the relative residential stability of a community, in the form of homeownership and housing costs.
- **Mobility/Transportation Opportunity:** Contains indicators that assess a community’s relative opportunities for overcoming rural isolation.
- **Health/Environment Opportunity:** Measures the relative health outcomes of the people within a community, in the form of infant and teen health and general health.
- **Civic Life Opportunity:** A relative social and political engagement of an area, in the form of households that speak English and voter turnout.

The ROI: Place is a relative measure of an area’s assets in education, the economy, housing, mobility/transportation, health/environment, and civic life.

- **Education Opportunity:** Assesses a census tract’s relative ability to provide educational opportunity, in the form of high-quality schools that meet the basic educational and social needs of the population.
- **Economic Opportunity:** Measures the relative economic climate of a community, in the form of access to employment and business climate.
- **Housing Opportunity:** Measures relative availability of housing in a community, in the form of housing sufficiency and housing affordability.
- **Health/Environment Opportunity:** A relative measure of how well communities meet the health needs of their constituents, in the form of access to health care and other health-related environments.
- **Civic Life Opportunity:** Measures the relative social and political stability of an area, in the form of neighborhood stability (living in same residence for one year) and US citizenship.

Table 3-20 and **Figure 3-17** show the following key findings:

- The City has high rates of high school graduation rates as well as high math and English proficiency. Arcadia also has higher rates of college educated adults and overall higher levels of UC and CSU eligibility than the County and State.
- Residents of Arcadia experience high employment as well as higher levels of minimum basic income. Job availability, quality, and growth are all at lower levels in Arcadia when compared to the County and State rates, however, the difference is not significant.
- While homeownership rates are higher in the City of Arcadia than in the County and State, levels of cost burden are similar to the state at about 53 percent. The County of Los Angeles has a lower



CITY OF ARCADIA 6TH CYCLE Housing Element Update

housing cost burden when compared to both the City and the State. Housing adequacy is higher in the City and affordability is lower than the County and State.

- Vehicle availability is higher in Arcadia while commute times are lower than the County and State. Residents of the City also experience higher rates of internet access.
- Overall health and environmental opportunities are similar between the City, County and State. Although, Arcadia has lower rates of teen pregnancy and less years of life lost and higher access to healthcare.
- Voting rates in Arcadia are lower than in the State, but slightly higher than the County. Rates of English speakers are slightly lower than the State and higher than the County. The rate of US Citizenship is the same as the State and is higher in the City than the County.

Table 3-20: Local, County and State Regional Opportunity Indicators for Place and People

ROI Indicator		Arcadia	Los Angeles County	California
Education	People			
	College Educated Adults	62%	35%	38%
	Math Proficiency	90%	70%	70%
	English Proficiency	88%	63%	65%
	Elementary Truancy	12%	25%	24%
	Place			
	High School Graduation Rate	98%	78%	83%
	UC/CSU Eligibility	70%	40%	41%
	Teacher Experience	58%	43%	36%
	High School Discipline Rate	0%	4%	6%
Economic	People			
	Employment Rate	94%	90%	89%
	Minimum Basic Income	79%	59%	64%
	Place			
	Job Availability	634.50	716.96	701.75
	Job Quality	35%	39%	40%
	Job Growth	1%	2%	3%
Housing	Bank Accessibility	0.33	0.22	0.24
	People			
	Home Ownership	62%	48%	55%
	Housing Cost Burden	54%	47%	52%
	Place			
	Housing Adequacy	96%	86%	91%
Mobility	Housing Affordability	0.11	0.15	0.19
	People			
	Vehicle Availability	92%	83%	86%
	Commute Time	51%	53%	60%
Health and	Internet Access	4.91	4.34	4
	People			
	Infant Health	96%	95%	95%
	Birth to Teens	1%	7%	7%
	Years of Life Lost	17.48	27.93	29.84
		Place		




CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-20: Local, County and State Regional Opportunity Indicators for Place and People

ROI Indicator		Arcadia	Los Angeles County	California
	Air Quality	12.52	11.89	10.01
	Prenatal Care	83%	83%	83%
	Access to Supermarket	53%	61%	53%
	Health Care Availability	2.09	2.02	1.76
Civic Life	People			
	Voting Rates	25%	24%	31%
	English Speakers	87%	83%	88%
	Place			
	US Citizenship	83%	77%	83%
	Neighborhood Stability	89%	87%	85%

Source: UC Davis Center for Regional Change and Rabobank, 2014.

Figure 3-17: Local and State Regional Opportunity Indicators for Place and People



Source: UC Davis Center for Regional Change and Rabobank, 2014.

Regional Opportunity Index



CITY OF ARCADIA 6TH CYCLE Housing Element Update


Figure 3-18 identifies the achievement levels that persons living within the City have and **Figure 3-20** displays the opportunity that different census tracts can provide. As shown in **Figure 3-18** and **Figure 3-20** below, the majority of Arcadia is classified as a high opportunity zone with pockets of lower opportunity at the southern end of the City and mid-eastern boundary. This indicates a high level of relative opportunities that people are able to achieve as well as a high level of relative opportunities that Arcadia provides.

Compared to the greater region, Arcadia generally has more opportunities. As shown below, areas southwest and southeast of the City have access to less opportunities. Communities such as the city of Los Angeles, Montebello, West Covina, and more are generally areas that do not have census tracts with high opportunities in regard to people or place. Previously, these areas were identified as predominantly Non-White and lower income (**Figure 3-5** and **Figure 3-15**). The combination of these factors could lead to less available opportunities and resources in the areas. Areas north of the City, tend to have greater access to opportunities, which reflects the economic and racial makeup of these communities. Overall, the City of Arcadia has access to a high amount of resources compared to many other communities in the region.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-18: Regional Opportunity Index, People – City of Arcadia




Source: UC Davis Center for Regional Change and Rabobank, 2014



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-19: Regional Opportunity Index, People – Region




Source: UC Davis Center for Regional Change and Rabobank, 2014.



CITY OF ARCADIA 6TH CYCLE Housing Element Update


Figure 3-20: Regional Opportunity Index, Place – City of Arcadia





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-21: Regional Opportunity Index, People – City of Arcadia



Source: UC Davis Center for Regional Change and Rabobank, 2014.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Tax Credit Allocation Committee (TCAC) Opportunity Area Maps

Additionally, the Department of Housing and Community Development (HCD) together with the California Tax Credit Allocation Committee (TCAC) established the California Fair Housing Task Force to provide research, evidence-based policy recommendations, and other strategic recommendations to HCD and other related State agencies/departments to further the fair housing goals (as defined by HCD). The Task force developed the TCAC/HCD opportunity Area Maps to understand how public and private resources are spatially distributed. The Task Force defines opportunities as pathways to better lives, including health, education, and employment. Overall, opportunity maps are intended to display which areas, according to research, offer low income children and adults the best chance at economic advancement, high educational attainment, and good physical and mental health.

According to the Task Force's methodology, the tool allocates the 20 percent of the tracts in each region with the highest relative index scores to the "Highest Resource" designation and the next 20 percent to the "High Resource" designation. Each region then ends up with 40 percent of its total tracts as "Highest" or "High" resource. These two categories are intended to help State decision-makers identify tracts within each region that the research suggests low income families are most likely to thrive, and where they typically do not have the option to live—but might, if given the choice. As shown in **Figure 3-22** below, most of Arcadia is classified with the highest resource designation with just the southern portion of the City designated as high to moderate resource. Communities within the southern portion of the City and south of the City are more likely to be lower income and predominantly populations of color. The City of Arcadia is committed to exploring programs and avenues to improve housing access and opportunity to both existing residents, future residents, and households in nearby areas.


Central and south Los Angeles communities are generally characterized by low access to resources. In some areas, the communities are characterized by high segregation and poverty. Currently there are no areas characterized as low resource nor high segregation and poverty within the City of Arcadia. Overall, the City and surrounding communities are relatively high resource compared to the greater Los Angeles area.

Opportunity indicators included in the AI also help inform communities about disparities in access to opportunity. HUD-provided index scores are based on nationally available data sources and assess residents' access to key opportunity assets in Los Angeles County. However, these indices are only available to Entitlement Jurisdictions (with population over 50,000 and receiving CDBG funds from HUD). For Urban County jurisdictions for which a HUD-provided index is not provided, a similar analysis as that provided by the indices was conducted using information for the region.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-22: TCAC/HCD Opportunity Map – City of Arcadia



Source: California Tax Credit Allocation Committee and Department of Housing and Community Development, 2020.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Opportunity Indicators

For many households, access to neighborhoods with higher levels of opportunity can be more difficult due to discrimination and when there may not be a sufficient range and supply of housing in such neighborhoods. In addition, the continuing legacy of discrimination and segregation can impact the availability of quality infrastructure, educational resources, environmental protections, and economic drivers, all of which can create disparities in access to opportunity.

HUD developed the opportunity indicators to help inform communities about disparities in access to opportunity, the scores are based on nationally available data sources and assess resident's access to key opportunity assets in each jurisdiction. As data for Arcadia as a local jurisdiction was not available, data for the Los Angeles-Long Beach-Anaheim Region was used for this analysis. **Table 3-19** provides the index scores (ranging from zero to 100) for the following opportunity indicator indices:

- **Low Poverty Index:** The low poverty index captures poverty in a given neighborhood. The poverty rate is determined at the census tract level. The higher the score, the less exposure to poverty in a neighborhood, the maximum score being 100. For example, a low poverty index score of 100 means no exposure to poverty.
- **School Proficiency Index:** The school proficiency index uses school-level data on the performance of 4th grade students on State exams to describe which neighborhoods have high-performing elementary schools nearby and which are near lower performing elementary schools. The higher the score, the higher the school system quality is in a neighborhood, the maximum score being 100. For example, a school proficiency index score of 100 means immediate access to schools with the highest testing performance.
- **Labor Market Engagement Index:** The labor market engagement index provides a summary description of the relative intensity of labor market engagement and human capital in a neighborhood. This is based upon the level of employment, labor force participation, and educational attainment in a census tract. The higher the score, the higher the labor force participation and human capital in a neighborhood, the maximum score being 100. For example, a labor market engagement index score of 100 means the maximum eligible population is employed and a part of the labor market in the community.
- **Transit Trips Index:** This index is based on estimates of transit trips taken by a family that meets the following description: a three-person single-parent family with income at 50% of the median income for renters for the region (i.e. the Core-Based Statistical Area (CBSA)). The higher the transit trips index, the more likely residents in that neighborhood utilize public transit. The maximum score being 100; for example, a transit trips index score of 100 means immediate access to schools with the highest testing performance.
- **Low Transportation Cost Index:** This index is based on estimates of transportation costs for a family that meets the following description: a three-person single-parent family with income at 50 percent of the median income for renters for the region/CBSA. The higher the index, the lower the cost of transportation in that neighborhood.
- **Jobs Proximity Index:** The jobs proximity index quantifies the accessibility of a given residential neighborhood as a function of its distance to all job locations within a region/CBSA, with larger employment centers weighted more heavily. The higher the index value, the better the access to employment opportunities for residents in a neighborhood.
- **Environmental Health Index:** The environmental health index summarizes potential exposure to harmful toxins at a neighborhood level. The higher the index value, the less exposure to toxins harmful to human health. Therefore, the higher the value, the better the environmental quality of a neighborhood, where a neighborhood is a census block-group.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-21 below displays the opportunity indices by race and ethnicity for persons in the Los Angeles-Long Beach- Anaheim region. Key findings from the opportunity indicators (shown below) include:

- There is moderate exposure to poverty among the population in the region, with the Hispanic population received the lowest poverty index at 35.53 indicating the greatest exposure to poverty.
- Additionally, the access to quality education system is low to moderate among all racial/ethnic groups. The Non-Hispanic White and Asian or Pacific Islander Populations experience the highest access to quality education (68.03 and 61.94 respectively) while the Non-Hispanic Black population experiences the lowest access to quality education (33.82).
- The region offers low to moderate labor and economic opportunity. The Non-Hispanic Black population has the lowest labor market index at 35.34 and the Non-Hispanic White population has the highest index at 67.43.
- Access to transportation is relatively high for all racial and ethnic groups within the region with index scores falling between 77 and 87.
- Additionally, transportation is considered affordable in the region with scores in the 70 range for all race and ethnic groups.
- The region offers low to moderate job proximity with scores ranging from 40 to 55. The White population experiences the nest access to employment opportunities in the region with a score of 54.59 while the Non-Hispanic Black population experiences has the lowest score (40.72).
- Across all race and ethnic groups there were very low environmental health index scores, meaning there is high exposure to harmful pollutants in the region. Each group has a score below 25, indicating poor environmental quality across the City.
- Persons of all race and ethnic groups who have an income below the federal poverty line experience each lower opportunity, higher exposure to income and education barriers and higher exposure to harmful pollutants, as well and lower access to affordable transportation.
- Persons of all race and ethnic groups who have an income below the federal poverty line in the region experienced a lower opportunity index score in all categories except for the Low Transportation Cost Index.

Table 3-21: Opportunity Indicators by Race and Ethnicity in the Los Angeles-Long Beach-Anaheim Region

	Low Poverty Index	School Proficiency Index	Labor Market Index	Transit Index	Low Transportation Cost Index	Jobs Proximity Index	Environmental Health Index
Total Population							
White, Non-Hispanic	65.19	68.03	67.43	77.63	73.13	54.59	21.35
Black, Non-Hispanic	36.07	33.82	35.34	87.25	79.02	40.72	11.92
Hispanic	35.53	39.72	35.73	86.48	77.78	43.70	12.36
Asian or Pacific Islander, Non-Hispanic	55.03	61.94	57.64	85.13	75.98	51.11	13.13
Native American, Non-Hispanic	48.40	50.70	48.58	81.04	75.36	45.88	17.68
Population below federal poverty line							
White, Non-Hispanic	53.66	60.62	59.62	83.19	78.51	56.98	18.46
Black, Non-Hispanic	24.12	28.03	26.41	88.34	81.07	36.90	11.74
Hispanic	25.05	33.70	29.50	89.09	80.94	44.63	10.63



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-21: Opportunity Indicators by Race and Ethnicity in the Los Angeles-Long Beach-Anaheim Region

	Low Poverty Index	School Proficiency Index	Labor Market Index	Transit Index	Low Transportation Cost Index	Jobs Proximity Index	Environmental Health Index
Asian or Pacific Islander, Non-Hispanic	45.45	57.59	51.41	88.58	80.61	52.88	11.05
Native American, Non-Hispanic	33.63	39.10	36.05	84.43	78.22	47.65	16.22

Note 1: Data Sources: Decennial Census; ACS; Great Schools; Common Core of Data; SABINS; LAI; LEHD; NATA

Note 2: Refer to the Data Documentation for details (www.hudexchange.info/resource/4848/affh-data-documentation).

Educational Opportunity

Arcadia has a relatively high score regarding education. The City of Arcadia is served by the Arcadia Unified School District, El Monte Union High and El Monte City Elementary School Districts. The majority of the City is provided public school by the Arcadia Unified School District³² while the southern portion of Arcadia is served by the El Monte School Districts.³³

Meeting UC/CSU Requirements: Arcadia Unified School District had an approximately 95 percent achievement rate in 2018-2019, which is significantly higher than both the state and El Monte Union High School District. In the 2019-2020 school year, the Arcadia Unified School District and the County's achievement dropped significantly while El Monte Union High and the State's achievement stayed relatively constant.

Overall, the schools that served Arcadia are generally high scoring compared to other local schools and the schools in the State. Arcadia schools generally spend more money per student than the State with the exception of Arcadia Unified School District.

Table 3-22 below shows a comparison of the school districts, the County and the State based on resources, enrollment, class sizes, and more. Some key difference between the school districts include:

- Arcadia has a relatively high score regarding education. The City of Arcadia is served by the Arcadia Unified School District.³⁴
- *Pupil to teacher ratio*: Arcadia Unified School District had the highest pupil to teacher ratio out of all three school districts, the County, and the State.
- *Funding*: Arcadia Unified School District spends the least amount of money per student when compared to the El Monte School Districts.
- *Free and Reduced-Priced Meals*: Only approximately 26 percent of students in the Arcadia Unified School District receive free or reduced-price meals while approximately 88 to 93 percent of students in the El Monte School Districts receive subsidized meals. In the State of California, approximately 60 percent of students receive subsidized meals and about 68 percent of students in the County receive them.
- *Cohort Dropout Rates*: Approximately 11 percent of students in 2018-2019 dropped out before graduating in the El Monte Union High School District while approximately less than one percent of

³² Arcadia Unified School District. School Boundaries. Available at <https://www.ausd.net/apps/pages/ArcadiaUnifiedSchoolBoundariesMap>. Accessed on December 2, 2021.

³³ El Monte Union High School District. SchoolSite Locator. Available at <http://apps.schoolsitelocator.com/?districtcode=47473>. Accessed on December 2, 2021.

³⁴ El Monte Union High School District. SchoolSite Locator. Available at <http://apps.schoolsitelocator.com/?districtcode=47473>. Accessed on December 2, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

students in the Arcadia Unified School District dropped out. The rate of El Monte Union High students dropped out to approximately 5 percent in 2019-2020, which was still above the rate at which students dropped out in Arcadia Unified School District.

- *Meeting UC/CSU Requirements:* Arcadia Unified School District had an approximately 95 percent achievement rate in 2018-2019, which is significantly higher than both the state and El Monte Union High School District. In the 2019-2020 school year, the Arcadia Unified School District and the County's achievement dropped significantly while El Monte Union High and the State's achievement stayed relatively constant.

Overall, the schools that served Arcadia are generally high scoring compared to other local schools and the schools in the State. Arcadia schools generally spend more money per student than the State with the exception of Arcadia Unified School District.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-22: School District Data (2018-2020)

	Arcadia Unified (K-12)		El Monte City School District (K-6 or K-8)		El Monte Union High		Los Angeles County		State of California	
	2018-2019	2019-2020	2018-2019	2019-2020	2018-2019	2019-2020	2018-2019	2019-2020	2018-2019	2019-2020
Pupil to Teacher ratio	22:1	21.9:1	20:1	20.6:1	21:1	20.7:1	20.3:1	--	21:1	--
Average Teacher Experience	13 years	13 years	11 years	11 years	14 years	15 years	14 years	--	12 years	--
Ethnic Diversity Index ¹	37	38	21	21	23	23	38	38	47	47
Free and Reduced-Price Meals	26%	25.9%	93.3%	92.6%	87.8%	88.7%	68.5%	68.8%	59.4%	59.3%
Dollars per Student	\$12,171	\$12,449	\$13,912	\$14,310	\$15,212	\$15,833	--	--	\$12,967	\$13,173
Cohort Dropouts	0.6%	0.7%	N/A	N/A	11%	5.3%	10.6%	9.5%	9%	8.9%
Cohort Graduates	98.8%	96.7%	N/A	N/A	83.9%	84.9%	81.8%	82.2%	84.5%	84.3%
Cohort Graduates meeting UC/CSU Course Requirements	94.5%	0.4%	N/A	N/A	48.8%	46.9%	56.6%	53.6%	50.5%	50.9%
<i>Source: Education Data Partnership. Fiscal, Demographic, and Performance Data on California's K-12 Schools. Available https://www.ed-data.org/. Accessed on December 3, 2021.</i> Notes: The Ethnic Diversity Index reflects how evenly distributed these students are among the race/ethnicity categories. The more evenly distributed, the higher the number. A school where all of the students are the same ethnicity would have an index of 0.										



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Employment Opportunity


Although the employment rate and median income are high in Arcadia, job availability and quality are lower in the City when compared to the State and County. **Figure 3-23** shows that job proximity is the highest in the center of the City. Arcadia does not have any areas in which job proximity is the closest, however it has higher job proximity than neighboring cities to the south. Cities to the east, such as Monrovia and Duarte have similar levels of job proximity to Arcadia. To the west, there is a high concentration of high job proximity areas in Pasadena. Regionally, job proximity varies in, however the largest patch of closest job proximity appears to be located near the City of Los Angeles. Directly southwest and southeast of Arcadia, communities experience lower job proximity. Overall, Arcadia has a moderate level of job proximity compared to the Los Angeles Metropolitan Area.

Additionally, there are various levels of job proximity within the City itself. As mentioned above, higher job proximity is located in the center of the City. The southern portion of the City, where median income is the lowest and more protected groups are concentrated, has lower job proximity when compared to the rest of the City. Within the southern portion of the City, there are higher concentrations of non-white populations, single-mothers with children, and persons who earn lower incomes. There is one census tract in the southern portion of the City that has a high concentration of persons with disabilities, however most people within this protected class live in the center of the City where job proximity is higher. Lower job proximity could be a potential constraint to fair housing.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-23: Job Proximity Index – City of Arcadia (HUD 2014-2017)



Source: Longitudinal Employer-Household Dynamics (LEHD) data, 2014



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Access to Transit

AllTransit explores metrics that reveal the social and economic impact of transit, specifically looking at connectivity, access to jobs, and frequency of service. According to the data provided, Arcadia scored a 6.8 AllTransit performance score, illustrating a low to moderate combination of trips per week and number of jobs accessible that enable a moderate number of people to take transit to work. According to the data shown in **Table 3-23**, Arcadia's AllTransit performance score illustrates a moderate combination of trips per week and number of jobs accessible that enable a moderate number of people to take transit to work. In total, 188,373 jobs are accessible within a 30-minute trip from Arcadia, however just 2.67 percent of commuters use transit. Additionally, AllTransit identified the following transit related statistics for Arcadia:

- 97.8 percent of all jobs in Arcadia are located within ½ mile of transit
- There are 113,696 customer households within a 30-minute transit commute of local businesses
- 1.26 percent of workers in Arcadia walk to work
- 0.44 percent of workers in Arcadia bike to work
- 8.4 percent of low income households live near transit

By comparison, the City of Pasadena scored higher than Arcadia at 8.3, the City of Monrovia scored lower than Arcadia at 5.6, and the County scored the same as Arcadia at 6.8.

Table 3-23: Opportunity Indicator – Transit

Jurisdiction	All Transit Performance Score	Transit Trips Per Week within ½ Mile	Jobs Accessible in 30-min Trip	Commuters Who Use Transit	Transit Routes within ½ Mile
Arcadia	6.8	1,187	188,373	2.67%	4
Pasadena	8.3	2,935	248,166	6.77%	11
Monrovia	5.6	832	100,808	3.41%	3
Los Angeles County	6.8	2,608	321,664	6.66%	8


Source: All-transit, American Community Survey 2019

While the AllTransit metrics consider the two major transit agencies – Foothill Transit and Metro-Los Angeles – the metrics do not consider Arcadia Transit. Arcadia Transit provides curb-to-curb shared transportation to seniors and persons with disabilities as well as an affordable fixed route service. The City's fixed-route service which connects the Metro Gold Line Arcadia Station with major activity centers such as Santa Anita Park, City Hall, the Methodist Hospital, Westfield Santa Anita Mall, and the Los Angeles County Arboretum. The transit service is free to seniors, persons with disabilities, and children under 5.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-24: Job Proximity Index – AllTransit Performance Score – City of Arcadia





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-24 shows that there are various levels of access to transit throughout the City. The southern and central parts of the City have the lowest level of transit access. In these areas of the City, people are more likely to be part of one of the protected classes such as low income, non-White, and or disabled. Persons with mobility issues, such as some people with disabilities, are disproportionately affected by lack of transit in the southern and central portions of the City. Housing is the most affordable in these areas and therefore impacts where persons with lower incomes can afford to live.

Access to transportation increases both economic and environmental/health opportunities. In an effort to increase both mobility and economic access, the City of Arcadia has identified the Las Tunas/Live Oak Corridor and the downtown area as opportunities for increased density to accommodate low and very low units. These areas are proximate to both regional as well as local transit and as the map above shows, these areas score well with connectivity.

Environmental Justice

The California Office of Environmental Health Hazard Assessment (OEHHA) developed a screening methodology to help identify California communities disproportionately burdened by multiple sources of pollution called the California Communities Environmental Health Screening Tool (CalEnviroScreen). In addition to environmental factors (pollutant exposure, groundwater threats, toxic sites, and hazardous materials exposure) and sensitive receptors (seniors, children, persons with asthma, and low birth weight infants), CalEnviroScreen also takes into consideration socioeconomic factors. These factors include educational attainment, linguistic isolation, poverty, and unemployment. Research has shown a heightened vulnerability of people of certain ethnicities and lower socioeconomic status to environmental pollutants. **Figure 3-25** below displays mapped results for the CalEnviroScreen in Arcadia. The map shows that most of Arcadia is low scoring, with the exception of two partial census tracts (6037431502 and 6037432500) towards the southern edge of the City. **Table 3-24** below identifies the CalEnviroScreen scores given to these census tracts. Overall, low scoring signifies low pollution burdens in the City, therefore, the City of Arcadia shows low exposure to harmful pollutants.

Table 3-24: CalEnviroScreen 3.0		
Census Tract Number	6037431502	6037432500
Pollutant (measured in Percentile*)		
Ozone	69	69
PM 2.5	66	66
Diesel	51	48
Pesticides	0	24
Toxic Releases	83	86
Traffic	35	56
Drinking Water	95	97
Cleanups	0	0
Groundwater Threats	23	50
Hazardous Waste	57	72
Impaired Water	63	72
Solid Waste	76	70
Health Risk/ Burden (Measured in Percentile*)		
Asthma	3	61
Low Birth Weight	43	82
Cardiovascular Rate	75	39
Education	43	73
Linguistic Isolation	75	92



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-24: CalEnviroScreen 3.0

Census Tract Number	6037431502	6037432500
Poverty	37	58
Unemployment	48	51
Housing Burden	59	74
Note: * Percentile derived using a weighted scoring system to determine average pollution burden/ socioeconomic scores relative to other census tracts. Source: CalEnviroScreen 3.0 Map. Arcadia. Accessed through https://oehha.maps.arcgis.com/apps/webappviewer/index.html?id=4560cfbce7c745c299b2d0cbb07044f5		


Figure 3-25 shows the environmental conditions for the whole City. The southern portions of the City are characterized by people that are more likely to earn lower incomes and be part of one of the protected classes. Additionally, the southern portions of the City are more industrialized compared to the rest of the community, which could explain worse off environmental conditions. Higher income neighborhoods in the northern portion of the City tend to have better environmental condition scores in comparison. Therefore, lower income families and people within protected groups are more likely to experience poorer environmental conditions a than those who are not.

Regionally, the City of Arcadia has a relatively low CalEnviroScreen score. The majority of communities to the south, east, and west all have higher scores than Arcadia, meaning that they experience higher levels of exposure to pollutants. Many of these communities have high concentrations of people of color and lower median incomes than the City of Arcadia.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-25 CalEnviroScreen, City of Arcadia




Source: CalEnviroScreen, 4.0 Results 2021, Accessed through HUD AFFH Data and Mapping Tool



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-26 CalEnviroScreen, Region



Source: CalEnviroScreen, 4.0 Results 2021, Accessed through HUD AFFH Data and Mapping Tool



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Summary of Disparities in Access to Opportunity Factors

While the City of Arcadia is considered a high resource area and relatively affluent when compared to neighboring cities, there are some disparities between communities within the City. The most obvious pattern identified in the analysis is the discrepancy between the northern and southern parts of the City. The following factors were identified as factors contributing to disparities in access to opportunity:

- While there are less jobs within close proximities to residential areas in the southern portion of the City, there are also less residences due to the commercial and industrial zoning and the Arcadia Logistics Center Specific Plan which does not include residential units.
- There is disparity between the northern and southern portion of the City with regards to job proximity and CalEnviroScreen.

G. Discussion of Disproportionate Housing Needs

The analysis of disproportionate housing needs within Arcadia evaluated existing housing need, need of the future housing population, and units within the community at-risk of converting to market-rate.

Existing Needs

The County of Los Angeles Housing Authority administers Section 8 Housing Choice vouchers within the City of Arcadia. For the year 2020 within the City of Arcadia, 101 households received Section 8 vouchers. Additionally, the County currently has a waitlist to receive Section 8 Housing Choice vouchers. Approximately 57 households on the County waitlist are at an Arcadia mailing address.

Housing Needs in Arcadia

A variety of factors affect housing needs for different households. Most commonly, disability, household income and households' characteristics shape the type and size of housing units needed, as well as accessibility based on existing units in a City. **Table 3-25** through **Table 3-31** display data for demographic characteristics of Arcadia, as compared to the County of Los Angeles and the State of California. Additional detailed analysis of the Arcadia community demographics is outline in **Section 2: Community Profile** of the Technical Background Report.

Table 3-25 displays the data for persons with disabilities in the City, County, and State. Overall, about 10 percent of the California population reported having at least one disability. Similarly, in the County, nearly 10 percent of persons reported at least one disability. The City of Arcadia reported a higher percentage than the State and the City at 18.6 percent. Of the 18.56 percent Arcadia residents who reported a disability, the majority were ambulatory difficulties and independent living difficulties, which could be tied to the City's senior population. Ease of reasonable accommodation procedures and opportunity for accessible housing can provide increased housing security for the population with disabilities.

Table 3-25: Population by Disability Type, Compared by Geography, 2019

Disability	City of Arcadia	County of Los Angeles	California
Total with a Disability	18.6%	9.9%	10.6%
Hearing Difficulty	2.5%	2.5%	2.9%
Vision Difficulty	1.2%	2.0%	2.0%
Cognitive Difficulty	2.6%	4.1%	4.3%
Ambulatory Difficulty	4.6%	5.7%	5.8%
Self-Care Difficulty	2.7%	2.9%	2.6%
Independent Living	3.7%	5.4%	5.5%

Source: American Community Survey, 5-Year Estimates, 2019



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-26 below displays data from the Los Angeles County Point in Time Count. The Count gathers data on the homeless population in the County as well as in all jurisdictions within the County. According to the data from 2017 to 2018 Arcadia experienced a slight drop in the homeless population, then a significant increase through 2020. Overall, Arcadia's homeless population was higher than nearby jurisdictions such as Monrovia and Pasadena (77 and 27 persons respectively). However, Arcadia did have a lower amount than El Monte. Overall, Arcadia has experienced an increase in homelessness over the last year and has a moderate number of individuals experiencing homelessness when compared to neighboring jurisdictions. The City of Arcadia is currently conducting its own detailed homelessness inventory. As part of this outreach, a support team is interviewing and documenting all individuals in the City experiencing homelessness. This information is specific to each person contacted with the goal to determine the type of services necessary in each situation. The City is also analyzing a "Tiny Homes" project in southeast Arcadia to temporarily house those experiencing homelessness.

Table 3-26: Homelessness in Arcadia and Surrounding Cities

Jurisdiction	2017	2018	Count Change	2019	2020	Count Change
Monrovia	42	69	27	80	77	-3
Pasadena*	575	677	102	542	527	15
Arcadia	17	15	-2	77	106	29
El Monte	240	517	277	428	433	5
Los Angeles County	45,979	45,039	-940	49,521	54,291	4,770

Source: Los Angeles Point in Time Count, 2017, 2018, 2019, 2020.
Note:

*Source for Homelessness in Pasadena: Pasadena Partnership. Pasadena Homelessness Count 2020. Available at https://pasadenapartnership.org/wp-content/uploads/2020/06/Pasadena-Homeless-Count_2020-FINAL.pdf. Accessed on December 20, 2021.

Table 3-27 and **Table 3-28** display household type and income data for the State, County, and City. Overall, the City has a larger percentage of family households than the County and State; this includes family households, married-couple family households, and those with children. Of the three jurisdictions, the State has the largest percentage of non-family households at approximately 11 percent more than Arcadia. The City has a percentage of households with at least one senior over the age of 60 that is approximately 10 percent more than the County and nearly 28 percent more than the State.

Table 3-27: Population by Familial Status, Compared by Geography, 2019

Familial Status	City of Arcadia	County of Los Angeles	California
Total Households	19,520	3,316,795	13,044,266
Family Households	79.9%	66.7%	68.7%
Married-Couple Family Households	58.2%	45.1%	49.8%
With Children	--	28.3%	34%
Non-Family Households	20.1%	33.3%	31.3%



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Households with one or more people 60 years +	47.2%	37.9%	29.2%
Source: American Community Survey, 5-Year Estimates, 2019			

Regarding household income, the City had a higher median household income than the County and State in 2019. As **Table 3-28** shows, Arcadia trends towards lower percentages of its residents earning lower incomes. Just over 28 percent of City residents earn a median income under \$50,000 annually, compared to 38 percent and 34 percent for the County and State, respectively.

Table 3-28: Households by Income, Compared by Geography, 2019


Households Income	City of Arcadia	County of Los Angeles	California
Less than \$10,000	5.9%	5.6%	4.8%
\$10,000-\$14,999	2.5%	4.8%	4.1%
\$15,000-\$24,999	4.5%	8.4%	7.5%
\$25,000-\$34,999	6.4%	8.1%	7.5%
\$35,000-\$49,999	8.8%	11.2%	10.5%
\$50,000-\$74,999	12%	15.9%	15.5%
\$75,000-\$99,999	12.9%	12.3%	12.4%
\$100,000-\$149,999	19.0%	15.8%	16.6%
\$150,000-\$199,999	11.3%	7.8%	8.9%
\$200,000 or More	16.7%	10.2%	12.2%
Median Income	\$93,574	\$68,044	\$75,235
Source: American Community Survey, 5-Year Estimates, 2019			

Table 3-29 displays data for households experiencing overpayment or cost burden in the State, County and City. Housing Cost burden has a number of consequences for a household, mainly displacement from their existing living situation creating limited access essential goods and often employment by potentially increasing commute times. The City has a slightly lower percentage of households that have a high-cost burden over 30 percent when compared to the County and State. Overall, the percentage of households that experience a cost burden greater than 50 percent is similar amongst the City, County, and State with all three reporting about 20 percent. Arcadia generally does not have a community characterized by high cost burdens, however, when cost burden is separated between homeowners and renters, it is obvious that renters are disproportionately affected by cost burden. The majority of areas in Arcadia have lower rates of cost burden for homeowners and higher rates of cost burden for renters. Increased opportunity for affordable housing and housing assistance funds help to prevent cost burden on households.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-27: Overpayment by Homeowners (ACS, 2019)




Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-28: Overpayment by Renters (ACS, 2019)




Legend

City Boundary

Overpayment by Renters (2015-2019) - ACS Tract Level

Percent of Renter Households for whom Gross Rent (Contract Rent Plus Tenant-Paid Utilities) is 30.0 Percent or More of Household Income



0 0.75 1.5 Miles

Source: U.S. Census Bureau, American-Community Survey, 5-Year Estimates, 2019



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-29: Households by Overpayment, Compared by Geography

Overpayment/Cost Burden	City of Arcadia	County of Los Angeles	California
Cost Burden > 30%	36.7%	40.3%	40.1%
Cost Burden > 50%	20.3%	19.2%	19.4%
Cost Burden Not Available	2.5%	1.5%	1.4%

Source: Consolidated Planning/CHAS Data, 2013- 2017.

Table 3-30 displays data for household tenure (owner vs. renter) for the State, County and City. Homeownership is a crucial foundation for helping families with low incomes build strength, stability and independence. The opportunity for transition into the homebuyer's market is important for persons and households in different communities, homeownership allows for increased stability and opportunity to age in place. **Table 3-30** shows that the City has a higher rate of homeownership compared to the County and State.

Additionally, **Table 3-31** displays data for overcrowding in the State, County and City. Overcrowding is defined as between 1.01 and 1.5 persons per room in a household, and severe overcrowding is defined as more than 1.51 persons per room. Overcrowding often occurs when nonfamily members combine incomes to live in one household, such as college students and roommates, it also occurs when there is not enough size appropriate housing options for large or multigenerational families. The City experiences low rates of overcrowding in comparison to the County and the State. Overcrowding is also shown to occur more often in renter households rather than owner households. In Arcadia, owner households that are severely overcrowded represent 0.3 percent of all households, while severely overcrowded renter households represent 2.9 percent.

Table 3-30: Households by Tenure, Compared by Geography, 2019

Household Tenure	City of Arcadia	County of Los Angeles	California
Owner Households	59.6%	45.8%	54.8%
Renter Households	40.5%	15.2%	45.2%
Total Occupied Housing Units	19,520	3,316,795	13,044,266

Source: American Community Survey, 5-Year Estimates, 2019.

Table 3-31: Households by Overcrowding, Compared by Geography

Overcrowding and Tenure	City of Arcadia	County of Los Angeles	California
Owner Households			
Overcrowded	1.3%	4.1%	3.0%
Severely Overcrowded	0.3%	1.5%	1.0%
Renter Households			
Overcrowded	3.7%	8.7%	8.1%
Severely Overcrowded	2.9%	7.5%	5.3%

Source: American Community Survey, 5-Year Estimates, 2019.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

HOUSING NEEDS FOR EXTREMELY LOW INCOME HOUSEHOLDS

According to HCD extremely low income households are defined as households that earn 0 to 30 percent of the local annual median income (AMI). In Arcadia, the threshold is based on the Los Angeles-Long Beach-Glendale, CA HUD Metropolitan's AMI. For a family or household of four people, the maximum amount of annual income in the Los Angeles-Long Beach-Glendale, CA HUD Metropolitan Area is \$35,450 to be considered extremely low income.³⁵

Table 3-32 below shows local, regional and statewide data regarding extremely low income households and their tenure. Arcadia has the lowest proportion of extremely low income households compared to the other jurisdictions. Los Angeles County has a higher proportion of extremely low income households in comparison to the State and City. It is more likely that an extremely low income household would own rather than rent housing in Arcadia than in the other jurisdictions. Although there is a higher rate of home ownership, there is a need for stable, affordable housing in the City.

Table 3-32: Extremely Low Income Households¹ by Tenure						
	# of Extremely Low Income Owners	% of Total Extremely Low Income HH	# of Extremely Low Income Renters	% of Total Extremely Low Income HH	Total Extremely Low Income HH	% of Extremely Low Income HH in the Jurisdiction
Arcadia	1,020	41%	1,495	59%	2,515	13%
Los Angeles County	136,760	21%	504,295	79%	641,055	19%
California	536,865	27%	1,424,685	73%	1,961,550	15%

Source: CHAS HUD. 2013-2017 data. Available at <https://www.huduser.gov/portal/datasets/cp.html>.

1- ELI is defined as households that earn less up to 30 percent of AMI.

Table 3-33 shows cost burden for extremely low income households. The data shows 100 percent of ELI households experience some type of cost burden. Extremely low income families make up the largest group of people to experience a cost burden of greater than 50 percent. Extremely low income households also account for approximately 37 percent of households that experience cost burdens of greater than 30 percent.

Table 3-33: Extremely Low Income Household Overpayment						
	Cost Burden of >30 percent	Percent of Extremely Low Income Households > 30 percent cost burden	Cost burden of > 50 percent	Percent of Extremely Low Income > 50 percent cost burden	Total Extremely Low Income HH Experiencing Cost Burden	Percent of Extremely Low Income Experiencing Cost Burden

³⁵ HUD. 2021 Adjusted Home Income Limits. Available at https://www.huduser.gov/portal/datasets/home-datasets/files/HOME_IncomeLmts_State_CA_2021.pdf. Accessed on December 7, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Extremely Low Income Owners	725	39%	575	34%	2,515	100%
Extremely Low Income Renters	1,120	61%	1100	66%		
Total	1,845	100%	1,675	100%	-	-

Source: CHAS HUD. 2013-2017 data. Available at <https://www.huduser.gov/portal/datasets/cp.html>.

Projected Needs for ELI Households

To calculate projected needs, the City assumed 50 percent of its very low income regional housing needs are extremely low income households. The City was allocated 1,102 very low income units, and as a result, approximately 551 units are projected for extremely low income households. As shown above, the majority of extremely low income households face a variety of housing problems such as high cost burden and low ownership rates. Additionally, some extremely low income households could face other issues such as having special needs or disabilities that could exacerbate housing problems. In order to provide ample housing for extremely low income households, the City allows for a variety of housing types, such as single-room occupancy (SRO) and supportive housing.

A Single-Room Occupancy is defined as a building or buildings constructed or converted for residential living consisting of one-room dwelling units, where each unit is occupied by a single individual or two persons living together as a domestic unit, and where the living and sleeping spaces are combined. A unit that contains both a bathroom and kitchen shall be considered a studio unit and not a Single-Room Occupancy. Single-Room Occupancies are permitted in all multi-family residential zones (R-2, R-3 and R-3-R) either through supportive housing, transitional housing, or residential care facility.

The term Supportive Housing (per California Government Code Section 65582[f], as may be amended) shall mean a dwelling unit occupied by a target population, with no limit on length of stay, that is linked to on-site or off-site services that assist the supportive housing resident(s) in retaining the housing, improving their health status, and maximizing their ability to live and, when possible, work in the community. A target population means persons with low incomes having one or more disabilities, including mental illness, HIV or AIDS, substance abuse, or other chronic health conditions, or individuals eligible for services provided under the Lanterman Developmental Disabilities Services Act (Welfare and Institutions [W&I] Code Section 4500) and may include—among other populations—adults, emancipated youth, families, families with children, elderly persons, young adults aging out of the foster care system, individuals exiting from institutional settings, veterans, and homeless people. Supportive Housing (Housing Type) is permitted in CMD, MU, DMU with a minor use permit for upper floors only. Supportive Housing with six or fewer residents (small), excluding staff, is permitted in R-M, R-0, R-1, R-2, R-3, and R-3-R residential zones. Supportive Housing with more than seven persons (large), excluding staff, is permitted with a conditional use permit in C-O and C-G commercial zones.

Housing Stock in Arcadia

Table 3-34 and **Table 3-35** display comparative housing stock data for the State, County and City. **Table 3-32** shows data for occupied housing units by type. A variety of housing stock provides increased opportunity in communities for different size and household types. The majority of housing stock in Arcadia is classified as one-unit, detached housing, or single-family housing. Just under 17 percent of Arcadia homes include 10 or more units and are referred to as multi-family housing. In comparison to the County



CITY OF ARCADIA 6TH CYCLE Housing Element Update

and the State, Arcadia has a greater amount of single-family homes and a smaller amount of multi-family housing that includes at least 10 units.

Table 3-34: Occupied Housing Units by Type, Compared by Geography

Housing Unit Type	City of Arcadia	County of Los Angeles	California
1, detached	60.3%	48.6%	57.7%
1, attached	8.7%	6.3%	7.0%
2 apartments	1.6%	2.7%	2.4%
3 or 4 apartments	4.8%	5.8%	5.5%
5 to 9 apartments	7.7%	7.9%	6.0%
10 or more apartments	16.9%	27.1%	17.5%
Mobile home or other type of housing	0.0%	1.6%	3.8%

Source: American Community Survey, 5-Year Estimates, 2019.

Table 3-35 displays housing stock by year built for the City, County, and State. Older housing generally requires more upkeep and regular maintenance which can cause a cost burden on both renters and homeowners. A majority of Arcadia and the State's housing units were built between 1940 and 1989 whereas the distribution of development was slightly more dispersed from 1950 to 1990 in the State. Overall, increased numbers of older housing stock can lead to displacement, cost burden, and substandard living conditions.

Table 3-35: Occupied Housing Units by Type, Compared by Geography

Housing Unit Type	City of Arcadia	County of Los Angeles	California
Built 2014 or later	1.2%	1.2%	1.7%
Built 2010 to 2013	1.5%	1.2%	1.7%
Built 2000 to 2009	6.1%	5.4%	11.2%
Built 1990 to 1999	7.8%	6.3%	10.9%
Built 1980 to 1989	10.1%	11.6%	15.0%
Built 1970 to 1979	13.2%	13.8%	17.6%
Built 1960 to 1969	15.1%	14.8%	13.4%
Built 1950 to 1959	23.0%	20.5%	13.4%
Built 1940 to 1949	13.9%	10.4%	5.9%
Built 1939 or earlier	8.1%	14.8%	9.1%

Source: American Community Survey, 5-Year Estimates, 2019.

SUBSTANDARD HOUSING

Substandard housing is defined by the U.S. Census as:

1. Housing without hot and cold piped water, a flush toilet and a bathtub or shower; and
2. Households with kitchen facilities that lack a sink with piped water, a range or stove or a refrigerator.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-36 below shows substandard housing within Arcadia, Los Angeles County, and the State of California. The City of Arcadia has the highest percent of occupied housing units with complete plumbing facilities and the lowest percent of occupied housing units with complete kitchen facilities when compared to Los Angeles County and the State. Approximately 97.8 percent of occupied housing units in Arcadia have complete kitchen facilities. Per the City's Code Enforcement data, there are four properties in the City that are considered substandard. Although the City has a lower proportion of units with complete kitchen facilities, the difference is not substantial and should not be viewed as an impediment to fair housing.

Table 3-36: Substandard Housing			
Jurisdiction	Total Occupied Housing Units	With complete Plumbing Facilities (percent)	With complete Kitchen Facilities (percent)
Arcadia	19,520	99.7%	97.8%
Los Angeles County	3,316,795	99.5%	98.5%
California	13,044,266	99.6%	98.9%
<i>Source: American Community Survey, 5-Year Estimates, 2019.</i>			

Future Growth Need

The City's future growth need is based on the RHNA production of 1,102 extremely low/very low and 570 low income units within the 2021 – 2029 planning period. **Appendix A** of this Housing Element shows the City's ability to meet its 2021 – 2029 RHNA needs at all income levels. This demonstrates the City's ability to accommodate the anticipated future affordable housing needs of the community.

Displacement Risk

The potential for economic displacement risk can result from a variety of factors, including large-scale development activity, neighborhood reinvestment, infrastructure investments, and changes in local and regional employment opportunity. Economic displacement can be an inadvertent result of public and private investment, where individuals and families may not be able to keep pace with increased property values and market rental rates.

Affordable covenants help to ensure that certain housing units remain affordable for an extended period of time. Covenants help balance the housing market in a community and provide lasting affordable options to low and very low income households. The City of Arcadia has multiple housing projects which include units with affordability covenants. According to **Table 3-37** below, the City has no affordable units at risk of conversion to market rates.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-37: Affordable Housing Units in Arcadia with Covenants

Accessor Parcel Number	Project Name/Address	Number of Affordable Unit	Units by Bedroom Size					Covenant Recordation Number	Recordation Date	Covenant Expiration
			Studio	1 BR	2 BR	3 BR	4 BR			
5788-022-014	Heritage Park Apts., 150 West Las Tunas	54		45	9			03-2733831	2004	2059
5778-014-012	Campus Commons, 16 Campus Dr.	42		33	9			20101891076	2012	2067
5773-014-062	Alta Street Classics, 119 Alta St., #A	1						20080589887	2007	2052
5773-014-063	Alta Street Classics, 119 Alta St., #B	1						20080589895	2007	2052
5773-014-064	Alta StreetC Classics, 119 Alta St., #C	1						20120199978	2007	2052
5773-014-059	Alta Street Classics, 121 Alta St., #A	1						20080601949	2007	2052
5773-014-060	Alta Street Classics, 121 Alta St., #B	1						20080589878	2007	2052
5773-014-061	Alta Street Classics, 121 Alta St., #C	1						20080589882	2007	2052



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Urban Displacement Analysis

The UC Berkeley Urban Displacement projects provides a database for Los Angeles, Orange and San Diego Counties displaying gentrifications and socioeconomic indicators based on 2015 ACS data. The final (2018) version of the database shows whether each Census tract comprising these three Southern California counties gentrified between 1990 and 2000; gentrified between 2000 and 2015; gentrified during both of these periods; or exhibited characteristics of a “disadvantaged” tract that did not gentrify between 1990 and 2015. The outcome of the data is a map which displays displacement typology by census tract (outlined below).

Table 3-38: Displacement Typologies

Displacement Typology	Definition and Qualifier
Low Income/Susceptible to Displacement:	Low or mixed low-income tract in 2018
Ongoing Displacement of Low-Income Households:	- Low or mixed low-income tract in 2018 - Absolute loss of low-income households, 2000-2018
At Risk of Gentrification:	- Low-income or mixed low-income tract in 2018 - Housing affordable to low or mixed low-income households in 2018 - Didn't gentrify 1990-2000 OR 2000-2018 - Marginal change in housing costs OR Zillow home or rental value increases in the 90th percentile between 2012-2018 - Local and nearby increases in rent were greater than the regional median between 2012-2018 OR the 2018 rent gap is greater than the regional median rent gap
Early/Ongoing Gentrification:	- Low-income or mixed low-income tract in 2018 - Housing affordable to moderate or mixed moderate-income households in 2018 - Increase or rapid increase in housing costs OR above regional median change in Zillow home or rental values between 2012-2018 - Gentrified in 1990-2000 or 2000-2018
Advanced Gentrification	- Moderate, mixed moderate, mixed high, or high-income tract in 2018 - Housing affordable to middle, high, mixed moderate, and mixed high-income households in 2018 - Marginal change, increase, or rapid increase in housing costs - Gentrified in 1990-2000 or 2000-2018
Stable Moderate/Mixed Income:	Moderate, mixed moderate, mixed high, or high-income tract in 2018
Risk of Becoming Exclusive:	- Moderate, mixed moderate, mixed high, or high-income tract in 2018 - Housing affordable to middle, high, mixed moderate, and mixed high-income households in 2018 - Marginal change or increase in housing costs
Becoming Exclusive:	- Moderate, mixed moderate, mixed high, or high-income tract in 2018 - Housing affordable to middle, high, mixed moderate, and mixed high-income households in 2018 - Rapid increase in housing costs - Absolute loss of low-income households, 2000-2018 - Declining low-income in-migration rate, 2012-2018 - Median income higher in 2018 than in 2000
Stable/Advanced Exclusive:	- High-income tract in 2000 and 2018 - Affordable to high or mixed high-income households in 2018 - Marginal change, increase, or rapid increase in housing costs




CITY OF ARCADIA 6TH CYCLE Housing Element Update

The City of Arcadia has a variety of Displacement Typologies including areas characterized as Stable/Moderate Income, Becoming Exclusive, Stable/Advanced Exclusive, and Low-Income/Susceptible to Displacement. The distribution of typologies follows similar patterns to income distribution within the City. Northern portions of the City are more exclusive and typically have higher median incomes than southern portions of the City. Communities to the east such as Monrovia have census tracts characterized by Advanced Gentrification and Low-Income/Susceptible to Displacement. These communities are typically lower income and characterized by higher proportions of non-white, specifically Hispanic and Asian, communities. Communities to the south and southwest also exhibit similar patterns to those in Monrovia. Overall, Arcadia does not have any communities that are characterized by Advanced Gentrification; however some census tracts are at risk of further exclusivity. The impacts that candidate housing sites could have in relation to Displacement Typologies are analyzed later in this section.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-29: Displacement Typologies in Arcadia



Legend

Displacement Typology

- Low-Income/Susceptible to Displacement
- Ongoing Displacement
- At Risk of Gentrification
- Early/Ongoing Gentrification
- Advanced Gentrification

- Stable Moderate/Mixed Income
- At Risk of Becoming Exclusive
- Becoming Exclusive
- Stable/Advanced Exclusive
- High Student Population
- Unavailable or Unreliable Data





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Cost of Preservation and Replacement Analysis

“At-Risk” Analysis

Jurisdictions are required by State Housing Element Law to analyze assisted housing that may convert from lower income to market rate housing over the next 10 years. State law identifies housing assistance as a rental subsidy, mortgage subsidy or mortgage insurance to an assisted housing development. Government assisted housing may convert to market rate housing for several reasons, including expiring subsidies, mortgage payments, or expiration of affordability restrictions. Other affordable housing developments in the City such as Naomi Gardens, Heritage Park, and the Campus Commons have received LIHTC funding and are not at-risk of conversion to market-rate. There are no housing units with covenants in Arcadia at-risk of converting to market-rate between 2021 and 2031.

Summary of Disproportionate Housing Needs Factors

As part of the Housing Element, the City considers characteristics of the current housing stock and housing needs as key factors in fair housing. Federal, State, and local data provide regional context, background information, and supportive data which helps the City to understand fair housing issues and to identify key fair housing factors for Arcadia. Some key findings identified through this analysis are stated below:

- The City of Arcadia has a high amount of persons with disabilities in the City compared to the State and County. Therefore, the City should support furthering reasonable accommodations in the municipal code.
- Arcadia has the second highest amount of persons experiencing homelessness compared to surrounding cities. The City should therefore look into ways to house and invest in persons experiencing homelessness through policy.
- Cost burden greater than 50 percent is highest in Arcadia compared to the county and state
- the majority (60.4 percent) is detached single family housing, which indicates that Arcadia’s housing cost is disproportionately high. This suggests a lack of affordable housing in the City.
- The majority of residences were built between 1940 and 1989. This suggests that the housing stock of Arcadia is relatively older and should be upgraded or redone in order to provide acceptable housing for residents.
- Arcadia has a higher rate of substandard housing compared to the County and State, which suggests to the City that efforts should be put towards ensuring housing with standard facilities through municipal code.

H. Assessment of Local Contributing Factors to Fair Housing in Arcadia

The AI does not identify impediments to fair housing specific to Arcadia, however, some of the regional impediments to fair housing identified within jurisdictions in Los Angeles County may assist Arcadia in opening the community up to a broader range of future residents.

- Fair housing information needs to be disseminated through many media forms to reach the targeted groups.
- Hispanics and Blacks continue to be under-represented in the homebuyer market and experience large disparities in loan approval rates.
- Housing choices for special needs groups, especially persons with disabilities and seniors, are limited.
- Fair housing enforcement activities, such as random testing, are limited.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

- Patterns of racial and ethnic concentration exist in the region, although there are no racially or ethnically concentrated areas of poverty in Arcadia.

The analysis conducted in this section regarding fair housing issues within Arcadia yielded the following conclusions in order of priority:

Table 3-39: Local Contributing Factors

Fair Housing Issue	Contributing Factor	Priority	Actions
1. Lack of Affordable Housing <i>Housing Mobility, New Opportunities in Higher Opportunity Areas</i>	Arcadia residents generally earn a high annual income, approximately 38 percent higher than the Los Angeles County median household income. Additionally, Community Profile states that the median home value in Arcadia is \$1,097,600 which is high for surrounding jurisdictions and greater than the County overall. The cost burden of housing in Arcadia is higher when compared to the County and the state. 36 percent of the City's households earn a lower income (at or below 80 percent of the area median family income). Additionally, 37 percent of the City's households pay over 30 percent of their income for housing and are considered cost burdened. The City currently does not have a diverse stock of affordable housing and will implement programs to increase production of housing for all income levels	High	Program 5-3: Residential Design Guidelines Program 5-15: Encourage Development of Housing Sites Listed in Inventory Program 5-16: Housing Density Bonus Program 5-25: Participation in the San Gabriel Valley housing Trust Program 5-27: Section 8 Housing Choice Voucher Program Program 5-35: Mitigating Constraints for the Development of Affordable Housing Projects
2. Barriers to Housing for Persons with Disabilities <i>Housing Mobility, New Opportunities in Higher Opportunity Areas</i>	Affordability, design, and location limit the supply of housing for persons with disabilities. Amendments to the Fair Housing Act, as well as state law, require ground-floor units of new multi-family construction with more than four units to be accessible to persons with disabilities. However, units built prior to 1989 are not required to be accessible to persons with disabilities. The City of Arcadia has a higher population with disabilities than the surrounding region. Additionally, a majority of the residences were built between 1940 and 1989 suggesting that the housing stock was not required to be accessible to persons with disabilities. The City could provide additional enforcement and outreach	Medium	Program 5-3: Residential Design Guidelines Program 5-19: Inclusionary Housing Policy Program 5-23: Public Information about Affordable Housing Program 5-27: Section 8 Housing Choice Voucher Program Program 5-28: Affordable Housing for Families and Persons with Special Needs



CITY OF ARCADIA 6TH CYCLE Housing Element Update

	on fair housing for both landlords and residents with regards to people with disabilities. Additionally, the City has plans to update its reasonable accommodation procedures to address some issues associated with physical disabilities.		Program 5-34: Mitigating Constraints to Housing Choice for Persons with Disabilities
3. Fair Housing Enforcement and Outreach <i>Mobility, Place Based Strategies for Community Revitalization</i>	Previous fair housing inquiries in Arcadia have gone unresolved. Additionally, the City only conducts outreach through the Housing Rights Center. The City could provide additional general information and outreach on fair housing within Arcadia. The City is considered a high opportunity and resource area, additional enforcement and outreach on fair housing may improve opportunities for households in the region to move to Arcadia.	Medium	Program 5-3: Residential Design Guidelines Program 5-23: Public Information about Affordable Housing Program 5-32: Fair Housing Assistance

AB 686

AB 686 requires that jurisdictions identify sites throughout the community in a manner that is consistent with its duty to affirmatively further fair housing. The site identification requirement involves not only an analysis of site capacity to accommodate the RHNA (provided in **Appendix A**), but also whether the identified sites serve the purpose of replacing segregated living patterns with truly integrated and balanced living patterns, transforming racially and ethnically concentrated areas of poverty into areas of opportunity.

Figure 3-30 through **Figure 3-35** below identify the sites to accommodate future housing as identified in the adequate sites analysis, overlaid on demographic data using the 2019 American Community Survey 5-Year Estimates.

- **Figure 3-30** Arcadia proposed RHNA Sites, Hispanic/Latino, 2018
- **Figure 3-31** Arcadia Proposed RHNA Sites, Non-White Population, 2018
- **Figure 3-32** Arcadia Proposed RHNA Sites, Low and Moderate Income, 2015
- **Figure 3-33** Arcadia Proposed RHNA Sites, Racially Concentrated Areas of Affluence, 2018
- **Figure 3-34** Arcadia Proposed RHNA Sites, Racially/Ethnically Concentrated Areas of Poverty, 2009-2013
- **Figure 3-35** Arcadia Proposed RHNA Sites, TCAC/HCD Opportunity Areas, 2021
- **Figure 3-36** Arcadia Proposed RHNA Sites, CalEnviroScreen 4.0 Scores



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Potential Effects on Integration and Segregation Trends

This analysis evaluates the potential effects candidate housing sites and their affordability could have on currently patterns of residential segregation based on race and ethnicity and/or income once housing is built within the City. Previous analyses have established that there are varying levels of racial and ethnic segregation in Arcadia. The data has shown that communities to the in the northern parts of the City typically having predominantly White populations with higher household incomes than those in the south.

Figure 3-30 shows the proposed candidate sites to meet the RHNA for Arcadia in relation to the location of residents of Hispanic origin. These sites take into consideration access to goods, services, and public transportation and are therefore ideal areas for the City to focus much of its future housing growth. It is anticipated that accessory dwelling unit (ADU) growth, including growth for affordable ADUs, will occur in the less dense areas of the community, specifically in single unit residential neighborhoods. Additionally, the City meets its RHNA obligation for Above Moderate income through projects in the pipeline (which are also mapped in the figure below). **Figure 3-30** shows the following findings:


- 274 proposed sites to accommodate the RHNA allocation (totaling 5,175 potential units, or 44 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as Hispanic less than 20 percent. Of those units, 1,296 are proposed as affordable to low and very low incomes.
- 118 proposed sites to accommodate the RHNA allocation (totaling 5,571 potential units, or 48 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as Hispanic between 20 and 40 percent. Of those units, 1,287 are proposed as affordable to low and very low incomes.
- 24 proposed sites to accommodate the RHNA allocation (totaling 886 potential units, or 8 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as Hispanic between 40 and 60 percent. Of those units, 188 are proposed as affordable to low and very low incomes.
- There are no block groups that have a percentage of the population that identifies as Hispanic above 60 in Arcadia.

Figure 3-30 shows the approximately 10,746 units, or 92 percent of all projected housing units, are within areas of the City where a minority (under 40 percent) of the population identifies as Hispanic. These projected units include approximately 2,583 low income units, or approximately 93 percent of all low income units. Since the majority of potential units would be in areas with less than 40 percent of the population identifying as Hispanic, projected housing units have the potential to overburden these areas. However, the City is made up of census tracts characterized mostly by Asian majority populations and increased housing in these areas would help alleviate housing costs and overcrowding for residents of the City.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-30: Proposed RHNA Sites in Arcadia, Hispanic/Latino Population



Arcadia AFFH

Legend

☆ Site Candidates

Percent Hispanic Population

- < 20%
- 20% - 40%
- 40% - 60%
- 60% - 80%
- > 80%





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-31 shows the proposed candidate sites to meet the RHNA for Arcadia in relation with census data showing the percentage of the population within each block group that is Non-White. **Figure 3-31** shows the following findings:


- One proposed site to accommodate the RHNA allocation (totaling 80 potential units, or less than one percent of the total potential units) are located within block groups that have a percentage of the population that identifies as Non-White between 40 and 60 percent. Of those units, none are proposed as affordable to low and very low incomes.
- 263 proposed sites to accommodate the RHNA allocation (totaling 8,786 potential units, or 76 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as Non-White between 60 and 80 percent. Of those units, 2,099 are proposed as affordable to low and very low incomes.
- 152 proposed sites to accommodate the RHNA allocation (2,766 potential units, or 24 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as Non-White above 80 percent. Of those units, 672 are proposed as affordable to low and very low incomes.

Figure 3-31 shows the approximately 11,552 units, or 99 percent of all projected housing units, are within areas of the City where a strong majority (over 60 percent) of the population identifies as Non White. These projected units include approximately 2,771 low income units, or approximately 100 percent of all low income units. The City is made up of census tracts characterized mostly by Asian majority populations, which make them Non White majority communities. As a result, the placement of housing would not overburden any one racial or ethnic group as the units are evenly distributed within the City.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-31: Proposed RHNA Sites in Arcadia, Non-White Population



Arcadia AFFH

Legend

☆ Site Candidates

Percent Non-White Population

- < 20%
- 20% - 40%
- 40% - 60%
- 60% - 80%
- > 80%





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-32 shows location of proposed candidate sites to meet the RHNA for Arcadia in comparison with census data showing the percentage of the population within each block group who is categorized as low income or moderate income by the American Community Survey. **Figure 3-32** shows the following findings:

- 14 proposed sites to accommodate the RHNA allocation (totaling 442 potential units, or 4 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as low or moderate income below 20 percent. Of those units, 90 are proposed as affordable to low and very low incomes.
- 188 proposed sites to accommodate the RHNA allocation (totaling 7,158 potential units, 82 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as low or moderate income between 20 and 40 percent. Of those units, 1,722 are proposed as affordable to low and very low incomes.
- 214 proposed sites to accommodate the RHNA allocation (totaling 4,032 potential units, or 35 percent of the total potential units) are located within block groups that have a percentage of the population that identifies as low or moderate income between 40 and 60 percent. Of those units, 959 are proposed as affordable to low and very low incomes.
- There are no block groups that have a percentage of the population that identifies as low or moderate income above 60 percent.

There are approximately 11,190 projected units, or 96 percent of all projected housing units, in areas where over 20 percent of the population are considered low to moderate income earners. Of these units, 2,681 are low income units, 1,037 moderate units and 7,497 above moderate units. By increasing the number of affordable housing opportunities in areas with higher proportions of low to moderate income earners, burdens such as overcrowding, overpayment, and lack of access to affordable housing have the potential to be eased. Development of more moderate and above moderate income units in these areas has the potential to exasperate gentrification. However, by gradually increasing the amount of these units over the planning period, moderate and above moderate income units could potentially improve conditions in these communities. Average median incomes could increase, and as a result, more interest in investment in these neighborhoods could occur.


The remaining 442 projected housing units are in higher earning areas with lower proportions of low to moderate income earners (less than 20 percent). Approximately 90 of these units are projected for lower income households, which would increase the amount of affordable housing in areas of the City where there are more opportunities and better environmental health. This would further the integration of variety of income groups within the City and create a more diverse neighborhood setting in regard to income.

Since the community is made up of communities with proportions of households with low to moderate incomes ranging from 10-50 percent, projecting the majority of potential housing units would not overburden these areas. The candidate site strategy also gives lower income households more opportunities to live in areas with lower proportions of low to moderate income households, thus giving them better access to resources and opportunities.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-32: Arcadia Proposed RHNA Sites, Low and Moderate Income



Arcadia AFFH

Legend

☆ Site Candidates

Percent Low- and Moderate-Income Population

- < 10%
- 10% - 25%
- 25% - 50%
- 50% - 75%
- > 75%





CITY OF ARCADIA 6TH CYCLE Housing Element Update


Figure 3-33 shows locations of Racially Concentrated Areas of Affluence (RCAA) in the City of Arcadia. RCAAs are defined as census tracts where 1) 80 percent or more of the population is white, and 2) the median household income is \$125,000 or greater (slightly more than double the national the median household income in 2016.³⁶ While the City has census tracts where the median household income is greater than or equal to \$125,000, there are no tracts where the population is greater than or equal to 80 percent White, resulting in no RCAAs identified within the City bounds (See **Figure 3-33**).

³⁶ HCD. (2021). Affirmatively Furthering Fair Housing. Available at https://www.hcd.ca.gov/community-development/affh/docs/affh_document_final_4-27-2021.pdf.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-33: RCAAs in Arcadia



Arcadia AFFH

Legend

★ Site Candidates

Racially Concentrated Areas of Affluence

Identified RCAA by Census Tract

White Non-Hispanic Population ≥ 80 Percent

Income > \$125,000





CITY OF ARCADIA 6TH CYCLE Housing Element Update


Figure 3-34 shows location of Racially/Ethnically Concentrated Areas of Poverty (R/ECAP) in the City of Arcadia. R/ECAPs are defined as census tracts where 1) 50 percent or more of the community identifies as non-white, and 2) 40 percent or more of the population lives at or below the federal poverty line.³⁷ **Figure 3-34** shows that there are no R/ECAPS within the City of Arcadia.

³⁷ Ibid.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-34: R/ECAPs in Arcadia



Arcadia AFFH

Legend

★ Site Candidates

Racially/Ethnically Concentrated Areas of Poverty (R/ECAP)

HUD, 2009 - 2013 by Census Tract

□ 0 - Not a R/ECAP

▨ 1 - R/ECAP





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-35 shows location of Opportunity Composite Score by Census Tract (TCAC/HCD) in the City of Arcadia. TCAC/HCD Opportunity composite scores are a measure of the concentration of race in a small area compared to a county level along with 30 percent of the population living below the poverty line.³⁸

Figure 3-35 concludes that:

- 395 proposed sites to accommodate the RHNA allocation (totaling 10,722 potential units, or 92 percent of the total potential units) are located within a highest resource zone. Of the proposed units, 2,539 are proposed as affordable to Low and Very Low incomes.
- 21 proposed sites to accommodate the RHNA allocation (totaling 910 potential units, or 8 percent of the total potential units) are located within a high resource zone. Of the proposed units, 232 are proposed as affordable to Low and Very Low incomes.


Figure 3-35 shows proposed candidate sites to meet RHNA for Arcadia in relation with the TCAC/HCD Opportunity areas within the City. TCAC is the California Tax Credit Allocation Committee/Housing and Community Development Opportunity Area Maps which show how resources are spatially distributed throughout the City; however it is generally considered high to highest resource. The distribution of housing sites would not overburden any community and would result in more affordable housing being available in areas that are characterized by highest resource availability. This would give lower income households better access to resources and opportunities and generally would further integration of Arcadia's residents.

³⁸ Ibid.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-35: TCAC/HCD in Arcadia



Arcadia AFFH

Legend

☆ Site Candidates

TCAC Opportunity Areas (2021)

■ Highest Resource

■ High Resource

■ Moderate Resource

■ Moderate Resource (Rapidly Changing)

■ Low Resource

■ High Segregation & Poverty

■ Missing/Insufficient Data





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-36 shows the CalEnviroScreen 4.0 scores of census tracts in the City of Arcadia. The California Office of Environmental Health Hazard Assessment (OEHHA) developed a screening methodology to help identify California communities disproportionately burdened by multiple sources of pollution as well as socioeconomic factors called the California Communities Environmental Health Screening Tool (CalEnviroScreen). Scores range from 0 to 100, with the higher scores indicating higher burdens of pollution in conjunction with socioeconomic burdens. Research has shown a heightened vulnerability of people of certain ethnicities and lower socioeconomic status to environmental pollutants. The pattern is reflected in Arcadia communities as well. Communities in the southern tracts of the City tend to be lower income earning. CalEnviroScreen scores in these areas are also high while opportunity scores are lower than the majority of the City. **Figure 3-36** concludes that:


- 260 proposed sites to accommodate the RHNA allocation (totaling 5,794 potential units, or 50 percent of the total potential units) are located within areas characterized by scores that are below 40 percent. Of the proposed units, 1,374 are proposed as affordable to Low and Very Low incomes.
- 156 proposed sites to accommodate the RHNA allocation (totaling 5,838 potential units, or 50 percent of the total potential units) are located within census tracts that are characterized as having scores between 40 and 60 percent. Of the proposed units, 1,397 are proposed as affordable to Low and Very Low incomes.
- No units are proposed in areas with scores over 60 percent.

Since the distribution of potential housing units is fairly uniform, no one community would be overburdened with newly developed housing units.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-36: CalEnviroScreen 4.0 in Arcadia



Arcadia AFFH

Legend

☆ Site Candidates

CalEnviroScreen 4.0 (2021)

0-10%	51-60%
11-20%	61-70%
21-30%	71-80%
31-40%	81-90%
41-50%	91-100%





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-37 below displays the mapped displacement typology for Arcadia. The data shows that Arcadia has a mix of typologies throughout the City. **Figure 3-37** concludes the following:


- 171 proposed sites to accommodate the RHNA allocation (totaling 5,366 potential units, or 46 percent of the total potential units) are located within block groups designated as 'Becoming Exclusive'. Of those units, 1,279 are proposed as affordable to low and very low incomes.
- 13 proposed sites to accommodate the RHNA allocation (totaling 300 potential units, or 3 percent of the total potential units) are located within block groups designated as 'Low-Income/Susceptible to Displacement'. Of those units, 78 are proposed as affordable to low and very low incomes.
- 196 proposed sites to accommodate the RHNA allocation (totaling 4,994 potential units, or 43 percent of the total potential units) are located within block groups designated as 'Stable Moderate/Mixed Income'. Of those units, 1,177 are proposed as affordable to low and very low incomes.
- 36 proposed sites to accommodate the RHNA allocation (totaling 972 potential units, or 8 percent of the total potential units) are located within block groups designated as 'Stable/Advanced Exclusive'. Of those units, 237 are proposed as affordable to low and very low incomes.

The distribution of potential housing units would further integrate Arcadia's communities in regard to income. Approximately 9 percent of all low and very low income potential units are projected to be in areas that are characterized as Stable/Advanced Exclusive, which would give more opportunities for affordable housing in these areas. Additionally, low and very low income housing is projected in areas where there is a risk of becoming exclusive. By putting more affordable housing in these areas in addition to some moderate and above moderate units, these neighborhoods could be further integrated. Overall, the City of Arcadia is made up of areas that are becoming more exclusive and or are already exclusive. However, by encouraging the development of low income and very low income housing in these areas through the implementation of the 6th Cycle Housing Element Update, gentrification would be mitigated.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure 3-37: Displacement Typologies in Arcadia



Arcadia AFFH

Legend

☆ Site Candidates

Displacement Typology

Light Blue: Low-Income/Susceptible to Displacement
 Medium Blue: Ongoing Displacement
 Light Purple: At Risk of Gentrification
 Medium Purple: Early/Ongoing Gentrification
 Dark Purple: Advanced Gentrification

Light Tan: Stable Moderate/Mixed Income
 Tan: At Risk of Becoming Exclusive
 Brown-Tan: Becoming Exclusive
 Brown: Stable/Advanced Exclusive
 Grey: High Student Population
 Light Grey: Unavailable or Unreliable Data



AB 686 Sites Analysis AFFH Findings



CITY OF ARCADIA 6TH CYCLE Housing Element Update

The fair housing analysis above displays the following results:

- The City has capacity to accommodate the future housing at all income levels
- The sites identified to accommodate the RHNA allocation are concentrated in areas proximate to transit.
- The areas identified to accommodate the low and very low income RHNA create opportunities for lower income residents to access housing in higher resource areas.
- The areas identified to accommodate the low and very-low income RHNA are in areas where the City will plan for higher density housing and are in resource rich areas.

I. Summary of Programs to Support Fair Housing

To enhance mobility and promote inclusion for protected classes, the chief strategy included in this housing element is to provide sites suitable for affordable housing in high-resource, high opportunity areas, as demonstrated by the analysis of the housing resource sites contained in **Appendix A**. Programs listed in **Chapter 10: Implementation Plan** that affirmatively further fair housing issues in Arcadia include the following:

- Program 5-4: Section 8 Housing Choice Voucher Program
- Program 5-25: Fair Housing
- Program 5-26: Fair Housing Assistance
- Program 5-23: Homeless Program Assistance
- Program 5-27: Supportive Housing/Low Barrier Navigation Centers

Enhancing Housing Mobility Strategies

- 5-6. Residential Sites Inventory
- 5-7. Expansion of the Downtown Mixed-Use Area to Permit Residential Uses
- 5-8. Establish an Overlay in the Downtown Mixed-Use Area to Permit Residential Uses
- 5-9: Increase Density of the Mixed Use Zone
- 5-10. Expand and Update the Residential Flex Overlay in the Las Tunas Corridor
- 5-11. Expand and Update the Residential Flex Overlay in the Live Oak Corridor
- 5-12. Establish an Overlay to Permit Residential Uses in the Commercial General Zone
- 5-13. Increase Density of the R-3 Zone
- 5-14. Develop a Specific Plan for the Arcadia Golf Course
- 5-16. Housing Density Bonus
- 5-23. Public Information about Affordable Housing
- 5-24. Emergency Shelters, Transitional, and Supportive Housing
- 5-28. Affordable Housing for Families and Persons with Special Needs
- 5-29. Homeless Program Assistance
- 5-33. Supportive Housing/Low Barrier Navigation Centers
- 5-34. Update Reasonable Accommodation Procedures
- 5-35. Water and Sewer Service Providers

Encouraging the Development of New Affordable Housing in High Resource Areas

- 5-6. Residential Sites Inventory
- 5-7. Expansion of the Downtown Mixed-Use Area to Permit Residential Uses
- 5-8. Establish an Overlay in the Downtown Mixed-Use Area to Permit Residential Uses



CITY OF ARCADIA 6TH CYCLE Housing Element Update

- 5-9: Increase Density of the Mixed Use Zone
- 5-10. Expand and Update the Residential Flex Overlay in the Las Tunas Corridor
- 5-11. Expand and Update the Residential Flex Overlay in the Live Oak Corridor
- 5-12. Establish an Overlay to Permit Residential Uses in the Commercial General Zone
- 5-13. Increase Density of R-3 Zone
- 5-14. Develop a Specific Plan for the Arcadia Golf Course
- 5-15. Encourage Development of Housing Sites Listed in Inventory
- 5-17. ADU and JADU Incentive and Monitoring Program
- 5-18. Candidate Sites Used in Prior Housing Element Planning Cycle
- 5-19. Inclusionary Housing Policy
- 5-20. Lot Consolidation Incentives
- 5-21. Preservation of Rental Opportunities
- 5-25. Participation in the San Gabriel Valley Housing Trust
- 5-26. SB 35 Streamlining
- 5-27. Section 8 Housing Choice Voucher Program
- 5-28. Affordable Housing for Families and Persons with Special Needs
- 5-32. Fair Housing Assistance
- 5-35. Mitigating High Development Fees and Development Standards for Affordable Housing Projects

Improving Place-Based Strategies to Encourage Community Conservation and Revitalization, including preservation of existing Affordable Housing

- 5-1. Home Rehabilitation
- 5-2. Code Enforcement
- 5-3. Residential Design Guidelines
- 5-4. Preservation of At-Risk Units
- 5-5. Preservation of Middle-Income Housing through New Housing Providers
- 5-19. Inclusionary Housing Policy
- 5-20. Lot Consolidation Incentives
- 5-21. Preservation of Rental Opportunities
- 5-30. Housing Sustainability
- 5-35. Mitigating High Development Fees and Development Standards for Affordable Housing Projects

Protecting Existing Residents from Displacement

- 5-1. Home Rehabilitation
- 5-2. Code Enforcement
- 5-4. Preservation of At-Risk Units
- 5-18. Candidate Sites Used in Prior Housing Element Planning Cycle
- 5-21. Preservation of Rental Opportunities
- 5-22. Replacement Unit Program

4. Housing Resources

A. Regional Housing Needs Allocation



CITY OF ARCADIA 6TH CYCLE Housing Element Update

The Housing Element is required to identify potential candidate housing sites by income category to meet the City's RHNA allocation. The sites identified within the Housing Element represent the City of Arcadia's ability to plan for housing at the designated income levels within the 6th housing cycle planning period (2021-2029). The identified sites are either residentially zoned or within Focus Areas identified by the City with the potential to accommodate residential uses. As described in **Appendix A: Adequate Sites**, the development capacity for each site depends on its permitted density, consistency with surrounding uses, the City's past performance and development trends and the site's location as well as known development factors.

Residential Sites Inventory

The residential sites inventory [summary table](#) can be found in **Table A-223** within **Appendix A**. The table identifies each candidate housing site within Arcadia's inventory by APN. The sites inventory contains, by parcel, relevant information to the calculation of unit capacity and an assessment of redevelopment propensity based on existing use present on the site.

Selection of Suitable Sites

The City of Arcadia conducted a thorough analysis of all parcels within the City to determine which areas may have the most realistic potential to redevelop for residential uses within the planning period. The City has identified 23 parcels within residentially zoned land at existing densities. Additionally, the City has identified several Focus Areas to allow for residential use and/or higher density that is compatible with adjacent development.

Net Unit Capacity Calculation

Total unit capacity for the City was calculated on a per-parcel basis. Net unit capacity per parcel was calculated by evaluating for buildable acreage, multiplying by an assumed buildout density based on zoning, and subtracting any existing units. As opposed to calculating capacity using maximum density, the City assumed a build out density at 80 percent of the maximum density to provide a more conservative estimate of actual unit production. Potential constraints, to the extent they are known, such as environmentally sensitive areas and steep slopes were considered, and deductions were made where those factors decreased the net buildable area of a parcel. Additional adjustments were made for special circumstances, for example, for sites smaller than 0.5 acres. The City is also utilizing a calculation of affordability to project a more conservative and realistic buildout of affordable units. These assumptions are outlined within in **Table A-224** within **Appendix A**.

Development of Non-Vacant Sites and Conversion to Residential Uses

The City of Arcadia does not have sufficient vacant land available to accommodate 50 percent of the Low and Very Low income RHNA. To accommodate the need at all income levels, the City has analyzed 365 sites to permit residential development in the Downtown area, Las Tunas/Live Oak Corridor, and Commercial-General properties.

As part of the candidate housing sites analysis, the City has evaluated recent projects that have redeveloped to include residential units. Those projects are shown in **Table A-3** of **Appendix A**

Use of Small Parcels

The City has identified 25 parcels which do not meet the HCD sizing criteria standards. The City believes there is viable opportunity for residential development on these sites through regulatory incentives and waivers. For sites smaller than one half of an acre, the City has codified a program to incentivize small lot development and consolidation. A program to encourage developers to utilize small sites is described in **Chapter 10: Implementation Plan** and a detailed description of the assumptions related to these sites is outlined in **Appendix A**.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Accessory Dwelling Unit Production

Accessory dwelling units (ADUs) are housing units which may be developed in addition to an existing single- or multi-family residential use. These housing units can be free-standing or attached to a primary structure and are intended to provide additional housing on an existing residential lot. Often ADUs provide housing for family members or are rented to members of the community.

The City of Arcadia has determined based on past performance that it is appropriate to anticipate the development of ~~21772~~ ADUs from 2021 – 2029. This projection is based primarily on the uptick in permitting that the City experienced between 2018 and 2020. The calculation based on this projection is outlined in **Appendix A**.

Regional Housing Needs Allocation

Future Housing Needs

Future housing need refers to the share of the regional housing need that has been allocated to the City. The State Department of Housing and Community Development (HCD) has supplied a regional housing goal to the Southern California Association of Governments (SCAG). SCAG was then required to allocate the housing goal to each jurisdiction within the region through a RHNA Plan. In allocating the region's future housing needs to jurisdictions, SCAG is required to take the following factors into consideration pursuant to Section 65584 of the State Government Code:

- Market demand for housing;
- Employment opportunities;
- Availability of suitable sites and public facilities;
- Commuting patterns;
- Type of tenure of housing;
- Loss of units in assisted housing developments;
- Over-concentration of lower income households; and
- Geological and topographical constraints.

HCD, through a determination process, allocates units to each region across California. It is then up to each region to determine a methodology and process for allocating units to each jurisdiction within that region. SCAG adopted its Regional Housing Needs Allocation (RHNA Plan) in March 2021. The RHNA covers an 8-year planning period (starting in 2021) and addresses housing issues that are related to future growth in the region. The RHNA allocates to each city and county a “fair share” of the region's projected housing needs by household income group. The major goal of the RHNA is to assure a fair distribution of housing among cities and counties within the SCAG region, so that every community provides an opportunity for a mix of housing for all economic segments.

Arcadia's share of the SCAG regional growth allocation is 3,214 new units for the current planning period (2021-2029). **Table 3-40** Housing Needs for 2021-2029, indicates the City's RHNA need for the stated planning period.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 3-40: Housing Needs for 2021 – 2029

Income Category	Percent of Median Family Income (MFI)	Arcadia's RHNA Allocation for the 2021 – 2029 Planning Period
Very Low Income	0-50% MFI	1,102
Low Income	51-80% MFI	570
Moderate Income	81-120% MFI	605
Above Moderate Income	>120% MFI	937
Total		3,214

Summary of Sites Inventory and RHNA Obligations

Table 3-41: Summary of RHNA Status and Sites Inventory

	Very Low Income	Low Income	Moderate Income*	Above Moderate Income	Total
RHNA (2021-2029)	1,102	570	605	937	3,214
Remaining Unmet RHNA	1,102	570	605	937	3,214
Unit Capacity on Site Inventory					
Pipeline Projects	81		~~080~~	974	~~1,055~~ 135
Existing Residentially Zoned Land	~~2737~~		~~1607~~ 112	~~6476~~ 12702	~~1,0911,091~~ 1045
Accessory Dwelling Unit Projection	~~148~~ 185		~~56~~	~~658~~ 1	~~217~~ 272
Remaining RHNA	~~1,166~~ 1,1291,170		~~433~~ 407440	~~---~~ 0	~~1,600~~ 1,5361 ,611
Rezone Strategies					
Downtown Mixed-Use	~~342~~ 352		~~205~~ 137	~~80~~ 482	~~1,362~~ 1,361
Mixed-Use Upzone	~~133~~ 2		~~765~~ 676	~~317~~ 293	~~505~~ 502
Live Oak and Las Tunas Residential Flex Overlay	~~221~~ 233		~~139~~ 5131	~~575~~ 499	~~903~~ 851
C-G Residential Flex	~~22~~ 40		~~130~~ 9389	~~560~~ 516	~~869~~ 870
R-3 Upzone	~~165~~ 4		~~97~~ 68	~~404~~ 373	~~635~~ 636
Arcadia Golf Course	~~80~~ 50		~~00~~	~~106~~ 136	186
Rezone Strategies Potential Development Capacity	~~1,171~~ 1,141		~~610~~ 445639	~~2,679~~ 2,8742 591	~~4,460~~ 4,1604 ,405
Total Potential Development Capacity	~~1,677~~ 1,684		~~782~~ 643804	~~4,365~~ 4,6314 ,242	~~6,823~~ 6,9586 ,722
Sites Surplus/Shortfall	~~+5~~ +12		~~+199~~ 77+38	~~+3,305~~ ~~+3,428~~ +3,69 4	--
Percentage Buffer	~~0%~~ 1%		~~332~~ 9%6%	~~353~~ 66%394 %	--



CITY OF ARCADIA 6TH CYCLE Housing Element Update

5. Financial Resources

Providing an adequate supply of decent and affordable housing requires funding from various sources, the City has access to the following funding sources.

A. Section 8 Housing Choice Voucher

The Section 8 Housing Choice Voucher Program is a Federal government program established by the 1974 Housing and Community Development Act to assist very low income families, the elderly, and the disabled with rent subsidy payments in privately owned rental housing units. Section 8 participants are able to choose any housing that meets the requirements of the program and are not limited to units located within subsidized housing projects. They typically pay 30 to 40 percent of their income for rent and utilities. The Los Angeles Housing Authority Administers Section 8 Housing Choice vouchers within the City. In 2020 the County allocated 101 Section 8 vouchers to residents in the community.

B. Grants and Programs

The City receives a variety of financial resources towards expanding economic opportunities for the community of Arcadia.

Community Development Block Grants (CDBG)

The Community Development Block Grant (CDBG) program provides annual grants on a formula basis for cities to develop viable urban communities by providing suitable living environments and expanding economic opportunities, primarily for low and moderate income persons (up to 80% AMI). CDBG funds can be used for a wide variety of activities, including:

- Housing rehabilitation;
- Lead-based paint screening and abatement;
- Construction or rehabilitation of public-facilities and infrastructure; and
- Public services for low income households and those with special needs.

San Gabriel Valley Regional Housing Trust

The City has participated in the San Gabriel Valley Regional Housing Trust (SGVRHT) since 2020. This housing trust allows San Gabriel Valley cities to work together in order to build affordable housing.³⁹ The Trust has sought funds, which would be matched, to retain, build, and or support affordable housing in the City and region.

CalCHA and CSCDA-CIA

The City Council adopted resolutions to join two newly formed Housing Authorities, CalCHA and CSCDA-CIA. These authorities create middle income multifamily housing through the

Create opportunity to create middle income multifamily housing through issuance of tax-exempt bonds to acquire existing apartment buildings. Units acquired are converted to rent restricted housing for middle income households earning no greater than 120% of Area Median Income with rent capped at no...

Proposed acquisition

³⁹ San Gabriel Valley Housing Trust. Available at <https://www.sgvrht.org/about>. Accessed on September 7, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

C. Opportunities for Energy Conservation

The primary uses of energy in urban areas are for transportation lighting, water heating, and space heating and cooling. The high cost of energy demands that efforts be taken to reduce or minimize the overall level of urban energy consumption. Energy conservation is important in preserving non-renewable fuels to ensure that these resources are available for use by future generations. There are also a number of benefits associated with energy conservation including improved air quality and lower energy costs.

Title 24

The City abides to Title 24 standards as mandated by the State. Title 24 establishes energy efficiency standards for residential and nonresidential buildings (new structures and additions) to reduce energy consumption. The standards are updated every three years to achieve greater efficiency and reach for new goals.

Energy Use and Providers

The Clean Power Alliance (CPA) is the new electricity generation provider for the City of Arcadia. The CPA is a nonprofit entity, formed to bring clean, renewable power choices to the communities it serves. The Clean Power Alliance purchases clean power which is delivered to residents through Southern California Edison (SCE). The City of Arcadia has selected CPA's Lean Power as the default option for the community, which provides 36 percent clean power. The SCE is still responsible for delivering grid reliability and resolving any issues with electricity service. Currently, SCE has no immediate plans for expansion of infrastructure. However, every year SCE expands and improves existing facilities according to demand.

The Southern California Gas Company (SCGC) provides natural gas service for the City. Natural gas is a "fossil fuel" and is a non-renewable resource. Most of the major natural gas transmission pipelines within the City are owned and operated by SCGC. SCGC has the capacity and resources to deliver gas except in certain situations that are noted in state law. As development occurs, SCGC will continue to extend its service to accommodate development and supply the necessary gas lines.



CITY OF
ARCADIA

Technical Background Report

Section 4

Review of Past Performance





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Section 4: Review of Past Performance

Program Evaluation for Households with Special Needs

As part of analyzing prior programs, this Appendix A must provide an outline of the effectiveness of goals, policies, and programs in meeting the housing needs of Arcadia's special needs populations. The following section identifies 5th Cycle accomplishments by special needs groups.

Seniors

Section 2: Community Profile of the Technical Background Report shows that 19.08 percent (11,905 residents) of Arcadia residents are over the age of 65. A variety of housing types have been made available to seniors in the City. The table below shows what types and where senior housing is permitted:



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table 1: Senior Housing Types Permitted in Arcadia

Land Uses																			
Housing Types	Residential						Commercial			Industrial	Downtown Zones					Special Purpose Zones			
	R-M	R-0	R-1	R-2	R-3	R-3R	C-O	C-G	C-R	M-1	CBD	MU	DMU	C-M	PF	OS-OR	OS-RP	RR	S-1
Residential Care Facility - Six or fewer persons	P	P	P	P	P	P	NA	NA	NA	NA	-	-	P	P	NA	NA	NA	NA	NA
Residential Care Facilities - Seven or More Persons	NA	NA	NA	NA	NA	NA	C	C	-	-	NA	NA	NA	NA	NA	NA	NA	NA	NA
Supportive Housing - Housing Type	-	-	-	P	P	P	NA	NA	NA	NA	M (UF)	M (UF)	M (UF)	-	NA	NA	NA	NA	NA
Supportive Housing - Residential Care Facility Small Type	P	P	P	P	P	P	NA	NA	NA	NA	-	-	C	C	NA	NA	NA	NA	NA
Supportive Housing - Residential Care Facility Large Type	NA	NA	NA	NA	NA	NA	C	C	-	-	NA	NA	NA	NA	NA	NA	NA	NA	NA



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Notes:

P – Permitted

A – Permitted as an Accessory Use

M – Minor Use Permit Required

C – Conditional Use Permit Required

(UF)- Uses are Permitted on Upper Floor only

NA- No Information

Source: City of Arcadia Municipal Code, Division 2: Zones, Allowable Uses, and Development Standards



CITY OF ARCADIA 6TH CYCLE Housing Element Update

During the 5th Cycle, the City committed to offering low income homeowners, such as some senior households, grants up to \$20,000 for home rehabilitation. From 2017-2020, 48 grants were issued to households to make necessary improvements to their homes. During the 5th Cycle, the City also monitored 100 affordable housing units at Naomi Gardens in order to ensure their availability to low income elderly mobility impaired residents. The Housing Choice Voucher Program extends rental subsidies to extremely low and very low income households, including families, seniors, and the disabled. The Los Angeles County Housing Authority provided Housing Choice Vouchers to 385 households from 2017 to 2020 in Arcadia.

Persons with Disabilities

Persons with disabilities may require varying accessibility improvements and may also have a limited ability to earn adequate income. According to 2019 ACS data, about 17.37 percent of Arcadia residents have at least one disability. Of that percentage, approximately 26.43 percent have an ambulatory difficulty. The following most common disabilities in Arcadia are independent living and self-care difficulties.

During the 5th Cycle, the City committed to facilitating the development of affordable housing for persons with disabilities. In order to bring barriers to fair housing down, the City revised and updated its Reasonable Accommodation ordinance in 2016. Additionally, the City committed to offering low income homeowners grants up to \$20,000 for home rehabilitation. From 2017-2020, 48 grants were issued to households to make necessary improvements to their homes.

Low income families with persons with disabilities may qualify for Housing Choice Vouchers. As noted above, the Los Angeles County Housing Authority provided Housing Choice Vouchers to 385 households from 2017 to 2020 in Arcadia.

Large Households

Large households consist of five or more residents and may have a harder time finding adequately sized units to avoid overcrowding. **Section 2** of this Housing Element shows that approximately 2,179 households in Arcadia had five or more members, this includes 1,429 5-person households, 408 6-person households, and 342 7-or-more person households.

During the 5th cycle, the City committed to offering low income homeowners grants up to \$20,000 for home rehabilitation. From 2017-2020, 48 grants were issued to households to make necessary improvements to their homes. Large, lower income families may qualify for Housing Choice Vouchers. As noted above, the Los Angeles County Housing Authority provided Housing Choice Vouchers to 385 households from 2017 to 2020 in Arcadia.

Farmworkers

Farmworkers include persons seasonally or permanently employed in the agricultural industry and generally earn lower incomes than many other workers. While the City does not have agriculture, the Santa Anita Racetrack brings in seasonal racetrack workers in to live and work on the site. The racetrack provides housing for those who work with horses, backstretch workers, and more. This is a special population that is



CITY OF ARCADIA 6TH CYCLE Housing Element Update

unique to Arcadia and perhaps several additional cities in the State. The City has identified this group as a special needs population that faces challenges with regards to affordable housing and living conditions.

Lower income families may qualify for Housing Choice Vouchers. As noted above, the Los Angeles County Housing Authority provided Housing Choice Vouchers to 385 households from 2017 to 2020 in Arcadia.

Single-Parent Households

Single-parent households often require special consideration and assistance due to their greater need for affordable and accessible day care, health care, and other supportive services. Single parents make up 4,323 of Arcadia households, with 76.7 being single mothers and 23.3 percent being single fathers. Approximately 20 percent of single mother households are considered to be living under the poverty line.

Lower income families may qualify for Housing Choice Vouchers. As noted above, the Los Angeles County Housing Authority provided Housing Choice Vouchers to 385 households from 2017 to 2020 in Arcadia.

The City of Arcadia offers a variety of community resources for children and single-parents in the community. Children in Arcadia are served by three school districts—Arcadia Unified School District, El Monte Union High School District, and El Monte City Elementary School District. The Arcadia Unified School District is a nationally renowned public school district that proudly educates more than 9,000 students throughout 11 award-winning schools. Programs and strategies, such as [The Leader in Me](#), [Universal Design for Learning \(UDL\)](#), [Restorative Practices](#), Multi-Tiered System of Support (MTSS) and more are implemented district-wide. In 2006, the Arcadia community demonstrated its generosity and its commitment to education by passing a [\\$218 million bond measure](#) for the refurbishment and modernization of school facilities across the District. Through this grant, school technology and renovated all classrooms, libraries/media centers, science labs, sports/recreation facilities, and arts and music education spaces, creating high-tech classrooms and learning environments were upgraded throughout the entire district. As of 2021, Arcadia Unified is continuing to upgrade its facilities, technology, classrooms, and campuses thanks to this bond measure. El Monte Union High School District provides educational programs for over 8,000 students in grades 9 through 12 and 11,000 in adult education. El Monte Union High School District provides opportunities for students to prepare for college applications and has its own career center to help students find their paths after school. El Monte City Elementary School District serves proximately 8,300 students with fourteen schools, which include five California Distinguished Schools and six ERP Honor Roll Schools. These schools serve children ages K-6 or K-8. There is also one special setting at Thompson School with students being mainstreamed as appropriate into Durfee Elementary School's classes as they sit on the same campus. The district also offers Federal Head Start/State Pre-School classes and the Opportunity Program for students who require an alternative educational setting.

Persons Experiencing Homelessness

Homelessness has become an increasingly important issue in the region and throughout the State of California. There are a number of factors that may contribute to a person experiencing homelessness; **Section 2: Community Profile** provides a detailed definition of “homelessness” and an analysis of the City and County’s unhoused population. From November to December 2021, the City of Arcadia implemented a



CITY OF ARCADIA 6TH CYCLE Housing Element Update

comprehensive census of Arcadia's unhoused individuals. Over the two month period, census teams encountered 79 individuals experiencing homelessness within the City and 55 individuals participated in the survey.

In 2018, the City adopted the Five Year Homelessness Plan. The plan outlines several Strategic Goals, including training first responders, strengthening the Coordinated Entry System, enhancing the Emergency Shelter System, partnering with other cities to expand Rapid Rehousing, and expanding the Countywide Outreach System.

Extremely Low Income Households

Extremely low income households are those that earn 30 percent or less of the household median family income (HMFII) for Orange County. Extremely low income households may require rental assistance and other community services assistance. According to CHAS data, there are approximately 2,115 extremely low income households in Arcadia, including both renters and homeowners.

Extremely low income families may qualify for Housing Choice Vouchers. As noted above, the Los Angeles County Housing Authority provided Housing Choice Vouchers to 385 households from 2017 to 2020 in Arcadia.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Review of 5th Cycle Programs

The following chart is a review of the City of Arcadia's housing project and program performance in the 2013-2020 Planning Period. It is an evaluation of the 5th Cycle's Policy Program and considers the City's progress towards completing all programs outlined within the 5th Cycle Housing Element.

Name of Program	Objective	Program Accomplishments	Status for Sixth Cycle
5-1 Home Rehabilitation	Maintain the City's housing stock by offering low income homeowners grants up to \$18,000 to make necessary home improvements including plumbing, electrical, roofing, termite control, painting, energy improvements and accessibility improvements.	The City made minor modifications to the program during the 5th Cycle. Most recently, the City Council authorized an increase in the maximum grant for single-family homes from \$15,000 to \$20,000 and for condominiums from \$10,000 to a maximum of \$15,000. From 2017 to 2020, approximately 10 – 13 grants were issued to qualified homeowners each year and a total of 48 homeowners during this time frame have received grants.	Continued. The City of Arcadia has been successful in assisting an estimated 13 households per year within the 5 th cycle. The City understands that safe and adequate housing is essential for healthy living, and that home rehabilitation assistance can help increase access to healthy homes and support the ability for residents to age in place in appropriate living situations. The City will continue to incorporate the homeowner grants available during the 6 th cycle.
5-2 Code Enforcement	Implement adopted regulations aimed at property maintenance in a manner that is helpful to homeowners and property owners to maintain beautiful neighborhoods and high property values.	The City's Code Enforcement department continues to provide code enforcement activities and connect households with City rehabilitation programs and provides proactive code enforcement of vacant properties in an effort to resolve code violations. In addition, the City banned Air BNB's in an effort to keep housing units for housing purposes. From 2018 to 2020, the City received approximately 1,000 property maintenance code enforcement cases	Continued. It is necessary for the City to respond to and enforce building code and safety requirements. Code enforcement supports safe, accessible, and sanitary housing opportunities. The City will continue to address noncompliant properties through existing methods as well as new methods should they become available during the 6 th cycle.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Name of Program	Objective	Program Accomplishments	Status for Sixth Cycle
		each year. Approximately 600 of these cases were related to housing maintenance.	
5-3 Residential Design Guidelines	Preserve neighborhood character and encourage high-quality residential design throughout the city through the implementation of Residential Design Guidelines for single-family and multifamily development.	The City continues to implement the Design Guidelines during the City's architectural design review process of single-family and multifamily development applications. In October 2019, the City updated the City's Residential, Non-Residential and Signage Design Guidelines and created new Guidelines for Mixed-Use Developments. The City also implemented a City Center Design Plan for the Downtown Area.	Continued. The City will continue to review and encourage high-quality residential design that will enhance the City's character and the quality of life. The program was ongoing in the 2014-2021 planning period and will continue into the 2021-2029 planning period.
5-4 Preservation of At-Risk Units	Monitor status of units at-risk of losing their affordability and converting to market-rate.	The City continues to monitor Naomi Gardens, which provides 100 units affordable to very low and low income elderly mobility impaired households, on annual basis by maintaining contact with the property owner and HUD Multifamily Housing division to ensure continued funding through the Section 8 program.	Continued. The City monitored Naomi Gardens through the 5th cycle and will continue to monitor the property on an annual basis to ensure that it remains affordable through the 6th cycle. The City will continue to work with property owners to maintain and preserve exiting affordable housing stock. Naomi Gardens has received LIHTC funding.
5-5 Residential Sites Inventory	Maintain an inventory of vacant and underutilized properties with the appropriate densities and development standards to accommodate the remaining Regional Housing Needs Assessment of 1,054 units.	The City annually updates the inventory of vacant and underutilized sites, provides inventory to interested developers and monitors development trend in the City.	Continued. The City will continue to make available appropriate sites to accommodate their RHNA allocations and will continue to provide information to interested developers. Annual reports will be prepared throughout the planning period and the program will be included in the 6 th cycle.
5-6 Lot Consolidation Initiatives	Incentivize the process to consolidate lots to provide housing opportunity sites by	The City's fee schedule was updated to include the fee waiver to incentivize the consolidation process. In addition,	Continued: The City adjusted the fee schedule, waiver, and shortened the processing time when possible to incentivize lot consolidation



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Name of Program	Objective	Program Accomplishments	Status for Sixth Cycle
	streamlining the Lot Line Adjustment process, which can consolidate four or fewer lots without the need of a public hearing or discretionary action; by offering fee waivers and priority in permit processing.	the City continues to streamline the consolidation process through its Lot Line Adjustment process by providing short processing times (10 business days), however, some of the Lot Line Adjustment applications are accompanied by various other development applications which cannot be processed in that short timeframe.	during the 5th cycle. The City will continue to promote the lot consolidation program through the 6th cycle and will work with developers to utilize the program to increase housing options, specifically affordable housing, in the City.
5-7 Section 8 Housing Choice Voucher Program	Participate in HUD's Section 8 Housing Choice Voucher Program, administered by the Los Angeles County Housing Authority, to provide assistance to extremely low and very low income households by paying the difference between 30% of the household income and the cost of rent.	The City continues to participate in the Section 8 Housing Choice Voucher program through the Los Angeles County Housing Authority. The City provides specific information about the Section 8 program, but forwards inquiries for participation to the Los Angeles County Housing Authority for further processing. From 2017 – 2020 approximately 385 households received vouchers and approximately 50 – 60 households were on the waiting list each year.	Continued: Arcadia participated in Los Angeles County Housing Authority's Section 8 Voucher program in the 5th cycle and will continue to do so in the 6th cycle. The City recognizes the importance of housing support programs and will continue to advertise and provide information about the program.
5-8 Affordable Housing for Families and Persons with Special Needs	Facilitate the development of housing affordable to persons with disabilities, including persons with development disabilities.	The City continues to explore affordable housing opportunities when presented and encourage housing developers to include accessibility for individuals with disabilities in their project designs. In addition, the City updated the Reasonable Accommodation ordinance in 2010, and again under the Development Code update, that was adopted on November 15, 2016.	Continued: The program was ongoing during the 5th cycle. The City will continue to promote the adopted ordinance to housing developers during the 6th Cycle to ensure the development of affordable housing to those with disabilities. The City will also continue to investigate ways to lower barriers and distribute information regarding the development of housing for people with disabilities during the 6 th Cycle.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Name of Program	Objective	Program Accomplishments	Status for Sixth Cycle
5-9 Housing Sustainability	Provide programs that promote sustainable development in the City.	Through the development process, the City continues to enforce City building codes and ordinances, including Green building codes, construction recycling, water efficiency and sustainable Arcadia education program to enhance energy efficiency in residential construction and maintenance.	Continued: The City established the Sustainable Arcadia educational programs and enforced green building codes during the 5th cycle. The City provides information on water conservation and several environmental programs to promote and support sustainability on the City's website. The City also provides the current California Green Building Standards Checklist for residential and commercial development through the City website. The City recognizes the need to work toward more sustainable development to protect the environment and will continue to do so during the 6th cycle.
5-10 Residential Neighborhood Integrity	Preserve the City's residential neighborhood integrity by addressing commercial housing uses such as birthing homes, boarding homes, single-room occupancy housing, and similar uses in residential zones.	The City's updated Development Code was adopted on November 15, 2016 which addressed location and development standards for single-room occupancy housing and classified birthing hotels as boarding homes which are prohibited in City per the updated Development Code. In addition, short-term rentals are not allowed in the City.	Completed: The City updated the Development Code to address the uses listed within the 5 th cycle, as it will remain moving forward.
5-11 Fair Housing	Provide information to residents, landlords of residential property and other professionals involved in the insurance, construction, sale or lease of residential property of the laws pertaining to fair housing by contracting with the Housing Rights Center.	The City continues to contract with HRC to provide fair housing services to residents. The City also provides information on fair housing programs, HRC and services provided by the City through the City newsletter and community events, including the annual Senior Fair.	Continued: The City of Arcadia contracts with HCR who provides information to residents on fair housing services during the 5 th cycle. The City acknowledges the importance of fair housing access for a community, and the City is committed to understanding and mitigating fair housing issues that may arise. The City provides HRC contact information and shares informational flyers provided by the HRC on the City website.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Name of Program	Objective	Program Accomplishments	Status for Sixth Cycle
			The City will continue to contract with HCR during the 6th cycle to provide necessary and appropriate fair housing resources and information to the community.
5-12 Transitional and Supportive Housing	Amend City zoning ordinance to be in accordance with Government Code Section 655839(a)(5) to consider transitional housing and supportive housing as a residential use of property.	The City's updated Development Code was adopted on November 15, 2016 which included provisions to accommodate transitional and supportive housing as a residential use and defined both terms in accordance with Government Code Section 65582.	Completed: The City updated the Zoning Ordinance in accordance with Government Section 655839(a)(5) within the 5 th cycle, as it will remain moving forward. Going forward with the 6 th Cycle, the City will ensure that the use table is amended so ensure that the use table is amended to allow supportive and transitional housing is otherwise permitted.



CITY OF
ARCADIA

Technical Background Report

Appendix A

Adequate Sites





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Appendix A: Adequate Sites

Adequate Sites Analysis Overview

The Housing Element is required to identify potential candidate housing sites by income category to meet the City's RHNA Allocation. The sites identified within the Housing Element represent the City of Arcadia's plan for housing at the designated income levels within the 6th housing cycle planning period (2021 – 2029). The identified sites are either residentially zoned at a minimum of 30 du/acre or within Focus Areas identified by the City with supporting strategies to stimulate future housing growth. As described in this appendix, the development capacity of each site depends on permitted density and specific assumptions identified for each Focus Area. Currently, there are ~~48-23~~ sites that meet the default density and ~~700-365~~ sites that will be rezoned or upzoned to meet the default density.

The appendix contains ~~Table A-24~~ Table A-242, which identifies each candidate housing site within Arcadia's sites inventory. The sites are identified by assessor parcel number (APN) as well as a unique identifier used to track sites within the inventory. Additionally, the following information is provided for each parcel.

- Address
- Ownership
- Zoning (including overlays if applicable)
- Size (net developable acres removing known development constraints)
- Assumed density
- Vacancy status
- Previous housing element identification
- Potential development capacity (dwelling units) by income category
- Description of existing use

Table A-1 shows the City's 2021-2029 RHNA need by income category as well as a summary of the sites identified to meet the need. The analysis within this appendix shows that the City of Arcadia has the capacity to meet their 2021-2029 RHNA allocation through a variety of methods, including:

- Identification of development capacity on sites which permit development of residential uses at or above 30 dwelling units per acre
- Development of approved projects which do not have certificates of occupancy (Pipeline Projects)
- Future development of Accessory Dwelling Units (ADUs)
- Identification of residential property for rezone to higher-density residential use
- Identification of non-residential property for rezone to residential use
- Identification of property with expressed developer interest



CITY OF ARCADIA 6TH CYCLE Housing Element Update


Table A-1: Summary of RHNA Status and Sites Inventory

	Very Low Income	Low Income	Moderate Income*	Above Moderate Income	Total
RHNA (2021-2029)	1,102	570	605	937	3,214
Unit Capacity on Site Inventory					
Pipeline Projects	81		~~800~~	974	1, ~~135~~ <u>055</u>
Existing Residentially Zoned Land	~~27~~ <u>37</u>		~~112~~ <u>1607</u>	~~702~~ <u>647612</u>	~~1,091~~ <u>1045</u>
Accessory Dwelling Unit Projection	~~185~~ <u>148</u>		~~65~~	~~81~~ <u>65</u>	~~272~~ <u>217</u>
Remaining RHNA	~~1,129~~ <u>1,166</u> <u>1170</u>		~~407~~ <u>433440</u>	--	~~1,536~~ <u>1,611</u> <u>0</u>
Focus Areas					
Downtown Mixed-Use	~~35~~ <u>242</u>		~~205~~ <u>137205</u>	~~88~~ <u>2804</u>	~~1,362~~ <u>11361</u>
Mixed-Use Upzone	~~132~~ <u>133</u>		~~76~~ <u>5676</u>	~~317~~ <u>293</u>	~~505~~ <u>502</u>
Live Oak and Las Tunas Residential Flex Overlay	~~233~~ <u>221</u>		~~139~~ <u>95131</u>	~~575~~ <u>499</u>	~~903~~ <u>851</u>
C-G Residential Flex	~~220~~ <u>224</u>		~~93~~ <u>89130</u>	~~560~~ <u>516</u>	~~869~~ <u>870</u>
R-3 Upzone	~~164~~ <u>165</u>		~~97~~ <u>6897</u>	~~404~~ <u>373</u>	~~635~~ <u>635</u>
Arcadia Golf Course	~~50~~ <u>80</u>		0	~~136~~ <u>106</u>	186
Rezone Strategies Potential Development Capacity	~~1,171~~ <u>411,175</u>		~~445~~ <u>610639</u>	~~2,874~~ <u>2,6792</u> <u>591</u>	~~4,160~~ <u>4,4604</u> <u>405</u>
Total Potential Development Capacity	~~1,677~~ <u>84</u>		~~643~~ <u>782804</u>	~~4,631~~ <u>4,3654</u> <u>242</u>	~~6,958~~ <u>6,8236</u> <u>722</u>
Sites Surplus/Shortfall	~~+12~~ <u>+5</u>		~~+38~~ <u>177199</u>	~~+3,428~~ <u>6943</u> <u>05</u>	--
Percentage Buffer	~~1%~~ <u>0%</u>		~~6%~~ <u>2933%</u>	~~394%~~ <u>36653</u> <u>%</u>	--



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-1: Sites Inventory





CITY OF ARCADIA 6TH CYCLE Housing Element Update

1. Selection of Sites

The City of Arcadia has identified sites with capacity to accommodate the 2021-2029 RHNA. The identified sites were evaluated based on surrounding and existing on-site development to determine the extent to which on-site uses have the potential to redevelop within the planning period (2021-2029). The City has also conducted an analysis to identify non-residentially zoned sites with characteristics indicating they have the potential to redevelop within the planning period. Through the analysis of existing residentially zoned sites, the City has identified 23 properties at their existing densities and six “Focus Areas” to apply strategies and programs to allow for and encourage the development of residential uses. The City has identified the following number of properties as part of specific Focus Areas to accommodate the 6th cycle RHNA:

- 27 parcels as part of the Downtown Mixed-Use Expansion strategy
- 16 parcels as part of the Downtown Mixed-Use Overlay strategy
- ~~60~~59 parcels as part of the Mixed-Use Upzone Strategy
- ~~37~~9 parcels as part of the Las Tunas and Live Oak Residential Flex Overlay strategy
- 57 parcels as part of the C-G Residential Flex Overlay strategy
- 165 parcels as part of the High Density Residential (R-3) Upzone strategy
- The Arcadia Golf Course redevelopment

2. Projects in the Pipeline

The City has identified a number of projects currently in, or that have completed the entitlement process. These projects are likely to be developed and/or first occupied during the planning period and count as credit towards the 2021-2029 RHNA allocation. The City has currently identified ~~134~~13 projects with a planned development of ~~1,135-0551,087~~ net units, ~~268~~1 of which will be affordable to Low and Very Low income households. These pipeline projects are projected to provide additional housing to the City have not yet been built and are in various stages of the development process. ~~Table A-2~~ Table A-2 below summarizes the details for each pipeline project.

Five of the Pipeline Projects described below are designated to accommodate affordable housing. All Pipeline Projects with units affordable to Low and Very Low income households and the units will be deed-restricted for this income category. Project ID 24, the Alexan Project, includes 26 units affordable to Low and Very Low income households and the units will be deed-restricted for this income category. ~~All pipeline projects with Project ID 26 includes 80 moderate income units that are senior housing units within an assisted living project. The designation of the affordability level for Project ID 26 was~~The affordability level of all Pipeline Projects have been agreed upon by both the City and the developer. The City will continue to work with the developer to ensure the affordability of these units for ~~moderate income~~low and very low income households.



Table A-2: Pipeline Projects

ID	Project APN's	Project Name	Acres	Existing General Plan Land Use	Existing Zoning	Extremely Low/Very Low Income	Low Income	Moderate Income	Above Moderate Income	Net Yield	Project Status
15,19, 3,4,6,7	5773-010-901,-007,-008,-018,-019,-020	Huntington Plaza Mixed-Use Project	1.56	DMU, C 1.0	DMU, CBD	0	0	0	139	139	Entitled – Building Plan Check Submittal Pending
26	5776-001-012	Artis Senior Living Senior Assisted Living Care Facility	2.82	C	C-G	9	9	89	9	89	Entitled – Building Plan Check Submittal Pending
17	5775-022-032	205 N. Santa Anita Ave	0.38	DMU	DMU	11	0	0	91	102	Planning Review
21	5783-002-013	901 W. Duarte	0.68	HDR	R-3	0	0	0	12	12	Entitled – Building Plan Check Submittal Pending
20, 25	5788-020-015, 5788-020-029	2607 S. Santa Anita	2.89	MDR	R-2	0	0	0	33	33	Entitled
10,9	8573-024-005, 8573-024-006	122-128 E. Live Oak Mixed-Use Project	0.41	MU	MU	0	0	0	12	12	Entitled
1, 2, 11, 12, 16, 22, 23	5775-025-029,-031,-032, -033,-037, -038, -034	25 N. Santa Anita Ave Mixed-Use Project	3.79	CBD, DMU	C 1.0 DMU	17	0	0	140	157	Planning Review
13	5772-002-001	921 N. Santa Anita Ave	0.34	HDR	R-3	0	0	0	2	2	Plan Check
8	5779-012-030	43 Genoa St	0.19	HDR	R-3	0	0	0	2	2	Plan Check
5	5779-010-010	141 Fano St	0.18	HDR	R-3	0	0	0	2	2	Plan Check
18	5778-010-017	1022 La Cadena	0.48	HDR	R-3	0	0	0	9	9	Plan Check
14	5779-019-007	416 Genoa St	0.36	MDR	R-2	0	0	0	1	1	Entitled – In Building Plan Check Review
24	5773-006-036	150 N. Santa Anita Mixed-Use Project	2.18	DMU	DMU	26	0	0	293	319	Scheduled for Hearing
27,28	5777-038-014, -012	Huntington Village Mixed-Use Project	11.52	C-G	C	27	0	0	222	248	Planning Review



CITY OF ARCADIA 6TH CYCLE Housing Element Update

3. Redevelopment of Non-Vacant Sites for Residential Use

The City of Arcadia does not have sufficient vacant land available to accommodate 50 percent of the low/very-low income RHNA. According to SCAG's HELPR tool, there are no vacant sites within the City that meet the 0.5 to 10 acre HCD sizing criteria. To accommodate the housing need at all income levels, the City has analyzed sites that currently permit residential development as well as the re-zoning of a number of sites that are not currently zoned as residential.

As part of the candidate housing sites analysis, the City has evaluated recent projects that have redeveloped on non-vacant sites to include residential units. Those projects, including the zoning, land use prior to redevelopment, and a project analysis of the approved development plan, are shown in **Table A-3**. While the City understands that it does not have a history of affordable development on small sites, the City will adopt an Inclusionary Policy (Program 5-19) as a mechanism to ensure the development of affordable units.

The City has also conducted a parcel specific analysis of existing uses for each of the identified sites. This analysis of existing uses, including indicators of a likelihood that the existing use could redevelop within the next eight years, is provided in **Table A-322**. This analysis is based on information readily available to the City, existing use data, and other information that can be found through online research. As part of the site selection process, the City analyzed existing residentially zoned parcels that have propensity to develop at their existing densities. The City identified 23 parcels to accommodate a total of 1,091 units, 277 of which can accommodate Low and Very Low income households. The history of redevelopment presented in Table A-3 factored into the development of the City's focus areas and informed the potential of the development of non-vacant sites for residential use. Additionally, Table A-24 presents the sites inventory along with a description of existing use and a justification explaining the factors considered in the selection of the site and why the site is a viable candidate for the inventory.

In addition to sites that can accommodate housing at their existing capacity, the City identified six Focus Areas that would benefit from residential development to apply strategies such as upzoning and rezoning to achieve the remaining unmet RHNA.

Table A-3: Example Development of Non-Vacant Sites for Residential Uses

Project Address/ APN	Dwelling Units	Zoning	Use Prior to Redevelopment	Project Analysis
57 Wheeler Avenue	38	Downtown Mixed-Use	Commercial	The project required approval of a Conditional Use Permit, Tentative Parcel Map, and Architectural Design Review applications for a mixed-use development consisting of three stories of 38 residential apartment units over 17,850 square feet of ground floor commercial. The property was previously developed with a restaurant and parking lot. Construction has been completed.
56 E. Duarte Road APN: 5781-005-036	37	Mixed-Use	Commercial	The project required approval of General Plan Amendment, Zone Change, Conditional Use Permit, Tentative Tract Map, and



CITY OF ARCADIA 6TH CYCLE Housing Element Update

				Architectural Design Review applications for a mixed-use development consisting of two stories of 37 residential condominium units over 19,360 square feet of ground floor commercial. The property was previously developed with a commercial building and parking lot. Construction has been completed
17 Las Tunas APN: 5788-020-030 & 5788-020-031	77 MF Units 3 Live Work Units	Mixed-Use	Commercial	The project required approval of a Planned Development, Tentative Tract Map, Lot Line Adjustment, Multiple-Family Architectural Design Review, Protected Tree Encroachment and Protected Healthy Tree Removal applications for 77 residential condominium units, three (3) live/work unit with 2,487 SF of commercial space, and 8,500 square feet of ground. Construction has been completed.
180 W. Huntington Drive APN: 5775-024-023	96	SP-SP	Commercial	The project required approval of a Specific Plan, General Plan Amendment and Zone Change applications to allow a hotel and a 50-unit condominium development. Subsequent modifications to the specific plan changed the condominium development to a mixed-use project and increase the number of units from 50 to 96 units. Project has been entitled and construction plans have been approved for permit issuance.
117-129 E. Huntington Drive & 124-134 Wheeler Avenue APNs 5773-010-007 – 008, 5773-010-901, -018, -019, -020, and -021.	139	Central Business District & Downtown Mixed-Use	Commercial	The project required approval of a Minor Use Permit, Major Administrative Modification, Architectural Design Review, and Vesting Tentative Tract Map applications for the mixed-use development consisting a 4 and 5 story building with 139 residential condominium units over 10,000 square feet of ground floor commercial. The project has been



CITY OF ARCADIA 6TH CYCLE Housing Element Update

				entitled and is in plan check review with Building Services.
656 W. Huntington Dr APN: 5778-001-137 - 170	34	R-3	Commercial	The project required approval of an Architectural Design Review, Modification, and Tentative Tract Map applications a 34-unit condominium residential development. Construction has been completed.
968 - 998 Arcadia Ave APN: 5783-002-112 - 129	28	R-3	28-unit Multi-Family Development	The project required approval of an Multiple-Family Architectural Design Review and Tentative Tract Map applications for a 28-unit condominium residential development. Construction has been completed.
919 Fairview Ave APN: 5783-006-087 - 098	12	R-3	One Single Family Dwelling & an eight-unit Multi-Family Development	The project required approval of an Multiple-Family Architectural Design Review, Protected Tree Encroachment, and Tentative Tract Map applications for a 12-unit condominium residential development. Construction has been completed.
736 – 738 Camino Real Ave APN: 5383-029-041 - 058	18	R-3	Four Single Family Dwellings & a four-unit Multi-Family Development	The project required approval of an Multiple-Family Architectural Design Review and Tentative Tract Map applications for an 18-unit condominium residential development. Construction has been completed.
330 - 340 Genoa St APN: 5779-019-124 - 129	6	R-2	Six-unit Multi-Family Development	The project required approval of an Multiple-Family Architectural Design Review and Tentative Tract Map applications for a 6-unit condominium residential development. Construction has been completed.
825 Arcadia Ave APN: 5783-014-088 - 105	18	R-3	18-unit Multi-Family Development	The project required approval of an Multiple-Family Architectural Design Review and Tentative Tract Map applications for an 18-unit condominium residential development. Construction has been completed.
506 - 586 S. 2 nd Ave	20	R-2	Church	The project required approval of an Multiple-Family Architectural Design Review, Protected Tree



CITY OF ARCADIA 6TH CYCLE Housing Element Update

APN: 5779-008-065 - 080				Encroachment and Tentative Tract Map applications for a 20-unit condominium residential development. Construction has been completed.
598 - 608 S. 2 nd Ave APN: 5779-008-041 - 049	8	R-2	8-unit Multi-Family Development	The project required approval of a Multiple-Family Architectural Design Review and Tentative Tract Map applications for an 8-unit condominium residential development. Construction has been completed.
415 California St APN: 5773-016-188 - 207	20	R-3	10-unit Multi-Family Development	The project required approval of a Multiple-Family Architectural Design Review and Tentative Tract Map applications for a 10-unit condominium residential development. Construction has been completed.
627 - 633 Fairview Ave APN: 5778-002-053 - 064	12	R-3	3-unit Multi-Family Development	The project required approval of a Multiple-Family Architectural Design Review and Tentative Tract Map applications for a 3-unit condominium residential development. Construction has been completed.
501 N. Santa Anita Ave APN: 5775-027-031 - 050	20	R-3	Church	The project required approval of a Multiple-Family Architectural Design Review, Variance, Modification, Protected Tree Encroachment and Tentative Tract Map applications for a 20-unit condominium residential development. Construction has been completed.
414 S. 2 nd Ave APN: 5779-004-023	6	R-2	4-unit Multi-Family Development	The project required approval of a Multiple-Family Architectural Design Review, Healthy Tree Removal, Protected Tree Encroachment and Tentative Tract Map applications for a 6-unit condominium residential development. The project is under construction.
901 W. Duarte Rd APN: 5783-002-013	13	R-3	Single Family Dwelling	The project required approval of a Multiple-Family Architectural Design Review, Healthy Tree Removal, Protected Tree Encroachment and Tentative Tract Map applications for a 13-unit condominium residential



CITY OF ARCADIA 6TH CYCLE Housing Element Update

				development. The project has been entitled.
All developments listed in Table A-3 above were developed for market rate housing. While the City understands that it does not have a history of affordable development on small sites, the City will adopt an Inclusionary Policy (Program 5-19) as a mechanism to ensure the development of affordable units.				

Summary of Redevelopment Assumptions for Infill and Mixed-Use Sites

For parcels that are not currently residentially zoned, the City utilized the SCAG HELPR and local data to conduct additional analysis. The City analyzed the following factors to better understand and demonstrate the realistic development potential for parcels within each strategy:

- When ratio of improvement assessed value to land value is less than 1
- Structures built prior to 1985

These factors were used to develop the redevelopment percentages applied to the realistic capacity calculations. The table below describes the number of parcels identified with propensity to redevelop.

<u>Table A-4: Redevelopment Assumptions for Infill and Mixed-Use Sites</u>				
<u>Focus Area</u>	<u>Lower Valued Commercial/Retail¹</u>	<u>Built Before 1985</u>	<u>Percentage of Sites With at Least One Factor</u>	<u>Redevelopment Percentage²</u>
<u>Downtown Mixed-Use Expansion and Downtown Mixed-Use Overlay</u>	<u>16</u>	<u>20</u>	<u>47%</u>	<u>50%</u>
<u>Mixed-Use Upzone</u>	<u>49</u>	<u>51</u>	<u>85%</u>	<u>50%</u>
<u>Las Tunas and Live Oak Residential Flex Overlay</u>	<u>24</u>	<u>32</u>	<u>82%</u>	<u>100%</u>
<u>C-G Residential Flex Overlay</u>	<u>45</u>	<u>52</u>	<u>91%</u>	<u>50%</u>
<u>R-3 Upzone</u>	<u>114</u>	<u>114</u>	<u>69%</u>	<u>25%</u>
¹ When the ratio of improvement assessed value to land value is less than 1				
² A reduction factor applied to the calculated capacity to account for the likelihood of conversion to higher density housing				

The redevelopment assumptions listed in the table above were identified for each focus area based on the analysis of land value ratios, age of existing structure, the history of development in the zone, and how the City envisions development in each focus area. Each redevelopment percentage was identified as follows:

- Downtown Mixed-Use Expansion and Downtown Mixed-Use Overlay – The City identified parcels to add to the Downtown Mixed-Use zone and others to incorporate into a residential overlay. The analysis of land value ratios and age of structures indicates the area is ripe for redevelopment. The area is also in close proximity to the Gold Line transit station indicating likely latent demand for transit-



CITY OF ARCADIA 6TH CYCLE Housing Element Update

oriented development. These factors, combined with existing incentives for developers to develop Transit-Oriented Development projects, indicated to the City that a 50% redevelopment assumption is reasonable for this strategy.

- Mixed-Use Upzone – All parcels in the Mixed-Use zone that can accommodate a minimum of 16 units were identified as part of this strategy. While the analysis of land value ratios and age of structures indicates a high propensity for redevelopment as housing, the development history,– indicates it is likely that development will still include some commercial components. Therefore, a redevelopment percentage of 50% was determined reasonable for the strategy.
- Las Tunas and Live Oak Residential Flex Overlay – The parcels that have been identified as part of this zone have a high propensity to redevelop as indicated by the analysis of factors in the table above. It is the City's intent to strongly encourage residential development on these parcels to catalyze the revitalization of the area and determined that a 100% redevelopment assumption is reasonable for this strategy. While the City is projecting 100% redevelopment assumption for this strategy, the City is still assuming only 80% build-out on each site as housing to account for potential commercial uses incorporated into each site.
- C-G Residential Flex Overlay – The C-G zone shows characteristics of high likelihood for redevelopment based on the factors analyzed above. The City acknowledges the zone is also attractive to commercial uses and therefore only estimates a redevelopment percentage of 50%.
- R-3 Upzone – The R-3 Upzone includes all parcels that can accommodate a minimum of 16 units in the R-3 Zone. While a high percentage of parcels were identified with the propensity to redevelop, many high-density multi-family units are already built out. The City determined that 25% was a reasonable percentage to assume based on the existing housing stock densification within the zone.

4. Accessory Dwelling Units

Accessory dwelling units (ADUs) are housing units which may be developed in addition to an existing single- or multi-family residential use. These housing units can be free-standing or attached to a primary structure and are intended to provide additional housing on an existing residential lot. Other ADUs provide housing for family members or are rented to members of the community. In accordance with State Law, ADUs are allowed in all zones that allow single dwelling unit or multiple dwelling unit development. Junior Accessory Dwelling Units (JADUs) are permitted only in single dwelling unit zones.

As a result of new legislation and an increased effort by the City to promote ADUs, the City has seen an increase in applications. In 2018, the City permitted 13 ADUs, followed by 14 in 2019 and 22 in 2020. The City had issued 36 ADU permits in 2021 and has issued 42 ADU permits by building in 2022 as of August. As of November 9, 2021, the City had issued 36 ADU permits, had 8 ADU Zoning Clearance projects in review, 9 ADUs approved for Zoning Clearance, and 36 ADU permits in Plan Check accounting for a total count of 89 potential ADUs. While the City is still processing these applications, these ADUs are likely to receive permits in 2021.

Additionally, the passing of SB 9 allows property owners to split a single-family lot into two lots, and either add a second home to their lot or split the lot into two and place duplexes on each. This creates the opportunity for four housing units on a property that is currently limited to a single-family home. The City anticipates that the passing of SB 9 will encourage the creation of ADUs and second units on single-family lots.

The City of Arcadia has determined based on past performance that it is appropriate to anticipate the development of 272217 accessory dwelling units during the 6th planning cycle. Table A-5 Table A-4 below displays the calculation and estimated projection for the 8-year planning period. To project the number of



CITY OF ARCADIA 6TH CYCLE Housing Element Update

ADUs throughout the planning period, the City has taken the average of the ADU counts from 2018 to 202~~21~~ with the anticipation that new legislation and housing policies will continue to generate a high number of ADUs throughout the planning cycle.

$$\frac{2018 \text{ to } 2021 \text{ ADU Production}}{2018 \text{ to } 202~~21~~ \text{ (in years)}} = \text{Projected ADUs}$$

$$\frac{13 + 14 + 2~~20~~ + 36 + 4289}{54} = 25~~34~~$$

Table A-5: ADU Assumptions

Year	ADUs
Projection Period Total	~~272~~217
2029	~~34~~ 25
2028	~~34~~ 25
2027	~~34~~ 25
2026	~~34~~ 25
2025	~~34~~ 25
2024	~~34~~ 25
2023	~~34~~ 25
2022	~~344~~ 2
2021	~~83~~ 69
2020	~~2~~ 20
2019	14
2018	13

Additionally, to facilitate the development of ADUs available for lower income households, the City has developed several policies and programs to encourage the development of ADUs for lower income households (see **Chapter 10: Implementation**). For the purposes of this projection exercise, the City assumes a percentage of ADUs develop affordably based on ADU Affordability Assumptions produced by the Southern California Association of Governments (SCAG). The SCAG conducted analysis consists of the following steps:

- Calculating maximum rent limits for RHNA income categories for one-person and two person households by county
- Conduct survey of rents for ADUs in the SCAG region
- Use survey data to determine proportion of ADUs within each income category
- Create assumption of how many persons will occupy each ADU, finalize proportions

Table A-6: SCAG Affordability Breakdown for LA County II

Income Category	Units
Extremely Low	15.0%
Very Low	8.5%



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Low	44.6%
Moderate	2.1%
Above Moderate	29.8%

Using the proportions SCAG created for Los Angeles County, the City has allocated the following ADUs for each income category:

Table A-7: Accessory Dwelling Unit Projections by Income Category	
Income Category	Units
Low and Very Low Income	~~185~~ <u>148</u>
Moderate Income	~~6~~ <u>5</u>
Above Moderate Income	~~81~~ <u>65</u>
Total	~~272~~ <u>217</u>

To assist the City's ADU development projections, Arcadia has included **Program 5-17**, which explores actions the City will take to promote and monitor the development of ADUs during the planning period. As outlined in the program, these actions may include:

- Developing public awareness campaigns
- Working with existing ADU owners to maintain existing affordable ADU rentals
- Establishing fee-waivers for ADUs that will be made affordable
- Exploring potential State and Regional funding sources for affordable ADUs

5. Selection of Sites to Accommodate Remaining Need

Downtown Mixed-Use Expansion & Overlay

The City has identified General Commercial and Commercial Manufacturing zoned properties in and adjacent to Downtown Arcadia as an opportunity to introduce high density residential flex overlays to expand existing Downtown Mixed-Use zoning. The City also considered the land value ratio and age of the structure in selecting these sites. Expanding the opportunity for high density residential in the downtown area is compatible with adjacent Central Business District and Downtown Mixed-Use zoned parcels and will allow up to 80 units per acre. Table A-8 Table A-7 below highlights examples of recently redeveloped Downtown Mixed-Use sites.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table A-8: Downtown Mixed-Use Development

Project Address	Zoning	Lot Size (Acres)	Dwelling Units	Projected Potential Affordable Units ²	Density (du/acre)	<u>Project Analysis</u>
57 Wheeler Avenue ¹	DMU	0.78	38	7	48	<u>The project replaced a restaurant with surface parking and consisted of a mixed-use development consisting of three stories of 38 residential apartment units over 17,850 square feet of ground floor commercial.</u>
117-129 E. Huntington Drive & 124-134 Wheeler Avenue	CBD & DMU	1.74	139	27	80	<u>The project will replace a one-story commercial building with a surface lot with a 4 to 5 story mixed use development with 139 residential condominium units over 10,000 square feet of ground floor commercial.</u>
150 North Santa Anita Avenue	DMU	2.18	319	63	146	<u>This project will replace a surface parking lot as well as an existing bank. The project will be a mixed-use project with 319 dwelling units.</u>
¹ At the time of this development, the DMU zone allowed a maximum density of 50 du/acre ² This column shows the minimum potential affordable units that could have been developed if the City's inclusionary policy proposed in the Housing Element were adopted.						

Downtown Mixed-Use Expansion



CITY OF ARCADIA 6TH CYCLE Housing Element Update

The City has identified 27 sites that are currently commercially zoned to be rezoned to Downtown Mixed-Use. Rezoning these sites will allow for residential uses at 80 du/acre. Of the 38.8 acres of land identified as part of this strategy, 37.36 acres met the criteria required by AB 1397 for sites projected to accommodate Low and Very Low income units. An assumed density of 64 du/acre was applied to calculate the theoretical capacity of each site. The theoretical capacity of these sites is projected at 2,470 units. However, a planning-level redevelopment percentage of 50 percent has been applied to project a more feasible assumption of future housing development on Mixed-Use sites. The realistic capacity of these sites is projected at 1,209 units, 3103 of which are projected to be affordable to Low and Very Low income households. Four parcels smaller than the criteria required by AB 1397 were also identified as part of the Downtown Mixed-Use Expansion. See **Section 6** of this Appendix and [Table A-21](#) [Table A-20](#) for the assumptions and projected redevelopment of small parcels.

Downtown Mixed-Use Overlay

The City has identified 16 sites that are currently commercially zoned to implement a Downtown Mixed-Use Overlay that will allow for residential uses at 80 du/acre. Of the 8 acres of land identified as part of this strategy, 2.7 acres met the criteria required by AB 1397 for sites projected to accommodate Low and Very Low income units. An assumed density of 64 du/acre was applied to calculate the theoretical capacity of each site. The theoretical capacity of these sites is projected at 504 units. However, a planning-level redevelopment percentage of 50 percent has been applied to project a more feasible assumption of future housing development on Mixed-Use sites. The realistic capacity of these sites is projected at 2,152 units, 39 of which are projected to be affordable to Low and Very Low income households. 14 parcels smaller than the criteria required by AB 1397 were also identified as part of the Downtown Mixed-Use Expansion. See **Section 6** of this Appendix and [Table A-21](#) [Table A-20](#) for the assumptions and projected redevelopment of small parcels.


[Table A-9](#) [Table A-8](#) displays the capacity and opportunity for the Downtown Mixed-Use Expansion and Downtown Mixed-Use Overlay which will contribute capacity towards the City's RHNA allocation. [Figure A-2](#) [Figure A-2](#) and [Figure A-3](#) [Figure A-3](#) below maps the sites identified within this Focus Area which can help accommodate a portion of the City's RHNA allocation. These parcels were identified due to their potential to revitalize Arcadia's downtown district and provide high density housing near transit. The implementation of Program 5-7: Expansion of the Downtown Mixed-Use Area to Permit Residential Uses, Program 5-19: Inclusionary Housing Policy, and other programs with incentives for affordable housing contribute to the justification for including these sites in the inventory.

Table A-9: Downtown Mixed-Use Expansion and Overlay – Redevelopment Analysis							
Focus Area	Acreage	Max Density	Assumed Density	Net Units			
				Low/Very Low	Moderate	Above Moderate	Total
DMU Expansion	38.8	80	64	<u>3103</u>	<u>18222</u>	<u>714784</u>	1,209
DMU Overlay	8	80	64	39	<u>2315</u>	<u>9198</u>	<u>1522</u>
Total	46.8	--	--	342	<u>137205</u>	<u>81582</u>	<u>1,3621</u>



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-2: Downtown Mixed-Use Expansion





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-3: Downtown Mixed-Use Overlay





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Mixed-Use Upzone

The City has identified the Mixed-Use zone as an opportunity to increase density to promote the development of more residential units which could be supported by adjacent uses. The City will increase the maximum density on Mixed-Use sites from 30 du/acre to 50 du/acre. [Table A-10](#)~~Table A-9~~ below describes examples of previously completed projects in the focus area.

Table A-10: Mixed-Use Development					
Project Address	Zoning	Lot Size (Acres)	Dwelling Units	Projected Potential Affordable Units ¹	Density (du/acre)
122-128 E. Live Oak	MU	0.41	12	2	30
56 East Duarte	MU	1.67	37	7	22
314 East Live Oak	MU	0.87	32	6	37
¹ This column shows the minimum potential affordable units that could have been developed if the City's inclusionary policy proposed in the Housing Element were adopted.					

There are ~~59.60~~ sites or ~~27.0626~~ acres that are within the Mixed-Use zone. Of the ~~27.026~~ acres of land, approximately ~~25.355~~ acres met the criteria required by AB 1379 for sites projected to accommodate Low and Very Low income units. An assumed density of 40 du/acre was applied to calculate the theoretical capacity of each site. The theoretical capacity of these sites is projected at 1,049 units. However, a redevelopment percentage of 50 percent has been applied to project a more feasible assumption of future housing development on Mixed-Use sites. The realistic capacity of these sites is projected at ~~5025~~ units, ~~13332~~ of which are projected to be affordable to Low and Very Low income households. Four parcels smaller than the criteria required by AB 1397 were also identified as part of the Mixed-Use Upzone. See **Section 6** of this Appendix and [Table A-21](#)~~Table A-20~~ for the assumptions and projected redevelopment of small parcels.

[Table A-11](#)~~Table A-10~~ below displays the capacity and opportunity in this Focus Area to help accommodate the City's RHNA allocation. [Figure A-4](#)~~Figure A-4~~ and [Figure A-5](#)~~Figure A-5~~ below maps the sites identified within this Focus Area and the distribution across income categories. The implementation of Program 5-9 Increase Residential Density of the Mixed-Use Zone, Program 5-19: Inclusionary Housing Policy, and other programs with incentives for affordable housing contribute to the justification for the net capacity assumptions.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table A-11: Mixed-Use Upzone – Redevelopment Analysis

Acreage	Rezoned Max Density	Assumed Density	Net Units			
			Low/Very Low	Moderate	Above Moderate	Total
~~25.55~~ <u>27.06</u>	50	40	~~133~~ <u>2</u>	~~56~~ <u>76</u>	~~317~~ <u>297</u>	~~502~~ <u>5</u>



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-4: Site Inventory – Mixed-Use Upzone (1)





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-5: Site Inventory – Mixed-Use Upzone (2)





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Las Tunas and Live Oak Corridor

The City has identified the Las Tunas and Live Oak Corridor as an opportunity to both increase density and introduce residential density on viable commercial properties. The adjacent Mixed-Use zoning and access to transit supports the increase of residential uses in the corridor. The City identified two sets areas along the corridor with opportunities based on adjacent use and densities to introduce Residential Flex Overlays within the corridor. **Table A-12** below shows examples of previously completed projects in the Live Oak and Las Tunas Corridor.

Table A-12: Las Tunas and Live Oak Corridor Development					
Project Address	Zoning	Lot Size (Acres)	Dwelling Units	Projected Potential Affordable Units	Density (du/acre)
135 – 139 W Live Oak Ave	R-F Overlay	0.81	17	3	21
122-128 E. Live Oak	MU	0.41	12	2	30
314 East Live Oak	MU	0.87	32	6	37
17 Las Tunas Dr	MU	1.8	77	15	42
¹ This column shows the minimum potential affordable units that could have been developed if the City's inclusionary policy proposed in the Housing Element were adopted.					

Las Tunas Residential Flex Overlay

The City has identified ~~26-25~~ sites on Las Tunas Dr that are currently commercially zoned to implement a Residential Flex Overlay that will allow for residential uses at 60 du/acre. Of the ~~14.69~~~~13.88~~ acres of land identified as part of this strategy, 13.~~1091~~ acres met the criteria required by AB 1397 for sites projected to accommodate Low and Very Low income units. Parcels within the Las Tunas corridor have the capacity to accommodate ~~665~~~~626~~ units of development at an assumed density of 48 du/acre, ~~171-163~~ of which are projected to accommodate housing affordable to low and very low income households. Two parcels smaller than the criteria required by AB 1397 were also identified as part of the Las Tunas Residential Flex Overlay. See **Section 6** of this Appendix and **Table A-21** for the assumptions and projected redevelopment of small parcels.

Live Oak Residential Flex Overlay

The City has identified ~~123~~ sites on Live Oak Ave that are currently commercially zoned to implement a Residential Flex Overlay that will allow for residential uses at 50 du/acre. Of the ~~6.155~~ acres of land identified as part of this strategy, ~~5.686~~~~.04~~ acres met the criteria required by AB 1397 for sites projected to accommodate Low and Very Low income units. Parcels within the Las Tunas corridor have the capacity to accommodate ~~238~~~~225~~ units of development at an assumed density of 40 du/acre, ~~586~~2 of which are projected to accommodate housing affordable to low and very low income households. One parcel smaller than the criteria required by AB 1397 were also identified as part of the Residential Flex Overlay (1). See **Section 6** of this Appendix and **Table A-21** for the assumptions and projected redevelopment of small parcels.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Table A-12 displays the capacity and opportunity for the Live Oak and Las Tunas Residential Flex Overlays which will help accommodate the City's RHNA allocation. **Figure A-6** below maps the sites identified within this Focus Area which can help accommodate a portion of the City's RHNA allocation. These parcels were identified due to their potential to revitalize Arcadia's downtown district and provide high density housing near transit. The implementation of Program 5-10: Expand and Update the Residential Flex Overlay in the Las Tunas Corridor, Program 5-11: Expand and Update the Residential Flex Overlay in the Live Oak Corridor, Program 5-19: Inclusionary Housing Policy, and other programs with incentives for affordable housing contribute to the justification for including these sites in the inventory.

Table A-13: Live Oak and Las Tunas – Redevelopment Analysis							
Focus Area	Acreage	Max Density	Assumed Density	Net Units			
				Low/Very Low	Moderate	Above Moderate	Total
Las Tunas Residential Flex Overlay	~~13.91~~ 13.88	60	48	~~171~~ 163	~~71~~ 96	~~423~~ 367	~~665~~ 626
Live Oak Residential Flex Overlay	~~6.04~~ 6.14	50	40	~~62~~ 58	~~24~~ 35	~~152~~ 132	~~238~~ 225
Total	~~19.95~~20.02	--	--	~~233~~221	~~95~~131	~~575~~499	~~903~~851



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-6: Site Inventory – Residential Flex Overlay





CITY OF ARCADIA 6TH CYCLE Housing Element Update

C-G Residential Flex Overlay

The City has identified General Commercial zoned properties as a redevelopment opportunity where underutilized, smaller scale commercial development can transition to support residential development.

Table A-14 below describes the history of residential development on C-G Zoned parcels.

Table A-14: Residential Development on C-G Properties					
Project Address	Zoning	Lot Size (Acres)	Dwelling Units	Projected Potential Affordable Units ¹	Density (du/acre)
135-139 West Live Oak	C-G	0.81	17	3	21
656 West Huntington Drive	C-G	1.69	34	6	20
180 West Huntington Drive	C-G	2.88	96	19	33
¹ This column shows the minimum potential affordable units that could have been developed if the City's inclusionary policy proposed in the Housing Element were adopted.					

The City identified 57 sites (73.5 acres) as part of the C-G Residential Flex Overlay Focus Area. An assumed density of 24 du/acre was applied to calculate the theoretical capacity of each site. The theoretical capacity of these sites is projected at 1,738 units. However, a redevelopment percentage of 50 percent has been applied to project a more feasible assumption of future housing development in this Focus Area. The realistic capacity of these sites is projected at 870 units, 224 of which are projected to be affordable to Low and Very Low income households

Table A-15 below displays the capacity and opportunity in this Focus Area which can help accommodate the City's RHNA allocation. **Figure A-7** below maps the sites identified within this Focus Area which can help accommodate the City's RHNA allocation. The implementation of Program 5-12: Establish an Overlay to Permit Residential Uses in the Commercial General Zone, Program 5-19: Inclusionary Housing Policy, and other programs with incentives for affordable housing contribute to the justification for including these sites in the inventory.

Table A-15: C-G Residential Flex Overlay – Redevelopment Analysis						
Feasible Acreage	Max Density	Assumed Density	Net Units			
			Low/Very Low	Moderate	Above Moderate	Total
73.5	30	24	<u>220</u>	<u>89</u>	<u>560</u>	<u>869</u>

Legend

- City Boundary
- C-G Residential Flex Overlay
- Pipeline Projects
- 5th Cycle Site
- Consolidated Sites

Viewports:

- Viewport 1:** Shows the northern part of the city, including the Sierra Madre area and the 5th Cycle Site (orange) near the city boundary.
- Viewport 2:** Shows the eastern part of the city, including the 5th Cycle Site (orange) near the city boundary.
- Viewport 3:** Shows the southern part of the city, including the 5th Cycle Site (orange) near the city boundary.
- Viewport 4:** Shows the western part of the city, including the 5th Cycle Site (orange) near the city boundary.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

R-3 Upzone

The R-3 Zone has been identified by the City as an area with the opportunity to support increased density that is compatible with adjacent higher density residential uses and other uses that support residential development. Higher density within this Focus Area can be expected to accommodate lower income units.

Table A-16: Residential Redevelopment on R-3 Properties

Project Address	Zoning	Lot Size (Acres)	Dwelling Units	Projected Potential Affordable Units ¹	Density (du/acre)
656 W. Huntington Dr	R-3	1.69	34	6	20
968 - 998 Arcadia Ave	R-3	0.83	28	5	34
919 Fairview Ave	R-3	0.64	12	2	18
736 – 738 Camino Real Ave	R-3	0.89	18	3	20
825 Arcadia Ave	R-3	0.87	18	3	20
415 California St	R-3	0.70	20	4	29
627 - 633 Fairview Ave	R-3	0.57	12	2	21
901 W. Duarte Rd	R-3	0.68	13	2	19
¹ This column shows the minimum potential affordable units that could have been developed if the City's inclusionary policy proposed in the Housing Element were adopted.					

There are 165 sites or 177.21 acres that are within the R-3 zone. Of the 177.21 acres of land, all acres met the criteria required by AB 1379 for sites projected to accommodate Low and Very Low income units. An assumed density of 32 du/acre was applied to calculate the theoretical capacity of each site. The theoretical capacity of these sites is projected at 2,540 units. Through the history of redevelopment of R-3 sites, additional incentives for affordable housing, and inclusionary policy programs, a reasonable redevelopment of 25 percent has been applied. This redevelopment percentage will project a more feasible assumption of future housing development on non-vacant sites with existing multi-family housing. The realistic capacity of these sites is projected at 635~~6~~ units, 165~~4~~ of which are projected to be affordable to Low and Very Low income households. No parcels smaller than the criteria required by AB 1397 were identified as part of the R-3 Upzone. See Section 3 of this Appendix and ~~Table A-21~~**Table A-20** for the assumptions and projected redevelopment of small parcels.

~~Table A-17~~**Table A-16** below displays the capacity and opportunity in this Focus Area which can help accommodate the City's RHNA allocation. ~~Figure A-8~~**Figure A-8**, ~~Figure A-9~~**Figure A-9** and ~~Figure A-10~~**Figure A-10** below map the sites identified within this Focus Area which can help accommodate the City's RHNA allocation. The implementation of Program 5-13: Increase Density of the R-3 Zone, Program 5-19: Inclusionary Housing Policy, and other programs with incentives for affordable housing contribute to the justification for including these sites in the inventory.



CITY OF ARCADIA 6TH CYCLE Housing Element Update


Table A-17: R- 3 Upzone – Redevelopment Analysis

Acreage	Max Density	Assumed Density	Net Units			
			Low/Very Low	Moderate	Above Moderate	Total
177.21	40	32	1654	9768	404373	636635



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-8: Site Inventory – R-3 Upzone (1)





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-9: Site Inventory – R-3 Upzone (2)





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-10: Site Inventory – R-3 Upzone (3)





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Arcadia Golf Course

The City has also identified the Arcadia Golf Course as a site to accommodate units across the income categories. The City owns the Arcadia Par 3 Golf Course and ~~has recently~~~~is currently~~ negotiating with development teams to evaluate the future sale of the property and/or redevelopment of the site. The City ~~has~~ released a Request for Proposals through the Surplus Land Act (SLA) process ~~and has gone through~~~~and is working through~~ the steps of the SLA process with the development teams mentioned above. At the conclusion of this process, the Arcadia City Council decided not to move forward with a project at the time. This was communicated to HCD and clearance was provided by the department. The decision not to move forward included reasons such as price, terms of the projects submitted, timing, and issues surrounding the Council District within which the site is located. As part of the SLA process with HCD, the City committed to providing affordable units on the property as part of any future residential project (at least 15% of the units). Although no agreement was made through the SLA process and recent negotiations, it is still anticipated ~~It is anticipated~~ that the City will enter into a Purchase and Sale Agreement and a Development Agreement with a selected Development Team on the entitlement of the site. The City has continued to evaluate the site, and determine the proper unit mix and development type. The RFP represented that the resulting project will also likely retain a substantial open space component and provide market-rate units in a Specific Plan format, which is still the case.

The projected number of units in this area reflect the current proposals under evaluation, not the number of units the final approved development will include. Based on the proposals received, the City is estimating committing to developing a total number of 186 units, 80 of which will be affordable to low or very low income households (44 percent of the total, meeting the City's affordable development requirement). The remaining units may include a mixture of moderate and above moderate income, to be conservative in the assumption of projected units, the City is projecting the remaining units will be available to above moderate income households. Currently, the land is zoned and designated in the General Plan as open space and the City is committed to maintaining a portion of this land as a community resource. It is anticipated that 13.5 acres of the site will be designated as High Density Residential (R-3) and 11.5 acres will be zoned for Open Space (OS) to be retained by the City for recreation and open space. The re-zoning of the site would occur along with the projected Specific Plan to ensure that the property is re-zoned and the projected units are built at the density and type appropriate for affordable housing. The City will begin the process of initiating the Specific Plan in 2023 and anticipates the development of units on this site in 2025.

It is estimated~~The City is committing to providing that~~ 80 units of housing for affordable to low and very low incomes ~~will be provided~~ on the site. This projection is based on an analysis of submitted plans by development teams through the RFP process the City engaged in. Of the bidders for the project, three of the considered bidders opined that an affordable housing project of 80 units was the critical mass necessary to make the project financially viable. As a result of the cost-benefit analysis provided, the City was informed that a smaller affordable housing component would not be sustainable over time in large part due to the fixed costs necessary (i.e. management and operating costs) that are proportionally higher on a per unit basis, which would create a gap in the ability to finance and construct an affordable project of a smaller size. Each of the developer teams who participated in the RFP are reputable affordable housing developers who concluded that 80 units was the proper target for low and very low income units on the site.

~~Per the requirements of the SLA, a portion of the project will be dedicated to affordable housing units (at least 25% of all units developed). In addition, the resulting project will also likely retain a substantial open space component and provide market rate units in a Specific Plan format. The projected number of units in this area reflect the current proposals under evaluation, not the number of units the final approved~~



CITY OF ARCADIA 6TH CYCLE Housing Element Update

development will include. ~~Table A-18~~ ~~Table A-17~~ below displays the projected assumptions for net unit yield based on expressed developer interest. ~~Figure A-11~~ ~~Figure A-11~~ below maps the Arcadia Golf Course. The implementation of Program 5-14: Develop a Specific Plan for the Arcadia Golf Course, Program 5-19: Inclusionary Housing Policy, and other programs with incentives for affordable housing also contribute to the justification for including these sites in the inventory.


Table A-18: Arcadia Golf Course – Projected Redevelopment

Acreage	Assumed Density	Net Units			
		Low/Very Low	Moderate	Above Moderate	Total
25.86	N/A	~~50~~ 80	0	~~136~~ 106	186



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Figure A-11: Site Inventory – Arcadia Golf Course





CITY OF ARCADIA 6TH CYCLE Housing Element Update

6. Development of Small Site Parcels

The City of Arcadia has identified candidate housing sites that are smaller than half an acre in size within several Focus Areas. Assembly Bill 1397 identifies general size requirements for candidate housing sites of greater than half an acre and less than 10 acres in size. The City has an existing Lot Consolidation program and a history of densifying housing on parcels less than a half an acre. **Table A-19** shows that the City has a history of development on parcels smaller than half an acre. While the City understands that it does not have a history of affordable development on small sites, the City will adopt an Inclusionary Policy (Program 5-19) as a mechanism to ensure the development of affordable units. Program 5-20 also supports the development of small sites through lot consolidation incentives and streamlining. Additionally, in an effort to be conservative with the assumption of development on small sites, the City has applied a 20 percent redevelopment percentage on top of the assumed density which was calculated at 80 percent of the maximum density of the underlying zone. The sites accounted for in **Table A-1** reflect only 20 percent of the total theoretical capacity possible on small sites identified within the City. The City also identified potential small sites that are likely to consolidate for the development of affordable housing.

Table A-19: Development of Small Sites

Project Address	Zoning	Lot Size (Acres)	Dwelling Units	Density (du/acre)	Use Prior to Redevelopment
54 El Dorado	R-3	0.18	3	17	Three unit multi-family development
900 N. Santa Anita Ave	R-3	0.25	4	16	Single Family Dwelling
1036 Sunset Blvd	R-3	0.42	8	19	Four unit Multi-Family Development
148 El Dorado St.	R-3	0.18	3	17	Single Family Dwelling
225 Santa Rosa Rd	R-3	0.30	4	13	Two single family dwellings
31 S. 2 nd Ave..	R-3	0.17	3	18	Two single family dwellings
33 California St	R-3	0.18	4	22	Single Family Dwelling
316 – 320 S. 3 rd Ave.	R-2	0.39	4	10	Two single family dwellings
1013 – 1019 Holly Ave.	R-3	0.45	9	20	Two single family dwellings
130 Alta St	R-3	0.18	3	17	Three unit multi-family development
19-23 Christina St.	R-3	0.32	6	19	Eight unit multi-family development
799 - 803 Arcadia Ave.	R-3	0.30	6	20	Two unit multi-family development



CITY OF ARCADIA 6TH CYCLE Housing Element Update

40 - 42 Fano St	R-3	0.18	3	17	Three unit multi-family development
681 N. 1 st Ave	R-3	0.18	6	33	Church
215 - 217 El Dorado St.	R-2	0.18	2	11	Two unit multi-family development
613 - 615 S. 2 nd Ave.	R-3	0.18	4	22	Single Family Dwelling
138 California St.	R-3	0.18	3	17	Single Family Dwelling
20 Alta St.	R-3	0.18	3	17	Single Family Dwelling
507 W. 3 rd Ave	R-2	0.17	2	12	Single Family Dwelling
5731 -5735 Baldwin Ave.	R-3	0.20	4	20	Single Family Dwelling
323 & 327 S. 3 rd Ave	R-2	0.37	4	11	Three detached Single Family Dwellings
616 - 618 S. 3 rd Ave	R-2	0.17	2	12	Single Family Dwelling
129 El Dorado St	R-3	0.18	3	17	Two detached Single Family Dwellings
1118 Sunset Blvd	R-3	0.15	2	13	Single Family Dwelling
907-915 Arcadia Ave (Lot Consolidation)	R-3	0.18 & 0.43	13	21	Six detached Single Family Dwellings
329 Diamond St	R-2	0.15	2	13	Single Family Dwelling
1222 Temple City Blvd	R-3	0.43	10	23	Four unit multi-family development
216 S. 3 rd Ave	R-3	0.14	2	14	Single Family Dwelling
126 - 128 Diamond St	R-3	0.18	3	17	Single Family Dwelling
118 – 120 Alta St (Lot Consolidation)	R-3	0.13 & 0.13	6	23	Two Single Family Dwellings
139 – 145 Alice St (Lot Consolidation)	R-3	0.16 & 0.27	8	19	Single Family Dwelling
30 Fano St	R-3	0.18	3	17	Three-unit Multi-Family development



CITY OF ARCADIA 6TH CYCLE Housing Element Update

22 – 26 E. Colorado Blvd (Lot Consolidation)	R-3	0.16 & 0.16	8	25	Seven-unit Multi-Family development
116 Bonita St	R-3	0.18	3	17	Vacant
155 Alice St	R-3	0.17	3	18	Three-unit Multi-Family development
1028 W. Duarte Rd	R-3	0.16	3	19	Single Family Dwelling
157 – 159 Genoa St	R-3	0.19	4	21	Two Single Family Dwellings
121 Bonita St	R-3	0.18	3	17	Two Detached Single Family Dwellings
418 Fairview Ave	R-3	0.32	6	19	Single Family Dwelling
135 El Dorado St	R-3	0.18	3	17	Single Family Dwelling
9828 E. Naomi Ave	R-3	0.22	3	14	Single Family Dwelling
1027 Arcadia Ave	R-3	0.26	6	23	Three-unit Multi-Family development
230 California St	R-3	0.26	5	19	Single Family Dwelling
837 – 843 W. Huntington Dr	R-3	0.44	10	23	Eight-unit Multi-Family development
314 California St	R-3	0.29	5	17	Single Family Dwelling
1111- 1117 La Cadena Ave	R-3	0.38	8	21	Two Attached Single Family Dwellings
147 Alice St	R-3	0.17	3	18	Three Single Family Dwellings
125 California St	R-3	0.18	3	17	Three Single Family Dwellings
122 – 128 E. Live Oak Ave (Lot Consolidation)	MU	0.20 & 0.20	12	30	Vacant
405 S. 1 st Ave	MU	0.19	4	21	Two Single Family Dwellings



CITY OF ARCADIA 6TH CYCLE Housing Element Update

This history of development, combined with additional policy programs to increase density, incentive programs targeting small sites and promoting small lot consolidation, and the implementation of an inclusionary policy serves as the basis of justification for the inclusion of small sites in the sites inventory for Low and Very Low incomes within identified focus areas. Many of the sites identified to as part of the sites inventory are not vacant. To account for the challenges of infill development and potential for redevelopment that would be required on many of these sites, the City will adopt an interim inclusionary policy within 9 months of the Housing Element adoption. After evaluating the inclusionary policy, the City will adopt an Ordinance requiring 20% net unit capacity identified on small sites within 36 months of the Housing Element. a feasibility assumption of 20 percent was applied to the net unit capacity identified on small sites. The small sites feasibility adjustment is used in lieu of the feasibility adjustment that is applied to each of the Focus Areas. ~~Table A-20~~**Table A-19** summarizes the theoretical capacity of the identified sites smaller than half an acre using the assumptions identified for each focus area while ~~Table A-21~~**Table A-20** summarizes the realistic capacity of small sites after applying the redevelopment percentage.

Table A-20: Small Site Parcels – Theoretical Development Analysis

Focus Area	# of Sites	Net Units			
		Low/Very Low	Moderate	Above Moderate	Total
Downtown Mixed-Use	18	110	41	270	421
Mixed-Use Upzone	4	17	8	41	66
Las Tunas and Live Oak Corridor	3	14	6	36	56

Table A-21: Small Site Parcels – Feasible Redevelopment Analysis

Focus Area	# of Sites	Net Units			
		Low/Very Low	Moderate	Above Moderate	Total
Downtown Mixed-Use	18	22	8	54	84
Mixed-Use Upzone	4	3	2	8	13
Las Tunas and Live Oak Corridor	3	3	1	7	11

Table A-22: Small Site Parcels – Consolidated Lots

APNs	Consolidated Acreage	Net Units				Consolidation Justification
		Low/Very Low	Moderate	Above Moderate	Total	
5771-021-018 5771-021-029	5.75	34	21	82	137	
5773-014-001 5773-014-002	0.67	7	4	15	26	
5773-013-017 5773-013-016 5773-013-015	0.53	6	3	10	19	
5779-001-020 5779-001-019 5779-001-018	0.55	6	3	10	19	



CITY OF ARCADIA 6TH CYCLE Housing Element Update

5779-001-017 5779-001-016 5779-001-015	0.54	6	3	10	19	
5779-003-001 5779-003-003 5779-003-002	0.49	5	3	9	17	
5779-003-035 5779-003-034 5779-003-033	0.49	6	3	9	18	
5779-011-018 5779-011-017	0.53	5	3	12	20	
5779-010-033 5779-010-032 5779-010-031	0.67	7	4	14	25	
5779-011-016 5779-011-015 5779-011-014	0.52	5	3	11	19	
5779-010-003 5779-010-002 5779-010-001	0.49	5	2	11	18	
5779-012-017 5779-012-016	0.53	5	3	11	19	
5779-014-020 5779-014-021 5779-014-033 5779-014-018 5779-014-019	0.84	7	6	16	29	
5779-016-006 5779-016-005 5779-016-004	0.44	3	3	9	15	
8573-001-001 8573-001-004 8573-001-005 8573-001-006 8573-001-007 8573-001-026	0.99	13	7	25	45	
8573-013-044 8573-013-045 8573-013-047 8573-013-048	0.85	11	6	22	39	
5789-021-013 5789-021-019	0.81	8	5	18	31	
8573-024-001 8573-024-002 8573-024-003 8573-024-004	1.01	10	5	23	38	
5790-027-030 5790-027-034	0.58	6	3	13	22	
5790-028-028	1.00	10	6	22	38	



CITY OF ARCADIA 6TH CYCLE Housing Element Update

5790-028-032						
5790-028-033						

~~The potential candidate sites which are anticipated to be consolidated into groups of parcels with propensity for higher density residential development are identified within Table A-22.~~ This analysis is further supported by an existing City program to expedite the processing of lot consolidation and an additional program, **Program 5-20 Lot Consolidation Incentives** which can be seen in **Chapter 10: Implementation Plan**.

7. Water, Sewer and Dry Utility Availability

The City of Arcadia has water, sewer, and dry utilities (gas and electric) that exist or are planned to accommodate residential development in the community. The City has the infrastructure in place which is designed and located to accommodate potential for additional housing identified for the 6th Cycle Housing Element. Existing utilities would have the capacity to serve future housing development.

Water and Sewer

The City of Arcadia's Urban Water Management Plan (2020) identifies the water services and sewer system distribution throughout the community. The City is the sole provider of water services and sewer system distribution for all residents in the City. All the identified sites are within areas that the City services. According to the UWMP, the City of Arcadia has identified potential reservoir, pipeline, and booster station projects in addition to a joint well project with the City of Sierra Madre to increase water supply.

As a built-out community, the City's existing water system services all areas within the City limits through various trunk and main lines. The City also provides storm drains, sewer system lines, and other wastewater infrastructure to all areas within the City. The wastewater generated in Arcadia flows into regional trunk lines operated by the County Sanitation Districts of Los Angeles. The Sanitation Districts manage a joint sewer outfall system that conveys collected wastewater to treatment plants located in Whittier. Since new development has the potential to result in increased demand for water and wastewater flows, the City regularly monitors the water and sewage systems to ensure adequate service is provided for existing and future planned residential development. The City's Urban Water Management Plan (UWMP¹) in conjunction with their Sewer System Management Plan (SSMP²) outline plans to accommodate for future use and plans for the maintenance and expansion of existing utility infrastructure.

Each site has been evaluated to ensure there is adequate access to water and sewer connections as well as dry utilities such as electric, gas, and telecommunication lines. Most sites are situated with a direct connection to a public street that has the appropriate water and sewer mains and other infrastructure to service the candidate sites.

Utilities

The Southern California Gas Company provides natural gas services to the City. SoCal Gas is a gas-only utility and, in addition to serving the residential, commercial, and industrial markets, provides gas for enhanced oil recovery (EOR) and EG customers in Southern California. Clean Power Alliance (CPA) is the main electrical service provider for Arcadia. CPA is a non-profit electric utility that works to bring clean

¹ City of Arcadia. (2020). Urban Water Management Plan. Available at: <https://www.arcadiaca.gov/Shape%20Arcadia/Public%20Works%20Services%20Department/Water%20&%20Sewer%20Services/Final%202020%20UWMP.pdf>.

² City of Arcadia. (2014). Sewer System Management Plan. Available on <https://www.arcadiaca.gov/Shape%20Arcadia/Public%20Works%20Services%20Department/Water%20&%20Sewer%20Services/Sewer%20System%20Management%20Plan%202014.pdf>.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

power to the people of Arcadia. Southern California Edison (SCE) will assist CPA in providing services through allowing the use of SCE infrastructure to deliver electricity to households and buildings throughout the City. CPA and SCE will continue to provide adequate services to Arcadia including increased household growth as projected by the City's RHNA allocation.

In accordance with the California Public Utilities Commission all electric and gas service will be provided for future development in Arcadia as requested. SoCal Gas and Southern California Edison regularly partner with the City to provide services and obtain authorization to construct any required facilities. The City has a mature energy distribution system that will be able to add additional service connections for future residential land uses.

Internet and telephone line connections are also available within the City. According to the City of Arcadia's website, telephone and internet companies that serve the City include AT&T, Frontier Communications, Giggle Fiber, and Spectrum.³ The City has existing utility lines in residential, commercial, and industrial use areas that would be able to be utilized for future housing development.

³ City of Arcadia. Cable & Internet. Available at https://www.arcadiaca.gov/discover/living_in_arcadia/cable_internet_.php. Accessed on November 15, 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Calculations of Unit Capacity

This section contains a description of the candidate sites identification to meet Arcadia's RHNA need at all income levels. The full list of these sites is presented in **Table A-22**.

8. Capacity Calculations

Net Unit Calculations

The total unit capacity for the City was calculated on a per-parcel basis. Net unit capacity per parcel was calculated by evaluating buildable acreage, multiplying by an assumed buildout density based on zoning, and subtracting any existing units. As opposed to calculating capacity using the max density, the City used an assumed density that is 80 percent of the max density to provide a more conservative estimate of actual unit production. The 80% of maximum density calculation is based on the average application of development standards, including setbacks, lot coverage, heights and other applicable standards. Since zoning densities are expressed in gross dwelling units per acre, the 80% estimate provides for a realistic estimate of the net unit yield base on zoning code adopted densities.

Currently there are 23 sites that meet the default density of 30 du/acre and 365 sites that will be rezoned to meet the default density. Potential constraints, to the extent they are known, such as environmentally sensitive areas and steep slopes were considered, and deductions were made where those factors decreased the net buildable area of a parcel. The deduction for these sites was conducted in Table A-1 which projects a lower build out based on redevelopment assumptions based on historic trends, local knowledge, and environmental factors.

Buildout Capacity Assumption

The total net unit capacity for certain Focus Areas and strategies were also adjusted based on a feasibility percentage identified by the City through an analysis of development trends in the City and historical development. Additionally, density bonuses were not factored into any of the net unit calculations.

Affordability Calculation

Arcadia's 2021-2029 Housing Element sites analysis assumes that each identified candidate housing site will develop at a range of income levels. Arcadia recognizes that not all sites within the inventory will develop such that they meet the exact affordability assumptions identified. For example, some sites may develop at higher density or affordability levels through the use of density bonus incentives and some may develop with majority market rate units (units affordable to the moderate and above moderate income households).

With the implementation of an Inclusionary Policy and other policies to incentivize the development of affordable housing as established within the goals, policies, and programs within the Housing Element, the City assumed the following affordability characteristics for sites within the inventory:

25% of units available in the low and very-low income categories

~~10~~5% in the moderate income category

65% in the above moderate income category

The City has established goals, policies, and programs within the Housing Element (**Chapter 5: Housing Element; Chapter 10: Implementation Plan**) aimed at identifying funding opportunities and partnering with the development community to increase the amount of affordable housing built in future developments. The City recognizes that should a "No Net Loss" situation occur, they will be required to identify additional sites. To project an accurate number and avoid overestimating the potential housing development as a



CITY OF ARCADIA 6TH CYCLE Housing Element Update

result of rezone strategies, the City applied feasibility adjustments based on past performance, knowledge of land value ratios and the age of structures. To the best of their ability, none of the sites identified that are privately-owned are known to have a lease or use that would constrain the future development of housing.

To avoid overestimating potential housing development in the City, feasibility adjustments were applied based on past performance to the Focus Areas identified by the City. ~~Table A-23~~ **Table A-22** below summarizes the Focus Area assumptions that were used to calculate the capacity of the Sites Inventory.

Table A-23: Capacity Calculation Overall Assumptions				
Focus Area	Assumed Redevelopment Percentage	Minimum Density	Max Density	Assumed Density (80%)
Downtown Mixed-Use Expansion	50%	64	80	64
Downtown Mixed-Use Overlay	50%	64	80	64
Mixed-Use Upzone	50%	40	50	40
Las Tunas Residential Flex Overlay	100%	48	60	48
Live Oak Residential Flex Overlay	100%	40	50	40
C-G Residential Flex Overlay	50%	24	30	24
R-3 Upzone	25%	32	40	32
Development of Small Sites (< 0.5 acres)*	20%	Dependent on Underlying Zoning	Dependent on Underlying Zoning	Dependent on Underlying Zoning
*Note: Small sites were analyzed separately from the Focus Areas. The Focus Area density assumptions apply only to small sites within their underlying zone, however, the redevelopment percentage for small sites is applied to sites smaller than half an acre instead of the Focus Area redevelopment percentage.				

A breakdown of the calculation for the projected units is provided below.

$$\text{Theoretical Capacity} = \text{acres} \times 80\% \text{ Max Density}$$

$$\text{Net Capacity} = (\text{Theoretical Capacity} - \text{Net Units}) \times \text{Affordability Assumption}$$

$$\text{Projected Units to Meet RHNA} = \text{Net Capacity} \times \text{Redevelopment Percentage}$$

8. Zoning and General Plan Designations

The City of Arcadia is able to accommodate a portion of the RHNA allocation using existing general plan and land use designations on parcels within the City. The City has also identified a number of sites which require a change to an existing Zone's development standards, the Zone or an Overlay Zone designation to accommodate housing at appropriate densities for all income levels. All changes align with the goals of the General Plan land use designations.

- Downtown Mixed-Use Zone Expansion – The existing DMU site will be expanded across 27 adjacent sites that have been identified to be able to accommodate high density residential development at 64 to 80 du/ac.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

- Downtown Mixed-Use Overlay – 16 commercially zoned sites adjacent to the Downtown Mixed-Use Zone have been identified as having capacity to allow for higher density residential uses at 64 to 80 du/acre.
- Mixed-Use Zone – 60 sites have been identified as part of the existing mixed-use zone to allow for a higher density of residential development at 40 to 50 du/acre.
- Las Tunas Residential Flex Overlay – 26 commercially zoned sites have been identified for the implementation of an overlay that will allow for residential uses at 48 to 60 du/ac.
- Live Oak Residential Flex Overlay – 13 commercially zoned sites have been identified for the implementation of an overlay that will allow for residential uses at 40 to 50 du/ac.
- C-G Residential Flex Overlay – 57 commercially zoned sites have been identified as part of the C-G zone as being able to support residential development at 24 to 30 du/ac.
- R-3 Upzone – 165 sites have been identified as part of the existing R-3 zone to allow for a higher density of residential development at 32 to 40 du/ac.

9. Adequate Sites Table

Table A-24: Full Sites Inventory																						
ID	APN	Identified Lot Consolidation	Address	Owner	Existing Zoning	Existing General Plan Land Use	Vacancy	4th Cycle Site?	5th Cycle Site?	Existing Units	Gross Acreage	HCD Sizing Criteria	Existing Zone Density (Assumed)	Rezoned Density (Assumed)	Inventory Category	Potential Rezoned Unit Yield	Assumed Net Yield	LVL	Mod	Above Mod	Existing Use and Description	Justification
29	5773-014-037	No	128 E HUNTINGTON DR	STERPA,SEBASTIAN O AND CAROLE TRS	CBD	C 1.0	No	No	No	2	0.5	Yes	64	No Rezone	Propensity	32	30	8	<u>5</u>	<u>17</u>	<u>This parcel contains two commercial one-story buildings along with approximately 30 percent of the parcel used for surface parking.</u>	<u>The parcel consists only of one-story commercial structures that are over 50 years old. Additionally, a large portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
30	5773-007-038	No	140 E SAINT JOSEPH ST	RMK PARTNERSHIP	DMU	DMU	No	No	No	2	0.5	Yes	64	No Rezone	Propensity	32	30	8	<u>5</u>	<u>17</u>	<u>The parcel contains two one-story structures with storage space and industrial businesses along with 30 percent of the parcel used for surface parking</u>	<u>The parcel consists only of one-story commercial structures that are almost 40 years old. Additionally, a large portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
31	5773-013-034	No	10 S SANTA ANITA AVE	FADELL,JAMES J CO TR	CBD	C 1.0	No	No	No	0	0.5	Yes	64	No Rezone	Propensity	32	32	8	<u>5</u>	<u>19</u>	<u>This parcel contains one single story structure with commercial businesses along with approximately 75 percent of the parcel used for surface parking</u>	<u>The parcel consists only of one single-story commercial structure that is over 30 years old. Additionally, a majority of the parcel is being utilized for surface parking. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
32	5773-012-023	No	30 S SANTA ANITA AVE	WEINER,MILTON AND ADELINE TRS	DMU	DMU	No	No	No	0	0.5	Yes	64	No Rezone	Propensity	34	34	9	<u>5</u>	<u>20</u>	<u>This parcel is entirely dedicated to surface parking</u>	<u>Since this site consists entirely of surface parking, this site could realistically turn over into a higher intensity use. It is inside the priority growth area and there are no environmental constraints.</u>
33	5773-011-062	No	108 E SANTA CLARA ST	LINK,NORMA D CO TR	DMU	DMU	No	No	No	0	0.5	Yes	64	No Rezone	Propensity	34	34	9	<u>5</u>	<u>20</u>	<u>This parcel contains three single story structures with commercial and industrial businesses along with approximately 30 percent of the parcel used for surface parking</u>	<u>The parcel consists only of one-story commercial structures that are over 40 years old. Additionally, a large portion of the parcel is being utilized for surface parking. It is inside the priority growth area and there are no environmental constraints. This site could realistically turn over into a higher intensity use</u>
34	5773-006-053	No	13 E SANTA CLARA ST	RECREATIONAL EQUIPMENT INC	DMU	DMU	No	No	No	0	0.6	Yes	64	No Rezone	Propensity	36	36	9	<u>5</u>	<u>22</u>	<u>This parcel is entirely dedicated to surface parking</u>	<u>Since this site consists entirely of surface parking, this site could realistically turn over into a higher intensity use. It is inside the priority growth area and there are no environmental constraints.</u>
35	5773-014-038	No	102 E HUNTINGTON DR	ARCADIA INVESTMENT HOLDING LLC	CBD	C 1.0	No	No	No	0	0.6	Yes	64	No Rezone	Propensity	36	36	9	<u>5</u>	<u>22</u>	<u>This parcel contains one single-story structure with commercial businesses along with fueling pumps and approximately 30 percent of the parcel used for surface parking</u>	<u>The parcel consists of only one single-story commercial structure that is almost 40 years old. Additionally, a large portion of the parcel is being utilized for surface parking. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use</u>
36	5773-013-018	No	60 E HUNTINGTON DR	METROPOLITAN LIFE INSURANCE CO	CBD	C 1.0	No	No	No	0	0.6	Yes	64	No Rezone	Propensity	37	37	9	<u>6</u>	<u>22</u>	<u>This parcel contains one single-story commercial building along with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists only of one single-story commercial structures that is over 60 years old. Additionally, a large portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
37	5773-012-022	No	55 E HUNTINGTON DR	FOOTHILL MOUNTAIN VIEW OFFICE	CBD	C 1.0	No	No	No	0	0.6	Yes	64	No Rezone	Propensity	37	37	9	<u>6</u>	<u>22</u>	<u>This parcel contains one office building along with approximately 50 percent of the parcel being used for parking</u>	<u>This parcel contains one commercial property that is over 30 years old. Additionally, a large portion of the parcel is being utilized for surface parking. It is inside the priority growth area and there are no environmental constraints. This site could realistically turn over into a higher intensity use.</u>
38	5775-022-035	No	305 N SANTA ANITA AVE	DRAKE FINANCIAL LLC	DMU	DMU	No	No	No	0	0.6	Yes	64	No Rezone	Propensity	38	38	10	<u>6</u>	<u>22</u>	<u>This parcel contains one single story structure with commercial businesses along with approximately 30 percent of the parcel used for surface parking</u>	<u>The parcel consists of only one single-story commercial structure that is over 60 years old. Additionally, a large portion of the parcel is being utilized for surface parking. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use</u>
39	5775-022-031	No	251 N SANTA ANITA AVE	DRAKE FINANCIAL LLC	DMU	DMU	No	No	No	1	0.6	Yes	64	No Rezone	Propensity	39	38	10	<u>6</u>	<u>22</u>	<u>This parcel contains two commercial single-story buildings along with approximately 30 percent of the parcel used for surface parking.</u>	<u>This parcel consists of two single-story commercial structures that are almost 50 years old. Additionally, a large portion of the parcel is being utilized for surface parking. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
40	5773-006-907	No	41 WHEELER AVE	U S POSTAL SERVICES	DMU	DMU	No	No	No	0	0.7	Yes	64	No Rezone	Propensity	42	42	11	<u>6</u>	<u>25</u>	<u>This parcel is entirely dedicated to surface parking</u>	<u>Since this site consists entirely of surface parking, this site could realistically turn over into a higher intensity use. It is inside the priority growth area and there are no environmental constraints.</u>

42	5773-007-036	No	125 E SANTA CLARA ST C	BERBERIAN, O R AND F L TRS	DMU	DMU	No	Yes	Yes	0	0.7	Yes	64	No Rezone	Propensity	46	46	12	<u>7</u>	<u>27</u>	<u>This parcel contains two commercial one story buildings along with approximately 30 percent of the parcel used for surface parking.</u>	<u>The parcel consists only of one-story commercial structures that are over 50 years old. Additionally, a large portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
43	5773-006-067	No	223 N 1ST AVE	223 NORTH FIRST ST I LLC ET AL	DMU	DMU	No	No	No	0	0.7	Yes	64	No Rezone	Propensity	47	47	12	<u>7</u>	<u>28</u>	<u>This parcel contains one commercial structure along with approximately 60 percent of the parcel used for surface parking.</u>	<u>A majority of this parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
44	5773-006-929	No	29 E SANTA CLARA ST	METRO GOLD LINE FOOTHILL	DMU	DMU	No	No	No	0	0.8	Yes	64	No Rezone	Propensity	50	50	14	<u>8</u>	<u>28</u>	<u>This parcel is entirely dedicated to parking.</u>	<u>All of this parcel is being utilized for parking. This site could realistically turn over into a higher intensity use. Proximity to the metro would increase mobility for residents.</u>
45	5775-022-805	No	21 W SANTA CLARA ST	PACIFIC BELL	DMU	DMU	No	No	No	0	0.9	Yes	64	No Rezone	Propensity	55	55	15	<u>8</u>	<u>32</u>	<u>This parcel contains one single-story commercial structure along with approximately 60 percent of the parcel used for surface parking</u>	<u>The parcel consists of only one single-story commercial structure that is over 50 years old. Additionally, a majority of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use</u>
46	5773-007-033	No	225 N 2ND AVE	APW DEVELOPMENT CO	DMU	DMU	No	No	No	0	0.9	Yes	64	No Rezone	Propensity	57	57	15	<u>9</u>	<u>33</u>	<u>This parcel contains a commercial structure along with approximately 30 percent of the parcel used for surface parking.</u>	<u>This parcel consists of only one commercial structure that is over 40 years old. Additionally, a large portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
47	5773-006-068	No	125 N FIRST AVE	ITTAH, MARC TR	DMU	DMU	No	No	No	0	0.9	Yes	64	No Rezone	Propensity	60	60	16	<u>9</u>	<u>35</u>	<u>This parcel contains a commercial structure and a parking structure.</u>	<u>This parcel consists of only one commercial business and the rest is dedicated to parking. This site could realistically turn over into a higher intensity use.</u>
49	5773-014-051	No	166 E HUNTINGTON DR	PERASSO, TOMMY TR	CBD	C 1.0	No	No	No	1	1.1	Yes	64	No Rezone	Propensity	73	72	19	<u>11</u>	<u>42</u>	<u>This parcel contains one single story structure with a commercial business along with approximately 75 percent of the parcel used for surface parking</u>	<u>This parcel consists of only one single-story commercial business and the majority is dedicated to parking. This site could realistically turn over into a higher intensity use.</u>
50	5773-006-064	No	214 N SANTA ANITA AVE	RECREATIONAL EQUIPMENT INC	DMU	DMU	No	No	No	0	1.2	Yes	64	No Rezone	Propensity	77	77	20	<u>12</u>	<u>45</u>	<u>This parcel contains one single story structure with a commercial business along with approximately 50 percent of the parcel used for surface parking</u>	<u>This parcel consists of only one single-story commercial business and the majority is dedicated to parking. It is inside the priority growth area and there are no environmental constraints. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
51	5773-011-036	No	136 E SANTA CLARA ST	WINNAMAN, PHYLLIS B TR	DMU	DMU	No	Yes	Yes	0	1.2	Yes	64	No Rezone	Propensity	77	77	20	<u>12</u>	<u>45</u>	<u>This parcel contains two single-story commercial structures along with approximately 30 percent of the parcel used for surface parking</u>	<u>The parcel consists only of one-story commercial structures that are over 40 years old. Additionally, a large portion of the parcel is being utilized for surface parking. It is inside the priority growth area and there are no environmental constraints. This site could realistically turn over into a higher intensity use.</u>
52	5773-012-901	No	Wheeler Ave	ARCADIA CITY	DMU	DMU	No	No	No	0	1.3	Yes	64	No Rezone	Propensity	80	80	21	<u>12</u>	<u>47</u>	<u>This parcel is entirely dedicated to surface parking</u>	<u>Since this site consists entirely of surface parking, this site could realistically turn over into a higher intensity use. It is inside the priority growth area and there are no environmental constraints. The land value ratio is less than one, indicating potential for developer interest.</u>
53	5783-006-018	No	1017 FAIRVIEW AVE	VOGEL, ROBERT K TR	R-3	HDR	No	No	No	9	0.5	Yes	24	32	R-3 Upzone	16	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains a two-story multi-family residential building along with approximately 30 percent of the parcel used for surface parking</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. Additionally, a large portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
54	5779-005-043	No	402 CALIFORNIA ST F	STANSBURY, SYDNEY L TR	R-3	HDR	No	No	No	12	0.5	Yes	24	32	R-3 Upzone	16	4	1	<u>1</u>	<u>2</u>	<u>This parcel contains residential condominium buildings</u>	<u>The structure on this parcel is over 30 years old. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units.</u>
55	5379-028-021	No	1119 ARCADIA AVE	LAYDA, IVAN AND HILDA TRS	R-3	HDR	No	No	No	12	0.5	Yes	24	32	R-3 Upzone	16	4	1	<u>1</u>	<u>2</u>	<u>This parcel contains two-story multi-family housing with a pool along with approximately 30 percent of the parcel used for surface parking</u>	<u>The structure on this parcel is over 60 years old and a large portion of the parcel is being utilized for surface parking. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units.</u>
57	5772-005-001	No	805 N 1ST AVE	LOUIE, ANTORIA Y AND KENNETH AND	R-3	HDR	No	No	No	0	0.5	Yes	24	32	R-3 Upzone	16	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains a religious structure along with approximately 20 percent of the parcel used for surface parking.</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. Additionally, a large portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
58	5773-016-091	No	319 CALIFORNIA ST G	GLOBAL FINANCIAL GROUP INC	R-3	HDR	No	No	No	7	0.5	Yes	24	32	R-3 Upzone	16	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains residential condominium buildings</u>	<u>The structure on this parcel is over 20 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>

59	5383-029-038	No	720 W CAMINO REAL AVE	BDK ARCADIA LLC	R-3	HDR	No	No	No	0	0.5	Yes	24	32	R-3 Upzone	16	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains multi- family housing and a pool.</u>	<u>The structure on this parcel is older and contains less than the assumed existing density. Additionally, a large portion of the parcel is being utilized for a surface pool. This site could realistically turn over into a higher intensity use.</u>
60	5382-001-042	No	1140 W DUARTE RD	WANG,YONG H AND CAROLYN A	R-3	HDR	No	No	No	7	0.5	Yes	24	32	R-3 Upzone	16	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains low-density single-story multi- family housing.</u>	<u>The structure on this parcel is over 60 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
69	5379-022-112	No	1156 ARCADIA AVE NO 8	KIM,WILLIAM Y AND OK H	R-3	HDR	No	No	No	8	0.5	Yes	24	32	R-3 Upzone	17	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains residential condominium buildings</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
70	5779-003-066	No	167 ELDORADO ST A	QIN,MINGYI	R-3	HDR	No	No	No	6	0.5	Yes	24	32	R-3 Upzone	17	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
71	5773-013-058	No	31 ALTA ST A	ZHANG,MARGARET H	R-3	HDR	No	No	No	11	0.5	Yes	24	32	R-3 Upzone	17	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
72	5773-014-050	No	139 ALTA ST NO A	CHONG,YEE JEANE	R-3	HDR	No	No	No	10	0.5	Yes	24	32	R-3 Upzone	17	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways</u>	<u>The structure on this parcel contains less than the assumed existing density. Additionally, a large portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
74	5778-015-018	No	409 FAIRVIEW AVE	FURREY,JERRY B AND ROBERTA L TRS	R-3	HDR	No	No	No	11	0.6	Yes	24	32	R-3 Upzone	17	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains two-story multi- family housing and a pool.</u>	<u>The structure on this parcel is over 60 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
75	5777-028-015	No	722 S OLD RANCH RD	DEGRAZIO,MARGARET E TR ET AL	R-3	HDR	No	No	No	12	0.6	Yes	24	32	R-3 Upzone	17	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains two-story multi- family housing</u>	<u>The structure on this parcel is over 70 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
76	5379-029-084	No	1129 FAIRVIEW AVE NO E2	LIM,ELIZABETH H TR	R-3	HDR	No	No	No	10	0.6	Yes	24	32	R-3 Upzone	17	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
78	5783-006-063	No	1001 FAIRVIEW AVE	LEE,SHIN G AND JAIMEI C TRS	R-3	HDR	No	No	No	10	0.6	Yes	24	32	R-3 Upzone	18	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains multi- family housing.</u>	<u>The structure on this parcel is over 30 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
79	5783-001-046	No	1033 W DUARTE RD NO J	LINCOLN,CATHERINE R TR	R-3	HDR	No	No	No	10	0.6	Yes	24	32	R-3 Upzone	18	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains multi- family housing along with approximately 30 percent of the parcel dedicated to driveways</u>	<u>The structure on this parcel is over 30 years old and contains less than the assumed existing density. Additionally, a large portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
80	5778-002-064	No	627 FAIRVIEW AVE #A	QUAN,ALEX	R-3	HDR	No	No	No	12	0.6	Yes	24	32	R-3 Upzone	18	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
82	5773-016-172	No	205 S 3RD AVE	TAHOE MANAGEMENT AND	R-3	HDR	No	No	No	8	0.6	Yes	24	32	R-3 Upzone	18	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
83	5781-005-031	No	53 CHRISTINA ST	MEDALLION PROPERTIES LLC	R-3	HDR	No	No	No	10	0.6	Yes	24	32	R-3 Upzone	18	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure is over 40 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
84	5383-033-011	No	817 W CAMINO REAL AVE	TSENG,RICHARD C AND	R-3	HDR	No	No	No	5	0.6	Yes	24	32	R-3 Upzone	18	13	3	<u>2</u>	<u>8</u>	<u>This parcel contains multi- family housing along with approximately 30 percent of the parcel dedicated to driveways</u>	<u>This structure is over 60 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
85	5773-016-118	No	327 CALIFORNIA ST B	TOOKMANIAN,ROSE ET AL TRS	R-3	HDR	No	No	No	7	0.6	Yes	24	32	R-3 Upzone	18	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
86	5783-012-066	No	898 S GOLDEN WEST AVE	GIANNINI,PETER E ET AL TRS	R-3	HDR	No	No	No	8	0.6	Yes	24	32	R-3 Upzone	18	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
87	5778-011-052	No	826 LA CADENA AVE UNIT E	WU YI LIU	R-3	HDR	No	No	No	10	0.6	Yes	24	32	R-3 Upzone	18	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains residential condominium buildings and a pool</u>	<u>This structure contains less than the assumed existing density. Additionally, a portion of the surface is dedicated to a pool. This site could realistically turn over into a higher intensity use.</u>
88	5783-011-126	No	719 ARCADIA AVE C	LIM,ELIZABETH H TR	R-3	HDR	No	No	No	12	0.6	Yes	24	32	R-3 Upzone	18	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
89	5783-011-035	No	730 FAIRVIEW AVE	NEW WORLD INTERNATIONAL LLC	R-3	HDR	No	Yes	Yes	4	0.6	Yes	24	32	R-3 Upzone	18	14	4	<u>2</u>	<u>8</u>	<u>This parcel contains low-density single-story multi- family housing.</u>	<u>The structure on this parcel is over 70 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
90	5783-011-134	No	728 W FAIRVIEW AVE A	LI,GUOFEN	R-3	HDR	No	No	No	8	0.6	Yes	24	32	R-3 Upzone	18	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains two-story residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>

91	5783-011-081	No	735 ARCADIA AVE UNIT J	YU,JU YEOL AND	R-3	HDR	No	No	No	13	0.6	Yes	24	32	R-3 Upzone	18	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains two-story residential condominium buildings and a pool</u>	<u>This structure is over 40 years old and contains less than the assumed existing density. Additionally, a portion of the surface is dedicated to a pool. This site could realistically turn over into a higher intensity use.</u>
92	5783-007-089	No	1020 W HUNTINGTON DR B	SANTIAGO,JULIO C TR	R-3	HDR	No	No	No	6	0.6	Yes	24	32	R-3 Upzone	19	13	3	<u>2</u>	<u>8</u>	<u>This parcel contains residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways</u>	<u>The structure on this parcel contains less than the assumed existing density. Additionally, a large portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
93	5773-016-125	No	417 CALIFORNIA ST G	SIROTT,STANLEY A TR	R-3	HDR	No	No	No	7	0.6	Yes	24	32	R-3 Upzone	19	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains two-story residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
94	5777-029-056	No	723 S OLD RANCH RD A	FAIRVIEW APARTMENTS	R-3	HDR	No	No	No	11	0.6	Yes	24	32	R-3 Upzone	19	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains two-story residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
95	5783-007-057	No	825 S GOLDEN WEST AVE NO 10	MCBANE,KIP K TRUST	R-3	HDR	No	No	No	10	0.6	Yes	24	32	R-3 Upzone	19	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains residential condominium buildings</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
96	5773-016-107	No	211 S 5TH AVE	FUJIOKA FAMILY LTD PTNSHP NO 1	R-3	HDR	No	No	No	7	0.6	Yes	24	32	R-3 Upzone	19	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure on this parcel is over 20 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
97	5773-016-180	No	213 S 3RD AVE A	THIELE,GARY E	R-3	HDR	No	No	No	8	0.6	Yes	24	32	R-3 Upzone	19	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains two-story residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways</u>	<u>This structure contains less than the assumed existing density and a large portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
99	5783-004-040	No	930 FAIRVIEW AVE APT 0012	ARCADIA PRESBYTERIAN CHURCH	R-3	HDR	No	No	No	12	0.6	Yes	24	32	R-3 Upzone	19	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains two-story residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. Additionally, a large portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
100	5779-004-029	No	302 S 2ND AVE	VOGEL,ROBERT K	R-3	HDR	No	No	No	12	0.6	Yes	24	32	R-3 Upzone	19	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains multi- family housing along with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is almost 40 years old and contains less than the assumed existing density. A large portion of the parcel is currently being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
101	5778-009-026	No	1107 HOLLY AVE	GELBER,LOUISE C TR	R-3	HDR	No	No	No	12	0.6	Yes	24	32	R-3 Upzone	20	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains low-density multi-family housing with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a large portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
102	5783-006-098	No	921 FAIRVIEW AVE E	WARD,DOUGLAS A AND HYUNMI J	R-3	HDR	No	No	No	12	0.6	Yes	24	32	R-3 Upzone	20	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
104	5777-035-040	No	1025 W HUNTINGTON DR NO M	YUEH LING HSU	R-3	HDR	No	No	No	13	0.6	Yes	24	32	R-3 Upzone	20	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains residential condominium buildings</u>	<u>This structure is over 50 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
105	5773-016-155	No	298 S 2ND AVE B	REN,SONGYANG AND	R-3	HDR	No	No	No	10	0.7	Yes	24	32	R-3 Upzone	20	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains two-story residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities</u>
107	5783-002-034	No	917 W DUARTE RD UNIT 13	ROSENZWEIG,CAR OL N TR ET AL	R-3	HDR	No	No	No	13	0.7	Yes	24	32	R-3 Upzone	21	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This structure is over 40 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>

109	5778-006-003	No	636 FAIRVIEW AVE	DAI,BINGZHI AND	R-3	HDR	No	No	No	14	0.7	Yes	24	32	R-3 Upzone	21	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains multi- family housing along with a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for a pool. This site could realistically turn over into a higher intensity use. Additionally, it is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
110	5778-005-012	No	514 FAIRVIEW AVE	BELLWOOD LIMITED PARTNERSHIP	R-3	HDR	No	Yes	Yes	2	0.7	Yes	24	32	R-3 Upzone	21	19	5	<u>3</u>	<u>11</u>	<u>This parcel contains low-density multi-family housing with a majority of the parcel consisting of open dirt space utilized for parking and driveways.</u>	<u>The structure on this parcel is over 80 years old, contains less than the assumed existing density, and majority portion of the parcel consists of open dirt space. This site could realistically turn over into a higher intensity use. Additionally, it is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
111	5783-002-105	No	923 W DUARTE RD	LIU,YAN DUO	R-3	HDR	No	No	No	8	0.7	Yes	24	32	R-3 Upzone	21	13	3	<u>2</u>	<u>8</u>	<u>This parcel contains two-story residential condominium buildings</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
112	5778-006-002	No	628 FAIRVIEW AVE	RAMMELL,ROMAINE AND GLADYS TRS	R-3	HDR	No	No	No	15	0.7	Yes	24	32	R-3 Upzone	21	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use. Additionally, it is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
113	5778-005-013	No	518 FAIRVIEW AVE	CARLIN,VIRGINIA L TR	R-3	HDR	No	Yes	Yes	1	0.7	Yes	24	32	R-3 Upzone	21	20	5	<u>3</u>	<u>12</u>	<u>This parcel contains a single-family structure with a majority of the parcel consisting of open dirt space utilized for parking and driveways.</u>	<u>The structure on this parcel is over 80 years old, contains less than the assumed existing density because it is a single-family residence, and majority portion of the parcel consists of open dirt space. This site could realistically turn over into a higher intensity use. Additionally, it is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
115	5379-022-018	No	1127 W DUARTE RD	WILLMINGTON,EDWIN M AND MARY TRS	R-3	HDR	No	No	No	12	0.7	Yes	24	32	R-3 Upzone	21	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
116	5379-022-023	No	1131 W DUARTE RD	LEE,JAMES C AND	R-3	HDR	No	No	No	16	0.7	Yes	24	32	R-3 Upzone	21	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
118	5379-022-125	No	1141 W DUARTE RD NO M	FINNEGANS WAKE LP	R-3	HDR	No	No	No	12	0.7	Yes	24	32	R-3 Upzone	21	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
119	5778-010-040	No	1025 HOLLY AVE NO 12	SHEN,RU LIEH AND CHI FEN TRS	R-3	HDR	No	No	No	12	0.7	Yes	24	32	R-3 Upzone	21	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
120	5783-002-096	No	900 ARCADIA AVE 85	LIM,HANS S CO TR	R-3	HDR	No	No	No	14	0.7	Yes	24	32	R-3 Upzone	21	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
121	5379-029-034	No	1137 FAIRVIEW AVE NO K	SHI,ZU S AND	R-3	HDR	No	No	No	11	0.7	Yes	24	32	R-3 Upzone	21	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
122	5379-029-073	No	1141 FAIRVIEW AVE UNIT E	LIM,ELIZABETH H TR	R-3	HDR	No	No	No	15	0.7	Yes	24	32	R-3 Upzone	22	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>

123	5779-016-026	No	122 ALICE ST	SIROTT,STANLEY A TR	R-3	HDR	No	Yes	Yes	0	0.7	Yes	24	32	R-3 Upzone	22	22	6	<u>3</u>	<u>13</u>	<u>This parcel is entirely dedicated to surface parking</u>	<u>Since this site consists entirely of surface parking, this site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
126	5777-030-031	No	881 W HUNTINGTON DR UNIT A	NEMANI,PRASADA RAO CO TR	R-3	HDR	No	No	No	14	0.7	Yes	24	32	R-3 Upzone	22	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
127	5778-009-024	No	437 W DUARTE RD NO 5	400 W HUNTINGTON LLC	R-3	HDR	No	No	No	12	0.7	Yes	24	32	R-3 Upzone	23	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
128	5779-005-060	No	334 CALIFORNIA ST NO H	FENG,CHENG A CO TR	R-3	HDR	No	No	No	16	0.7	Yes	24	32	R-3 Upzone	23	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
129	5783-010-044	No	740 W HUNTINGTON DR UNIT L	CHENG,ANTON CO TR	R-3	HDR	No	No	No	11	0.7	Yes	24	32	R-3 Upzone	23	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use</u>
130	5783-010-021	No	760 W HUNTINGTON DR	YANG,KAREN H	R-3	HDR	No	No	No	13	0.7	Yes	24	32	R-3 Upzone	23	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
131	5379-037-036	No	1130 W HUNTINGTON DR UNIT 1	MEGA INTERNATIONAL COMMERCIAL	R-3	HDR	No	No	No	14	0.7	Yes	24	32	R-3 Upzone	23	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
132	5779-001-079	No	408 S SANTA ANITA AVE 16	TUNG,ALVIN C AND	R-3	HDR	No	No	No	16	0.7	Yes	24	32	R-3 Upzone	23	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
133	5779-011-063	No	14 ELDORADO ST NO 11	ZHANG,HAILONG	R-3	HDR	No	No	No	15	0.7	Yes	24	32	R-3 Upzone	23	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
135	5379-029-057	No	1121 FAIRVIEW AVE I	MANOHARA,HARIS H M CO TR	R-3	HDR	No	No	No	17	0.7	Yes	24	32	R-3 Upzone	23	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
136	5382-001-067	No	1100 W DUARTE RD	UPTON,JANICE TR	R-3	HDR	No	No	No	1	0.7	Yes	24	32	R-3 Upzone	23	22	6	<u>3</u>	<u>13</u>	<u>This parcel contains a religious structure along with over 50 percent of the parcel used for surface parking.</u>	<u>The structure on this parcel is over 30 years old and contains less than the assumed existing density. Additionally, a majority of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
137	5778-007-025	No	628 ARCADIA AVE	HYTAM LLC AND	R-3	HDR	No	No	No	8	0.7	Yes	24	32	R-3 Upzone	23	15	4	<u>2</u>	<u>9</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
138	5783-005-052	No	850 ARCADIA AVE NO 15	KARADIMAS,VLAD A	R-3	HDR	No	No	No	15	0.8	Yes	24	32	R-3 Upzone	24	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. Additionally, a significant of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>

139	5382-002-058	No	1156 W DUARTE RD APT 0001	CHRISTY,INGE J	R-3	HDR	No	No	No	14	0.8	Yes	24	32	R-3 Upzone	24	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. Additionally, a significant of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
140	5383-002-005	No	922 W DUARTE RD	YUAN,STANLEY	R-3	HDR	No	No	No	14	0.8	Yes	24	32	R-3 Upzone	24	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
141	5783-011-098	No	750 FAIRVIEW AVE UNIT P	ARCADIA PINES ASSOCIATES	R-3	HDR	No	No	No	16	0.8	Yes	24	32	R-3 Upzone	24	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
142	5777-035-027	No	921 W HUNTINGTON DR	QI,DAN AND	R-3	HDR	No	No	No	20	0.8	Yes	24	32	R-3 Upzone	25	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old and a significant portion of the parcel is being utilized for cars and a pool. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units.</u>
143	5773-016-070	No	315 CALIFORNIA ST UNIT E	ACH HEALTHCARE PROPERTY LLC	R-3	HDR	No	No	No	20	0.8	Yes	24	32	R-3 Upzone	25	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old and a significant portion of the parcel is being utilized for cars. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
144	5773-002-051	No	425 N 1ST AVE UNIT H	TAM,SIMON AND	R-3	HDR	No	No	No	16	0.8	Yes	24	32	R-3 Upzone	26	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a very short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
145	5783-002-049	No	931 W DUARTE RD 7	CLEMINSON,LUCILLE E	R-3	HDR	No	No	No	14	0.8	Yes	24	32	R-3 Upzone	26	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
146	5778-015-011	No	428 W HUNTINGTON DR NO 11	ANAND,SRIVAIKUTAM AND	R-3	HDR	No	No	No	11	0.8	Yes	24	32	R-3 Upzone	26	15	4	<u>2</u>	<u>9</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
148	5783-002-129	No	988 ARCADIA AVE A	MAO,XULIANG	R-3	HDR	No	No	No	18	0.8	Yes	24	32	R-3 Upzone	26	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This structure contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
149	5383-001-090	No	1004 W DUARTE RD NO 10	OUR SAVIOR LUTHERAN CHURCH	R-3	HDR	No	No	No	10	0.8	Yes	24	32	R-3 Upzone	26	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
151	5778-003-015	No	526 W HUNTINGTON DR	TAO,LI AND	R-3	HDR	No	No	No	21	0.8	Yes	24	32	R-3 Upzone	26	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old and a significant portion of the parcel is being utilized for cars. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units. Additionally, it is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
152	5383-001-079	No	1218 TEMPLE CITY BLVD APT 0016	HOPKINS,MARK AND MARY TR ET AL	R-3	HDR	No	No	No	16	0.9	Yes	24	32	R-3 Upzone	27	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
154	5783-008-043	No	750 ARCADIA AVE NO 12	417 425 E LIVE OAK LLC AND	R-3	HDR	No	No	No	12	0.9	Yes	24	32	R-3 Upzone	27	15	4	<u>2</u>	<u>2</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>

155	5778-010-023	No	420 FAIRVIEW AVE	OESER,EUGENIA TR	R-3	HDR	No	No	No	14	0.9	Yes	24	32	R-3 Upzone	27	13	3	2	8	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use. Additionally, it is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
156	5783-014-077	No	838 FAIRVIEW AVE NO G	STRANDQUIST,MIC HAEL A	R-3	HDR	No	No	No	16	0.9	Yes	24	32	R-3 Upzone	27	11	3	2	6	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
157	5783-004-058	No	914 FAIRVIEW AVE UNIT 16	CHURCH OF THE GOOD SHEPHERD	R-3	HDR	No	No	No	16	0.9	Yes	24	32	R-3 Upzone	27	11	3	2	6	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
158	5783-013-048	No	731 FAIRVIEW AVE NO 10	SCIARRA,JOSEPH A AND NANCY L TRS	R-3	HDR	No	No	No	10	0.9	Yes	24	32	R-3 Upzone	27	17	4	3	10	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
159	5783-014-007	No	852 FAIRVIEW AVE	PAUL REVERE LIFE INSURANCE CO	R-3	HDR	No	No	No	21	0.9	Yes	24	32	R-3 Upzone	27	6	2	1	3	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
160	5783-014-033	No	821 ARCADIA AVE	NAHAS,OHANES J	R-3	HDR	No	No	No	16	0.9	Yes	24	32	R-3 Upzone	27	11	3	2	6	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
161	5379-028-024	No	1125 ARCADIA AVE	AC FOOTHILL LLC	R-3	HDR	No	No	No	18	0.9	Yes	24	32	R-3 Upzone	27	9	2	1	6	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
162	5783-004-026	No	933 ARCADIA AVE	NARRAMORE CHRISTIAN FOUNDATION	R-3	HDR	No	No	No	20	0.9	Yes	24	32	R-3 Upzone	27	7	2	1	4	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
163	5783-002-068	No	924 ARCADIA AVE NO 117	CAPITAL SUN INVESTMENT LLC	R-3	HDR	No	No	No	17	0.9	Yes	24	32	R-3 Upzone	27	10	3	2	5	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
164	5783-005-077	No	1160 S GOLDEN WEST AVE NO 1	DEMETRIADES,STE RGE AND ANNA TRS	R-3	HDR	No	No	No	18	0.9	Yes	24	32	R-3 Upzone	27	9	2	1	6	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
165	5783-014-105	No	825 ARCADIA AVE A	601 LAS TUNAS LLC	R-3	HDR	No	No	No	18	0.9	Yes	24	32	R-3 Upzone	27	9	2	1	6	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
166	5383-034-046	No	816 W NAOMI AVE UNIT 18	KKW INVESTMENTS LLC	R-3	HDR	No	No	No	18	0.9	Yes	24	32	R-3 Upzone	28	10	3	2	5	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
167	5383-033-048	No	807 W CAMINO REAL AVE NO S	SINGPOLI INVESTMENT LLC	R-3	HDR	No	No	No	19	0.9	Yes	24	32	R-3 Upzone	28	9	2	1	6	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
168	5383-029-058	No	738 W CAMINO REAL AVE I	PME INVESTMENT LLC	R-3	HDR	No	No	No	18	0.9	Yes	24	32	R-3 Upzone	28	10	3	2	5	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>

169	5783-001-074	No	1058 ARCADIA AVE	CHOI,HELEN R TR	R-3	HDR	No	No	No	10	0.9	Yes	24	32	R-3 Upzone	28	18	5	<u>3</u>	<u>10</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
170	5778-010-109	No	460 FAIRVIEW AVE UNIT 18	MEILOON PLUS LLC	R-3	HDR	No	No	No	18	0.9	Yes	24	32	R-3 Upzone	29	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
172	5790-030-012	No	435 E LIVE OAK AVE	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	21	1	Yes	24	32	R-3 Upzone	30	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
173	5778-002-009	No	637 FAIRVIEW AVE	623 WEST DUARTE ROAD LLC	R-3	HDR	No	No	No	20	1	Yes	24	32	R-3 Upzone	31	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
175	5783-007-022	No	928 W HUNTINGTON DR	STARNES INVESTMENT COMPANY LLC	R-3	HDR	No	No	No	21	1	Yes	24	32	R-3 Upzone	31	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains multi-family housing.</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
176	5783-007-010	No	1026 W HUNTINGTON DR	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	23	1	Yes	24	32	R-3 Upzone	31	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
179	5783-007-046	No	1002 W HUNTINGTON DR UNIT B	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	14	1	Yes	24	32	R-3 Upzone	31	17	4	<u>3</u>	<u>10</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
180	5383-001-062	No	1022 W DUARTE RD NO 18	TRIPOD PROPERTY LLC	R-3	HDR	No	No	No	18	1	Yes	24	32	R-3 Upzone	31	13	3	<u>2</u>	<u>8</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
181	5783-007-021	No	936 W HUNTINGTON DR	HSU AND MIAO LLC	R-3	HDR	No	No	No	24	1	Yes	24	32	R-3 Upzone	31	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains multi-family housing along with approximately 50 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 60 years old, and a significant portion of the parcel is being utilized for cars. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units. This site could realistically turn over into a higher intensity use.</u>
182	5783-007-024	No	918 W HUNTINGTON DR	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	20	1	Yes	24	32	R-3 Upzone	31	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 50 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
183	5783-009-010	No	828 W HUNTINGTON DR	M AND H CAPITAL INC AND	R-3	HDR	No	No	No	22	1	Yes	24	32	R-3 Upzone	31	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 20 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
184	5379-022-021	No	1147 W DUARTE RD	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	12	1	Yes	24	32	R-3 Upzone	31	19	5	<u>3</u>	<u>11</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
185	5783-006-014	No	915 FAIRVIEW AVE	M AND H CAPITAL INC AND	R-3	HDR	No	No	No	20	1	Yes	24	32	R-3 Upzone	31	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
186	5783-012-057	No	847 FAIRVIEW AVE NO J	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	20	1	Yes	24	32	R-3 Upzone	32	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>

187	5379-037-001	No	1148 W HUNTINGTON DR	LEWIS PROPERTIES INC	R-3	HDR	No	No	No	26	1	Yes	24	32	R-3 Upzone	32	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 70 years old and a significant portion of the parcel is being utilized for cars. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units. This site could realistically turn over into a higher intensity use.</u>
188	5778-004-011	No	515 FAIRVIEW AVE	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	22	1	Yes	24	32	R-3 Upzone	32	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
189	5778-002-051	No	609 FAIRVIEW AVE NO 1	L AND J INVESTMENT CO	R-3	HDR	No	No	No	18	1	Yes	24	32	R-3 Upzone	33	15	4	<u>2</u>	<u>9</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
190	5783-003-042	No	1015 ARCADIA AVE APT 0002	SIEN,RICHARD AND GRACE TRS ET AL	R-3	HDR	No	No	No	20	1	Yes	24	32	R-3 Upzone	33	13	3	<u>2</u>	<u>8</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
192	5778-009-093	No	415 W DUARTE RD UNIT 8	WEN REN LLC	R-3	HDR	No	No	No	21	1.1	Yes	24	32	R-3 Upzone	33	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains residential condominium buildings with approximately 10 percent of the parcel dedicated to a pool</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for a pool. This site could realistically turn over into a higher intensity use.</u>
193	5783-014-036	No	800 FAIRVIEW AVE	RALPHS GROCERY CO	R-3	HDR	No	No	No	21	1.1	Yes	24	32	R-3 Upzone	33	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains multi-family housing</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
194	5379-028-001	No	1150 FAIRVIEW AVE	FRANDSON,CHARLES L TR	R-3	HDR	No	No	No	23	1.1	Yes	24	32	R-3 Upzone	34	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
195	5379-021-003	No	1167 W DUARTE RD	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	18	1.1	Yes	24	32	R-3 Upzone	34	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains multi-family housing along with approximately 20 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
196	5783-001-021	No	1023 W DUARTE RD	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	24	1.1	Yes	24	32	R-3 Upzone	34	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
197	5778-003-040	No	506 W HUNTINGTON DR NO 21D	SANTA ANITA CHURCH	R-3	HDR	No	No	No	21	1.1	Yes	24	32	R-3 Upzone	35	14	4	<u>2</u>	<u>8</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
198	5779-017-029	No	121 ALICE ST	DAQUINO PROPERTIES LLC	R-3	HDR	No	No	No	0	1.1	Yes	24	32	R-3 Upzone	35	35	9	<u>5</u>	<u>21</u>	<u>This parcel contains a religious structure along with approximately 20 percent of the parcel used for surface parking.</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
200	5783-002-050	No	1005 W DUARTE RD	ROSEWOOD INVESTMENT OF ARCADIA	R-3	HDR	No	No	No	25	1.1	Yes	24	32	R-3 Upzone	35	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
201	5778-009-025	No	433 W DUARTE RD	L AND J INVESTMENT CO	R-3	HDR	No	No	No	23	1.1	Yes	24	32	R-3 Upzone	35	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
202	5783-004-078	No	1000 FAIRVIEW AVE APT 0001	ARCADIA BURGE LLC	R-3	HDR	No	No	No	20	1.1	Yes	24	32	R-3 Upzone	35	15	4	<u>2</u>	<u>9</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>

203	5383-031-096	No	749 W CAMINO REAL AVE NO G	RALPHS GROCERY CO	R-3	HDR	No	No	No	26	1.1	Yes	24	32	R-3 Upzone	36	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
204	5783-006-082	No	928 SUNSET BLVD	CALIF THOROUGHbred BREEDERS ASSN	R-3	HDR	No	No	No	14	1.2	Yes	24	32	R-3 Upzone	36	22	6	<u>3</u>	<u>13</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
206	5785-001-001	No	1600 S BALDWIN AVE	99 CENTS ONLY STORES	R-3	HDR	No	No	No	32	1.2	Yes	24	32	R-3 Upzone	38	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old and a significant portion of the parcel is being utilized for cars and a pool. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units. This site could realistically turn over into a higher intensity use.</u>
207	5379-028-052	No	1126 FAIRVIEW AVE UNIT 215	WASHE LLC	R-3	HDR	No	No	No	25	1.2	Yes	24	32	R-3 Upzone	39	14	4	<u>2</u>	<u>8</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
208	5778-010-087	No	456 FAIRVIEW AVE	UNITED CAPITAL INVESTMENT GROUP	R-3	HDR	No	No	No	30	1.3	Yes	24	32	R-3 Upzone	40	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
209	5778-009-144	No	471 W DUARTE RD NO 227	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	27	1.3	Yes	24	32	R-3 Upzone	41	14	4	<u>2</u>	<u>8</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 60 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
210	5778-009-117	No	1102 LA CADENA AVE NO 6	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	24	1.3	Yes	24	32	R-3 Upzone	41	17	4	<u>3</u>	<u>10</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
211	5778-006-045	No	618 FAIRVIEW AVE NO 234	GREAT WESTERN SAVING AND LOAN	R-3	HDR	No	No	No	34	1.3	Yes	24	32	R-3 Upzone	42	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains two-story residential condominium buildings</u>	<u>The structure on this parcel is over 30 years old. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units.</u>
212	5773-016-142	No	347 CALIFORNIA ST	PIC N SAVE OF CALIF INC	R-3	HDR	No	No	No	16	1.3	Yes	24	32	R-3 Upzone	42	26	7	<u>4</u>	<u>15</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
213	5383-031-068	No	760 W NAOMI AVE UNIT A	M AND H CAPITAL INC AND	R-3	HDR	No	No	No	30	1.3	Yes	24	32	R-3 Upzone	42	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
214	5783-007-018	No	1014 W HUNTINGTON DR	624 MEDICAL CENTER	R-3	HDR	No	No	No	34	1.4	Yes	24	32	R-3 Upzone	43	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 30 years old. Additionally, a significant portion of the parcel is being utilized for surface parking. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units.</u>
215	5383-031-113	No	748 W NAOMI AVE A	SOO PROPERTIES LLC	R-3	HDR	No	No	No	15	1.4	Yes	24	32	R-3 Upzone	43	28	7	<u>4</u>	<u>17</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
216	5379-022-094	No	1161 W DUARTE RD APT 0028	BALDWIN ARCADIA CENTER LP	R-3	HDR	No	No	No	28	1.4	Yes	24	32	R-3 Upzone	44	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
217	5784-007-032	No	442 W DUARTE RD D	KJR EASTERN ENTERPRISES INC AND	R-3	HDR	No	No	No	25	1.4	Yes	24	32	R-3 Upzone	46	21	5	<u>3</u>	<u>13</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>

221	5783-009-009	No	834 W HUNTINGTON DR	LINKWORLD PROPERTIES LLC	R-3	HDR	No	No	No	31	1.5	Yes	24	32	R-3 Upzone	47	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 60 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
222	5778-006-004	No	646 FAIRVIEW AVE	LINKWORLD PROPERTIES LLC	R-3	HDR	No	No	No	44	1.5	Yes	24	32	R-3 Upzone	48	4	1	<u>1</u>	<u>2</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old. Additionally, a significant portion of the parcel is being utilized for surface parking and a pool. With increased density in R-3, the site could be redeveloped to accommodate a higher number of dwelling units.</u>
223	5778-011-084	No	435 FAIRVIEW AVE UNIT 11	SANTA ANITA CHURCH	R-3	HDR	No	No	No	32	1.5	Yes	24	32	R-3 Upzone	49	17	4	<u>3</u>	<u>10</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to a pool, driveways, and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
224	5778-015-024	No	414 W HUNTINGTON DR	M AND R 2	R-3	HDR	No	No	No	0	1.6	Yes	24	32	R-3 Upzone	50	50	14	<u>8</u>	<u>28</u>	<u>This parcel contains a two-story rehabilitation center, with approximately 30 percent of the parcel dedicated to parking</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use. It is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
225	5383-002-068	No	1231 S GOLDEN WEST AVE NO 30	JOHNSON,SHANE A TR ET AL	R-3	HDR	No	No	No	30	1.6	Yes	24	32	R-3 Upzone	50	20	5	<u>3</u>	<u>12</u>	<u>This parcel contains two-story residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
226	5783-013-091	No	727 FAIRVIEW AVE A	TUCKER,FRANK AND JUDITH AND	R-3	HDR	No	No	No	22	1.6	Yes	24	32	R-3 Upzone	51	29	7	<u>4</u>	<u>18</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
227	5778-011-126	No	444 W HUNTINGTON DR NO 110	TF AND TB LP	R-3	HDR	No	No	No	30	1.7	Yes	24	32	R-3 Upzone	53	23	6	<u>3</u>	<u>14</u>	<u>This parcel contains two-story residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking and a pool. This site could realistically turn over into a higher intensity use. It is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
228	5778-011-161	No	452 W HUNTINGTON DR UNIT A	ARCADIA GATEWAY CENTRE DELAWARE	R-3	HDR	No	No	No	32	1.7	Yes	24	32	R-3 Upzone	53	21	5	<u>3</u>	<u>13</u>	<u>This parcel contains residential condominium buildings and a pool</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use. It is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
229	5379-028-084	No	1135 ARCADIA AVE NO 1	GERNON HOLDINGS LLC	R-3	HDR	No	No	No	32	1.7	Yes	24	32	R-3 Upzone	53	21	5	<u>3</u>	<u>13</u>	<u>This parcel contains residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
230	5778-001-170	No	656 W HUNTINGTON DR O-1	POST EXCHANGE LLC	R-3	HDR	No	No	No	34	1.7	Yes	24	32	R-3 Upzone	54	20	5	<u>3</u>	<u>12</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
231	5778-001-134	No	634 W HUNTINGTON DR NO 1	POST EXCHANGE LLC	R-3	HDR	No	No	No	30	1.7	Yes	24	32	R-3 Upzone	54	24	6	<u>4</u>	<u>14</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
232	5783-003-063	No	1024 FAIRVIEW AVE NO 1	L A DISTRICT CHURCH OF THE	R-3	HDR	No	No	No	20	1.7	Yes	24	32	R-3 Upzone	55	35	9	<u>5</u>	<u>21</u>	<u>This parcel contains two-story residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old and contains less than the assumed existing density. Additionally, a significant portion of the parcel is being utilized for surface parking and a pool. This site could realistically turn over into a higher intensity use.</u>
233	5784-006-008	No	474 W DUARTE RD	GARY W MORRIS LLC	R-3	HDR	No	No	No	40	1.8	Yes	24	32	R-3 Upzone	56	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>

234	5778-005-055	No	540 FAIRVIEW AVE APT 0040	KAKU,SHIGENOBU AND HIKARU TRS	R-3	HDR	No	No	No	40	1.8	Yes	24	32	R-3 Upzone	57	17	4	<u>3</u>	<u>10</u>	<u>This parcel contains two-story residential condominium buildings and a pool</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
235	5784-006-004	No	488 W DUARTE RD APT 0023	FASCHING,GEORGE W CO TR	R-3	HDR	No	No	No	38	1.8	Yes	24	32	R-3 Upzone	57	19	5	<u>3</u>	<u>11</u>	<u>This parcel contains multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
236	5779-005-080	No	301 S 5TH AVE NO A	INDUSTRIAL INVESTORS LLC	R-3	HDR	No	No	No	20	1.8	Yes	24	32	R-3 Upzone	57	37	9	<u>6</u>	<u>22</u>	<u>This parcel contains two-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use. Additionally, it is a relatively short walk from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
237	5778-008-003	No	515 W DUARTE RD	ULCICKAS,JULIE A TR	R-3	HDR	No	No	No	28	1.9	Yes	24	32	R-3 Upzone	60	32	8	<u>5</u>	<u>19</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
238	5778-008-060	No	535 W DUARTE RD NO 44A	AUTOMOBILE CLUB OF SOUTHERN	R-3	HDR	No	No	No	44	2.1	Yes	24	32	R-3 Upzone	67	23	6	<u>3</u>	<u>14</u>	<u>This parcel contains two-story residential condominium buildings and a pool</u>	<u>The structure on this parcel is over 50 years old and contains less than the assumed existing density. This site could realistically turn over into a higher intensity use.</u>
239	5383-029-028	No	1601 S BALDWIN AVE	STURNIOLO,CHARL ES A CO TR	R-3	HDR	No	Yes	Yes	0	2.2	Yes	24	32	R-3 Upzone	69	69	18	<u>10</u>	<u>41</u>	<u>This parcel contains a single-story health care center with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 30 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
240	5784-007-051	No	446 W DUARTE RD A	FIFTH AVENUE GROUP LLC	R-3	HDR	No	No	No	25	2.2	Yes	24	32	R-3 Upzone	70	45	11	<u>7</u>	<u>27</u>	<u>This parcel contains two-story residential condominium buildings and a pool</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
243	5784-001-077	No	658 W NAOMI AVE NO 26	GLENN AND BLT LLC AND	R-3	HDR	No	No	No	26	2.3	Yes	24	32	R-3 Upzone	73	47	12	<u>7</u>	<u>28</u>	<u>This parcel contains single-story residential condominium buildings with approximately 30 percent of the parcel dedicated to driveways and parking</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars. This site could realistically turn over into a higher intensity use.</u>
244	5783-009-073	No	848 W HUNTINGTON DR NO 42	HEPRAND HOSPITALITY INC	R-3	HDR	No	No	No	42	2.4	Yes	24	32	R-3 Upzone	75	33	8	<u>5</u>	<u>20</u>	<u>This parcel contains residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
245	5778-009-072	No	457 W DUARTE RD	EVERWIN INVESTMENT INC	R-3	HDR	No	No	No	46	2.4	Yes	24	32	R-3 Upzone	78	32	8	<u>5</u>	<u>19</u>	<u>This parcel contains two-story residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
246	5784-006-009	No	512 W DUARTE RD	BRE ESA PROPERTIES LLC	R-3	HDR	No	No	No	0	2.5	Yes	24	32	R-3 Upzone	81	81	21	<u>12</u>	<u>48</u>	<u>This parcel contains a religious structure with approximately 50 percent of the parcel dedicated to surface parking</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
247	5778-004-059	No	561 FAIRVIEW AVE	BRE NEWTON HOTELS PROPERTY OWNER	R-3	HDR	No	No	No	44	2.6	Yes	24	32	R-3 Upzone	82	38	10	<u>6</u>	<u>22</u>	<u>This parcel contains residential condominium buildings along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 50 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
248	5775-012-025	No	245 W COLORADO BLVD	ARCADIA HOTEL VENTURE LP	R-3	HDR	No	No	No	54	2.7	Yes	24	32	R-3 Upzone	84	30	8	<u>5</u>	<u>17</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use. It is within walking distance from the Arcadia Metro station, giving residents access to increased economic opportunities.</u>
249	5790-030-053	No	417 E LIVE OAK AVE	HUNTINGTON LANMARK LLC	R-3	HDR	No	No	No	60	2.8	Yes	24	32	R-3 Upzone	90	30	8	<u>5</u>	<u>17</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 60 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>

250	5778-010-086	No	436 FAIRVIEW AVE NO 45	ARCADIA GATEWAY CENTRE DELAWARE	R-3	HDR	No	No	No	45	3.2	Yes	24	32	R-3 Upzone	101	56	15	<u>8</u>	<u>33</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>The structure on this parcel is over 40 years old, contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
251	5778-001-098	No	W Huntington Dr	MEEKER FAMILY PARTNERS LP	R-3	HDR	No	No	No	74	3.4	Yes	24	32	R-3 Upzone	109	35	9	<u>5</u>	<u>21</u>	<u>This parcel contains two-story multi-family housing along with approximately 30 percent of the parcel dedicated to driveways, parking, and a pool</u>	<u>This parcel contains less than the assumed existing density, and a significant portion of the parcel is being utilized for cars and a pool. This site could realistically turn over into a higher intensity use.</u>
252	5784-007-021	No	400 W DUARTE RD	HUANG,MARTIN	R-3	HDR	No	No	No	0	3.6	Yes	24	32	R-3 Upzone	115	115	30	<u>17</u>	<u>68</u>	<u>This parcel contains a religious structure with approximately 60 percent of the parcel dedicated to surface parking</u>	<u>The structure on this parcel is over 60 years old and contains less than the assumed existing density. Additionally, a majority of the parcel is being utilized for surface parking. This site could realistically turn over into a higher intensity use.</u>
253	5778-003-130	No	582 W HUNTINGTON DR UNIT Q	LIVE OAK DEVELOPMENT I LLC	R-3	HDR	No	No	No	90	4.2	Yes	24	32	R-3 Upzone	133	43	11	<u>6</u>	<u>26</u>	<u>This parcel contains multiple clusters of three-story multi-family residential structure with first floor garages.</u>	<u>The parcel consists of one multiple clusters of three-story multi-family residential structure with first floor garages. With increased density, the parcel could be redeveloped to accomodate a higher number or units. The property bordered by similar multi-family residential uses on all sides. This site could realistically turn over into a higher intensity use.</u>
274	5771-021-017	No	143 E FOOTHILL BLVD	PAUL REVERE LIFE INSURANCE CO	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>This commercially zoned parcel contains a one story fast food restaurant and parking lot.</u>	<u>This parcel consists of a one-story commercial parcel. A large portion of the parcel is being used for a drive through and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
275	5770-009-026	No	5 W FOOTHILL BLVD	NAHAS,OHANES J	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>This commercially zoned parcel contains two one-story buildings, a gas station and convenience store</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial parcel. A large portion of the parcel is being used as surface parking and driveways. This site could realistically turn over to a higher intensity residential use.</u>
276	5772-001-007	No	50 E FOOTHILL BLVD	AC FOOTHILL LLC	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>This commercially zoned parcel contains one two-story office building. 75% of the parcel is surface parking.</u>	<u>This parcel consits of a two-story office building and is 38 years old and contains a large portion of surface parking. This site could realistically turn over to a higher intensity residential use.</u>
277	5775-011-030	No	250 W COLORADO BLVD	NARRAMORE CHRISTIAN FOUNDATION	C-G	C 1.0	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>This commerically zoned parcel contains a two-story office building on 50% of the parcel. The parcel has surface parking and driveways.</u>	<u>This parcel consits of a two-story office building and is 38 years old and contains a large portion of surface parking. This site could realistically turn over to a higher intensity residential use.</u>
278	5778-001-103	No	850 S BALDWIN AVE	CAPITAL SUN INVESTMENT LLC	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>This commerically zoned parcel contains a restaurant and surface parking. 75% of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building that is 42 years old. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
279	5775-021-037	No	41 W SANTA CLARA ST	DEMETRIADES,STE RGE AND ANNA TRS	C-G	C 1.0	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>This commercially zoned parcel contains a two-story building and surface parking lot.</u>	<u>The structure on this parcel is 56 years old. A small portion of the parcel is being used for surface parking. This site could realistically turn over to a higher intensity residential use.</u>
280	5787-024-036	No	601 LAS TUNAS DR	601 LAS TUNAS LLC	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>This commercially zoned parcel contains two-story office building with podium parking underneath.</u>	<u>The structure on this parcel is 53 years old. A small part of the parcel is surface parking. This site could realistically turn over to a higher intensity residential use.</u>
281	5772-001-006	No	54 E FOOTHILL BLVD	KKW INVESTMENTS LLC	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	17	17	4	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a one-story office building and surface parking next to an autobody shop.</u>	<u>The structure on this parcel is 65 years old. A small part of the parcel is surface parking. This site could realistically turn over to a higher intensity residential use.</u>
282	5783-008-045	No	1107 S BALDWIN AVE	SINGPOLI INVESTMENT LLC	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	17	17	4	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a one-story commercial building. 50% of this parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. A portion of the parcel is surface parking. This site could realistically turn over to a higher intensity residential use.</u>
283	5783-008-030	No	747 W DUARTE RD	PME INVESTMENT LLC	C-G	C	Yes	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	17	17	4	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains an office building and 75% of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. The structure on this parcel is 56 years old. A portion of the parcel is surface parking. This site could realistically turn over to a higher intensity residential use.</u>
284	5772-001-022	No	1000 N SANTA ANITA AVE	CHOI,HELEN R TR	C-G	C	No	No	No	0	0.7	Yes	0	24	C-G Residential Flex Overlay	17	17	4	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a one-story commercial building and 50% of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. The structure on this parcel is 62 years old. A portion of the parcel is surface parking. This site could realistically turn over to a higher intensity residential use.</u>
285	5784-001-020	No	1440 S BALDWIN AVE	MEILOON PLUS LLC	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	18	18	5	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a one-story commercial building and 75% of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This structure is 51 years old and and the parcel has surface parking. This site could realistically turn over to a higher intensity residential use.</u>

286	5383-035-019	No	745 W NAOMI AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	18	18	5	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a one-story commercial building and half of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This structure is 69 years old and the parcel has surface parking. This site could realistically turn over to a higher intensity residential use.</u>
287	5778-007-014	No	623 W DUARTE RD	623 WEST DUARTE ROAD LLC	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	18	18	5	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This structure is 60 years old and the parcel has surface parking. This site could realistically turn over to a higher intensity residential use.</u>
288	5783-008-031	No	753 W DUARTE RD	STARNES INVESTMENT COMPANY LLC	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	18	18	5	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a two-story commercial building and the parcel is around 25% surface parking.</u>	<u>This structure is 46 years old and the parcel has surface parking. This site could realistically turn over to a higher intensity residential use.</u>
289	5383-035-035	No	729 W NAOMI AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	18	18	5	<u>3</u>	<u>10</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel has a Land Value Ratio less than one. This structure is 52 years old and the parcel has surface parking. This site could realistically turn over to a higher intensity residential use.</u>
290	5383-035-028	No	745 W NAOMI AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	19	19	5	<u>3</u>	<u>11</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel has a commercial building and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
291	5778-007-001	No	1038 S BALDWIN AVE	TRIPOD PROPERTY LLC	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	20	20	5	<u>3</u>	<u>12</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot is 25% of this parcel.</u>	<u>This parcel is 52 years old and has a commercial building and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
292	5783-008-049	No	711 W DUARTE RD	HSU AND MIAO LLC	C-G	C	No	No	No	0	0.8	Yes	0	24	C-G Residential Flex Overlay	20	20	5	<u>3</u>	<u>12</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot is 25% of this parcel.</u>	<u>This parcel is 35 years old and has a commercial building and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
293	5383-035-034	No	W Naomi Ave	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	0.9	Yes	0	24	C-G Residential Flex Overlay	20	20	5	<u>3</u>	<u>12</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking spots.</u>	<u>This parcel is 36 years old and has a commercial building and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
294	5784-003-027	No	650 W DUARTE RD	M AND H CAPITAL INC AND	C-G	C	No	No	No	0	0.9	Yes	0	24	C-G Residential Flex Overlay	21	21	5	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and 50% of the parcel is surface parking.</u>	<u>This parcel is 66 years old and has a commercial building and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
295	5383-035-031	No	1201 S BALDWIN AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	0.9	Yes	0	24	C-G Residential Flex Overlay	21	21	5	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and 25% of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building that is over 50 years old. A small portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
296	5784-003-025	No	632 W DUARTE RD	M AND H CAPITAL INC AND	C-G	C	No	No	No	0	0.9	Yes	0	24	C-G Residential Flex Overlay	21	21	5	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and half of the parcel is surface parking.</u>	<u>This parcel is over 50 years old and has a commercial building and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
297	5383-035-030	No	720 W DUARTE RD	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	0.9	Yes	0	24	C-G Residential Flex Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building that is over 50 years old. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
298	5783-013-032	No	855 S BALDWIN AVE	LEWIS PROPERTIES INC	C-G	C	No	No	No	0	0.9	Yes	0	24	C-G Residential Flex Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This parcel has a commercial building and surface parking. This site could realistically turn over to a higher intensity residential use.</u>
299	5383-035-026	No	745 W NAOMI AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	0.9	Yes	0	24	C-G Residential Flex Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
300	8587-033-021	No	9974 LAS TUNAS DR	L AND J INVESTMENT CO	C-G	C	No	No	No	0	1	Yes	0	24	C-G Residential Flex Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This parcel consists of a one-story commercial building that is over 30 years old. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
301	8586-001-027	No	556 LAS TUNAS DR	SIEN,RICHARD AND GRACE TRS ET AL	C-G	C	No	No	No	0	1	Yes	0	24	C-G Residential Flex Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
302	5771-028-024	No	317 E FOOTHILL BLVD	WEN REN LLC	C-G	C	No	No	No	0	1	Yes	0	24	C-G Residential Flex Overlay	23	23	6	<u>3</u>	<u>14</u>	<u>This commercially zoned parcel contains a one-story commercial building and half of the parcel is surface parking.</u>	<u>This parcel consists of a one-story commercial building and a large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
303	5771-028-037	No	211 E FOOTHILL BLVD	RALPHS GROCERY CO	C-G	C	No	No	No	0	1.1	Yes	0	24	C-G Residential Flex Overlay	25	25	6	<u>4</u>	<u>15</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>

304	5775-023-015	No	101 W HUNTINGTON DR	FRANDSON,CHARL ES L TR	C-G	C 1.0	No	No	No	0	1.1	Yes	0	24	C-G Residential Flex Overlay	25	25	6	<u>4</u>	<u>15</u>	<u>This commercially zoned parcel contains a one-story commercial building and more than half of the parcel is surface parking.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building that is 45 years old. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
305	5383-035-025	No	745 W NAOMI AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	1.1	Yes	0	24	C-G Residential Flex Overlay	27	27	7	<u>4</u>	<u>16</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel consists of a one-story commercial building and surface parking lot. This site could realistically turn over to a higher intensity residential use.</u>
306	5383-038-021	No	1201 S BALDWIN AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	1.2	Yes	0	24	C-G Residential Flex Overlay	28	28	7	<u>4</u>	<u>17</u>	<u>This commercially zoned parcel contains a one-story commercial building.</u>	<u>This parcel consists of a one-story commercial building that is 64 years old. This site could realistically turn over to a higher intensity residential use.</u>
307	5775-011-002	No	275 COLORADO PL	SANTA ANITA CHURCH	C-G	C 1.0	No	No	No	0	1.2	Yes	0	24	C-G Residential Flex Overlay	29	29	7	<u>4</u>	<u>18</u>	<u>This mult-family residentially zoned parcel contains low-medium density residential buildings and parking lot.</u>	<u>This parcel consists of low-medium density residential buildings and parking lot and could realistically turn over to a higher intensity residential use.</u>
308	5781-005-002	No	8 E DUARTE RD	DAQUINO PROPERTIES LLC	C-G	C	No	No	No	0	1.2	Yes	0	24	C-G Residential Flex Overlay	29	29	7	<u>4</u>	<u>18</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building that is over 60 years old. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
309	5383-031-034	No	1423 S BALDWIN AVE	ROSEWOOD INVESTMENT OF ARCADIA	C-G	C	No	No	No	0	1.3	Yes	0	24	C-G Residential Flex Overlay	30	30	8	<u>5</u>	<u>17</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building that is over 45 years old. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
310	8587-033-020	No	9950 LAS TUNAS DR	L AND J INVESTMENT CO	C-G	C	No	No	No	0	1.3	Yes	0	24	C-G Residential Flex Overlay	30	30	8	<u>5</u>	<u>17</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot that is half of the parcel.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
311	5771-028-053	No	245 E FOOTHILL BLVD	ARCADIA BURGE LLC	C-G	C	No	No	No	0	1.3	Yes	0	24	C-G Residential Flex Overlay	30	30	8	<u>5</u>	<u>17</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot that is half of the parcel.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building. A large portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
312	5771-028-038	No	211 E FOOTHILL BLVD	RALPHS GROCERY CO	C-G	C	No	No	No	0	1.3	Yes	0	24	C-G Residential Flex Overlay	30	30	8	<u>5</u>	<u>17</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot that is half of the parcel.</u>	<u>This parcel consists of a one-story commercial building and a surface parking lot. This site could turn over to a higher intensity residential use.</u>
313	5775-011-032	No	201 COLORADO PL	CALIF THOROUGHbred BREEDERS ASSN	C-G	C 1.0	No	No	No	0	1.3	Yes	0	24	C-G Residential Flex Overlay	31	31	8	<u>5</u>	<u>18</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel consists of a one-story commercial building that is 64 years old and a surface parking lot. This site could realistically turn over to a higher intensity residential use.</u>
314	5781-006-049	No	130 E DUARTE RD	99 CENTS ONLY STORES	C-G	C	No	No	No	0	1.3	Yes	0	24	C-G Residential Flex Overlay	31	31	8	<u>5</u>	<u>18</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel consists of a one-story commercial building that is 57 years old and a surface parking lot. This site could realistically turn over to a higher intensity residential use.</u>
315	5778-006-010	No	1020 S BALDWIN AVE	WASHE LLC	C-G	C	No	No	No	0	1.4	Yes	0	24	C-G Residential Flex Overlay	32	32	8	<u>5</u>	<u>19</u>	<u>This commercially zoned parcel contains a one-story commercial building and surface parking lot.</u>	<u>This parcel has a Land Value Ratio less than one. This parcel consists of a one-story commercial building that is 62 years old. A small portion of the parcel is being used as surface parking. This site could realistically turn over to a higher intensity residential use.</u>
316	5772-001-028	No	20 E FOOTHILL BLVD	UNITED CAPITAL INVESTMENT GROUP	C-G	C	No	No	No	0	1.4	Yes	0	24	C-G Residential Flex Overlay	33	33	8	<u>5</u>	<u>20</u>	<u>This parcel contains a two-story commercial building with office space with over 50 percent of the lot utilized for surface parking.</u>	<u>This parcel contains a two-story commercial building that is not fully occupied. The structure is over 40 years old and due to the fact that the structure is not fully occupied, could realistically turn over into a higher intensity residential use.</u>
317	5383-035-029	No	1201 S BALDWIN AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	1.4	Yes	0	24	C-G Residential Flex Overlay	33	33	8	<u>5</u>	<u>20</u>	<u>This parcel contains a portion of a one-story commercial structure with more than 80 percent of the lot comprised of a surface parking lot.</u>	<u>The structure on the parcel is almost 60 years old with a large portion of the site underutilized due to the substantial presence of surface parking. Additionally, the land value ratio of the lot is less than one indicating that the site could realistically turn over into a higher intensity residential use.</u>
318	5383-038-027	No	1325 S BALDWIN AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	1.4	Yes	0	24	C-G Residential Flex Overlay	34	34	9	<u>5</u>	<u>20</u>	<u>This parcel contains a one-story strip mall with several tenants. A large portion of the parcel is currently being utilized as surface parking.</u>	<u>The structure on the parcel is over 60 years old and with the large amount of surface parking and low intensity use, the site could realistically turn over into a higher intensity residential use. Additionally, the site is adjacent to transit facilities and food services which make the site more attractive to developers, and would support mobility for populations that may be more car dependent.</u>

319	5783-010-056	No	700 W HUNTINGTON DR	GREAT WESTERN SAVING AND LOAN	C-G	C	No	No	No	0	1.5	Yes	0	24	C-G Residential Flex Overlay	36	36	9	<u>5</u>	<u>22</u>	<u>This parcel contains a two story bank structure with over 50 percent of the site utilized for surface parking.</u>	<u>The structure on the parcel is over 40 years old and with the large amount of surface parking resulting in underutilized land, the site could realistically turn over into a higher intensity residential use. Additionally, the site is adjacent to transit facilities.</u>
320	8586-001-009	No	610 LAS TUNAS DR	PIC N SAVE OF CALIF INC	C-G	C	No	No	No	0	1.6	Yes	0	24	C-G Residential Flex Overlay	39	39	10	<u>6</u>	<u>23</u>	<u>This parcel contains a one-story commercial building with approximately 50 percent of the site utilized for surface parking.</u>	<u>This parcel is over 60 years old and is underutilized due to the large portion of surface parking. This site could realistically turn over into a higher intensity residential use.</u>
321	5784-003-026	No	638 W DUARTE RD	M AND H CAPITAL INC AND	C-G	C	No	No	No	0	1.7	Yes	0	24	C-G Residential Flex Overlay	41	41	10	<u>6</u>	<u>25</u>	<u>This parcel contains a one-story commercial strip mall with approximately 25 percent of the site utilized for surface parking.</u>	<u>This parcel consists of a one-story partially unoccupied commercial strip mall. Additionally, a portion of the site is used for surface parking and is underutilized. The site could realistically turn over into a higher intensity residential use.</u>
322	5784-003-043	No	624 DUARTE RD	624 MEDICAL CENTER	C-G	C	No	No	No	0	2	Yes	0	24	C-G Residential Flex Overlay	47	47	12	<u>7</u>	<u>28</u>	<u>This parcel contains a one-story structure that contains medical uses and a large portion of the site is being used for surface parking.</u>	<u>The parcel consists of a one-story medical structure that is over 45 years old. The site could redevelop to include a mix of uses, including residential.</u>
323	5778-007-029	No	1104 S BALDWIN AVE	SOO PROPERTIES LLC	C-G	C	No	No	No	0	2.2	Yes	0	24	C-G Residential Flex Overlay	53	53	14	<u>8</u>	<u>31</u>	<u>This parcel contains a strip mall with two one-story structures as well as a two-story structure. A large portion of the parcel is being utilized for surface parking.</u>	<u>The land value ratio of the parcel is less than one and along with the large amount of surface parking on the site, indicates that the site is underutilized. The site could realistically redevelop to a higher intensity use.</u>
324	5383-035-024	No	745 W NAOMI AVE	BALDWIN ARCADIA CENTER LP	C-G	C	No	No	No	0	2.4	Yes	0	24	C-G Residential Flex Overlay	58	58	16	<u>9</u>	<u>33</u>	<u>This parcel consists entirely of surface parking and is adjacent to a Vons grocery store.</u>	<u>The sites land value ratio is less than one and by allowing for residential uses which were previously not allowed, the site could realistic turn over and develop into a higher intensity residential use.</u>
325	5778-007-010	No	627 W DUARTE RD	KJR EASTERN ENTERPRISES INC AND	C-G	C	No	No	No	0	2.4	Yes	0	24	C-G Residential Flex Overlay	58	58	16	<u>9</u>	<u>33</u>	<u>This parcel consists of a one story commercial strip mall with several food businesses. Additionally, a large portion of the site is being utilized as surface parking.</u>	<u>The structure on the site is over 60 years old and with a large portion of the site being utilized for surface parking as well as a land value ratio of less than one, the site shows indicators that it could redevelop into a higher intensity residential use.</u>
326	5383-035-014	No	838 W DUARTE RD	LINKWORLD PROPERTIES LLC	C-G	C	No	No	No	0	2.6	Yes	0	24	C-G Residential Flex Overlay	61	61	16	<u>6</u>	<u>39</u>	<u>This parcel contains one-story commercial buildings and surface parking lot that takes up half of the parcel.</u>	<u>This parcel is over 55 years old and has a Land Value Ratio less than one. This parcel can be redeveloped for a higher intensity residential use.</u>
327	5383-035-015	No	838 W DUARTE RD	LINKWORLD PROPERTIES LLC	C-G	C	No	No	No	0	2.9	Yes	0	24	C-G Residential Flex Overlay	69	69	18	<u>10</u>	<u>41</u>	<u>This commercially zoned parcel contains a portion of a one-story strip mall with over 50 percent of the site being utilized for surface parking.</u>	<u>This parcel consists of a one-story commercial building that is over 60 years old. Additionally, with a land value ratio of less than one and a large portion of the site being utilized as surface parking, this site could realistically turn over into a higher intensity residential use.</u>
328	5775-011-016	No	226 W COLORADO BLVD	SANTA ANITA CHURCH	C-G	C 1.0	No	No	No	0	4.9	Yes	0	24	C-G Residential Flex Overlay	117	117	30	<u>18</u>	<u>69</u>	<u>This parcel contains a church as well as several school buildings as well as a large amount of surface parking.</u>	<u>The site could realistically be reconfigured to allow for some residential or mixed use on the site.</u>
330	5773-004-028	No	126 LA PORTE ST	HE,YUE H	C-M	C	No	No	No	0	0.5	Yes	0	64	Downtown Mixed Use Overlay	33	33	8	<u>5</u>	<u>20</u>	<u>This parcel contains two one-story structures as well as surface parking.</u>	<u>The structures on this parcel are over 40 years old and with a large portion of the site utilized for surface parking, could redevelop to include residential uses.</u>
331	5773-008-003	No	324 N 2ND AVE	LIU,BREWIN L TR	C-M	C	No	No	No	0	2.2	Yes	0	64	Downtown Mixed Use Overlay	138	138	36	<u>21</u>	<u>81</u>	<u>This parcel contains a self-storage facility.</u>	<u>The site contains a one to two story self storage facility. Due to the structure's proximity to the Metro Gold Line, the site could potentially attract developers and redevelop into a higher intensity mixed or residential use.</u>
332	5773-005-034	No	310 N SANTA ANITA AVE	BOHLS,NANCY J TR	C-G	C 1.0	Yes	No	No	0	0.5	Yes	0	64	Downtown Mixed Use Expansion	33	33	8	<u>5</u>	<u>20</u>	<u>This parcel is adjacent to the Metro Gold Line and is currently occupied by a few one-story structures as well as outdoor storage for building materials.</u>	<u>The site is located in an ideal location, proximate to the Metro Gold Line Station. By allowing residential uses on this site, developers may be interested in building high density housing to make the most of transit-oriented development benefits.</u>
333	5775-022-049	No	325 N SANTA ANITA AVE	CHUNG,PATRICIA V	SP-AP	C 1.0	No	No	No	0	0.6	Yes	0	64	Downtown Mixed Use Expansion	35	35	9	<u>5</u>	<u>21</u>	<u>This parcel contains a one-story academic facility and 80 percent of the site is currently being utilized for surface parking.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. The existing commercial structure is over 36 years old and the lot is underutilized with surface parking surrounding the structure. This parcel, in addition to three other parcels in the inventory has received developer interest and conceptual plans for a multi-family housing development have been discussed with the City. The site could realistically turn over into a higher intensity residential use.</u>

334	5773-015-053	No	440 E HUNTINGTON DR	STANSBURY,MARILYN B TR	C-G	C	No	No	No	0	0.6	Yes	0	64	Downtown Mixed Use Expansion	40	40	10	<u>6</u>	<u>24</u>	<u>This parcel contains a four-story commercial facility and surface parking lot.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
335	5775-022-047	No	400 ROLYN PL	INTERNATIONAL CHURCH OF	SP-AP	C 1.0	No	No	No	0	0.7	Yes	0	64	Downtown Mixed Use Expansion	43	43	11	<u>6</u>	<u>26</u>	<u>This parcel contains a one-story commercial facility and 50 percent of the site is currently being utilized for surface parking.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use. This parcel is 58 years old and has developer interest.</u>
336	5773-015-054	No	450 E HUNTINGTON DR	NING HE AND YUAN LI LI	C-G	C	No	No	No	0	0.8	Yes	0	64	Downtown Mixed Use Expansion	48	48	13	<u>7</u>	<u>28</u>	<u>This parcel contains a two-story commercial facility and surrounding surface parking lot.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
337	5773-015-049	No	300 E HUNTINGTON DR	720 WEST CAMINO REAL LLC	C-G	C	No	No	No	0	0.8	Yes	0	64	Downtown Mixed Use Expansion	48	48	13	<u>7</u>	<u>28</u>	<u>This parcel contains a one-story commercial facility.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
338	5773-008-014	No	225 E SANTA CLARA ST	NEW,PATRICIA R TR ET AL	C-G	C	No	No	No	0	0.8	Yes	0	64	Downtown Mixed Use Expansion	52	52	14	<u>8</u>	<u>30</u>	<u>This parcel contains a three-story commercial facility and surface parking lot that is about 50% of the parcel.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
339	5773-008-013	No	255 E SANTA CLARA ST	LEE,RICHARD AND SHIN J	C-G	C	No	No	No	0	0.8	Yes	0	64	Downtown Mixed Use Expansion	52	52	14	<u>8</u>	<u>30</u>	<u>This parcel contains a three-story commercial facility and surface parking lot that is about 50% of the parcel.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
340	5773-009-065	No	301 E HUNTINGTON DR	BOGUSLAVSKY,ALEXANDER AND IRINA	C-G	C	No	No	No	0	0.9	Yes	0	64	Downtown Mixed Use Expansion	57	57	15	<u>9</u>	<u>33</u>	<u>This parcel contains a one-story commercial building with a surface parking lot that is 50% of the parcel.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. The parcel has a Land Value Ratio less than one. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
341	5775-022-045	No	W Colorado Blvd and N Santa Anita Ave	PIAO,XUEWEN AND	C-G	C 1.0	No	No	No	0	0.9	Yes	0	64	Downtown Mixed Use Expansion	59	59	16	<u>9</u>	<u>34</u>	<u>This parcel contains two one-story commercial building with a surface parking lot that is 50% of the parcel.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. The parcel has a Land Value Ratio less than one, and is 38 years old. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
342	5773-008-012	No	405 E Santa Clara St	CHAO,CRYSTAL	C-G	C	Yes	No	No	0	1	Yes	0	64	Downtown Mixed Use Expansion	61	61	16	<u>9</u>	<u>36</u>	<u>This parcel contains one two-story commercial building with a surface parking lot that is 50% of the parcel.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. The parcel has a Land Value Ratio less than one. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
343	5775-022-046	No	333 N SANTA ANITA AVE	AMAYA INVESTMENTS LLC	C-M	C 1.0	No	No	No	0	1	Yes	0	64	Downtown Mixed Use Expansion	62	62	17	<u>9</u>	<u>36</u>	<u>This parcel contains two two-story commercial building with a surface parking lot that is 50% of the parcel.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use, and has developer interest.</u>
345	5773-015-052	No	420 E HUNTINGTON DR	DOUBLE PEGASUS LLC	C-G	C	No	No	No	0	1.2	Yes	0	64	Downtown Mixed Use Expansion	77	77	20	<u>12</u>	<u>45</u>	<u>This parcel contains one three-story commercial building with a surface parking lot that is more than 50% of the parcel.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>

346	5773-009-070	No	233 E HUNTINGTON DR	LAM,KHAI AND	C-G	C	No	No	No	0	1.3	Yes	0	64	Downtown Mixed Use Expansion	85	85	22	<u>13</u>	<u>50</u>	<u>This parcel contains one one-story commercial building with a surface parking lot that is more than 50% of the parcel.</u>	<u>This parcel is located in the Downtown area close to the Metro Gold Line and would connect low income households to a greater number of opportunities throughout Los Angeles County. The parcel has a Land Value Ratio less than one and is over 70 years old. This structure and surrounding surface parking lot has potential for turnover into a higher intensity use.</u>
347	5773-009-081	No	488 E SANTA CLARA ST	MEI CIEN HUANG AND	C-G	C	No	No	No	0	1.3	Yes	0	64	Downtown Mixed Use Expansion	86	86	23	<u>13</u>	<u>50</u>	<u>This parcel contains one three-story and one one-story commercial building with a surface parking lot that is less than half of the parcel.</u>	<u>The parcel has commercial structures and an associated surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
348	5773-009-080	No	51 N 5TH AVE	KAHNG,RIPP AND YOUNG O	C-G	C	No	No	No	0	1.6	Yes	0	64	Downtown Mixed Use Expansion	105	105	27	<u>16</u>	<u>62</u>	<u>This parcel contains one three-story commercial building with a surface parking lot that is more than half of the parcel.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
349	5773-009-062	No	311 E HUNTINGTON DR	HONG,SONG KUK AND YOUNG SUN	C-G	C	No	No	No	0	2.1	Yes	0	64	Downtown Mixed Use Expansion	132	132	34	<u>20</u>	<u>78</u>	<u>This parcel contains one three-story commercial/hotel building with a surface parking lot that is more than half of the parcel.</u>	<u>The parcel has a commercial/hotel structure and a surrounding surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
350	5773-015-026	No	444 E HUNTINGTON DR	YING,CHI Q AND	C-G	C	No	No	No	0	2.2	Yes	0	64	Downtown Mixed Use Expansion	143	143	37	<u>21</u>	<u>85</u>	<u>This parcel contains one three-story commercial building with a surface parking lot that is more than half of the parcel.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
351	5773-008-011	No	401 E SANTA CLARA ST	KANG,CHIANG AND	C-G	C	No	No	No	0	2.3	Yes	0	64	Downtown Mixed Use Expansion	149	149	38	<u>22</u>	<u>89</u>	<u>This parcel contains one three-story commercial/hotel building with a surface parking lot that is more than half of the parcel.</u>	<u>The parcel has a commercial/hotel structure and a surrounding surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
352	5773-009-064	No	321 E HUNTINGTON DR	SIDDIQI,SARFARAZ H AND JOY E TRS	C-G	C	No	No	No	0	3.2	Yes	0	64	Downtown Mixed Use Expansion	206	206	53	<u>31</u>	<u>122</u>	<u>This parcel contains multiple two-story commercial/hotel building with a surface parking lot.</u>	<u>The parcel has commercial/hotel structures and a surrounding surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
353	5773-009-082	No	211 E Huntington Dr	TIAN,HUA AND	C-G	C	No	No	No	0	3.7	Yes	0	64	Downtown Mixed Use Expansion	239	239	61	<u>36</u>	<u>142</u>	<u>This parcel contains a multiple-story commercial/hotel building with a surface parking lot that is over 25% of the parcel.</u>	<u>The parcel has commercial/hotel structures and a surrounding surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
354	5773-009-069	No	333 E HUNTINGTON DR	KO,NAI SHIH AND	C-G	C	No	No	No	0	3.7	Yes	0	64	Downtown Mixed Use Expansion	239	239	61	<u>36</u>	<u>142</u>	<u>This parcel contains one three-story commercial and two one-story buildings with a surface parking lot that is more than half of the parcel.</u>	<u>The parcel has commercial structures and an associated surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
355	5773-015-055	No	440 E HUNTINGTON DR	MCGUIRE,ROBERT L AND CAROL M	C-G	C	No	No	No	0	5.2	Yes	0	64	Downtown Mixed Use Expansion	331	331	84	<u>50</u>	<u>197</u>	<u>This parcel contains one one-story commercial building with a surface parking lot that is more than half of the parcel.</u>	<u>The parcel has commercial structures and an associated surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
356	8573-024-030	No	162 E LIVE OAK AVE	LLIBRE,JUAN B CO TR	MU	MU	No	No	No	0	0.5	Yes	24	40	Mixed-Use Upzone	20	20	5	<u>3</u>	<u>12</u>	<u>This parcel contains one one-story commercial building with a surface parking lot and drive-through that is more than half of the parcel.</u>	<u>The parcel is located in the City's Mixed Use Zone. This parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain housing.</u>
357	5773-019-025	No	201 S 1ST AVE	BARTON,WILLIAM D TR	MU	MU	No	Yes	Yes	0	0.5	Yes	24	40	Mixed-Use Upzone	21	21	5	<u>3</u>	<u>13</u>	<u>The parcel contains a one-story commercial building and approximately 40 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone and has a land value ratio of less than one. The existing structure is also more than 70 years old indicating a potential for turnover into a higher intensity use.</u>
358	8573-023-009	No	30 E LIVE OAK AVE	STOKES,ALFRED E AND PATSY E TRS	MU	MU	No	Yes	Yes	0	0.6	Yes	24	40	Mixed-Use Upzone	22	22	6	<u>3</u>	<u>13</u>	<u>The parcel contains a one-story commercial building and half of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone and has a land value ratio of less than one. The existing structure is also more than 70 years old indicating a potential for turnover into a higher intensity use.</u>
359	5779-009-068	No	620 S 1ST AVE	STOKES,ALFRED E AND PATSY E TRS	MU	MU	No	No	No	0	0.6	Yes	24	40	Mixed-Use Upzone	22	22	6	<u>3</u>	<u>13</u>	<u>The parcel contains a one-story church building and half of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone and has a land value ratio of less than one. The parcel has a potential for turnover into a higher intensity use.</u>
360	5789-028-024	No	11 E LIVE OAK AVE	WEI,PHILLIP AND	MU	MU	No	Yes	Yes	0	0.6	Yes	24	40	Mixed-Use Upzone	22	22	6	<u>3</u>	<u>13</u>	<u>The parcel contains two one-story commercial buildings and part of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone and has a land value ratio of less than one. The parcel has a potential for turnover into a higher intensity residential use.</u>
361	5779-017-027	No	121 ALICE ST	LAI,MICHAEL D AND	MU	MU	No	No	No	0	0.6	Yes	24	40	Mixed-Use Upzone	23	23	6	<u>3</u>	<u>14</u>	<u>The parcel contains a one-story church building and a small surface parking lot.</u>	<u>This parcel is located in the City's Mixed Use Zone and has a land value ratio of less than one. The parcel is 60 years old and has a potential for turnover into a higher intensity residential use.</u>
362	8572-002-005	No	314 E LIVE OAK AVE	QU,BIN	MU	MU	No	No	No	0	1	Yes	24	40	Mixed-Use Upzone	38	38	10	<u>6</u>	<u>22</u>	<u>This parcel is vacant as of July 2022.</u>	<u>Sphere Energy was located on this lot but has permanently closed and been demolished. Therefore this site can be developed to contain high-density dwelling units.</u>
363	8572-001-022	No	405 LYNROSE ST	KAUFMANN,LINDA C TR	MU	MU	No	Yes	No	0	1	Yes	24	40	Mixed-Use Upzone	39	39	10	<u>6</u>	<u>23</u>	<u>The parcel contains a one-story commercial building and approximately 25 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone. The existing structure is also more than 55 years old indicating a potential for turnover into a higher intensity use.</u>
364	8572-002-900	No	330 E LIVE OAK AVE	YAO,LEON AND HELEN C	MU	MU	No	Yes	Yes	0	1.1	Yes	24	40	Mixed-Use Upzone	42	42	11	<u>6</u>	<u>25</u>	<u>The parcel contains a one-story commercial building and has a small surface parking lot.</u>	<u>This commercial parcel is located in the City's Mixed Use Zone. The existing structure has potential for turnover into a higher intensity use.</u>
365	8572-001-027	No	5705 LENORE AVE	ARCADIA PRESBYTERIAN CHURCH	MU	MU	No	No	No	1	1.1	Yes	24	40	Mixed-Use Upzone	44	43	11	<u>6</u>	<u>26</u>	<u>The parcel contains a one-story commercial building and approximately 25 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone. The existing structure is also 64 years old indicating a potential for turnover into a higher intensity use.</u>

366	8572-001-029	No	418 E LIVE OAK AVE	MAATZ,RUSSELL E AND MIE O TRS	MU	MU	No	No	No	0	1.4	Yes	24	40	Mixed-Use Upzone	54	54	15	<u>8</u>	<u>31</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone. The existing structure is also over 50 years old, indicating a potential for turnover into a higher intensity use.</u>
368	8572-001-030	No	406 E LIVE OAK AVE	HOUSE,KENNETH M CO TR	MU	MU	No	No	No	0	2	Yes	24	40	Mixed-Use Upzone	78	78	21	<u>12</u>	<u>45</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone. The existing structure is also over 50 years old, indicating a potential for turnover into a higher intensity use.</u>
369	8573-023-020	No	16 E LIVE OAK AVE	CHIU,CHI HUNG TR	MU	MU	No	No	No	0	2.5	Yes	24	40	Mixed-Use Upzone	101	101	26	<u>15</u>	<u>60</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone. The existing structure is also over 50 years old, indicating a potential for turnover into a higher intensity use.</u>
370	8572-002-010	No	298 E LIVE OAK AVE	MORALES,ESTHER M	MU	MU	No	No	No	0	3.9	Yes	24	40	Mixed-Use Upzone	157	157	40	<u>24</u>	<u>93</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone and has a land value ratio of less than one. The existing structure has a potential for turnover into a higher intensity use.</u>
371	8573-019-900	No	22 W LIVE OAK AVE	TOYODA,SATORU AND SACHIKO TRS	C-G	C	No	No	No	0	0.5	Yes	0	48	Las Tunas Residential Flex Overlay	24	24	6	<u>4</u>	<u>14</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is over 58 years old and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
372	8573-019-003	No	28 W LIVE OAK AVE	OUR LADY OF THE ANGELS OF THE	C-G	C	No	No	No	0	0.5	Yes	0	48	Las Tunas Residential Flex Overlay	25	25	6	<u>4</u>	<u>15</u>	<u>The parcel contains a one-story commercial building and approximately 25 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
373	8573-019-002	No	36 W LIVE OAK AVE	HUI WU AND	C-G	C	No	No	No	0	0.5	Yes	0	48	Las Tunas Residential Flex Overlay	25	25	6	<u>4</u>	<u>15</u>	<u>The parcel contains a one-story commercial building and approximately 25 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is approximately 47 years old, has a Land Value Ratio less than one, and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
374	8573-019-001	No	40 W LIVE OAK AVE	HU,CUILAN ET AL	C-G	C	No	No	No	0	0.6	Yes	0	48	Las Tunas Residential Flex Overlay	26	26	7	<u>4</u>	<u>15</u>	<u>The parcel contains a two-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
375	5788-021-016	No	46 LAS TUNAS DR	SALIB,MAGDY AND	C-G	C	No	No	No	0	0.7	Yes	0	48	Las Tunas Residential Flex Overlay	32	32	8	<u>5</u>	<u>19</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
376	5788-021-017	No	82 LAS TUNAS DR	GELBER,LOUISE C TR	C-G	C	No	No	No	0	0.7	Yes	0	48	Las Tunas Residential Flex Overlay	33	33	8	<u>5</u>	<u>20</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
377	5788-022-017	No	168 LAS TUNAS DR	HAIS,MICHAEL AND REENA M TRS	C-G	C	No	No	No	0	0.7	Yes	0	48	Las Tunas Residential Flex Overlay	34	34	9	<u>5</u>	<u>20</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
379	5788-020-052	No	59 LAS TUNAS DR	HUI,YING TAND AND	C-G	C	No	No	No	0	0.8	Yes	0	48	Las Tunas Residential Flex Overlay	39	39	10	<u>6</u>	<u>23</u>	<u>The parcel contains a one-story commercial building and over 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is 49 years old and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
380	8573-015-023	No	58 W LIVE OAK AVE	XU,QU	C-M	C/LI	No	No	No	0	0.9	Yes	0	48	Las Tunas Residential Flex Overlay	42	42	11	<u>6</u>	<u>25</u>	<u>The parcel contains a two-story commercial building and a small part of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
381	5788-021-001	No	123 W LIVE OAK AVE	MA,PAULINE	C-G	C	No	No	No	0	0.9	Yes	0	48	Las Tunas Residential Flex Overlay	45	45	11	<u>7</u>	<u>27</u>	<u>The parcel contains a one-story commercial building and half of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one, is 68 years old, and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>

382	8573-020-056	No	16 W LIVE OAK AVE	CORDANO,DEBORAH J TR	C-G	C	No	No	No	0	1	Yes	0	48	Las Tunas Residential Flex Overlay	47	47	12	<u>7</u>	<u>28</u>	<u>The parcel contains two one-story commercial buildings and half of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
383	8573-015-043	No	60 W LIVE OAK AVE	CHAMPION LAUREL ARCADIA LLC	C-M	C/LI	No	No	No	0	1.4	Yes	0	48	Las Tunas Residential Flex Overlay	66	66	18	<u>10</u>	<u>38</u>	<u>The parcel contains two two-story commercial buildings and 25% of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
385	5788-022-016	No	188 LAS TUNAS DR	OUYANG,JING ZHENG CO TR	C-G	C	No	No	No	0	2	Yes	0	48	Las Tunas Residential Flex Overlay	97	97	25	<u>15</u>	<u>57</u>	<u>The parcel contains a one-story commercial building and half of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
386	5789-020-042	No	115 E LIVE OAK AVE	WANG,YI TING	C-O	C	No	No	No	0	0.6	Yes	0	40	Live Oak Residential Flex Overlay	25	25	6	<u>4</u>	<u>15</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is approximately 56 years old and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
387	8572-010-023	No	600 E LIVE OAK AVE	M B EQUITY LLC	C-G	C	No	No	No	0	0.7	Yes	0	40	Live Oak Residential Flex Overlay	27	27	7	<u>4</u>	<u>16</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
388	5789-020-045	No	135 E LIVE OAK AVE	CCJL INVESTMENT LLC	C-G	C	No	No	No	0	0.7	Yes	0	40	Live Oak Residential Flex Overlay	28	28	7	<u>4</u>	<u>17</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
389	5790-027-001	No	225 E LIVE OAK AVE	YE,CHUN AND	C-G	C	No	No	No	0	0.8	Yes	0	40	Live Oak Residential Flex Overlay	30	30	8	<u>5</u>	<u>17</u>	<u>The parcel contains a two-story commercial building and approximately 25 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is 62 years old and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
390	5789-021-031	No	41 E LIVE OAK AVE	WONG,ANTHONY W AND	C-O	C	No	No	No	0	0.9	Yes	0	40	Live Oak Residential Flex Overlay	34	34	9	<u>5</u>	<u>20</u>	<u>The parcel contains a two-story commercial building and over 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure has a Land Value Ratio less than one, is 58 years old, and is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
432	5773-005-031	No	21 FLOWER ST	SUN,JUGUO AND	C-M	C	No	No	No	0	0.3	No	0	64	Downtown Mixed Use Overlay	16	16	4	<u>2</u>	<u>10</u>	<u>The parcel contains a one-story commercial building and a small part of the parcel is utilized for surface parking.</u>	<u>The parcel has a commercial structure that is over 30 years old and has an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
433	5775-022-042	No	311 N SANTA ANITA AVE	SAMUDRA,VAIBHAV A AND SMITA V	C-M	C 1.0	No	No	No	0	0.3	No	0	64	Downtown Mixed Use Expansion	16	16	4	<u>2</u>	<u>10</u>	<u>The parcel contains a two-story commercial building and over 50 percent of the parcel is utilized for surface parking.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
434	5773-005-032	No	26 LA PORTE ST	LIU,DIANA	C-M	C	No	No	No	0	0.3	No	0	64	Downtown Mixed Use Overlay	18	18	5	<u>3</u>	<u>10</u>	<u>The parcel contains a one-story commercial building and over 50 percent of the parcel is utilized for surface parking.</u>	<u>The parcel has a commercial structure that is 48 years old and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
435	5773-005-006	No	303 N 1ST AVE	CHIANG,PETER AND BEATRICE	DMU	DMU	No	No	No	0	0.3	No	64	64	Downtown Mixed Use Overlay	21	21	5	<u>3</u>	<u>13</u>	<u>The parcel contains a two-story commercial building and over 50 percent of the parcel is utilized for surface parking.</u>	<u>The parcel has a commercial structure that is 64 years old and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
436	5773-002-058	No	408 S SANTA ANITA AVE	LONG,REY A TR	C-G	C 1.0	No	No	No	0	0.3	No	0	64	Downtown Mixed Use Expansion	22	22	6	<u>3</u>	<u>13</u>	<u>The parcel contains a one-story commercial building and over 50 percent of the parcel is utilized for surface parking.</u>	<u>The parcel has a commercial structure that is 52 years old and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
437	5773-004-027	No	134 LA PORTE ST	JUN HUA TONG AND	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>The parcel contains a two-story commercial building and a small section of associated surface parking.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
438	5773-005-023	No	48 LA PORTE ST	YU,STANLEY M AND	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>The parcel contains a one-story commercial building and 50% of the parcel is associated surface parking.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>

439	5773-005-024	No	25 FLOWER ST	ARCADIA PROPERTY INVESTMENTS LLC	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	23	23	6	<u>3</u>	<u>14</u>	<u>The parcel contains a one-story commercial building and 50% of the parcel is associated surface parking.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This structure is 68 years old. This parcel can realistically be redeveloped to contain dwelling units.</u>
440	5773-005-005	No	47 E SAINT JOSEPH ST	TELLERIA,ANTHONY F AND DELORES A	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	23	23	6	<u>3</u>	<u>14</u>	<u>The parcel contains a two-story commercial building.</u>	<u>The parcel has a commercial structure and is 66 years old. This parcel can realistically be redeveloped to contain dwelling units.</u>
441	5773-004-026	No	127 E SAINT JOSEPH ST	GEISER,RALF AND ALICIA X TRS	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	24	24	6	<u>4</u>	<u>14</u>	<u>The parcel contains a one-story commercial building and 25% of the parcel is associated surface parking.</u>	<u>The parcel has a commercial structure and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
442	5775-022-026	No	W Colorado Blvd	LEE,YI N AND MEI H AND	C-G	C 1.0	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Expansion	24	24	6	<u>4</u>	<u>14</u>	<u>The parcel contains three one-story commercial buildings and 25% of the parcel is associated surface parking.</u>	<u>The parcel has commercial structures and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units.</u>
443	5773-004-811	No	N 2nd Ave and E St Joseph St	JIHANIAN,VAHE TR	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	27	27	7	<u>4</u>	<u>16</u>	<u>This parcel contains at-grade utilities.</u>	<u>The parcel contains at-grade utilities and could be consolidated to provide housing units.</u>
444	5775-022-048	No	325 N SANTA ANITA AVE	KUO,YU PYNG L	SP-AP	C 1.0	No	No	No	1	0.4	No	0	64	Downtown Mixed Use Expansion	27	26	7	<u>4</u>	<u>15</u>	<u>The parcel contains a one-story commercial building and has a small surface parking lot.</u>	<u>The parcel has commercial structures and an associated surface parking lot. This parcel can realistically be redeveloped to contain dwelling units. This parcel has developer interest.</u>
445	5773-004-810	No	La Porte St and N 2nd Ave.	KUO,CHOU YU	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	28	28	7	<u>4</u>	<u>17</u>	<u>This parcel contains at-grade utilities.</u>	<u>The parcel contains at-grade utilities and could be consolidated to provide housing units.</u>
563	5788-021-003	No	119 E LIVE OAK AVE	526 WEST HUNTINGTON DRIVE LLC	C-G	C	No	No	No	0	0.4	No	0	48	Las Tunas Residential Flex Overlay	17	17	4	<u>3</u>	<u>10</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>The existing commercial structure is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
570	8573-023-004	No	60 E LIVE OAK AVE	A AND K CHEN LLC	MU	MU	No	Yes	Yes	0	0.4	No	24	40	Mixed-Use Upzone	16	16	4	<u>2</u>	<u>10</u>	<u>The parcel contains a one-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone. The existing structure is also over 60 years old indicating a potential for turnover into a higher intensity use.</u>
571	5779-013-061	No	57 ALICE ST A	PANCHAL,ANANT AND DARSHANA	MU	MU	No	No	No	0	0.4	No	24	40	Mixed-Use Upzone	16	16	4	<u>2</u>	<u>10</u>	<u>This parcel contains two structures of multi-family homes.</u>	<u>This parcel is located in the City's Mixed Use Zone. The existing structures could be redeveloped for a higher density.</u>
572	5788-021-012	No	108 LAS TUNAS DR	CHOU,CINDY H	C-G	C	No	No	No	0	0.4	No	0	48	Las Tunas Residential Flex Overlay	20	20	5	<u>3</u>	<u>12</u>	<u>The parcel contains a one-story commercial building and surface parking.</u>	<u>The existing 63 year old commercial structure is underutilized. Additionally, the site is located in a corridor where commercial lots are typically underutilized and that the City has identified as a corridor to focus residential development in to revitalize the community.</u>
574	5789-028-012	No	19 E LIVE OAK AVE	LEE,REUBEN B AND AI WEE	MU	MU	No	Yes	Yes	1	0.4	No	24	40	Mixed-Use Upzone	17	16	4	<u>2</u>	<u>10</u>	<u>The parcel contains a two-story commercial building and approximately 50 percent of the parcel is utilized for surface parking.</u>	<u>This parcel is located in the City's Mixed Use Zone. This structure has the potential for turnover into a higher intensity use.</u>
575	8572-002-001	No	200 E LIVE OAK AVE	CHOWDARY,VINOD K AND	MU	MU	No	No	No	0	0.5	Yes	24	40	Mixed-Use Upzone	18	18	5	<u>3</u>	<u>10</u>	<u>The parcel contains a one-story commercial structure with several tenants. Additionally, over 50 percent of the site is utilized as surface parking.</u>	<u>The structure on this parcel is over 30 years old and with a high percentage of the lot utilized for surface parking, the site could realistically turn over into a higher intensity residential use.</u>
576	8572-002-009	No	288 E LIVE OAK AVE	CHOU,YOUNG I CO TR	MU	MU	No	No	No	0	0.5	Yes	24	40	Live Oak Residential Flex Overlay	18.58187603	18.581876	5	<u>3</u>	<u>10.58187603</u>	<u>The parcel contains a one-story commercial business with approximately 50 percent of the lot utilized as surface parking.</u>	<u>The structure on this parcel is almost over 30 years old and has a land value ratio that is less than one. Additionally, the parcel is located within one of the City's transit corridors and has been identified as an area where residential development is expanding. Due to these factors, the site could realistically turn over into a higher intensity residential use.</u>
772	8571-011-904	No	620 E LIVE OAK AVE	FIRST CHURCH OF CHRIST SCIENTIST	OS-OR	OS-OR	No	No	No	0	25.9	No	0	No Rezone	Arcadia Golf Course	186	186	80	<u>0</u>	<u>106</u>	<u>The parcel is currently a public Golf Course owned by the City.</u>	<u>The City has received verbal interest in developing housing on this parcel from local developers. Additionally, the City is currently going through the process outlined by the Surplus Land Act to sell the land and develop a Specific Plan for the Golf Course site. The City will require at least 80 units be affordable to Low and Very Low Income households.</u>
773	5771-021-018	Yes	169 E FOOTHILL BLVD	BANK OF AMERICA	C-G	C	No	No	No	0	0.5	Yes	0	24	C-G Residential Flex Overlay	13	13	3	<u>2</u>	<u>8</u>	<u>This parcel contains a single story bank building within an existing strip mall development with surface parking.</u>	<u>The structure on this parcel is over 56 years old. Additionally, the City has identified the site as a site with opportunity to consolidate with an adjacent parcel which is largely comprised of surface parking. The parcels land value ratio is also less than one indicating that the site is underutilized and could realistically turn over into a higher intensity use.</u>

773	5771-021-029	Yes	121 E FOOTHILL BLVD	HIGHLANDER CENTER LLC	C-G	C	No	No	No	0	5.2	Yes	0	24	C-G Residential Flex Overlay	124	124	32	<u>19</u>	<u>73</u>	<u>This parcel is a large commercial shopping center with various tenants. Approximately 75 percent of the parcel is used for surface parking lot</u>	<u>The parcel consists of a large commercial shopping center with various tenants that is more than 55 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the north. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
774	5773-014-001	Yes	30 S 1ST AVE	FOOTHILL FEDERAL CREDIT UNION	MU	MU	No	No	No	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel is entirely dedicated to surface parking.</u>	<u>Since this parcel consists entirely of surface parking, this site could realistically turn over into a higher intensity use. It is bordered on the east by residential uses.</u>
774	5773-014-002	Yes	30 S 1ST AVE	FOOTHILL FEDERAL CREDIT UNION	MU	MU	No	No	No	0	0.5	Yes	24	40	Mixed-Use Upzone	19	19	5	<u>3</u>	<u>11</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial bank structure that is more than 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east. The property is along a busy corridor which would be suitable to develop into residential or mixed use. This site could realistically turn over into a higher intensity use.</u>
776	5773-013-017	Yes	21 S 1ST AVE	HUANG, JUN L CO TR	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is more than 80 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. The property is along a busy corridor which would be suitable to develop into residential or mixed use. This site could realistically turn over into a higher intensity use.</u>
776	5773-013-016	Yes	25 S 1ST AVE	CROSS PROPERTY MANAGEMENT LLC	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is more than 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
776	5773-013-015	Yes	31 S 1ST AVE	CROSS PROPERTY MANAGEMENT LLC	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is more than 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
777	5779-001-020	Yes	401 S 1ST AVE	CANTWELL COLUMBIAN BUILDING CORP	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one two-story commercial office structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one two-story commercial office structure that is almost 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. A neighboring property was previously a similar use and is currently being redeveloped to a residential use. This site could realistically turn over into a higher intensity use.</u>
777	5779-001-018	Yes	409 S 1ST AVE	DING, JEAN AND	MU	MU	No	No	No	1	0.2	No	24	40	Mixed-Use Upzone	7	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one two-story medical office structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one two-story medical office structure that is 13 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. A neighboring property was previously a similar use and is currently being redeveloped to a residential use. This site could realistically turn over into a higher intensity use.</u>
778	5779-001-017	Yes	415 S 1ST AVE	VELK PROPERTIES INC	MU	MU	No	No	No	1	0.2	No	24	40	Mixed-Use Upzone	7	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is more than 20 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>

778	5779-001-016	Yes	419 S 1ST AVE	PISANO,JUDITH M TR	MU	MU	No	No	No	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story convenience/liquor store structure with approximately 70 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story onvenience/liquor store structure that is almost 50 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
778	5779-001-015	Yes	423 S 1ST AVE	HESS RENTALS LLC	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story medical office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story medical office structure that is almost 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
779	5779-003-001	Yes	S 1st Ave and El Dorado St	HARTMAN,JAY L AND LYNDA J TRS	MU	MU	No	Yes	Yes	0	0.1	No	24	40	Mixed-Use Upzone	5	5	1	<u>1</u>	<u>3</u>	<u>This parcel is entirely dedicated to surface parking.</u>	<u>Since this parcel consists entirely of surface parking, this site could realistically turn over into a higher intensity use. It is bordered on the east by residential uses.</u>
779	5779-003-003	Yes	414 S 1ST AVE	WILSON,CLAYTON AND ELAINE TRS	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial office structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is almost 50 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east. This site could realistically turn over into a higher intensity use.</u>
779	5779-003-002	Yes	420 S 1ST AVE	HARTMAN,JAY L AND LYNDA J TRS	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story potentially vacant restuarant structure with approximately 750 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story potentially vacant restuarant structure that is over 60 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east and a surface parking lot to the south. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
780	5779-003-035	Yes	400 S 1ST AVE	MYRDAHL,GARRY L AND VIVIAN A TRS	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial office structure with approximately 75 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is almost 50 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east. This site could realistically turn over into a higher intensity use.</u>
780	5779-003-034	Yes	404 S 1ST AVE	FU WAH YU AND	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial structure and a potential single-family home with approximately 40 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure and a potential single-family home that are over 90 years old. Additionally, 40 percent of the parcel is being utilized for surface parking. The property bordered by residential uses to the east. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
780	5779-003-033	Yes	406 S 1ST AVE	406 S FIRST AVE ASSOCIATES LLC	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial office structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east. This site could realistically turn over into a higher intensity use.</u>
781	5779-011-018	Yes	501 S 1ST AVE	GOURLEY,ROBERT D TR	MU	MU	No	No	No	0	0.3	No	24	40	Mixed-Use Upzone	13	13	3	<u>2</u>	<u>8</u>	<u>This parcel contains one single-story commercial office structure with approximately 30 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 65 years old. Additionally, 30 percent of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
781	5779-011-017	Yes	511 S 1ST AVE	YIP,ALVIN AND	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial office structure with approximately 30 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 60 years old. Additionally, 30 percent of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
799	5773-002-035	Yes	401 N 1ST AVE	JPM5 LLC	C-M	C	No	No	No	0	0.5	Yes	0	64	Downtown Mixed Use Overlay	31	31	8	<u>5</u>	<u>18</u>	<u>This parcel contains one single-story mixed-use structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of two single-story commercial/industrial structures that are over 40 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the north and west. This site could realistically turn over into a higher intensity use.</u>

782	5779-010-033	Yes	500 S 1ST AVE	UNIVERSAL FUNERAL CHAPEL LLC	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story mixed-use structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story mixed-use structure that is over 65 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
782	5779-010-032	Yes	506 S 1ST AVE	UNIVERSAL FUNERAL CHAPEL LLC	MU	MU	No	Yes	Yes	1	0.3	No	24	40	Mixed-Use Upzone	12	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains one single-story commercial office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 80 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
782	5779-010-031	Yes	116 ELDORADO ST	Information not Available	R-3	HDR	No	No	Yes	0	0.2	No	32	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel is entirely dedicated to surface parking.</u>	<u>Since this parcel consists entirely of surface parking, this site could realistically turn over into a higher intensity use. It is bordered on all sides by residential uses.</u>
798	5773-002-052	No	25 LA PORTE ST	DORIS J SARKISIAN	C-M	C	No	No	No	0	0.3	No	0	64	Downtown Mixed Use Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>This parcel contains one single-story commercial office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 40 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by higher density residential uses to the east, west, and north. This site could realistically turn over into a higher intensity use.</u>
783	5779-011-016	Yes	515 S 1ST AVE	WU,FRANK C AND TRACY S	MU	MU	No	No	No	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story dentist office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consisover 85 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
783	5779-011-015	Yes	519 S 1ST AVE	JAY AND DEE INVESTMENTS LLC	MU	MU	No	No	No	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial office structure with approximately 70 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 80 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
783	5779-011-014	Yes	523 S 1ST AVE	FIRST ARCADIA LLC	MU	MU	No	Yes	Yes	1	0.2	No	24	40	Mixed-Use Upzone	6	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story dentist office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story dentist office structure that is almost 95 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
784	5779-010-003	Yes	512 S 1ST AVE	GARCIA,EDWARD G AND BEATRICE TRS	MU	MU	No	No	No	0	0.1	No	24	40	Mixed-Use Upzone	3	3	1	<u>0</u>	<u>2</u>	<u>This parcel contains one single-story commercial office structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east and north. This site could realistically turn over into a higher intensity use.</u>
784	5779-010-002	Yes	516 S 1ST AVE	1045 FTL PROPERTIES LLC	MU	MU	No	No	No	0	0.1	No	24	40	Mixed-Use Upzone	3	3	1	<u>0</u>	<u>2</u>	<u>This parcel contains a single two-story commercial office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of a single two-story commercial office structure that is almost 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east. This site could realistically turn over into a higher intensity use.</u>
784	5779-010-001	Yes	518 S 1ST AVE	CRUPI,ROCCO F CO TR	MU	MU	No	No	No	0	0.3	No	24	40	Mixed-Use Upzone	12	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains one single-story commercial office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the east and south. This site could realistically turn over into a higher intensity use.</u>
785	5779-012-017	Yes	601 S 1ST AVE	ARCADIA BOARD OF REALTORS	MU	MU	No	No	No	1	0.3	No	24	40	Mixed-Use Upzone	13	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains one single-story commercial office structure with approximately 70 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial office structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
785	5779-012-016	Yes	611 S 1ST AVE	PATEL,DILIP S AND SHARDA D TRS	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story dentist office structure with approximately 70 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story dentist office structure that is almost 65 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>

786	5779-014-020	Yes	803 S 1ST AVE	LEE,NANCY	MU	MU	No	Yes	Yes	1	0.2	No	24	40	Mixed-Use Upzone	6	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story single-family residential home.</u>	<u>The parcel consists of one single-story single-family residential home that is almost 80 years old. The property is bordered by residential uses to the west and north. This site could realistically turn over into a higher density use.</u>
786	5779-014-021	Yes	805 S 1ST AVE	LEE,NANCY	MU	MU	No	Yes	Yes	1	0.1	No	24	40	Mixed-Use Upzone	5	4	1	<u>1</u>	<u>2</u>	<u>This parcel contains one single-story single-family residential home.</u>	<u>The parcel consists of one single-story single-family residential home that is almost 80 years old. The property is bordered by residential uses to the west and north. This site could realistically turn over into a higher density use.</u>
786	5779-014-033	Yes	815 S 1ST AVE	KOEPEK,KEVIN J TR ET AL	MU	MU	No	No	No	0	0.3	No	24	40	Mixed-Use Upzone	10	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is almost 50 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is bordered by residential uses to the west and north. This site could realistically turn over into a higher intensity use.</u>
786	5779-014-018	Yes	817 S 1ST AVE	MINADEO,ANTHONY AND WENDERS	MU	MU	No	No	No	0	0.1	No	24	40	Mixed-Use Upzone	5	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 40 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
786	5779-014-019	Yes	823 S 1ST AVE	MULLER INVESTMENTS LLC	MU	MU	No	No	No	1	0.2	No	24	40	Mixed-Use Upzone	6	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is almost 40 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is bordered by residential uses to the west. This site could realistically turn over into a higher intensity use.</u>
787	5779-016-006	Yes	816 S 1ST AVE	WANG,QING H	MU	MU	No	Yes	Yes	1	0.2	No	24	40	Mixed-Use Upzone	6	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains two single-story single-family residential homes.</u>	<u>The parcel consists of two single-story single-family residential homes that are over 80 years old. The property is bordered by residential uses to the south. This site could realistically turn over into a higher density use.</u>
787	5779-016-005	Yes	820 S 1ST AVE	KU,LEMUEL AND CATHY	MU	MU	No	Yes	Yes	0	0.1	No	24	40	Mixed-Use Upzone	5	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story single-family residential home.</u>	<u>The parcel consists of one single-story single-family residential home that is over 80 years old. The property is bordered by residential uses to the north. This site could realistically turn over into a higher density use.</u>
787	5779-016-004	Yes	824 S 1ST AVE	HILDRETH,BRUCE AND SONNIE	MU	MU	No	Yes	Yes	0	0.1	No	24	40	Mixed-Use Upzone	5	5	1	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial structure with approximately 75 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is bordered by residential uses to the north. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
790	8573-001-001	Yes	174 W LIVE OAK AVE	GOLDIN,STEVEN W TR	C-M	C/LI	No	No	No	0	0.2	No	0	48	Las Tunas Residential Flex Overlay	11	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains one single-story commercial structure with approximately 75 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is almost 65 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. This site could realistically turn over into a higher intensity use.</u>
790	8573-001-004	Yes	166 W LIVE OAK AVE	GOLDIN,STEVEN W TR	C-M	C/LI	No	No	No	0	0.2	No	0	48	Las Tunas Residential Flex Overlay	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is almost 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
790	8573-001-005	Yes	164 W LIVE OAK AVE	LIU,SHINN C AND	C-M	C/LI	No	No	No	0	0.2	No	0	48	Las Tunas Residential Flex Overlay	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains a single two-story office structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of a single two-story office structure that is over 20 years old. Additionally, 60 percent of the parcel is being utilized for surface parking. The property is bordered by residential uses to the south. The property is along a busy corridor which would be suitable to develop into residential or mixed use. This site could realistically turn over into a higher intensity use.</u>

790	8573-001-006	Yes	158 W LIVE OAK AVE	NOCERO,JOHN R AND CHRISTINE TRS	C-M	C/LI	No	No	No	0	0.1	No	0	48	Las Tunas Residential Flex Overlay	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
790	8573-001-007	Yes	154 W LIVE OAK AVE	ALEXANDER,SAM A AND MARY F TRS	C-M	C/LI	No	No	No	0	0.1	No	0	48	Las Tunas Residential Flex Overlay	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story light industrial structure with approximately 50 percent of the parcel used for surface parking and storage space.</u>	<u>The parcel consists of one single-story auto repair structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking and storage space. The property is bordered by residential uses to the south. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
790	8573-001-026	Yes	170 W LIVE OAK AVE	GOLDIN,STEVEN W TR	C-M	C/LI	No	No	No	0	0.1	No	0	48	Las Tunas Residential Flex Overlay	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking and storage space.</u>	<u>The parcel consists of one single-story commercial structure that is over 75 years old. Additionally, a majority of the parcel is being utilized for surface parking and storage space. The property is bordered by residential uses to the south. The property is along a busy corridor which would be suitable to develop into residential or mixed use. This site could realistically turn over into a higher intensity use.</u>
791	8573-013-044	Yes	88 W LIVE OAK AVE	ERICAL LLC	C-M	C/LI	No	No	No	0	0.2	No	0	48	Las Tunas Residential Flex Overlay	11	11	3	<u>2</u>	<u>6</u>	<u>This parcel contains a single two-story commercial structure with approximately 30 percent of the parcel used for surface parking.</u>	<u>The parcel consists of a single two-story underutilized warehouse, distribution, and storage structure that is over 80 years old. Additionally, 30 percent of the parcel is being utilized for surface parking. The property is bordered by residential uses to the south. The property is along a busy corridor which would be suitable to develop into residential or mixed use. This site could realistically turn over into a higher intensity use.</u>
791	8573-013-045	Yes	84 W LIVE OAK AVE	ARELLANO,SAMUE L M AND LOLA F TRS	C-M	C/LI	No	No	No	0	0.1	No	0	48	Las Tunas Residential Flex Overlay	6	6	2	<u>1</u>	<u>3</u>	<u>This parcel contains one single-story commercial structure with approximately 20 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 70 years old. Additionally, 20 percent of the parcel is being utilized for surface parking. The property is bordered by residential uses to the south. The property is along a busy corridor which would be suitable to develop into residential or mixed use. This site could realistically turn over into a higher intensity use.</u>
791	8573-013-047	Yes	80 W LIVE OAK AVE	GLOBAL SKYLINE INVESTMENT GROUP	C-M	C/LI	No	No	No	0	0.3	No	0	48	Las Tunas Residential Flex Overlay	15	15	4	<u>2</u>	<u>9</u>	<u>This parcel contains one single-story commercial structure with approximately 75 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
791	8573-013-048	Yes	68 W LIVE OAK AVE	POCHAN,CHU AND	C-M	C/LI	No	No	No	0	0.2	No	0	48	Las Tunas Residential Flex Overlay	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
792	5789-021-013	Yes	111 E LIVE OAK AVE	KELLY,DAVID L AND JEAN R TRS	C-O	C	No	No	No	0	0.5	Yes	0	40	Live Oak Residential Flex Overlay	19	19	5	<u>3</u>	<u>11</u>	<u>This parcel contains one single-story dentist office structure with approximately 70 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story dentist office structure that is almost 70 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property bordered by residential uses to the north. This site could realistically turn over into a higher intensity use.</u>

792	5789-021-019	Yes	67 E LIVE OAK AVE	CHU,FRANKT Y AND LINDA C J TRS	C-O	C	No	No	No	0	0.3	No	0	40	Live Oak Residential Flex Overlay	12	12	3	<u>2</u>	<u>7</u>	<u>This parcel contains one two-story office structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one two-story office structure that is over 30 years old. Additionally, a majority of the parcel is being utilized for surface parking or loading zones. The property is bordered by residential uses to the west and north. This site could realistically turn over into a higher intensity use.</u>
793	8573-024-001	Yes	100 E LIVE OAK AVE	B AND W XU LLC	MU	MU	No	No	No	1	0.4	No	24	40	Mixed-Use Upzone	16	15	4	<u>2</u>	<u>9</u>	<u>This parcel contains one single-story structure used for educational purposes with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story structure that is over 40 years old. Additionally, a majority of the parcel is being utilized for surface parking or open space. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. This site could realistically turn over into a higher intensity use.</u>
793	8573-024-002	Yes	108 E LIVE OAK AVE	LIVE OAK DEVELOPMENT I LLC	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	8	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains one single-story commercial structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking or open space. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
793	8573-024-003	Yes	114 E LIVE OAK AVE	CHOU,DEE TR	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	7	7	2	<u>1</u>	<u>4</u>	<u>This parcel contains one single-story commercial structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story commercial structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking or open space. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the south. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
793	8573-024-004	Yes	118 E LIVE OAK AVE	WORTHY,PARKER JR AND RUTH TRS	MU	MU	No	Yes	Yes	0	0.2	No	24	40	Mixed-Use Upzone	8	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains one single-story commercial structure with approximately 60 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one potentially vacant single-story commercial structure that is over 70 years old. Additionally, a majority of the parcel is being utilized for surface parking or open space. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property bordered by residential uses to the south a vacant lot to the east which can also redevelop into residential uses. This site could realistically turn over into a higher intensity use.</u>
794	5790-027-030	Yes	211 E LIVE OAK AVE	LIANG,GARY	C-G	C	No	No	No	0	0.2	No	0	40	Live Oak Residential Flex Overlay	8	8	2	<u>1</u>	<u>5</u>	<u>This parcel contains one single-story restuarant structure with approximately 75 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story education structure that is over 55 years old. Additionally, a majority of the parcel is being utilized for surface parking or open space. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property bordered by residential uses to the north. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
795	5790-028-028	Yes	325 E LIVE OAK AVE	ONUBBY LLC	C-G	C	No	No	No	0	0.5	Yes	0	40	Live Oak Residential Flex Overlay	19	19	5	<u>3</u>	<u>11</u>	<u>This parcel contains one single-story education structure with approximately 50 percent of the parcel used for surface parking or open space.</u>	<u>The parcel consists of one single-story education structure that is almost 60 years old. Additionally, a majority of the parcel is being utilized for surface parking or open space. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property bordered by residential uses to the east and north. This site could realistically turn over into a higher intensity use.</u>
795	5790-028-032	Yes	303 E LIVE OAK AVE	YEUNG,AMELIA S TR	C-G	C	No	No	No	0	0.3	No	0	40	Live Oak Residential Flex Overlay	10	10	3	<u>2</u>	<u>5</u>	<u>This parcel contains one single-story insurance office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story office structure that is almost 50 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property bordered by residential uses to the north. This site could realistically turn over into a higher intensity use.</u>

795	5790-028-033	Yes	311 E LIVE OAK AVE	SABATELLA,VERA A TR	C-G	C	No	No	No	0	0.2	No	0	40	Live Oak Residential Flex Overlay	9	9	2	<u>1</u>	<u>6</u>	<u>This parcel contains one single-story medical office structure with approximately 50 percent of the parcel used for surface parking.</u>	<u>The parcel consists of one single-story office structure that is over 55 years old. Additionally, a majority of the parcel is being utilized for surface parking. The property is along a busy corridor which would be suitable to develop into residential or mixed use. The property is bordered by residential uses to the north. The land value ratio is less than one, indicating potential for developer interest. This site could realistically turn over into a higher intensity use.</u>
796	5773-003-036	No	119 LA PORTE ST	RMK 2 PARTNERSHIP	C-M	C	No	No	No	0	0.5	Yes	0	64	Downtown Mixed Use Overlay	34	34	9	<u>5</u>	<u>20</u>	<u>This parcel contains one two-story office structure with approximately 50 percent of the parcel used for surface parking or loading zones.</u>	<u>The parcel consists of two two-story office structures that are over 30 years old. Additionally, a majority of the parcel is being utilized for surface parking or loading zones. The property is bordered by residential uses to the north. This site could realistically turn over into a higher intensity use.</u>
797	5773-003-037	No	135 LA PORTE ST	PLOTKIN JAMES R INC	C-M	C	No	No	No	0	0.4	No	0	64	Downtown Mixed Use Overlay	22	22	6	<u>3</u>	<u>13</u>	<u>This parcel contains two two-story industrial structures with approximately 50 percent of the parcel used for surface parking or loading zones.</u>	<u>The parcel consists of only one two-story office structure that is over 30 years old. Additionally, a majority of the parcel is being utilized for surface parking or loading zones. The property is bordered by residential uses to the north, southeast, and directly to the east. This site could realistically turn over into a higher intensity use.</u>



CITY OF
ARCADIA

Technical Background Report

Appendix B

Community Engagement Summary





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Appendix B: Community Engagement Summary

Section 65583 of the Government Code states that, "The local government shall make diligent effort to achieve public participation of all economic segments of the community in the development of the housing element, and the program shall describe this effort." Meaningful community participation is also required in connection with the City's Assessment of Fair Housing (AFH). A summary of citizen participation is provided below.

As part of the 6th Cycle Housing Element Update process, the City of Arcadia has conducted extensive public outreach activities beginning in March of 2021. These recent outreach efforts included Community Workshops, an online community survey, digital media and engagement, and noticed Public Hearings. Project materials, including summaries from community workshops and public meetings, notices, and draft public review documents are available on the City's website: <https://www.ArcadiaCA.gov/housing>.

Outreach for the 6th Cycle Housing Element to the Arcadia community, includes the following actions:

- **Housing Element Update Website** – The City developed a website to keep the community informed of the process, which can be accessed at <https://www.ArcadiaCA.gov/housing>. The website provides relevant information about the update process, key features of the housing element, project timeline and a calendar of events for outreach activities. The website also provided a link to the community survey tool as well as City contact information for residents and community members to send additional comments or request additional information.
- **Community Workshop #1 - Informational Video and Presentation** – In June, 2021, the City developed an outreach presentation and Staff informational videos to provide an overview of the RHNA process, the tentative schedule of the Housing Element Update and information on future opportunities for community participation. The outreach presentation video was provided in English and Chinese. Both videos were made available on the City's Housing Element Update Website, which can be accessed at <https://www.ArcadiaCA.gov/housing>. The Staff information videos were also made available at <https://vimeo.com/561008905>.
- **Online Community Survey** – From June 14, 2021 to August 6, 2021 the City of Arcadia launched an online community survey to gather feedback regarding the Housing Element Update. There was a total of 759 persons that participated in the survey. Participants were asked to consider potential policies and programs to include in the Housing Element. A postcard with information on the Housing Element Update and a link to the Community Survey was mailed to all property owners and residential tenants in the City; Residential tenants were included in the mailing in order to encourage public participation from all residents with a potential interest in housing issues in the community. The postcard was also made available at four separate public counters citywide to make information on the survey accessible to any resident visiting a City facility.
- **Community Workshop #2-** The City held a Community Workshop on September 23, 2021. During the workshop, the project team provided a presentation with an overview of the Housing Element and the process to date. Residents were also presented with information about how the City planned to achieve its RHNA. Community members had the opportunity to give public comments and respond to questions during the presentation. In total, 65 community members were in attendance. Workshop attendees were also provided the option of live Chinese translation, and meeting presentations were made available on the City's Housing Element Update website in both English and Chinese.
- **Social Media and City Publications** – The City posted information related to the housing element website and advertised community workshop information through the Spring and Summer City newsletter, mailed to all residents, posted to the City's website, and to the City's social media channels. The City posted on four social media platforms in order to reach the widest audience possible. Articles



CITY OF ARCADIA 6TH CYCLE Housing Element Update

on the Housing Element Update were also included in the 2021 March, April, May, August, and September "Hot Sheet" - a monthly publication mailed with City water bills that includes timely information on activities in Arcadia.

- **Public Comments** – Through the update process, the City received one inquiry on the Draft Housing Element. The City formally solicited input for the Public Review Draft of the Housing Element through various platforms from September 30 through November 1. The Public Review Draft was posted on the City's website and advertised on four different social media platforms. No comments were received despite the outreach efforts made by the City throughout the Public Review Draft comment period.

As required by Government Code Section 65585(b)(2), all written comments regarding the Housing Element made by the public have previously been provided to each member of the City Council.

This Appendix contains a summary of all public comments regarding the Housing Element received by the City at scheduled public meetings, and the Appendix has been provided to the City Council.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

1. Housing Element Update Website

The City developed a website to keep the community informed of the process, which can be accessed at <https://www.ArcadiaCA.gov/housing>. The website provides relevant information about the update process, key features of the housing element, project timeline and a calendar of events for outreach activities. The website also provided a link to the community survey tool as well as City contact information for residents and community members to send additional comments or request additional information.

Housing Element Update



The City of Arcadia is updating the Housing Element for the years 2021 to 2029. The Housing Element is a state-required policy document that plans for current and future housing needs within Arcadia. It identifies strategies for expanding housing opportunities and services for all household types and income groups and provides policy guidance for local decision-making related to housing.

NOTE: The Housing Element Update Project is **NOT** to be confused with the Tiny Shelter Project related to homelessness in Arcadia. That is a **SEPARATE** process that will occur outside of the Housing Element Update. For more information on the Tiny Shelter Project or homelessness in general, please see [ArcadiaCA.gov/tinysshelters](https://www.arcadiaca.gov/tinysshelters).

Housing Element Update Virtual Community Workshop

The Housing Element Update Community Workshop took place virtually on Thursday, September 23, 2021 at 6:00 p.m.. At this meeting, participants learned about the Housing Element Update process and the City's progress to date, heard an overview of the community survey results, and learned about potential strategies to accommodate the new housing units required by the State through the Regional Housing Needs Assessment (RHNA). The meeting was presented in English and Mandarin Chinese. A recording of the Workshop and a copy of the presentation are available below:

Virtual Community Workshop Presentation- Thursday, September 23, 2021

Workshop Video - English



Housing Element Update Community Workshop - 9/23/21

from **City of Arcadia**

1:57:48



Workshop Video - Chinese



**Housing Element Update Community Workshop - 9/23/21
(Chinese)**


from **City of Arcadia**

1:53:43



Meeting Invitations

[View flyer](#)



**HOUSING ELEMENT UPDATE
VIRTUAL WORKSHOP**
Thursday, September 23, 2021
6:00 p.m.

What is the "RHNA"?
State law provides a target for how many homes each region and city must plan for, based on current population, proximity to public transit and jobs, and expected population growth, etc. Called the Regional Housing Needs Allocation or "RHNA" (pronounced "ree-nah"), Arcadia must plan for new housing based on these targets.

Let's talk housing! Arcadia is a great place to live, but throughout the region there is a shortage of homes that impacts all of us. That's why now is the time to plan together for current and future housing needs in our community.

Join us virtually for the Housing Element Update Workshop on **Thursday, September 23, 2021 at 6:00 p.m.** where participants will hear how and where the City can accommodate additional housing over the next eight years and be able to provide feedback on options and strategies.

We hope that you can join us!

Workshop Information:
Date: Thursday, September 23, 2021
Time: 6:00 p.m.
To join via Zoom, go to: <https://krrley.hon.zoom.us/j/99512156792>
To join by telephone, please call +1 (669) 900-6833 or +1 (253) 215-8782 and enter the Webinar ID: 995 1215 6792

Please visit the City's website at ArcadiaCA.gov/housing to view additional information and see the results of the Community Housing Survey!

Questions? Contact Us!
Development Services Department
Planning Services
(626) 574-5423
Planning@ArcadiaCA.gov
ArcadiaCA.gov/housing

[View flyer - Chinese](#)



**新建住房比例最新
信息虚拟研讨会**
2021年9月23日 (星期四) 下午6时

"RHNA" 是什么?
州法根据当前人口、与公共交通和工作地点的临近程度以及预期的人口增长等因素，制定了一个目标，规定必须规划多少住房，以便达到地区和市区的目标。称为地区住房需求分配计划 (RHNA)，阿凯迪亚市必须根据这些目标制定新住房新建计划。

让我们来讨论住房问题！阿凯迪亚市是一个非常适合居住的地方，但整个地区都存在缺乏住房的问题，对我们所有人产生了影响。这是为什么现在是在为我们社区当前和未来的住房需求共同规划的时候了。

请参加我们于2021年9月23日 (星期四) 下午6时举办的新建住房比例最新信息研讨会。参加者将会听到阿凯迪亚市在今后八年内将如何以及在何处建造更多的住房，并能够提供有关选择和策略的反馈意见。

我们希望您能参加!

研讨会信息:
日期: 2021年9月23日 (星期四)
时间: 下午6时
如需通过Zoom参加研讨会，请进入
网页: <https://krrley-hon.zoom.us/j/99512156792>
如需通过电话参加研讨会，请拨打电话号码 +1 (669) 900-6833 或 +1 (253) 215-8782，并输入网络研讨会ID: 995 1215 6792

请访问阿凯迪亚市网站 ArcadiaCA.gov/housing，查看更多信息，并查看社区住房调查问卷结果!

有问题吗? 与我们联系!
发展服务部
规划服务部
(626) 574-5423
Planning@ArcadiaCA.gov
ArcadiaCA.gov/housing

Community Survey Summary

The City released a Community Survey related to the Housing Element Update on June 14, 2021 and over 700 responses were received. An initial summary of the survey results is available below. The survey results in their entirety will be included in the Draft Housing Element. [Housing Element Update Community Survey Summary](#)

What is the Housing Element?

The Housing Element is one of the 8 required Elements of the City's General Plan. The General Plan establishes long-range planning and policy in the City for land use and community design, economic development, circulation and infrastructure, resource sustainability, parks, recreation, and community resources, safety, noise, and housing. While the General Plan is a 25 year Plan, State law requires the Housing Element to be updated every eight years. The City is currently updating its Housing Element for the 2021-2029 period. A major component of this update is the 6th Cycle Regional Housing Needs Assessment ("RHNA"), in which the State estimates each region's housing needs for all income groups.

Informational Video and Presentation

Community outreach and participation is an important part of the Housing Element Update process. In an effort to keep the community informed, the City has prepared an outreach presentation, and informational videos by staff. To learn more about the Housing Element


Update process, get a better understating of the RHNA process, and get informed about future opportunities for community participation, please view the videos below. The outreach presentation is available in English and Chinese at the links below.



Introduction to the Housing Element Update (June 2021)

from **City of Arcadia**


01:54



Housing Element Presentation - English

Housing Element Presentation -

Chinese





Public Involvement

We want to hear from you! Relevant documents, public meeting notices, and other resources will be posted here, check back often. Email us at Planning@ArcadiaCA.gov, or sign up using the form at the bottom of this page, if you would like to be added to our mailing list for information and updates regarding the Housing Element Update.

What is RHNA?

The Regional Housing Needs Assessment ("RHNA") is a part of the State's housing element law that determines the projected and existing housing needs for each jurisdiction in the State. In its Housing Element, the City must demonstrate to the State that there are no unnecessary barriers to the housing approval process in order to meet the RHNA allocation for the City.

On March 4, 2021, the Southern California Association of Governments ("SCAG") released its final draft allocation of housing units for each jurisdiction in its region, which can be found [here](#). The City has received a final draft allocation of 3,214 new units for this upcoming planning period. Additional information on RHNA can be found at [SCAG](#) and at [California Department of Housing and Community Development \(HCD\)](#).



The City of Arcadia has been allocated a **RHNA of 3,214 total housing units** with the following income breakdown:

- 1,102 very-low income units;
- 570 low income units;
- 605 moderate income units; and
- 937 above-moderate income units.

HOUSING ELEMENT TIMELINE



Additional Documents

[Housing Types - Definitions](#)

[Frequently Asked Questions \(FAQ\)](#)



HOUSING ELEMENT UPDATE: 2021-2029 PLANNING PERIOD FAQ & FACT SHEET



What is the Housing Element? And why is it being updated?

The Housing Element is one of the City's 8 required Elements of the City's General Plan. The General Plan provides a framework for the management and growth of the City and guides future policy decisions. The Housing Element provides policies, programs, and actions that support housing growth across all income levels. State law requires that all cities update their Housing Element once every 8 years, and Housing Element planning periods are sometimes referred to as "cycles." The City's current Housing Element covers the planning period extending from 2014 to 2021, which is referred to as the "5th Housing Element cycle" in reference to the five required updates that have occurred since the comprehensive revision to State law in 1980. All cities in the Southern California Association of Governments ("SCAG") region are required to prepare a Housing Element update for the 6th planning cycle, which spans the 2021-2029 period. The SCAG region includes Los Angeles, Orange, Riverside, San Bernardino, Ventura, and Imperial counties.

Housing Element Certification

State law requires that the City's Housing Element be certified (approved) by the Department of Housing and California Development (HCD). A Housing Element is deemed certified when HCD has found that the Housing Element is in substantial compliance with State Law. Having a certified Housing Element avoids future penalties and/or fines on the City for noncompliance. In addition, having a certified Housing Element allows the City to be eligible for certain State assistance programs, grants and alternative funding sources. The Housing Element update process is considered complete once the State has certified the Housing Element.

The City's current Housing Element was adopted in 2013 and was deemed certified by HCD as fully compliant with State law.

What are the major issues that must be addressed in the Housing Element?

There are two major issues that must be addressed in the Housing Element update: 1) The City must develop policies and programs that support housing growth across all income levels, and 2) ensure that the City's regulations accommodate the housing needs of special needs groups.

1. A key component in the 2021-2029 Housing Element Update is the 6th Cycle Regional Housing Needs Assessment ("RHNA"). Every city in California is required to plan for new housing to accommodate its share of the regional need. The RHNA is the process established in State law by which housing needs are determined for each jurisdiction.
2. Under State law, Housing Elements must include policies and regulations that support housing for persons with special needs, including but not limited to, the elderly, large families, female-headed households, households with a disabled person, farm workers, and the homeless.

FAQ/Fact Sheet

1

Sign Up For Email Updates

Please enter your name and email address below to be added to our mailing list.

Your First Name*

Your Last Name*

Email*



I'm not a robot

reCAPTCHA
Privacy - Terms

Submit

Questions? Contact Us!

Do you have questions about the Housing Element? Do you want more information on ways you can participate? Please contact us below:

Development Services Department

Planning Services

(626) 574-5423

Planning@ArcadiaCA.gov

Housing Types Definitions

- **Single-Family Home:** a structure maintained and used as a single dwelling unit and occupied by a single household.
- **Multi-Family Home:** a single building that's set up to accommodate more than one household living separately.
- **Senior Housing:** housing intended and operated for occupancy by at least one person 55 years of age or older per unit.
- **Condominium/Townhome:** a multi-story house in a modern housing development which is attached to one or more similar houses by shared walls.
- **Accessory Dwelling Unit:** a smaller, independent residential dwelling unit located on the same lot as a stand-alone (i.e., detached) single-family home.
- **Transitional Housing:** a short-term stay when an individual or household is either waiting to secure permanent housing or has secured permanent housing that is not immediately available.
- **Mixed-Use Housing:** Development projects may be classified as "mixed-use" if they provide more than one use or purpose within a shared building or development area. Mixed-use projects may include any combination of housing, office, retail, medical, recreational, commercial, or industrial components. Housing units may be located vertically above another use, or horizontally next to another use.
- **Workforce Housing:** Housing that is affordable to private and public sector workers with incomes at or below that of teachers and public safety workers.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

2. Community Workshop #1 – Informational Video and Presentation

In June 2021, the City posted a virtual community workshop online. The workshop included a recorded presentation informing the public of the Housing Element Update, including an overview of the Housing Element, the Regional Housing Needs Assessment and the update process and timeline. The presentation also provided information regarding an online survey, developed by the City to solicit feedback from the community. The presentation is available for viewing by the public in English and with Chinese content and subtitles on the City's website at: <https://www.ArcadiaCA.gov/housing>.

Informational Video and Presentation

Community outreach and participation is an important part of the Housing Element Update process. In an effort to keep the community informed, the City has prepared an outreach presentation, and informational videos by staff. To learn more about the Housing Element Update process, get a better understating of the RHNA process, and get informed about future opportunities for community participation, please view the videos below. The outreach presentation is available in English and Chinese at the links below.



Introduction to the Housing Element Update (June 2021)

from City of Arcadia



Lisa L. Flores
Planning & Community
Development Administrator
Development Services Department

www.ArcadiaCA.gov/housing




01:54

vimeo



1



2



3



4



5



6



7



8



9

ARCADIA 2021-2029 Housing Element Update

什么是RHNA？

- 新建住房比例更新过程的基础
- 预测州、区域和地方各级的住房增长
- 根据加利福尼亚州每个县和市的收入类别量化住房需求
- 基于当前和预计的人口、就业和家庭增长

10

ARCADIA 2021-2029 Housing Element Update

如何确定RHNA分配？

住房和社区发展部 (HCD)
HCD确定全市的住房需求，并以分配给各城市区域委员会。

南加州政府协会 (SCAG)
SCAG制定了一种方法，将分配给每个城市区域委员会的住房需求分配给每个城市。

阿凯迪亚市 RHNA 2021-2029: 3,214套住房

11

ARCADIA 2021-2029 Housing Element Update

阿凯迪亚第6个RHNA周期

收入类别	占家庭中位收入 (MFI) 百分比	年收入范围*		RHNA分配 (住房套数)
		最低	最高	
低收入	0 - 50% MFI	\$36,600	\$48,000	1,400套住房
低收入	51 - 80% MFI	\$38,651	\$61,840	570套住房
中等收入	81 - 120% MFI	\$61,841	\$92,760	605套住房
较高收入	>120% MFI	\$92,761	—	97套住房
总计：				3,214套住房

*每个收入类别均定义为家庭收入范围，显示为占家庭中位收入 (MFI) 的百分比。一个三口之家在洛杉矶县的MFI为77,300美元。

12

ARCADIA 2021-2029 Housing Element Update

新建住房比例更新过程

13

ARCADIA 2021-2029 Housing Element Update

新建住房比例更新过程包括什么？

- 在线信息介绍
- 在线社区调查
- 社区宣传
- 更新本市的人口状况
- 确定适当的开发用地以适应增长
- 规划委员会和市议会听证会

14

ARCADIA 2021-2029 Housing Element Update

项目暂定时间表

开始	社区宣传	结束新居住住房比例	开始日期
8月	2021年6月至2021年8月	2021年9月	2022年2月

- 项目启动
- 人口分析和更新
- 信息视频
- 社区调查
- 在线社区调查
- 发表专家公众评论
- 试
- 规划委员会和市议会
- 最终听证会
- 最终听证会

15

ARCADIA 2021-2029 Housing Element Update

我们需要了解您的意见！

16

ARCADIA 2021-2029 Housing Element Update

我们需要了解您的意见

请访问：
www.ArcadiaCA.gov/housing

点击在线社区调查问卷链接开始。

17

ARCADIA 2021-2029 Housing Element Update

如何参加调查

- 使用您的手机或台式/笔记本电脑，点击市政府网站上提供的链接。
- 点击“开始”即可开始回答问卷。
- 仔细阅读所有说明和提示。

该调查为本市提供了重要的社区反馈，有助于制定新建住房比例的目标和政策。您的意见非常重要！

18

ARCADIA 2025-2029 Housing Element Update

如何参加调查

- 根据提示表达您的想法和意见。
- 完成第5页幻灯片，点击“提交最后的问题”，以便完成调查并提交全部回答。



该调查为本市提供了重要的社区反馈，有助于制定新建住房比例的目标和政策。您的意见非常重要！

18

19

ARCADIA 2025-2029 Housing Element Update

谢谢！

有问题吗？

请联系
规划服务部
(626) 674-6423
Planning@ArcadiaCA.gov

或访问市政府的网站：www.ArcadiaCA.gov/housing




18


20




1




2



3




4




5



6



7



8




9

2021-2029 Housing Element Update

What is RHNA?

- Foundation for the Housing Element Update Process
- Projects growth at a state, regional, and local housing level
- Quantifies housing need, by income category for each County and City in California
- Based on current and projected population, employment and household growth

10



11


2021-2029 Housing Element Update

Arcadia 6th Cycle RHNA

Income Category	% of Median Family Income	Annual Income Range*		RHNA Allocation (Housing Units)
		Min.	Max.	
Very Low Income	0 - 50% MFI	...	\$18,650	1,352 units
Low Income	51 - 80% MFI	\$18,651	\$61,840	570 units
Moderate Income	81 - 120% MFI	\$61,841	\$92,760	605 units
Above Moderate Income	>120% MFI	\$92,761	...	917 units
Total:				3,214 units

*Each income category is defined as a range of household incomes that represents a percentage of the Median Family Income (MFI). The MFI for a family of four in Los Angeles County is \$77,301.

12



13

2021-2029 Housing Element Update

What is Included in the Housing Element Update Process?

- Informational Online Presentation
- Online Community Survey
- Public Outreach
- Update of the City's demographic conditions
- Identification of adequate sites to accommodate growth
- Planning Commission and City Council Hearings

14



15



16

2021-2029 Housing Element Update

We Want Your Input

Provide your input and comments by taking a quick survey!

Go to: www.ArcadiaCA.gov/housing

Click the Online Community Survey link to begin.

17

2021-2029 Housing Element Update

How to Take the Survey

- Click the link provided on the City's website using either your phone or a desktop/laptop.
- Click "Begin" to start the survey.
- Read carefully through all instructions and prompts.

The survey provides the City with important community feedback to help shape goals and policies within the Housing Element. Your input is very important.

18

ARCADIA 2025-2029 Housing Element Update

How to Take the Survey

4. Respond to the provided prompts with your ideas and input.

5. Complete slide five and click "Submit Final Questions" to complete the survey and submit all responses.



The survey provides the City with important community feedback to help shape goals and policies within the Housing Element. Your input is very important!

19

ARCADIA 2025-2029 Housing Element Update

Thank You!

Questions?

Please Contact
Planning Services
 (626) 574-5423
Planning@ArcadiaCA.gov

Or Visit the City's webpage at www.ArcadiaCA.gov/housing



20



CITY OF ARCADIA 6TH CYCLE Housing Element Update

3. Online Community Survey

This section contains an outline of the community survey and a summary of the survey results. The online community received 759 responses from the public.

On June 14, 2021, the City of Arcadia launched an online community survey to gather additional feedback regarding potential policies and programs, housing types, and housing opportunities to include in the Housing Element. The survey also solicited feedback regarding potential barriers or constraints to housing access and the development of housing. The survey was available in both English and Chinese. The survey was live through August 6, 2021 and was available on the City's webpage, <https://www.ArcadiaCA.gov/housing>. In order to engage a greater number of Arcadia residents, the City mailed an informational postcard with a link to the community survey to all property owners and residential tenants in the City. The postcard was also made available at four public counters citywide to ensure information on the survey



Community Survey

The City of Arcadia created an online community survey to gather information and feedback from the public about the housing needs, challenges, and opportunities. The feedback received through the survey will help direct the 2021 – 2029 Housing Element. The survey was made public on Monday, June 14, 2021 and remained open until Friday, August 6, 2021. The survey was offered in both English and Chinese and gathered information from a total of 759 participants (**Table 1-1**). Questions about affordable housing, accommodation of more housing units, housing challenges, and public housing experience were addressed. Additionally, participants mapped out potential housing areas and provided feedback on their vision for the future of Arcadia. The data collected from this survey will help the City in creating a Housing Element Update that accommodates current needs and ensures that future growth is met.

Table 1-1 Survey Participation	
English Survey Participants	616
Chinese Survey Participants	143
Total Participants	759

Slide 1: Welcome

The first slide of the survey provided background information about the Housing Element, the update process, as well as an overview of the purpose and goals of the survey.

Slide 2: Community Housing

The community housing survey slide consisted of the four main topics: affordable housing, accommodating more housing units, housing challenges, and your housing experience. Each of the four topic areas included a list of questions as well as a comment box for participants to share longer form thoughts.

Affordable Housing

The Affordable Housing section asked participants to select the housing types that would best accommodate future affordable needs. The following housing type options were offered:

- Single Family Homes
- Multi-Family Condos/Townhomes
- Multi-Family Apartments
- Mixed-Use Housing
- Senior Housing
- Transitional and Supportive Housing
- Accessory Dwelling Units
- Single Room Occupancy

Figures 1a and 1b below display participant's responses to the English and Chinese survey question respectively.



Figure 1a: Which housing types would best accommodate future affordable needs?





Figure 1b: 哪种住房类别最能满足未来的可负担需求?



There were 1,142 English survey participant responses and 170 Chinese survey participant responses. The housing types identified to best accommodate future affordable needs are as follows:



English Survey Responses

- Single-family housing was selected by 27 percent of participants,
- Senior housing was selected by 19 percent of participants,
- Multi-family condos or townhomes was selected by 18 percent of participants,
- Multi-family apartments were selected by 13 percent of participant,
- Mixed-use housing was selected by 8 percent of participants,
- Accessory dwelling units were selected by 6 percent of participants,
- Transitional and supportive housing was selected by 6 percent of participants, and
- Single room occupancy was selected by 3 percent of participants.

Chinese Survey Responses

- Single-family housing was selected by 50 percent of participants,
- Multi-family condos or townhomes was selected by 18 percent of participants,
- Senior housing was selected by 12 percent of participants,
- Multi-family apartments were selected by 8 percent of participant,
- Mixed-use housing was selected by 5 percent of participants,
- Accessory dwelling units were selected by 3 percent of participants,
- Transitional and supportive housing was selected by 2 percent of participants, and
- Single room occupancy was selected by 2 percent of participants.

The Affordable Housing tab also asked participants if there are additional housing types or ideas that the City should consider, and participants provided various feedback. Key themes identified in the English comments include the following:

- High interest in single-family homes and duplexes.
- Moderate interest in low-income senior housing and mixed-use housing.
- Overall, many comments about apprehension towards housing development including affordable housing within the City of Arcadia.

Key themes identified in the Chinese comments include the following:

- 维持现状.

Accommodating More Housing Units

The Accommodating More Housing Units section described potential rezoning efforts the City may take to accommodate more housing units. Participants were asked to identify which types of areas would best accommodate additional housing units. The following types of area options were offered:

- Multi-Family Zones
- Commercial Area
- Mixed-Use Zones
- Zones Near Transit

Figures 2a and 2b below display participant's responses to the English and Chinese survey question respectively.

Figure 2a: The City may need to consider rezoning certain areas to accommodate more housing units. Which types of areas would best accommodate these units?





Figure 2b: 本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？



Based on participant responses the areas identified to best accommodate additional housing units are as follows:

English Survey Responses



- Zones near transit were selected by 33 percent of participants,
- Mixed-use zones were selected by 24 percent of participants,
- Commercial areas were selected by 23 percent of participants, and
- Multi-family zones were selected by 20 percent of participants.
- Overall, participant responses were generally evenly split between the four areas.

Chinese Survey Responses

- Multi-family zones were selected by 35 percent of participants,
- Mixed-use zones were selected by 24 percent of participants,
- Commercial areas were selected by 24 percent of participants, and
- Zones near transit were selected by 17 percent of participants.

Additionally, this tab asked participants to comment additional areas the City should consider to accommodate different housing types and various responses were received. Key themes identified in the English comments include the following:

- New housing should be developed on underutilized vacant or commercial land.
- New development should be near public transportation.
- There is limited interest in any housing development within the City of Arcadia.

Key themes identified in the Chinese comments include the following:

- 维持现状.
- 反对增加任何可负担房屋.

Housing Challenges

The Housing Challenges section asked participants to identify the most pressing housing related issues that the City should consider when updating the Housing Element. The following housing related issue options were offered:

- Shortage of Senior Housing
- Shortage of affordable housing for low-income households (earning less than \$61,840 for a household of 4)
- Not enough new housing development
- Not enough variety in housing types
- Not enough information on housing opportunities
- Not enough housing programs/support provided by the City

Figures 3a and 3b below display participant's responses to the English and Chinese survey question respectively.



Figure 3a: What are the most pressing housing related issues the City of Arcadia should consider when updating the Housing Element?





Figure 3b: 在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？





Based on participant responses the most pressing housing related issues were identified as follows:

English Survey Responses

- Shortage of senior housing was considered a pressing issue by 25 percent of participants,
- Shortage of affordable housing for low-income households was identified by 20 percent of participants,
- Lack of information on housing opportunities was a pressing issue for 16 percent of participants,
- Lack of new housing development was an issue for 14 percent of participants,
- Lack of housing programs/support provided by the City was an issue for 13 percent of participants, and
- Lack of variety in housing types was an issue for 12 percent of participants.
- Overall, 45 percent of the English survey participants cited the shortage of senior housing and affordable housing for low-income households to be the most pressing housing related issues in Arcadia.

Chinese Survey Responses

- Shortage of senior housing was considered a pressing issue by 29 percent of participants,
- Lack of new housing development was an issue for 26 percent of participants,
- Lack of information on housing opportunities was a pressing issue for 20 percent of participants,
- Shortage of affordable housing for low-income households was identified by 10 percent of participants,
- Lack of housing programs/support provided by the City was an issue for 9 percent of participants, and
- Lack of variety in housing types was an issue for 6 percent of participants.
- Overall, 55 percent of Chinese survey participants cited the shortage of senior housing and lack of new housing developments to be the most pressing housing related issues in Arcadia.

Additionally, survey participants were asked to share their thoughts on additional challenges to housing access in Arcadia. There were a variety of survey participant responses. Key themes identified in the English comments include the following:

- Affordability.
- High property taxes.
- Lack of public knowledge of existing housing programs.
- However, the majority of participants comment that there are no housing access issues and no changes to housing in Arcadia should be made.

Key themes identified in the Chinese comments include the following:

- 维持现状.
- 反对增加任何可负担房屋.

Your Housing Experience

The Your Housing Experience section asked participants to comment on their housing experience in Arcadia. Both English and Chinese survey participants left a variety of comments expressing the following:



- Many participants have lived in Arcadia for over 10 years.
- Many Participants live in single-family homes.
- Participants that have moved to Arcadia within the last 10 years find it expensive and difficult to purchase homes.

Additionally, this tab asked what type of housing participants would like their next home to be. The following types of housing options were offered:

- Single-Family Home
- Multi-Family Condo/Townhome
- Multi-Family Apartment

Figures 4a and 4b below display participant's responses to the English and Chinese survey question respectively.

Figure 4a: What type of housing would you like your next home to be?





Figure 4b: 您希望您的下一套住房是哪一种类型的住房？





There were 490 English survey participant responses and 94 Chinese survey participant responses. The housing types participants would prefer their next home to be are as follows:

English Survey Responses

- A single-family home is preferred by 85 percent of participants.
- Multi-family condos or townhomes are preferred by 12 percent of participants.
- Multi-family apartments are preferred by 3 percent of participants.

Chinese Survey Responses

- A single-family home is preferred by 87 percent of participants.
- Multi-family condos or townhomes are preferred by 10 percent of participants.
- Multi-family apartments are preferred by 3 percent of participants.

Participants were also asked if they plan to remain in Arcadia. **Figures 5a and 5b** display participant's responses to the English and Chinese survey question respectively.

Figure 5a: Would you like to remain in Arcadia?





Figure 5b: 您想继续住在阿凯迪亚吗？



Based on the survey responses participants preferences to remain in Arcadia were identified as follows:

English Survey Responses

- 75 percent of English survey participants would like to remain in Arcadia.
- 19 percent of English survey participants are unsure if they will remain in Arcadia.
- 5 percent of English survey participants would not like to remain in Arcadia.

Chinese Survey Responses

- 86 percent of Chinese survey participants would like to remain in Arcadia.
- 11 percent of Chinese survey participants are unsure if they will remain in Arcadia.
- 3 percent of Chinese survey participants would not like to remain in Arcadia.



For the participants who selected yes, they want to stay in Arcadia, they were asked to share how they could be encouraged or supported in their ability to live in Arcadia. Both English and Chinese survey participants left a variety of comments expressing the following:

- Interest in affordable senior housing.
- High interest in maintaining Arcadia's safety and low crime rate, cleanliness, and good school districts.
- Opposition to tiny homes and increases in housing density.

Slide 3: Map Markers

The Map Makers slide allowed participants to locate what types of housing development would be preferable throughout the City of Arcadia. Participants could select map markers for multi-family apartments, single-family housing, multi-family condos/townhomes, and mixed-use housing. For each map marker placement participants were prompted to comment on why they would like to see housing at the selected location. This information will help the City identify potential housing areas for future use.

Multi-Family Apartments

Both English and Chinese survey participants placed a total of 291 multi-family apartment map markers throughout the City of Arcadia and 141 placements were accompanied by comments. Both English and Chinese survey participants' key reasoning for the multi-family apartment location selection include the following:

- Locations that are vacant or underutilized (large unused parking lots),
- Locations near public transit or commercial areas, or
- Locations that are already zoned for high density mixed-use and multi-family housing.

Single-Family Housing

Both English and Chinese survey participants placed a total of 466 map makers throughout the City and 200 placements were accompanied by comments. Both English and Chinese survey participants' key reasoning for single-family housing location selection include the following:

- Locations that were near schools,
- Location near existing single-family homes, or
- Location that are vacant.

Multi-Family Condos/Townhomes

Both English and Chinese survey participants placed a total of 395 multi-family condo/townhome map markers placed around the City of Arcadia and 171 placements were accompanied with comments. Both English and Chinese survey participants' key reasoning for multi-family condos/townhome location selection include the following:

- Locations that are near public transit or the highway,
- Locations that are vacant or underutilized (large unused parking lots), and
- Locations where multi-family housing already exists.



Mixed-Use Housing

Both English and Chinese survey participants placed a total of 292 mixed-use housing map markers around the City of Arcadia and 150 placements were accompanied with comments. Both English and Chinese survey participants' key reasoning for mixed-use housing location selection include the following:

- Locations that are in or near Downtown Arcadia,
- Locations that are underdeveloped commercial areas, and
- Locations near public transit or highways.

Slide 4: Your Vision

The Your Vision slide provides a space for participants to express what their vision for the future of housing in Arcadia would look like. These comments will help inform the City about what kind of future the public would like to see reflected in the Housing Element Update.

There were 250 participant comments expressing various ideas about what the future housing of Arcadia should look like. Key themes identified in the comments include the following:

- High interest in single-family homes
- Some Interest in affordable housing as well as senior housing
- High interest in maintaining the existing living environment, safety and low crime rates, and cleanliness of the City

Slide 5: Participant Demographics

The Wrap Up slide thanked the participants for their input and concluded the survey by asking final questions to help assess the ideas contributed with various community demographics. The final questions asked participants if they live or work in Arcadia, their age range, if they rent or own their residence, a description of their current residence by housing type, and what type of housing they would like their next home to be. Additionally, this slide includes a final comments section for additional feedback and provides the housing element update team's contact information as well as a link to the housing element update webpage for public use.

The first wrap up question asked participants if they live or work in the City of Arcadia. **Figures 6a and 6b** below display participant's responses to the English and Chinese survey question respectively.



Figure 6a: Do you live or work in Arcadia?





Figure 6b: 您在阿凯迪亚居住或工作吗？



There were 403 English survey participant responses and 62 Chinese survey participant responses. The results are as follows:

English Survey Responses

- 80 percent of participants live in the City,
- 17 percent live and work in the City,
- 1 percent of participants only work in the City, and
- 2 percent of participants neither live nor work in the City of Arcadia.

Chinese Survey Responses

- 92 percent of participants live in the City,
- 8 percent live and work in the City, and
- No participants only work in the City nor did any participants identify as neither living nor working in the City.

The second wrap up question asked participants to identify their age range. **Figures 7a and 7b** below display participant's responses to the English and Chinese survey question respectively.



Figure 7a: What is your age range?





Figure 7b: 你属于哪一个年龄段？



There were 401 English survey participant responses and 61 Chinese survey participant responses. The results are as follows:

English Survey Responses

- 42 percent of participants were between 56 to 74 years of age.
- 35 percent of participant were between 40 to 55 years of age.
- 12 percent of participants were between 26 and 39 years of age.
- 8 percent of participants were 75 year of age or older.
- 3 percent of participants were 25 years of age or younger.
- Overall, the majority of participants were between 40 and 74 years of age.


Chinese Survey Responses

- 67 percent of participants were between 40 to 55 years of age.
- 20 percent of participants were between 26 and 39 years of age.
- 11 percent of participants were between 56 and 74 years of age.
- 2 percent of participants were 25 years of age or younger.
- No participants were 75 years of age or older.
- Overall, the majority of participants were between 26 and 55 years of age.

The third wrap up question asked participants if they own or rent their residence. **Figures 8a and 8b** below display participant's responses to the English and Chinese survey question respectively.



Figure 8a: Do you own or rent your residence **Figure 8b: 您是拥有自己的住房还是租房？**



There were 399 English survey participant responses and 62 Chinese survey participant responses. The results are as follows:

English Survey Responses

- 83 percent of participants own their home,
- 17 percent of participants rent their home, and
- No participants own property that they rent to others nor are any participants currently unhoused.

Chinese Survey Responses

- 85 percent of participants own their home,
- 15 percent of participants rent their home, and
- No participants own property that they rent to others nor are any participants currently unhoused.

The fourth wrap up question asked participants to identify the type of housing that best described their current residence. **Figures 9a and 9b** below display participant's responses to the English and Chinese survey question respectively.



Figure 9a: Of the following, which best describes your current residence?





Figure 9b: 以下哪一项最能描述您目前的住所？



There were 398 English survey participant responses and 62 Chinese survey participant responses. The results are as follows:

English Survey Responses

- 81 percent of participants describe their current residence as a single-family home.



- 11 percent of participants describe their current residence as multi-family condo or townhome.
- 8 percent of participants describe their current residence as multi-family apartment.
- No participants described their current residence as an accessory dwelling unit nor were there any participants currently unhoused.

Chinese Survey Responses

- 77 percent of participants describe their current residence as a single-family home.
- 16 percent of participants describe their current residence as multi-family condo or townhome.
- 11 percent of participants describe their current residence as multi-family apartment.
- No participants described their current residence as an accessory dwelling unit nor were there any participants currently unhoused.

The final wrap up question asked participants to identify what type of housing they would like their next home to be. **Figures 10a and 10b** below display participant's responses to the English and Chinese survey question respectively.

Figure 10a: What type of housing would you like your next home to be?







Figure 10b: 您希望您的下一套住房是哪一种类型的住房？



There were 393 English survey participant responses and 59 Chinese survey participant responses. The results are as follows:

English Survey Responses

- 84 percent of participants would like a single-family home,
- 13 percent of participants would like a multi-family condo or townhome, and
- 3 percent of participants would like a multi-family apartment.

Chinese Survey Responses

- 90 percent of participants would like a single-family home,
- 7 percent of participants would like a multi-family condo or townhome, and
- 3 percent of participants would like a multi-family apartment.

There was a total of 198 additional comments left by participants addressing the housing element update. Key themes identified in both the English and Chinese survey comments include the following:

- High interest in Arcadia remaining the same.
- Opposition to high-density and low-income housing.
- Opposition to any zoning or land use changes.
- Some interest in more senior housing as well as affordable housing.

Item	Comment
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	保持现在的住房类型和和平环境是支持我在这里居住的动力。如过增加不必要的游民设施，我会考虑搬离阿凯迪亚。
多户住宅 - 共管公寓/连栋住宅	交通便利
混合用途住宅	交通便利
多户住宅 - 公寓	激活促进地域商业。
Vision feedback	请不要开发游民设施在阿凯迪亚，这只是某些议员的政治考量而不是环境及经济发展考量。不必要的游民设施只会会摧毁现有的阿凯迪亚平和环境，现有居民的压力已经到了极限。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	Yes
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	平和的阿凯迪亚社区环境
混合用途住宅	有空地吧
多户住宅 - 公寓	有空地吧
Vision feedback	请不要以政治正确及某些议员的私利目的来设立游民设施。
您还有其他意见或建议吗？	平和的阿凯迪亚不需要以政治正确为目的而设立所谓的外来游民设施。请优先考虑阿凯迪亚本身居民的真正需求而而不是成为某些议员做秀的议题。
本市还应考虑哪些其他区来容纳不同类型的住房？	no need this kind of housing
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	current situation is fine
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	SAFE AND SCHOOL
您还有其他意见或建议吗？	There are to many new big houses in small lot
本市还应该考虑其他哪些住房类型或想法？	封闭管理的独栋house.
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全
独户住宅	安静
混合用途住宅	热闹
独户住宅	安静
Vision feedback	保留原有的特色，安静，安全，而不是过多的流浪汉
请告诉我们您在阿凯迪亚的住房经历。	租房一年，买到独立屋，目前还比较满意
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境优美、生活配套齐全
混合用途住宅	土地成本不高
独户住宅	环境好
多户住宅 - 公寓	离商业区近，生活便利
Vision feedback	希望向San Marino学习，尽量少开发，维护优美的城市环境
Vision feedback	希望有更多符合中产阶级的房子，带游泳池最好。现在的房价太贵了！！！
请告诉我们您在阿凯迪亚的住房经历。	住在孔雀园
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	方便，安全，教育
Vision feedback	尽量少开发低收入的住房，保证安全。
本市还应该考虑其他哪些住房类型或想法？	不应该考虑
请告诉我们您在阿凯迪亚的住房经历。	独立住宅，非常好
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	独立住宅最好
Vision feedback	就应该持续只发展独立住宅
您还有其他意见或建议吗？	最好只修独立住宅
请告诉我们您在阿凯迪亚的住房经历。	独立的房子
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	良好的环境，优秀的高中
Vision feedback	环境优美的独立屋能够提升城市安全性
您还有其他意见或建议吗？	增强城市的安全性，提升城市形象
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	生活便利、各种设施齐全
请告诉我们您在阿凯迪亚的住房经历。	很好
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	请考虑停车位和交通堵塞问题
本市还应该考虑其他哪些住房类型或想法？	在建房同时请考虑让社区变得更好，更安全
Vision feedback	请不要过度开发，希望政府尽力为下一代保留一个美丽宁静安全祥和的阿凯迪亚。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	學區
请告诉我们您在阿凯迪亚的住房经历。	Condo median 如有少量能够重重花草的地就更好。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全、方便。
独户住宅	因为这里有地。
本市还应该考虑其他哪些住房类型或想法？	反對建可負擔住房在Arcadia
请告诉我们您在阿凯迪亚的住房经历。	I live a single house that I own
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	nice neighborhood but I do not want the city tobuild 3000 plus house to accomodate possible another 12000 peoples that will crowd our school and streets
您还有其他意见或建议吗？	do not want the city to build 3000 plus unit .outragious idea
请告诉我们您在阿凯迪亚的住房经历。	獨立住宅
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	習慣周邊生活機能
多户住宅 - 共管公寓/连栋住宅	有空地使用
Vision feedback	希望能建造一些管理良好的老人公寓
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	方便，生活配套齊全。
请告诉我们您在阿凯迪亚的住房经历。	位置方便，但房子老舊，街道停車位少。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	新建公寓太多，但街道缺少停車位。
多户住宅 - 共管公寓/连栋住宅	商铺可变成商住混合
混合用途住宅	商铺可变成商住混合
本市还应考虑哪些其他区来容纳不同类型的住房？	不接受建在Arcadia Par 3 Golf , Las tunas 附近
请告诉我们您在阿凯迪亚的住房经历。	獨戶住宅
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	1. 没有建tiny house收容無家可歸的人,請市府保護我們的安全及平靜,而且我最担心是他們萬一傷人，city主辦tiny house萬一連帶被告，高額賠償金，令人擔憂，又不是高中生，隨口說支持，作保證人和幫助人是二回事。 2. Affordable house 没有蓋在南區, 而且還要蓋那麼多這種事。 3. 希望 city 是保護市民的.

您还有其他意见或建议吗？	不贊成建那麼多affordable house[, 也請市府先告訴我們， 建這些affordable house會影響我們什麼？
您还有其他意见或建议吗？	No tiny shelter
请告诉我们您在阿凯迪亚的住房经历。	We own our SFH since 2010
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Not so crowded
Vision feedback	Increase the FAR
您还有其他意见或建议吗？	No more Low Income house should be built in Arcadia
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Safety
请告诉我们您在阿凯迪亚的住房经历。	Too many homeless around
独户住宅	SFH only
独户住宅	SFH only
独户住宅	SFH only
Vision feedback	SFH only. No low income housing. No shelter
您还有其他意见或建议吗？	No low income housing. No homeless shelter. Nohomeless service hub
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Safe environment
Vision feedback	To create a safe environment and better community
您还有其他意见或建议吗？	I don't want low income housing in arcadia.
独户住宅	方便
Vision feedback	We need build more single home not low income house.
您还有其他意见或建议吗？	Can not build low income house in our city'scause it will low grade our estates value .
本市还应该考虑其他哪些住房类型或想法？	We need more single new houses.
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Good environment ,good neighbors hood and convenience.
Vision feedback	We need build more single house instead of lowincome houses.
您还有其他意见或建议吗？	We can not build low income houses that will down grade our city.
	Owning three and renting out one, keep apartments and condos out of Arcadia, we are a city of pride and prestige, anyone wants to propose apartmentsand affordable housing, please make sure to publicize your Arcadia residency so to avoid any distribution of hypocrisy.
请告诉我们您在阿凯迪亚的住房经历。	True pride of a Arcadia resident
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Keep apartments, condos, Tiny Shelters out of Arcadia, we are a city of pride and prestige, anyone wants to propose and affordable housing or TinyHomes, please make sure to publicize your Arcadia residency so to avoid any distribution of hypocrisy.
Vision feedback	Keep apartments, condos, Tiny Shelters out ofArcadia, we are a city of pride and prestige, anyone wants to propose and affordable housing or TinyHomes, please make sure to publicize your Arcadia residency so to avoid any distribution of hypocrisy.
您还有其他意见或建议吗？	在此已住近四十年兒女都已成家， 我們已經退休， 還是想要住在Arcadia
请告诉我们您在阿凯迪亚的住房经历。	学区好
	地大人少
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	自住独栋
请告诉我们您在阿凯迪亚的住房经历。	安全便利
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	可以有更多选择
独户住宅	更多选择
独户住宅	有需求
多户住宅 - 共管公寓/连栋住宅	这里有需求
多户住宅 - 公寓	保持本区域住房及人口类型的特点，更加安心地住在本市。
Vision feedback	安全！环境好！邻居很好！没有太多的游民及低收入者！人文环境很好！
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	环境好安静
独户住宅	可以解决很多人居住的问题
多户住宅 - 公寓	适合
多户住宅 - 共管公寓/连栋住宅	适合
混合用途住宅	Single house
本市还应该考虑其他哪些住房类型或想法？	希望Arcadia这个城市依然保持它的美好！不需要建很多住房！人口太多地域不够宽广会引起脏、乱、差！同时也为市市政府的管理减轻一些负担！
Vision feedback	多建独立屋或商住两用
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	不要建造很多公寓及住房！依然保持这个城市的美好与宁静！！！
您还有其他意见或建议吗？	安全的环境好的学区，友好的邻里关系
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Arcadia 应永久以独户为主， 这不应该被改变。
本市还应该考虑其他哪些住房类型或想法？	Arcadia 需要控制人口数量， 而不是无限制的去更改地块用途。不同意更改原地区区划
本市还应考虑哪些其他区来容纳不同类型的住房？	Arcadia 可在现状上新建、翻建、改建，不可以无限制扩大建设
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	独户
请告诉我们您在阿凯迪亚的住房经历。	富人区， 环境面貌好，城市安全
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Arcadia 属于富人区的现状不应被改变，在Arcadia 居住的门槛不应该被降低， 懒惰的人，不务正业的人没有资格享有甚至破坏勤劳努力的人带来的资源、环境。Arcadia 的城市安全必须得到保证！
Vision feedback	Close to bus station
多户住宅 - 公寓	20年搬到arcadia.贷款买房，为了孩子上学和一个安全的居住环境
请告诉我们您在阿凯迪亚的住房经历。	Close to bus station
混合用途住宅	Close to bus station
多户住宅 - 公寓	Arcadia 必须以独户为主，如果市政府不能保护这个城市的环境、安全，引入过多低收入人群甚至无收入人群的入驻，将会导致城市档次下降，房价暴跌，富人离开，任何会毀掉Arcadia
	的决策，都会让市政府成员罪名永载Arcadia 历史。
您还有其他意见或建议吗？	如果arcadia变成一个什么收入都可以搬进来的社区，而不是通过努力工作挣钱交高额地税和消费税，有限的学区资源源却能共享，那会考虑搬走
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Need to pay attention to the needs of existingresidents. They have paid property taxes and have the right to join to determine their future living environment.
Vision feedback	Rent
请告诉我们您在阿凯迪亚的住房经历。	房价便宜点
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	医院，学区， 安静的居住环境
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	安全， 美丽，体面邻居、中产社区
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	多建些affordable condos
Vision feedback	

本市还应该考虑其他哪些住房类型或想法？	请不要
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	不需要更多住房单位
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	不需要改变
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	美丽环境，安全，体面邻居
Vision feedback	如果阿卡迪亚建立很多低收入住房，治安会变差
请告诉我们您在阿凯迪亚的住房经历。	我在Arcadia住town house 20年了
您还有其他意见或建议吗？	维持社区目前房屋类型构成现状，坚决反对增加任何可负担住宅
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境好，学区好
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境好，治安好
请告诉我们您在阿凯迪亚的住房经历。	阿凯迪亚市是一个环境好，整洁干净，相对安全的区域。在这里养育孩子会比较有安全感。另外出门购物吃饭很方便
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境好，整洁干净，安全
Vision feedback	多盖town house
多户住宅-公寓	离地铁站近，适合年轻上班族
混合用途住宅	商业延伸，对城市收入，居民生活便利
独户住宅	环境优美
您还有其他意见或建议吗？	希望政府能打造一个安全，整洁的城市环境。本城市有很多养育孩子的家庭，安全是大家的重中之重。现在整体加加州治安下降非常厉害。请政府有所作为！
本市还应该考虑其他哪些住房类型或想法？	暂没有必要
本市还应该考虑其他哪些住房类型或想法？	维持现状就可以，土地资源有限
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	目前的居住环境
本市还应该考虑其他哪些住房类型或想法？	维持现状。
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状。
请告诉我们您在阿凯迪亚的住房经历。	维持现状。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	学区
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	维持现状。
您还有其他意见或建议吗？	土地资源有限，维持现状就是对人们最好的保护
Vision feedback	维持现状。
您还有其他意见或建议吗？	维持现状。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	整个社区的环境
多户住宅-共管公寓/连栋住宅	靠近高速路
多户住宅-共管公寓/连栋住宅	这里都是独栋住宅，需要混合住在比例。
多户住宅-共管公寓/连栋住宅	靠近高速公路购物中心。
Vision feedback	对于整个城市的安全表示担忧。
您还有其他意见或建议吗？	希望是政府加强城市的安全保护措施。
Vision feedback	安全、整潔、規範的社區是我們所有市民的訴求
请告诉我们您在阿凯迪亚的住房经历。	因为市政府的总总举措，一直在担心房价下跌，惴惴不安
本市还应该考虑其他哪些住房类型或想法？	不需要
本市还应考虑哪些其他区来容纳不同类型的住房？	不需要
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	市府房屋計劃單位規定比臨市的天普市要求多出許多，使得亞市居民的負擔多過臨近城市。比如在對中小企業的規定上、商用垃圾服務上……增加許多額外的負擔
请告诉我们您在阿凯迪亚的住房经历。	请保持现状
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	好学区，安全的环境
General Comment	请保持现状
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	社区安全 干净环境
本市还应考虑哪些其他区来容纳不同类型的住房？	请保持目前的住房数量，不要改变地块的区划，Arcadia目前已经有住房单位了。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	Arcadia是个小城市，目前的警力、消防不足以再增加住宅单位。请保持现状！
请告诉我们您在阿凯迪亚的住房经历。	Arcadia南边有很多condo房子的居住地人口稠密，而Huntington Dr. 北部人口相对稀少。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	好的学区、环境、治安、交通、餐饮、购物、娱乐等等
多户住宅-共管公寓/连栋住宅	这里人口相对较少
多户住宅-共管公寓/连栋住宅	这里人口相对较少
多户住宅-共管公寓/连栋住宅	这里人口相对较少
Vision feedback	Arcadia是个不大的城市，请保持现状，不要再改变zoning来增加住宅单位了！
您还有其他意见或建议吗？	保持现有的住宅单位，不要再增加。搞好城市治安是目前最重要的事情！
本市还应该考虑其他哪些住房类型或想法？	我不同意在Arcadia 盖任何房屋给游民住。
本市还应考虑哪些其他区来容纳不同类型的住房？	我不同意盖任房子给游民住。哪一位市议员要盖，就盖在这位议员的个人Property
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	意见同上
请告诉我们您在阿凯迪亚的住房经历。	在这件事以前满意
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	不建游民住所
Vision feedback	希望成为美丽治安安全的城市
Vision feedback	维持现状！反对增加任何可负担房屋！
您还有其他意见或建议吗？	维持现状！反对增加任何可负担房屋！
Vision feedback	维持现状！反对增加任何可负担房屋！
您还有其他意见或建议吗？	维持现状！反对增加任何可负担房屋！
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	学区，医院，治安，居住环境
Vision feedback	维持现状
您还有其他意见或建议吗？	居住转态保持原状

如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	优质的学区教育和安全的环境管理
请告诉我们您在阿凯迪亚的住房经历。	我现在住的是single house
Vision feedback	翻新老旧房屋，提高环境绿化，虫蚊灭杀，灭鼠需要加强
您还有其他意见或建议吗？	需要更多的环境绿化和蚊虫灭杀
本市还应该考虑其他哪些住房类型或想法？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应考虑哪些其他区来容纳不同类型的住房？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
请告诉我们您在阿凯迪亚的住房经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应该考虑其他哪些住房类型或想法？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应考虑哪些其他区来容纳不同类型的住房？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
请告诉我们您在阿凯迪亚的住房经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
General Comment	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	反对增加任何可负担房屋
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	维持现状
Vision feedback	维持现状，反对增加任何可负担房屋
您还有其他意见或建议吗？	反对Arcadia增加任何可负担房屋
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全
独户住宅	安全
多户住宅-公寓	安全
多户住宅-共管公寓/连栋住宅	安全
Vision feedback	安全
您还有其他意见或建议吗？	安全
Vision feedback	希望Arcadia能保持目前的住房开发模式，在这种成熟的社区已经没有地方开发可负担住宅。州政府应该在空置地区开开发新的住宅，而不是在成熟社区制造不必要的混乱，并且增加可负担住宅的的成本
Vision feedback	缺乏空地，不宜再大规模开发低端住宅
本市还应该考虑其他哪些住房类型或想法？	保持現狀
本市还应该考虑其他哪些住房类型或想法？	维持现状，反对增加任何可负担房屋
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状，反对增加任何可负担房屋
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋
本市还应该考虑其他哪些住房类型或想法？	维持现状，反对增加任何可负担房屋
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状，反对增加任何可负担房屋
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	维持现状，反对增加任何可负担房屋
Vision feedback	维持现状，反对增加任何可负担房屋
您还有其他意见或建议吗？	维持现状，反对增加任何可负担房屋
Vision feedback	包容低收入人群
本市还应考虑哪些其他区来容纳不同类型的住房？	維持現狀，反對affordable housing
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	維持現狀，反對affordable housing
本市还应该考虑其他哪些住房类型或想法？	維持現狀，反對affordable housing
请告诉我们您在阿凯迪亚的住房经历。	現狀最好
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	不要建造affordable housing
本市还应该考虑其他哪些住房类型或想法？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
Vision feedback	維持現狀，不要affordable housing,不要tiny house
本市还应考虑哪些其他区来容纳不同类型的住房？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
请告诉我们您在阿凯迪亚的住房经历。	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
Vision feedback	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
您还有其他意见或建议吗？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	反对任何扩建
Vision feedback	维持现状，不要做任何可负担房产的开发
本市还应该考虑其他哪些住房类型或想法？	维持现状，反对增加任何可负担房屋”
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状，反对增加任何可负担房屋”
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋”
请告诉我们您在阿凯迪亚的住房经历。	维持现状，反对增加任何可负担房屋”
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	维持现状，反对增加任何可负担房屋”
Vision feedback	维持现状，反对增加任何可负担房屋”
您还有其他意见或建议吗？	维持现状，反对增加任何可负担房屋”
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状
请告诉我们您在阿凯迪亚的住房经历。	维持现状

本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	不用改变 维持现状
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	规范社区管理
请告诉我们您在阿凯迪亚的住房经历。	一直住在house从未有所改变
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境绿化工作继续保持 社区治安可以得到提升
本市还应该考虑其他哪些住房类型或想法？	Arcadia应以独户永久为主，不应改变
本市还应该考虑其他哪些住房类型或想法？	坚决反对建游民小屋和低收入住宅，保护我们社区和学区的品质，维护治安
本市还应考虑哪些其他区来容纳不同类型的住房？	坚决反对游民小屋和低收入住宅
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维护治安
请告诉我们您在阿凯迪亚的住房经历。	我住亚市二十年了，对最近游民的涌入和治安问题深恶痛绝。请市议员们不要损害本市市民的利益。坚决反对建游民小屋和低收入住宅！
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	以前亚市安全宜居，希望继续维持下去。坚决反对建游民小屋和低收入住宅，请市议员们不要做让后代以你们为耻的事。谢谢！
独户住宅	保持亚市的高品质，坚决反对建游民小屋和低收入住房。而且多户住宅人口密度太高学校负担太重，高中已经人满为患
独户住宅	以高品质独户代替游民小屋
本市还应该考虑其他哪些住房类型或想法？	维持现状
Vision feedback	维持现状
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	保持独户住宅比例
Vision feedback	保持独立屋比例，这是Arcadia吸引人的地方
您还有其他意见或建议吗？	保持独户住宅比例
本市还应考虑哪些其他区来容纳不同类型的住房？	不需要建更多的住房单位
本市还应该考虑其他哪些住房类型或想法？	不需要
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	应维持现状
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境优美、购物方便、社区文化、居住安全
Vision feedback	维持现有的居住环境和社区安全，不应再开发多户住宅和混和用途住宅
本市还应该考虑其他哪些住房类型或想法？	坚决反对对本市建游民小屋和低收入住宅。我们许多人上班无法参加多次的市府会议，老年人们也无法参加反对游民会议，请市议员考虑到亚市的治安问题。
本市还应考虑哪些其他区来容纳不同类型的住房？	坚决反对建游民小屋和低收入住宅，维护治安
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	亚市高中已人满为患，再引进更多的人口，必将降低学区的品质
请告诉我们您在阿凯迪亚的住房经历。	我全家住在亞市二十年了，喜歡本市的安全舒適，高品质的学区。希望市議員們為子孫後代著想，不要建遊民小屋和低收入住宅。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	坚信市长和市议员们会考虑本市利益，不会做伤害亚市治安和亚市学区的事。坚决反对建游民小屋和低收入住宅
独户住宅	独户住宅品质高，不会降低亚市的品质
	我们住亚市二十年了，坚决反对建游民小屋和低收入住宅。上班人士和老年人大部分无法参加市府会议，请市长和和议员们不要做违背亚市治安和降低学区品质的事，不要为了一时利益做出伤害子孙后代的
Vision feedback	事。
请告诉我们您在阿凯迪亚的住房经历。	从我移民到美国，就一直住在这里，有27年了。我喜欢它美丽、干净、安全，但如今随着加州非法移民的增多，安全隐患倍增，这是我们最不愿意看到的而且是影响我们是否继续居住在此的最最大
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	教育，环境，安全
本市还应该考虑其他哪些住房类型或想法？	保留現狀
本市还应考虑哪些其他区来容纳不同类型的住房？	本市沒有地方適合
请告诉我们您在阿凯迪亚的住房经历。	我們住在 Arcadia 9年，眼見治安越來越差。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	環境優美，生活方便。
Vision feedback	更少的商业更少的混合住宅
本市还应该考虑其他哪些住房类型或想法？	維持現狀
本市还应考虑哪些其他区来容纳不同类型的住房？	維持現狀 不要改變
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	維持現狀
请告诉我们您在阿凯迪亚的住房经历。	2009购房搬入，至今还在居
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全安静购物方便
独户住宅	方.快捷
独户住宅	购物方便
独户住宅	上学
Vision feedback	希望保持现状维持原样
您还有其他意见或建议吗？	希望在Arcadia居住人才有资格参加新建住房的问卷表决权，这样才是真正尊重和听到在这块土地居住者声音。
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您是拥有自己的住房还是租房？	租房
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	否
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅

您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	单人房住宅
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住和工作
你属于哪一个年龄段？	56 – 74岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	多户住宅 - 公寓
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	56 – 74岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 公寓
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅

本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	否
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	多户住宅 - 公寓
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅

您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	单人房住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区

在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	56 – 74岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	56 – 74岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	单人房住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	56 – 74岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅

哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
您想继续住在阿凯迪亚吗？	是
你属于哪一个年龄段？	25岁以下
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁

您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
您在阿凯迪亚居住或工作吗？	居住和工作
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅

哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
您想继续住在阿凯迪亚吗？	不一定
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
您想继续住在阿凯迪亚吗？	不一定
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您想继续住在阿凯迪亚吗？	是
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
您在阿凯迪亚居住或工作吗？	居住
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
你属于哪一个年龄段？	56 – 74岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
您希望您的下一套住房是哪种类型的住房？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	否
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅

您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
您希望您的下一套住房是哪种类型的住房？	独户住宅
你属于哪一个年龄段？	40 - 55岁
您想继续住在阿凯迪亚吗？	是
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
您希望您的下一套住房是哪种类型的住房？	独户住宅
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅

您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您想继续住在阿凯迪亚吗？	不一定
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区

您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住和工作
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住和工作
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
您希望您的下一套住房是哪种类型的住房？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅

您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	多户住宅 - 公寓
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您在阿凯迪亚居住或工作吗？	居住和工作
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	不一定
您希望您的下一套住房是哪种类型的住房？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅

您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	26 - 39岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	56 – 74岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区

本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	否
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	单人房住宅
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足

在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	否
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是

哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
哪种住房类别最能满足未来的可负担需求？	单人房住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	单人房住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区

[illegible]

您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
您想继续住在阿凯迪亚吗？	不一定
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您想继续住在阿凯迪亚吗？	是
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是

哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	否
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	住房类型不全面
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区

在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	市政府提供的住房计划/支持不足
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
哪种住房类别最能满足未来的可负担需求？	过渡性和辅助性住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 公寓
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅

哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
您想继续住在阿凯迪亚吗？	是
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
您想继续住在阿凯迪亚吗？	不一定
您希望您的下一套住房是哪种类型的住房？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
哪种住房类别最能满足未来的可负担需求？	老年住宅
哪种住房类别最能满足未来的可负担需求？	附属住宅单元
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅

本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	新建住房不足
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	混合用途住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
哪种住房类别最能满足未来的可负担需求？	多户住宅 - 共管公寓/连栋住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少低收入家庭（四口之家的收入不到61,840美元）可负担的住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	是
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	缺少老年住宅
哪种住房类别最能满足未来的可负担需求？	独户住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	商业区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	混合用途区
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	多户住宅区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
您想继续住在阿凯迪亚吗？	不一定
哪种住房类别最能满足未来的可负担需求？	独户住宅
哪种住房类别最能满足未来的可负担需求？	老年住宅
本市可能需要考虑改变某些地块的区划，以容纳更多的住房单位。哪些类型的区最适合建造这些住房？	靠近公交车站的区
在更新新建住房比例时，阿凯迪亚市应考虑哪些最紧迫的住房相关问题？	有关住房机会的信息不足
您希望您的下一套住房是哪种类型的住房？	独户住宅
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	保持现在的住房类型和和平环境是支持我在这里居住的动力。如过增加不必要的游民设施，我会考虑搬离阿凯迪亚。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	Yes
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	平和的阿凯迪亚社区环境
本市还应考虑哪些其他区来容纳不同类型的住房？	no need this kind of housing
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	current situation is fine
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	SAFE AND SCHOOL
本市还应该考虑其他哪些住房类型或想法？	封闭管理的独栋house.
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全
请告诉我们您在阿凯迪亚的住房经历。	租房一年，买到独立屋，目前还比较满意
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境优美、生活配套齐全
请告诉我们您在阿凯迪亚的住房经历。	住在孔雀园
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	方便，安全，教育
本市还应该考虑其他哪些住房类型或想法？	不应该考虑
请告诉我们您在阿凯迪亚的住房经历。	独立住宅，非常好
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	独立住宅最好
请告诉我们您在阿凯迪亚的住房经历。	独立的房子
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	良好的环境，优秀的高中
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	生活便利、各种设施齐全
请告诉我们您在阿凯迪亚的住房经历。	很好
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	请考虑停车位和交通堵塞问题
本市还应该考虑其他哪些住房类型或想法？	在建房同时请考虑让社区变得更好，更安全
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	學區
请告诉我们您在阿凯迪亚的住房经历。	Condo median 如有少量能够重重花草的地就更好。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全、方便。
本市还应该考虑其他哪些住房类型或想法？	反對建可負擔住房在Arcadia
请告诉我们您在阿凯迪亚的住房经历。	I live a single house that I own
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	nice neighborhood but I do not want the city tobuild 3000 plus house to accomodate possible another 12000 peoples that will crowd our school and streets
请告诉我们您在阿凯迪亚的住房经历。	獨立住宅
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	習慣周邊生活機能
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	方便，生活配套齊全。
请告诉我们您在阿凯迪亚的住房经历。	位置方便，但房子老舊，街道停車位少。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	新建公寓太多，但街道缺少停車位。
本市还应考虑哪些其他区来容纳不同类型的住房？	不接受建在Arcadia Par 3 Golf , Las tunas 附近
请告诉我们您在阿凯迪亚的住房经历。	獨戶住宅

	1. 没有建tiny house收容無家可歸的人,請市府保護我們的安全及平靜,而且我最担心是他們萬一傷人， city主辦tiny house萬一連帶被告， 高額賠償金， 令人擔憂， 又不是高中生， 隨口說支持， 作保證人和幫助人是二回事。 2. Affordable house 没有蓋在南區, 而且還要蓋那麼多這種事。 3. 希望 city 是保護市民的.
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	We own our SFH since 2010
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Not so crowded
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	Safety
	Too many homeless around
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 本市还应该考虑其他哪些住房类型或想法？	Safe environment We need more single new houses.
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Good environment ,good neighbors hood and convenience.
	Owning three and renting out one, keep apartments and condos out of Arcadia, we are a city of pride and prestige, anyone wants to propose apartmentsand affordable housing, please make sure to publicize your Arcadia residency so to avoid any distribution of hypocrisy.
请告诉我们您在阿凯迪亚的住房经历。	True pride of a Arcadia resident
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	在此已住近四十年兒女都已成家， 我們已經退休， 還是想要住在Arcadia
	学区好
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	地大人少
	自住独栋
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	安全便利
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 本市还应该考虑其他哪些住房类型或想法？	安全！环境好！邻居很好！没有太多的游民及低收入者！人文环境很好！
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	Single house
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 本市还应该考虑其他哪些住房类型或想法？	多建独立屋或商住两用
本市还应考虑哪些其他区来容纳不同类型的住房？	安全的环境好的学区，友好的邻里关系
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	Arcadia 应永久以独户为主，这不应该被改变。
请告诉我们您在阿凯迪亚的住房经历。	Arcadia 需要控制人口数量， 而不是无限制的去更改地块用途。不同意更改原地区区划
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	Arcadia 可在现状上新建、翻建、改建，不可以无限制扩大建设
	独户
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	富人区， 环境面貌好，城市安全
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	20年搬到arcadia.贷款买房，为了孩子上学和一个安全的居住环境
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	如果arcadia变成一个什么收入都可以搬进来的社区，而不是通过努力工作挣钱交高额地税和消费税，有限的学区资源源却能共享，那会考虑搬走
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	Rent
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	房价便宜点
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	医院，学区， 安静的居住环境
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 本市还应该考虑其他哪些住房类型或想法？	安全， 美丽，体面邻居、中产社区
本市还应该考虑其他哪些住房类型或想法？	请不要
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	不需要更多住房单位
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	不需要改变
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	美丽环境，安全，体面邻居
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	我在Arcadia住town house 20年了
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	环境好，学区好
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	环境
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	环境好，治安好
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	阿凯迪亚市是一个环境好，整洁干净，相对安全的区域。在这里养育孩子会比较有安全感。另外出门购物吃饭很方便
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 本市还应该考虑其他哪些住房类型或想法？	环境好，整洁干净，安全
本市还应该考虑其他哪些住房类型或想法？	暫没有必要
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状就可以，土地资源有限
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	目前的居住环境
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状。
请告诉我们您在阿凯迪亚的住房经历。	维持现状。
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	维持现状。
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	维持现状。
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	学区
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	维持现状。
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	整个社区的环境
本市还应该考虑其他哪些住房类型或想法？	因为市政府的总总举措，一直在担心房价下跌，惴惴不安
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	不需要
请告诉我们您在阿凯迪亚的住房经历。	不需要
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	市府房屋計劃單位規定比臨市的天普市要求多出許多，使得亞市居民的負擔多過臨近城市。比如在對中小企業的規定上……增加許多額外的負擔
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？ 请告诉我们您在阿凯迪亚的住房经历。	请保持现状
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	好学区， 安全的环境
本市还应考虑哪些其他区来容纳不同类型的住房？	社区安全 干净环境
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	请保持目前的住房数量，不要改变地块的区划， Arcadia目前已经有很多住房单位了。
请告诉我们您在阿凯迪亚的住房经历。	Arcadia是个小城市，目前的警力、消防不足以再增加住宅单位。请保持现状！
如果您回答“是”， 什么会鼓励或支持您在阿凯迪亚居住？	Arcadia南边有很多condo房子的居住地人口稠密，而Huntington Dr. 北部人口相对稀少。
本市还应该考虑其他哪些住房类型或想法？	好的学区、环境、治安、交通、餐饮、购物、娱乐等等
	我不同意在Arcadia 盖任何房屋给游民住。

本市还应考虑哪些其他区来容纳不同类型的住房？	我不同意盖任房子给游民住。哪一位市议员要盖，就盖在这位议员的个人Property
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	意见同上
请告诉我们您在阿凯迪亚的住房经历。	在这件事以前满意
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	不建游民住所
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	学区，医院，治安，居住环境
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	优质的学区教育和安全的环境管理
请告诉我们您在阿凯迪亚的住房经历。	我现在住的是single house
本市还应该考虑其他哪些住房类型或想法？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应考虑哪些其他区来容纳不同类型的住房？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
请告诉我们您在阿凯迪亚的住房经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应该考虑其他哪些住房类型或想法？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应考虑哪些其他区来容纳不同类型的住房？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
请告诉我们您在阿凯迪亚的住房经历。	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
General Comment	亚凯迪亚不需要再新建任何种类的位宅了，已经太拥挤了！市政府官员应该向San Marino市学习才能维护本市以往的美好，现在本市每况日下，令人担忧。
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	反对增加任何可负担房屋
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	维持现状
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全
本市还应该考虑其他哪些住房类型或想法？	保持現狀
本市还应该考虑其他哪些住房类型或想法？	维持现状，反对增加任何可负担房屋
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状，反对增加任何可负担房屋
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋
本市还应该考虑其他哪些住房类型或想法？	维持现状，反对增加任何可负担房屋
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状，反对增加任何可负担房屋
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	维持现状，反对增加任何可负担房屋
本市还应考虑哪些其他区来容纳不同类型的住房？	維持現狀， 反對affordable housing
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	維持現狀， 反對affordable housing
本市还应该考虑其他哪些住房类型或想法？	維持現狀， 反對affordable housing
请告诉我们您在阿凯迪亚的住房经历。	現狀最好
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	不要建造affordable housing
本市还应该考虑其他哪些住房类型或想法？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
本市还应考虑哪些其他区来容纳不同类型的住房？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
请告诉我们您在阿凯迪亚的住房经历。	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	反对任何扩建
本市还应该考虑其他哪些住房类型或想法？	维持现状，反对增加任何可负担房屋”
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状，反对增加任何可负担房屋”
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维持现状，反对增加任何可负担房屋”
请告诉我们您在阿凯迪亚的住房经历。	维持现状，反对增加任何可负担房屋”
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	维持现状，反对增加任何可负担房屋”
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	维持现状
请告诉我们您在阿凯迪亚的住房经历。	维持现状
本市还应该考虑其他哪些住房类型或想法？	维持现状
本市还应考虑哪些其他区来容纳不同类型的住房？	不用改变 维持现状
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	规范社区管理
请告诉我们您在阿凯迪亚的住房经历。	一直住在house从未有所改变
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境绿化工作继续保持 社区治安可以得到提升
本市还应该考虑其他哪些住房类型或想法？	Arcadia应以独户永久为主，不应改变
本市还应考虑其他哪些住房类型或想法？	坚决反对建游民小屋和低收入住宅，保护我们社区和学区的品质，维护治安
本市还应考虑哪些其他区来容纳不同类型的住房？	坚决反对游民小屋和低收入住宅
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	维护治安
请告诉我们您在阿凯迪亚的住房经历。	我住亚市二十年了，对最近游民的涌入和治安问题深恶痛绝。请市议员们不要损害本市市民的利益。坚决反对建游民小屋和低收入住宅！
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	以前亚市安全安居，希望继续维持下去。坚决反对建游民小屋和低收入住宅，请市议员们不要做让后代以你们为耻的事。谢谢！
本市还应该考虑其他哪些住房类型或想法？	维持现状
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	保持独户住宅比例
本市还应考虑哪些其他区来容纳不同类型的住房？	不需要建更多的住房单位
本市还应该考虑其他哪些住房类型或想法？	不需要
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	应维持现状

如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	环境优美、购物方便、社区文化、居住安全
本市还应该考虑其他哪些住房类型或想法？	坚决反对本市建游民小屋和低收入住宅。我们许多人上班无法参加多次的市府会议，老年人们也无法参加反对游民会议，请市议员考虑到亚市的治安问题。
本市还应考虑哪些其他区来容纳不同类型的住房？	坚决反对建游民小屋和低收入住宅，维护治安
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	亚市高中已人满为患，再引进更多的人口，必将降低学区的品质
请告诉我们您在阿凯迪亚的住房经历。	我全家住在亞市二十年了，喜歡本市的安全舒適，高品质的学区。希望市議員們為子孫後代著想，不要建遊民小屋和低收入住宅。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	坚信市长和市议员们会考虑本市利益，不会做伤害亚市治安和亚市学区的事。坚决反对建游民小屋和低收入住宅
请告诉我们您在阿凯迪亚的住房经历。	从我移民到美国，就一直住在这里，有27年了。我喜欢它美丽、干净、安全，但如今随着加州非法移民的增多，安全隐患倍增，这是我们最不愿意看到的而且是影响我们是否继续居住在此的最最大
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	教育，环境，安全
本市还应该考虑其他哪些住房类型或想法？	保留現狀
本市还应考虑哪些其他区来容纳不同类型的住房？	本市沒有地方適合
请告诉我们您在阿凯迪亚的住房经历。	我們住在 Arcadia 9年，眼見治安越來越差。
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	環境優美，生活方便。
本市还应该考虑其他哪些住房类型或想法？	維持現狀
本市还应考虑哪些其他区来容纳不同类型的住房？	維持現狀 不要改變
在住房方面阿凯迪亚是否还面临其他挑战？请分享您的想法和经历。	維持現狀
请告诉我们您在阿凯迪亚的住房经历。	2009购房搬入，至今还在居
如果您回答“是”，什么会鼓励或支持您在阿凯迪亚居住？	安全安静购物方便
多户住宅-共管公寓/连栋住宅	交通便利
混合用途住宅	交通便利
多户住宅-公寓	激活促进地域商业。
混合用途住宅	有空地吧
多户住宅-公寓	有空地吧
独户住宅	安静
混合用途住宅	热闹
独户住宅	安静
混合用途住宅	土地成本不高
独户住宅	环境好
多户住宅-公寓	离商业区近，生活便利
独户住宅	因为这里有地。
多户住宅-共管公寓/连栋住宅	有空地使用
多户住宅-共管公寓/连栋住宅	商铺可变成商住混合
混合用途住宅	商铺可变成商住混合
独户住宅	SFH only
独户住宅	SFH only
独户住宅	SFH only
独户住宅	方便
独户住宅	可以有更多选择
独户住宅	更多选择
多户住宅-共管公寓/连栋住宅	有需求
多户住宅-公寓	这里有需求
独户住宅	环境好安静
多户住宅-公寓	可以解决很多人居住的问题
多户住宅-共管公寓/连栋住宅	适合
混合用途住宅	适合
多户住宅-公寓	Close to bus station
混合用途住宅	Close to bus station
多户住宅-公寓	Close to bus station
多户住宅-公寓	离地铁站近，适合年轻上班族
混合用途住宅	商业延伸，对城市收入，居民生活便利
独户住宅	环境优美
多户住宅-共管公寓/连栋住宅	靠近高速路
多户住宅-共管公寓/连栋住宅	这里都是独栋住宅，需要混合住在比例。
多户住宅-共管公寓/连栋住宅	靠近高速公路购物中心。
General Comment	请保持现状
多户住宅-共管公寓/连栋住宅	这里人口相对较少
多户住宅-共管公寓/连栋住宅	这里人口相对较少
多户住宅-共管公寓/连栋住宅	这里人口相对较少
独户住宅	安全
多户住宅-公寓	安全
多户住宅-共管公寓/连栋住宅	安全
独户住宅	保持亚市的高品质，坚决反对建游民小屋和低收入住房。而且多户住宅人口密度太高学校负担太重，高中已经人满为患
独户住宅	以高品质独户代替游民小屋
独户住宅	独户住宅品质高，不会降低亚市的品质
独户住宅	方.快捷
独户住宅	购物方便
独户住宅	上学
Vision feedback	请不要开发游民设施在阿凯迪亚，这只是某些议员的政治考量而不是环境及经济发展考量。不必要的游民设施只会会摧毁现有的阿凯迪亚平和环境，现有居民的压力已经到了极限。
Vision feedback	请不要以政治正确及某些议员的私利目的来设立游民设施。
Vision feedback	保留原有的特色，安静，安全，而不是过多的流浪汉

Vision feedback	希望向San Marino学习，尽量少开发，维护优美的城市环境
Vision feedback	希望有更多符合中产阶级的房子，带游泳池最好。现在的房价太贵了！！！
Vision feedback	尽量少开发低收入住房，保证安全。
Vision feedback	就应该持续只发展独立住宅
Vision feedback	环境优美的独立屋能够提升城市安全性
Vision feedback	请不要过度开发，希望政府尽力为下一代保留一个美丽宁静安全祥和的阿凯迪亚。
Vision feedback	希望能建造一些管理良好的老人公寓
Vision feedback	Increase the FAR
Vision feedback	SFH only. No low income housing. No shelter
Vision feedback	To create a safe environment and better community
Vision feedback	We need build more single home not low income house.
Vision feedback	We need build more single house instead of lowincome houses.
Vision feedback	Keep apartments, condos, Tiny Shelters out of Arcadia, we are a city of pride and prestige, anyone wants to propose and affordable housing or TinyHomes, please make sure to publicize your Arcadia residency so to avoid any distribution of hypocrisy.
Vision feedback	保持本区域住房及人口类型的特点，更加安心地住在本市。
Vision feedback	希望Arcadia这个城市依然保持它的美好！不需要建很多住房！人口太多地域不够宽广会引起脏、乱、差！同时也为市市政府的管理减轻一些负担！
Vision feedback	Arcadia 属于富人区的现状不应被改变，在Arcadia 居住的门槛不应该被降低，懒惰的人，不务正业的人没有资格享有甚至破坏勤劳努力的人带来的资源、环境。Arcadia 的城市安全必须得到保证！
Vision feedback	Need to pay attention to the needs of existingresidents. They have paid property taxes and have the right to join to determine their future living environment.
Vision feedback	多建些affordable condos
Vision feedback	如果阿卡迪亚建立很多低收入住房，治安会变差
Vision feedback	多盖town house
Vision feedback	维持现状。
Vision feedback	对于整个城市的安全表示担忧。
Vision feedback	安全、整潔、規範的社區是我們所有市民的訴求
Vision feedback	Arcadia是个不大的城市，请保持现状，不要再改变zoning来增加住宅单位了！
Vision feedback	希望成为美丽治安安全的城市
Vision feedback	维持现状！反对增加任何可负担房屋！
Vision feedback	维持现状！反对增加任何可负担房屋！
Vision feedback	维持现状
Vision feedback	翻新老旧房屋，提高环境绿化，虫蚊灭杀，灭鼠需要加强
Vision feedback	维持现状，反对增加任何可负担房屋
Vision feedback	安全
Vision feedback	希望Arcadia能保持目前的住房开发模式，在这种成熟的社区已经没有地方开发可负担住宅。州政府应该在空置地区开开发新的住宅，而不是在成熟社区制造不必要的混乱，并且增加可负担住宅的的成本
Vision feedback	缺乏空地，不宜再大规模开发低端住宅
Vision feedback	维持现状，反对增加任何可负担房屋
Vision feedback	包容低收入人群
Vision feedback	維持現狀，不要affordable housing,不要tiny house
Vision feedback	“维持现状”，“反对增加任何可负担房屋”“坚决反对affortable housing”
Vision feedback	维持现状，不要做任何可负担房产的开发
Vision feedback	维持现状，反对增加任何可负担房屋”
Vision feedback	维持现状
Vision feedback	保持独立屋比例，这是Arcadia吸引人的地方
Vision feedback	维持现有的居住环境和社区安全，不应再开发多户住宅和混和用途住宅
Vision feedback	我们住亚市二十年了，坚决反对建游民小屋和低收入住宅。上班人士和老年人大部分无法参加市府会议，请市长和和议员们不要做违背亚市治安和降低学区品质的事，不要为了一时利益做出伤害子孙后代的事。
Vision feedback	更少的商业更少的混合住宅
Vision feedback	希望保持现状维持原样
Vision feedback	居住
Vision feedback	40 - 55岁
Vision feedback	独户住宅
Vision feedback	独户住宅
Vision feedback	租房
Vision feedback	居住
Vision feedback	40 - 55岁
Vision feedback	租房
Vision feedback	独户住宅
Vision feedback	多户住宅·共管公寓/连栋住宅
Vision feedback	居住
Vision feedback	拥有自己的住房
Vision feedback	独户住宅
Vision feedback	居住和工作
Vision feedback	56 – 74岁
Vision feedback	租房
Vision feedback	多户住宅·公寓
Vision feedback	多户住宅·共管公寓/连栋住宅
Vision feedback	居住
Vision feedback	40 - 55岁
Vision feedback	拥有自己的住房

[illegible]

[illegible]

[illegible]

[illegible]

你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	租房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您在阿凯迪亚居住或工作吗？	居住
你属于哪一个年龄段？	40 - 55岁
您是拥有自己的住房还是租房？	拥有自己的住房
以下哪一项最能描述您目前的住所？	独户住宅
您希望您的下一套住房是哪种类型的住房？	独户住宅
您还有其他意见或建议吗？	平和的阿凯迪亚不需要以政治正确为目的而设立所谓的外来游民设施。请优先考虑阿凯迪亚本身居民的真实需求而而不是成为某些议员做秀的议题。
您还有其他意见或建议吗？	There are to many new big houses in small lot
您还有其他意见或建议吗？	最好只修独立住宅
您还有其他意见或建议吗？	增强城市的安全性，提升城市形象
您还有其他意见或建议吗？	do not want the city to build 3000 plus unit .outragious idea
您还有其他意见或建议吗？	不贊成建那麼多affordable houseI, 也請市府先告訴我們， 建這些affordable house會影響我們什麼？
您还有其他意见或建议吗？	No tiny shelter
您还有其他意见或建议吗？	No more Low Income house should be built in Arcadia
您还有其他意见或建议吗？	No low income housing. No homeless shelter. Nohomeless service hub
您还有其他意见或建议吗？	I don't want low income housing in arcadia.
您还有其他意见或建议吗？	Can not build low income house in our city'scause it will low grade our estates value .
您还有其他意见或建议吗？	We can not build low income houses that will down grade our city.
您还有其他意见或建议吗？	Keep apartments, condos, Tiny Shelters out ofArcadia, we are a city of pride and prestige, anyone wants to propose and affordable housing or TinyHomes, please make sure to publicize your Arcadia residency so to avoid any distribution of hypocrisy.
您还有其他意见或建议吗？	不要建造很多公寓及住房！依然保持这个城市的美好与宁静！！！
您还有其他意见或建议吗？	Arcadia 必须以独户为主，如果市政府不能保护这个城市的环境、安全，引入过多低收入人群甚至无收入人群的入驻，将会导致城市档次下降，房价暴跌，富人离开，任何会毁掉Arcadia
您还有其他意见或建议吗？	的决策，都会让市政府成员罪名永载Arcadia 历史。
您还有其他意见或建议吗？	维持社区目前房屋类型构成现状，坚决反对增加任何可负担住宅
您还有其他意见或建议吗？	希望政府能打造一个安全，整洁的城市环境。本城市有很多养育孩子的家庭，安全是大家的重中之重。现在整体加加州治安下降非常厉害。请政府有所作为！
您还有其他意见或建议吗？	土地资源有限，维持现状就是对人们最好的保护
您还有其他意见或建议吗？	维持现状。
您还有其他意见或建议吗？	希望是政府加强城市的安全保护措施。
您还有其他意见或建议吗？	保持现有的住宅单位，不要再增加。搞好城市治安是目前最重要的事情！
您还有其他意见或建议吗？	维持现状！反对增加任何可负担房屋！
您还有其他意见或建议吗？	维持现状！反对增加任何可负担房屋！
您还有其他意见或建议吗？	居住转态保持原状
您还有其他意见或建议吗？	需要更多的环境绿化和蚊虫灭杀
您还有其他意见或建议吗？	反对Arcadia增加任何可负担房屋
您还有其他意见或建议吗？	安全
您还有其他意见或建议吗？	维持现状，反对增加任何可负担房屋
您还有其他意见或建议吗？	“维持现状”，“反对增加任何可负担房屋”“坚决反对affordable housing”
您还有其他意见或建议吗？	维持现状，反对增加任何可负担房屋”
您还有其他意见或建议吗？	保持独户住宅比例
您还有其他意见或建议吗？	希望在Arcadia居住人才有资格参加新建住房的问卷表决权，这样才是真正尊重和听到在这块土地居住者声音。



CITY OF ARCADIA 6TH CYCLE Housing Element Update

4. Community Workshop #2

This section contains the PowerPoint presentation shown at the Community Workshop.


The City held a Community Workshop on September 23, 2021. During the workshop, the project team provided a presentation with an overview of the Housing Element and the process to date. Workshop attendees were given the option of a live Chinese translation and a recording of the presentation was made available on the City website in both English and Chinese. Residents were also presented with information about how the City planned to achieve its RHNA. Community members had the opportunity to give public comments and respond to questions during the presentation. In total, 65 community members were in attendance.



1



2



3




4



5



6



7




8



9



10



11

Arcadia 6th Cycle RHNA

Income Category	% of Median Family Income	Annual Income Range ¹		RHNA Allocation (Housing Units)
		Min.	Max.	
Very Low Income	0 - 50% MFI	--	\$38,650	1,102 units
Low Income	51 - 80% MFI	\$38,651	\$61,840	570 units
Moderate Income	81 - 120% MFI	\$61,841	\$92,760	605 units
Above Moderate Income	>120% MFI	\$92,761	--	937 units
Total:				3,214 units

¹Each income category (defined as a range of household incomes that represents a percentage of the Median Family Income (MFI). The MFI for a family of four in Los Angeles County is \$77,300.

2021-2029 Housing Element Update

12



13



14

Community Engagement

FAQ sheet is posted on the [City Website](#)

Community Workshop #1 (Virtual)

- Overview of Housing Element Update process
 - The Community's RHNA
- **Community Survey**
 - Housing Challenges & Needs
 - Housing Opportunity Programs
 - Potential Housing Areas
 - General Demographic Information

2021-2029 Housing Element Update

15




16

Online Community Survey Common Themes

- Leave Established Single-Family Neighborhoods intact/Minimize changes to these areas;
- Primary Challenges identified include a shortage of senior housing and affordable housing for low income;
- Housing Growth to be concentrated in zones near transit, Mixed use areas, and in multi-family areas (evenly mixed opinions).

2021-2029 Housing Element Update

17




18



19




20



21



22



23

Baseline Analysis Summary Table:

	Very Low Income 2,127	Low Income 275	Moderate Income 505	Above Moderate Income 937
ADU (2021-2029)	28	80	292	
Baseline Capacity				
Existing Residential Zoned Land	215	112	764	
Accessory Dwelling Unit Production	239	8	104	
Total Capacity	480	200	1,865	


24




25




26




27




28




29



30



31




32

Strategy 7: Summary Table

	Very Low Income	Low Income	Moderate Income	Above Moderate Income
RHNA (2023-2029)	1,100	570	405	572
Baseline: R-3 Upzone, Existing Residential (ADJ)	480	200	1,865	
Downstream Mixed Use	540	202	1,757	
Mixed-Use Upzone	560	194	965	
Live Oak Residential Flex	124	118	762	
C-G Residential Flex	108	100	694	
R-3 Upzone	142	70	470	
Arcadia Golf Course	48	72	72	
Reszone Strategies	1,214	747	4,740	
Total Potential Development Capacity	1,084	947	6,605	
Stakeholder Surveys/Shortfall	22	342	5,668	
Percentage Buffer	1%	56%	605%	

33



34

Q&A Instructions

Question to Consider
 Considering these strategies, where are there additional opportunities within Arcadia to accommodate the RHNA?

35



36



2021 2028 Housing Element Update

Thank you!

Questions?

Please Contact
Planning Services
(626) 574-5423
Planning@ArcadiaCA.gov

Or Visit the City's webpage at, www.ArcadiaCA.gov/housing





1



2




3



4



5



6



7



8



9

什么是RHNA?

- 新建住房比例更新过程的基础
- 预测州、区域和地方各级的住房增长
- 根据加利福尼亚州每个县和市的不同收入类别量化住房需求
- 基于当前和预计的人口、就业和家庭增长

10

如何确定RHNA分配?

住房和社区发展部 (HCD) → 南加州政府协会 (SACOG) → 阿凯迪亚市 RHNA 2021-2029: 3,214套住房

11

阿凯迪亚第6⁺RHNA周期

收入类别	占家庭总收入 (MFI) 百分比	年收入范围*		RHNA分配 (住房单元)
		最低	最高	
低收入	0 - 50% MFI	...	\$38,650	1,302套住房
中低收入	51 - 80% MFI	\$38,651	\$41,840	570套住房
中等收入	81 - 120% MFI	\$41,841	\$92,760	605套住房
较高收入	>120% MFI	\$92,761	...	537套住房
总计:				3,214套住房

*每个收入类别均定义为家庭收入范围，显示为与家庭年收入 (MFI) 的百分比。一个四口之家在洛杉矶县的家庭MFI为\$50,000。

12

我们目前处于该过程的哪个阶段?

- 2020年1月: 启动
- 2021年2月: 社区参与
- 2021年3月: 社区参与
- 2021年4月: 社区参与
- 2021年5月: 社区参与
- 2021年6月: 社区参与
- 2021年7月: 社区参与
- 2021年8月: 社区参与
- 2021年9月: 社区参与
- 2021年10月: 社区参与
- 2021年11月: 社区参与
- 2021年12月: 社区参与
- 2022年1月: 社区参与
- 2022年2月: 社区参与
- 2022年3月: 社区参与
- 2022年4月: 社区参与
- 2022年5月: 社区参与
- 2022年6月: 社区参与
- 2022年7月: 社区参与
- 2022年8月: 社区参与
- 2022年9月: 社区参与
- 2022年10月: 社区参与
- 2022年11月: 社区参与
- 2022年12月: 社区参与

13

社区参与

14

社区参与

常见问题表载于[市政府网站](#)

社区讲习班1期 (在线)

- 新建住房比例更新过程简介
- 社区的区域住房需求评估 (RHNA)

• 社区资源

- 住房挑战和需求
- 住房机会计划
- 可能的住房开发区
- 总居住信息

15

在线社区调查

调查时间: 2021年6月14日至6月15日, 总共720名参与者

616名英语参与者, 143名中文参与者

16

在线社区调查常见主题

- 保持现有单户住宅区完好无损/尽量减少对这些区域的更改;
- 确定的主要挑战包括老年人住房和低收入经适房短缺;
- 住房增长将集中在靠近公共交通的区域、混合使用区和多户住宅区 (各种意见的支持率大致相同)。

17

在线社区调查地图标记活动

- 将住宅集中在市中心区, 沿N Santa Anita Ave., 靠近区域交通枢纽
- 将住宅集中在Live Oak南区和First Avenue沿线的混合用途区

18



19



20



21



22




23



24



25



26



27



28



29



30



31



32


2021-2022 年基础设施项目利益相关者信息

	低收入	低收入	中等收入	低收入
RMMA (2021-2022)	5,700	570	605	857
低收入总计 (未来, 现有住宅ADU项目)	480	200	1,805	
低收入项目策略				
市中心区域开发	540	150	1,575	
低收入项目策略	160	134	965	
Live Oak项目策略	124	118	792	
低收入项目策略	108	100	694	
低收入项目策略	142	75	470	
阿凯迪亚高尔夫球场	48	72	72	
低收入项目策略	1,214	947	4,740	
低收入项目策略	5,084	947	6,005	
低收入项目策略	22	142	5,648	
低收入项目策略	1%	56%	605%	

33



34



35



36





CITY OF ARCADIA 6TH CYCLE Housing Element Update

5. Social Media and City Publications

Through the planning process, the City posted information related to the Housing Element update in the City's Spring and Summer newsletters, five monthly "Hot Sheet" publications, as well as various social media channels such as Twitter and WeChat. This section contains snippets of the distribution of materials related to the Housing Element through the newsletters and social media channels. The section also provides a summary of social media posts made from June 2021 through the end of October 2021.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

The City of Arcadia has a strong online, social media presence and often connects with residents through their multiple twitter accounts. Included in this section are examples of tweets that the City distributed to its residents in order to share information about events associated with the Housing Element Update.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

← Tweet



Shape Arcadia
@ShapeArcadia

The Housing Update Virtual Workshop is LIVE! Join via Zoom: kimley-horn.zoom.us/j/99512156792 | Join by telephone, at +1 (669) 900-6833 or +1 (253) 215-8782 and enter Webinar ID: 995 1215 6792. 🏠

HOUSING ELEMENT UPDATE VIRTUAL WORKSHOP

Thursday, September 23, 2021
6:00 p.m.

What is the "RHNA"?

State law provides a target for how many homes each region and city must plan for, based on current population, proximity to public transit and jobs, and expected population growth, etc. Called the Regional Housing Needs Allocation or RHNA (pronounced 'ree-nah'), Arcadia must plan for new housing based on these targets.

Let's talk housing! Arcadia is a great place to live, but throughout the region there is a shortage of homes that impacts all of us. That's why now is the time to plan together for current and future housing needs in our community.

Join us virtually for the Housing Element Update Workshop on **Thursday, September 23, 2021 at 6:00 p.m.** where participants will hear how and where the City can accommodate additional housing over the next eight years and be able to provide feedback on options and strategies.

We hope that you can join us!

Please visit the City's website at ArcadiaCA.gov/housing to view additional information and see the results of the **Community Housing Survey!**

**Questions?
Contact Us!**

Development Services Department
Planning Services
(626) 574-5423
Planning@ArcadiaCA.gov
ArcadiaCA.gov/housing

Workshop Information:

Date: Thursday, September 23, 2021
Time: 6:00 p.m.
To join via Zoom, go to: <https://kimley-horn.zoom.us/j/99512156792>
To join by telephone, please call +1 (669) 900-6833 or +1 (253) 215-8782 and enter the Webinar ID
Webinar ID: 995 1215 6792

6:00 PM · Sep 23, 2021 · Twitter Web App



8 tweets total about community workshop 2



CITY OF ARCADIA 6TH CYCLE Housing Element Update



10 tweets total about community survey



Housing Element Update: Social Media Summary

Total Posts on City's Social Media Platforms:

Twitter: 22

Facebook: 18

WeChat (Posts translated into Simplified Chinese): 10

Nextdoor: 15

Definitions

Impressions = Number of times people saw Tweet on Twitter

Engagements = Number of times people interacted with the Tweet (e.g., link clicks)

Housing Element Update Community Survey Posts				
	Twitter	Facebook	WeChat	Nextdoor
6/14	Posted <i>Impressions: 712 Engagements: 36</i>	Posted <i>Likes: 4</i>	<i>Access to WeChat was not available during this time.</i>	Posted <i>Impressions: 424</i>
6/21	Posted <i>Impressions: 753 Engagements: 31</i>			
6/22		Posted <i>Likes: 2</i>		
6/30	Posted <i>Impressions: 331 Engagements: 10</i>			
7/7	Posted <i>Impressions: 706 Engagements: 24</i>	Posted <i>Likes: 1</i>		Posted <i>Impressions: 317 Likes: 1</i>
7/9	Posted <i>Impressions: 416 Engagements: 20</i>	Posted <i>Likes: 1 Share: 1</i>		Posted <i>Impressions: 289</i>
7/12	Posted <i>Impressions: 372 Engagements: 15</i>	Posted <i>Likes: 1 Share: 1</i>		Posted <i>Impressions: 333</i>
7/15	Posted <i>Impressions: 560 Engagements: 11</i>			
7/21	Posted <i>Impressions: 1,019 Engagements: 29</i>			
7/23	Posted <i>Impressions: 454 Engagements: 10</i>	Posted <i>Likes: 1</i>		Posted <i>Impressions: 253</i>
7/29	Posted <i>Impressions: 305</i>	Posted <i>Likes: 1</i>		


	<i>Engagements: 1</i>			
8/5	Posted <i>Impressions: 502</i> <i>Engagements: 14</i>	Posted		Posted <i>Impressions: 204</i>
Total Posts	11	8		6

Housing Element Update Virtual Workshop Posts				
	Twitter	Facebook	WeChat	Nextdoor
9/9	Posted <i>Impressions: 268</i> <i>Engagements: 24</i>	Posted <i>Likes: 2</i>	Posted	Posted <i>Impressions: 514</i> <i>Likes: 1</i>
9/14	Posted <i>Impressions: 427</i> <i>Engagements: 27</i>	Posted		
9/16			Posted	
9/17	Posted <i>Impressions: 326</i> <i>Engagements: 11</i>	Posted		Posted <i>Impressions: 494</i>
9/19	Posted <i>Impressions: 231</i> <i>Engagements: 15</i>			
9/20		Posted <i>Likes: 1</i>	Posted	Posted <i>Impressions: 482</i>
9/21	Posted <i>Impressions: 116</i> <i>Engagements: 15</i>			
9/22	Posted <i>Impressions: 114</i> <i>Engagements: 7</i>	Posted <i>Likes: 1</i> <i>Share: 1</i>	Posted	Posted <i>Impressions: 499</i> <i>Likes: 2</i>
9/23	Posted <i>Impressions: 196</i> <i>Engagements: 8</i>	Posted <i>Likes: 1</i> <i>Share: 1</i>	Posted	Posted <i>Impressions: 498</i>
Total	7	6	5	5

Draft Housing Element Review/Comment Period Posts				
	Twitter	Facebook	WeChat	Nextdoor
10/6	Posted <i>Impressions: 142</i> <i>Engagements: 10</i>	Posted <i>Likes: 1</i>	Posted	
10/7				Posted

				<i>Impressions: 425</i>
10/14	Posted <i>Impressions: 129</i> <i>Engagements: 5</i>	Posted <i>Likes: 2</i>	Posted	Posted <i>Impressions: 412</i> <i>Likes: 1</i>
10/19			Posted	
10/21	Posted <i>Impressions: 98</i> <i>Engagements: 8</i>	Posted	Posted	Posted <i>Impressions: 386</i>
10/27	Posted <i>Impressions: 153</i> <i>Engagements: 12</i>	Posted <i>Likes: 1</i>	Posted	Posted <i>Impressions: 384</i>
Total Posts	4	4	5	4

Housing Element Update Community Survey Posts



Housing Element Update Virtual Workshop Posts



HOUSING ELEMENT UPDATE VIRTUAL WORKSHOP

Thursday, September 23, 2021
6:00 p.m.

What is the "RHNA"?

State law provides a target for how many homes each region and city must plan for, based on current population, proximity to public transit and jobs, and expected population growth, etc. Called the Regional Housing Needs Allocation or RHNA (pronounced "ree-nah"), Arcadia must plan for new housing based on these targets.

Let's talk housing! Arcadia is a great place to live, but throughout the region there is a shortage of homes that impacts all of us. That's why now is the time to plan together for current and future housing needs in our community.

Join us virtually for the Housing Element Update Workshop on Thursday, September 23, 2021 at 6:00 p.m. where participants will hear how and where the City can accommodate additional housing over the next eight years and be able to provide feedback on options and strategies.

We hope that you can join us!

Workshop Information

Date: Thursday, September 23, 2021
Time: 6:00 p.m.
To join via Zoom, go to: <https://join.zoom.us/j/99512156792>
To join by telephone, please call +1 (669) 900-6833 or +1 (253) 215-8782 and enter the Webinar ID: 995 1215 6792

Please visit the City's website at ArcadiaCA.gov/housing to view additional information and see the results of the Community Housing Survey!

Questions? Contact Us!

Development Services Department
Planning Services
(626) 574-5423
Planning@ArcadiaCA.gov
ArcadiaCA.gov/housing





Draft Housing Element Review/Comment Period Posts

← Tweet



Shape Arcadia
@ShapeArcadia

The Draft Housing Element (2021-2029) is now available for public review at ArcadiaCA.gov/Housing. Should you have any questions, please contact Planning Services by telephone at (626) 574-5423 or by email at Planning@ArcadiaCA.gov. 🏡 📧

**DRAFT HOUSING ELEMENT (2021-2029)
NOW AVAILABLE FOR PUBLIC REVIEW**

Visit www.ArcadiaCA.gov/Housing



4:32 PM · Sep 30, 2021 · Twitter Web App

||| View Tweet activity

1 Retweet 1 Like



City of Arcadia
City of Arcadia · 5 days ago

**DRAFT HOUSING ELEMENT (2021-2029)
NOW AVAILABLE FOR PUBLIC REVIEW**

Visit www.ArcadiaCA.gov/Housing



Draft Housing Element (2021-2029) Now Available for Public Review at www.ArcadiaCA.gov/Housing. The Draft Housing Element (2021-2029) is now available for public review at www.ArcadiaCA.gov/Housing. Should you have any questions, please contact Planning Services by telephone at (626) 574-5423 or by See more...



City of Arcadia, CA
cms9.revize.com

Posted to Subscribers of City of Arcadia

♡ Like 💬 Comment ➦ Share

356 impressions



Add a comment...



Arcadia Pio
5d · 🌐

The Draft Housing Element (2021-2029) is now available for public review at www.ArcadiaCA.gov/Housing. Should you have any questions, please contact Planning Services by telephone at (626) 574-5423 or by email at Planning@ArcadiaCA.gov. 🏡 📧

**DRAFT HOUSING ELEMENT (2021-2029)
NOW AVAILABLE FOR PUBLIC REVIEW**

Visit www.ArcadiaCA.gov/Housing



September 30, 2021 4:42 PM

**房屋元素草案 (2021-2029)
现在可供公众审查**

访问 www.ArcadiaCA.gov/Housing



住房要素草案 (2021-2029) 现在可在 www.ArcadiaCA.gov/Housing 上供公众审查。如果您有任何疑问, 请致电 (626) 574-5423 或发送电子邮件至 Planning@ArcadiaCA.gov 联系规划服务部。

♡ Like 💬 Comment

CITY OF ARCADIA

2021-2029 HOUSING ELEMENT UPDATE & PUBLIC SCOPING MEETING

The City of Arcadia is preparing the draft 2021-2029 Housing Element Update. The public is invited to attend this workshop to learn about the Housing Element Update and provide feedback.

This Community Workshop will discuss an overview of the Housing Element Update, overview of RHNA Allocation and a discussion on community outreach. This meeting will also serve as the City's Public Scoping meeting on the Program Environmental Impact Report (PEIR) that is being prepared for the Housing Element Update and will include an overview of the California Environmental Quality Act (CEQA) and issues to be covered in the PEIR. Please plan to join us virtually and provide your input!

Please visit the Housing Element Update website for more information at:

https://www.arcadiaca.gov/shape/development_services_department/planning___zoning/housing_element_update.php

WHEN: TBD

TIME: TBD

WHERE: TBD

For questions, please contact TBD





HOUSING ELEMENT UPDATE

The City of Arcadia has begun the process of updating the General Plan Housing Element for the 2021- 2029 period. The Housing Element is a multiyear policy tool that serves as a guide for future decisions that impact housing citywide. The goal of the Housing Element is to ensure the City can meet all the housing needs of Arcadia residents. The City welcomes public participation from our residents and stakeholders during the process to ensure that the most appropriate plans and policies are implemented that best fit the City of Arcadia and address the current and future housing needs. More information regarding upcoming workshops will be mailed to all City residents and updates will be posted on the City's website at ArcadiaCA.gov/Housing. You may also contact Arcadia Planning Services at 574-5423.



Friendly Pet Reminder!

Please be considerate of your neighbors by picking up after your pets and preventing nuisance barking. Contact the Pasadena Humane Society at (626) 792-7151 for assistance, information, or to report a complaint.



On-Demand Sustainability Webinars

The Public Works Services Department is hosting a webinar on sustainable gardening and water conservation for Arcadia residents. The webinar is available to view for one month only, please RSVP by emailing mjiang@ArcadiaCA.gov.

Coyote Safety Virtual Town Hall

The San Gabriel Valley Council of Governments (SGVCOG) will host a Coyote Safety Virtual Town Hall meeting for the City of Arcadia on **Thursday, May 27, 2021 from 6:00 p.m. to 7:00 p.m.** This Town Hall meeting will feature a presentation on SGVCOG's Neighborhood Coyote Program, Pasadena Humane Society and a Coyote Safety Q&A Panel that consists of wildlife experts and professionals.

Residents that wish to submit questions regarding coyote behavior, pet safety, coyote mitigation strategies, or other coyote-related topics may do so before the start of the Town Hall meeting by e-mailing Coyotes@sgvcog.org. Submitted questions will be answered during the Coyote Safety Q&A Panel of the meeting. RSVP at SGVCOG.org/coyotes-events. For more information, please contact Coyotes@sgvcog.org or call (626) 278-8039.



Amazing, Creative Programs at the Gilb Museum this Spring

The Gilb Museum is proud to present this year's first virtual exhibit: Community Collections Digital Exhibit. The Museum asks Arcadia community members to share their own personal collections to highlight and share with everyone, virtually. For more information, please visit Arcadiaca.gov/Museum or call 574-5440.

The community's response to the Museum's free educational and preschool kits has been so positive that the Museum will continue to offer them to the Arcadia community through the 2021 calendar year. Applications for kits can be found on the Museum's website, starting on the day the application period is open, and are available for curbside pickup. Educational kits for ages 5-12, preschool kits for children ages 2-5 and for children with special needs are offered. Each kit will only be available for a limited time. Each kit explores topics relating to the history of Arcadia and includes all the materials necessary to create related crafts and activities. For the year of 2020, the Gilb Museum was able to provide a total of 928 kits to members of the community and is expected to distribute 2,000 kits this year. Information and applications for educational kits can be found on the Museum's website.

Have you ever wanted to jump in a time machine and explore Arcadia's past, from the time of the dinosaurs to the Arcadia of the future? The Gilb Museum is pleased to announce the 3rd annual Virtual Summer Enrichment Program for the year 2021. During select weeks in the month of July, the Museum staff will explore different periods in Arcadia's history, while highlighting items in the Museum's collection. This year's Virtual Summer Enrichment Program will include educational videos and educational kits available on a first-come-first-serve basis. Visit ArcadiaCA.gov/Museum for more information on how to apply for kits.

Annual Registration Fee for the Unoccupied Residence Registry Begins July 1, 2021



Beginning **July 1, 2021**, there will be an annual registration fee of \$1,492 required for the Unoccupied Residence Registration. The fee will allow the City to continue regular inspections of these properties to help ensure they remain secured, well-maintained, and do not become a nuisance to the community.

An unoccupied residence is a single-family residence that has not been occupied for at least 30 days. Houses that are actively under construction, in escrow to be sold or transferred, or being actively marketed by an identified listing agent are not considered unoccupied.

Registration of unoccupied residences is required and includes providing up-to-date contact information for the property owner, contact information for two authorized persons, with at least one being available on a 24-hour basis, as well as the annual fee. In lieu of providing two authorized contacts, property owners may designate a property management company as their contact. The property management company should be located within 20 miles of the unoccupied residence and be available on a 24-hour basis.


Property owners of unoccupied residences, including those that are already listed on the registry, can begin paying the annual registration fee starting July 1, 2021, and may register at Arcadia City Hall, or online at ArcadiaCA.gov/UnoccupiedReg.

For more information, please contact the Code Services Division at 574-5432, or email DSDCodeServices@ArcadiaCA.gov.



HOUSING ELEMENT UPDATE

Earlier in the year, the City of Arcadia began the important process of updating its 6th Cycle Housing Element, covering the years 2021-2029. The goal of the Update is to plan for the current and future housing needs of all Arcadia residents. Community participation is a vital part of the update process. Therefore, the City has developed a community survey to find out which housing issues are important to the community, and to help the City develop a plan that best reflects the community's housing needs. The survey is anonymous and takes about 5-10 minutes to complete. The City has also developed a Frequently Asked Questions (FAQ) page to provide more detailed information on the Update. Please visit ArcadiaCA.gov/Housing to provide your input by taking the community survey, view the FAQ page, learn more about the update process, sign up for email updates, and view any upcoming announcements and opportunities for public participation.



Arcadia Transit Is Here for You!


Arcadia Transit would like to thank all frontline workers including our very own transit bus drivers who have continued to provide uninterrupted service throughout the COVID-19 pandemic. We are running our regular fixed route schedules and Dial-A-Ride service. Arcadia Transit is committed to the safety and health of our riders. Our buses are clean, safe, and convenient. For more information on our services, please visit ArcadiaCA.gov/Transit.

New to Arcadia Transit?


The Arcadia Transit app is a great way to learn about Arcadia's local transit system. The Arcadia Transit Fixed-Route provides general public transit service on three bus lines - Green, Blue, and Red. Plan your trip, get real-time schedules, and rely on our essential transportation services to get you where you need to go. Download DoubleMap Bus Tracker on the App Store or Google Play first, then select Arcadia as the transit system to view.

Dial-A-Ride

Arcadia Transit's Dial-A-Ride offers curb-to-curb shared transportation to seniors and persons with disabilities, responding to individual travel requests as they are received. Each Arcadia Transit vehicle is clearly marked and features comfortable seating, and is wheelchair accessible. The Arcadia Transit Dial-A-Ride service will take you to any destination within City limits! Visit the Community Center, Library, City Hall, or ArcadiaCA.gov/Transit for registration.



The Residential Landscaping Guide provides homeowners with the City's standards, requirements, and expectations for landscaping in the front yard and/or street side areas. To obtain a copy of the guide, visit the Development Services Department at City Hall, or go to ArcadiaCA.gov/RLG.



SPRING 2021 CITY OF ARCADIA NEWSLETTER

City Council

Roger Chandler, *Mayor*
Sho Tay, *Mayor Pro Tem*
Tom Beck, *Council Member*
Paul P. Cheng, *Council Member*
April A. Verlato, *Council Member*

City Officials

Gene Glasco, *City Clerk*
Dominic Lazzaretto, *City Manager*

City Council Meetings

The City Council meets the first and third Tuesday of the month at 7 p.m. in the Council Chambers at City Hall. Meetings are broadcast live on the City's government access cable channel - AT&T channel 99 and Charter Communications digital channel 15-257. Meetings are also available for viewing from the City website.

ArcadiaCA.gov

Follow Us on

@EnrichArcadia
@ProtectArcadia
@ShapeArcadia
@DiscoverArcadia

City Hall 574-5400
Building 574-5416
City Council 574-5403
City Manager 574-5401
Development Services 574-5415
Fire Administration 574-5100
Graffiti Hotline 821-4333
Historical Museum 574-5440
Library 821-5567
Planning 574-5423
Police Administration 574-5151
Public Works Services 254-2720
Recreation & Community Services 574-5113
Senior Citizen Services 574-5130
Shopping Cart Removal (888) 787-2278
Water Conservation Hotline 574-3000
Water Service 254-2700

ARCADIA

COMMUNITY NEWS



COVID-19 Vaccination Information

Please visit the County Public Health's website at **VaccinateLACounty.com** for the latest COVID-19 vaccine implementation information. The webpage includes:

- FAQs
- Responses to myths and misinformation
- Information about scams
- A place to sign up for email updates
- A Vaccine Distribution page that explains the phases and tiers of distribution
- A COVID-19 vaccine management dashboard where people can track how much vaccine has been distributed

Who Will Get Vaccine When

The Vaccine Distribution page describes the phases and tiers of vaccination, with more information about how these phases may roll out. This page is being updated regularly as the groups within each phase and tier are further refined.

Note: Additional groups may be added as more vaccinations become available. Check the Los Angeles County website at **VaccinateLACounty.com for the latest information and to book an appointment if you are in the eligible group.*

Improvements Around City Hall

The new project around City Hall will include construction of a new sidewalk, curb ramps, and minor landscaping improvements in the parkway along the west side of eastbound Huntington Drive from Centennial Way to the northeast corner of City Hall. With the completion of the Marriott's Le Méridien hotel, there will be a sidewalk link from the southwest corner of the Huntington Drive and Santa Clara Street intersection to Centennial Way, creating a nice loop along Huntington Drive for pedestrians to take a short stroll throughout the day. Construction around City Hall is expected to begin in April.



INSIDE THIS ISSUE

- 3 Arcadia Transit
- 4 Summer Watering Schedule
- 5 Coyote Safety Virtual Town Hall
- 6 Sports Camp
- 8 Follow Us on Facebook




Home Improvement Grants 3



Housing Element Update 5



Community Connect Program 7



Candidates Being Sought for City Boards and Commissions

The Arcadia City Clerk's Office is currently accepting applications from residents who would like to serve on a City Board or Commission. Arcadia's Board and Commission members serve without compensation. To serve on a Board or Commission, applicants must be 18 years or older, a registered voter, and a resident of the City of Arcadia.

Arcadia's Board and Commission members serve in an advisory capacity and provide critical input on quality of life issues in Arcadia. The Arcadia Beautiful Commission, Human Resources Commission, Library Board of Trustees, and Senior Citizens' Commission each have openings.

Anyone with an interest in serving may obtain a Citizen Service Resume by visiting the City's website at **ArcadiaCA.gov/Service**. Applications must be mailed to the City Clerk's Office on or before the close of business on **Thursday, May 20, 2021**. Appointments are expected to be made at the **Tuesday, June 15, 2021**, City Council meeting.

Please contact the City Clerk's Office at 574-5455 if you would like further information about Board and Commission service in the City of Arcadia.

Home Safety During COVID



Though only 27% of fires happen in homes, these blazes are responsible for most fire deaths (79%) and injuries (73%). A combination of fewer working fire sprinklers and smoke alarms in residences and the presence of elderly individuals contribute to these statistics. With the uncertainty around COVID-19, more people are forced to stay home and work remotely, and the risk of fire continues to grow.

While 2020 data is still being collected, it is reasonable to assume we will see an annual increase in fires as more people spend more time in their residences, especially as cooking becomes more common.

The National Fire Protection Association's (NFPA) latest report on "Home Structure Fires" studied incidents between 2013-2017 and determined that of the average 354,400 home structure fires per year, most were caused by cooking (49%), followed by the following:

- Heating equipment (14%)
- Electrical distribution and lighting equipment (10%)
- Intentional (8%), this includes arson and fires started by children
- Smoking materials (5%)

Fire safety should always be of paramount concern for the home starting with the following reminders:

Cooking Fire Safety


- If you're cooking with quicker-acting equipment, stay in the room and keep an eye on things.
- Turn off the stove, fryer, broiler, or grill if you have to leave the kitchen.
- Use a timer for longer cooking tasks, such as baking, simmering, or roasting. Forgotten cooking leads to fires.
- Keep fuel sources, such as towels or empty boxes, away from the stove. Make sure pot and pan handles are not sticking outward.
- Always try to keep small kids out of an active kitchen.

Heater Fire Safety

- Keep combustibles at least three feet away from any type of heating equipment and enforce the same distance rule for kids.
- Turn off portable heaters if you leave or go to bed.
- Have your heating equipment inspected by a qualified contractor on a regular basis.

Electrical Fire Safety

- Never charge devices under covers or pillows.
- Avoid overloading electrical circuits by plugging numerous things into outlet adapters, and never use adapters for larger appliances such as refrigerators.
- Ensure all cords are in good shape and from the manufacturer. Remember, extension cords are merely temporary solutions to achieve plug-in distance.



Arcadia Transit Is Here for You!

Arcadia Transit is here for your essential trips during the ongoing COVID-19 crisis and Los Angeles County's path to recovery. We are running our regular fixed route schedules and dial-a-ride service. Arcadia Transit is committed to the safety and health of our riders. Our buses are clean, safe, and convenient. For more information on our services, please visit ArcadiaCA.gov/Transit.

Have you downloaded the Arcadia Transit App?

- Plan your trip, get real-time schedules, and rely on our essential transportation services to get you where you need to go. Download DoubleMap Bus Tracker on the App Store or Google Play first, then select Arcadia as the transit system to view.

Protect Yourself When Using Arcadia Transit

- A Federal directive requires a face mask to be worn on public transit at all times. Wear a mask over your nose and mouth when in public settings.
- We ask riders to spread out whenever possible, allowing yourself six feet of physical distance from others.
- Please avoid riding Arcadia Transit if you are feeling sick.



HOME IMPROVEMENT GRANTS AVAILABLE

Arcadia residents in need of home repairs may be eligible for federal grant assistance under the Home Improvement Program. Qualified homeowners meeting income limits are eligible to receive assistance of up to \$20,000 for a single-family home, and up to \$15,000 for a condominium or townhome. The program can help fund general home repairs, replacement of heating and air conditioner units, home insulation, water heaters, window and exterior doors (limited to single-family homes), energy efficiency improvements, and more!


To qualify, property owners must own and occupy the residence and meet the household income limits and restrictions listed below.

Number of persons in the household	Maximum combined income per household*
1	\$63,100
2	\$72,100
3	\$81,100
4	\$90,100
5	\$97,350
6	\$104,550

**Income limits subject to change. Household income includes a percentage of all financial assets. No additional properties may be owned.*

This Program is funded in part by the U.S. Department of Housing and Urban Development through the Los Angeles County Community Development Commission's Community Development Block Grant Program.

An application and brochure can be obtained by contacting the Development Services Department at 574-5408 or HIP@ArcadiaCA.gov, or downloaded at ArcadiaCA.gov/HIP.



New Flashing Yellow Arrow Coming to Duarte Road at Holly Avenue Traffic Signal

In the interest of improved safety and efficiency, as a pilot project, a Flashing Yellow Arrow (FYA) for the left turns on Duarte Road at the Holly Avenue traffic signal will be installed.



Steady Red:
Stop

Steady Yellow:
Prepare to Stop
Flashing Yellow:
Left turn after yielding
to oncoming
traffic/pedestrians

Steady Green:
Protected Left Turn

A FYA allows waiting motorists to make a left-hand turn after yielding to oncoming traffic. It tends to be more eye-catching and is a constant reminder to the driver to use caution in yielding to oncoming traffic, as opposed to the solid green light. This new FYA will provide more efficiency for left turners with the permissive left turns allowed in the off-peak hours but could also be turned off during heavy pedestrian activity periods where there is a greater potential interaction with permissive left turners. Be on the lookout as the City plans to install more FYAs at traffic signals throughout town!

Spring Cleaning

Free Bulky Item Pickup



Are you moving or simply looking to get rid of old furniture and appliances? Arcadia residents residing in single-family homes have four (4) free bulky item pickups per year. Multi-family complex residents have two (2) free pickups per unit, per year. Contact Waste Management at (800) 266-7551 or online at Home.WM.com/Arcadia to arrange your bulky item pickup today. These items may include:

- Couches, rugs, and other large furniture
- Refrigerators, washing machines, and other large appliances
- Mattresses and box springs
- Water heaters
- Large bundled branches that do not fit in your green waste container
- Bulky electronic waste (computers, TVs, printers, etc.)



The State of California has recently approved regulations for Senate Bill 1383. These regulations set a goal of reducing the state's landfilled organic waste by 50%-75% statewide. In order to achieve this goal, cities are tasked with having organics (food waste and green waste) recycling programs at all properties, including single-family residential properties. In addition, cities must work with counties to facilitate a food rescue program that creates a 20% increase in the recovery of currently disposed edible food from grocery stores, restaurants, and other large food generators to address food insecurity in California.

Stay tuned for more information on how you will play a part in the success of this organics recycling program in future announcements. For more information, please visit CalRecycle.CA.gov/Organics/slcp.



Composting at Home

Composting at home is a sustainable practice that turns unwanted food scraps and yard trimmings into a rich, pesticide-free soil conditioner. You can use a compost bin, worm composting bin, or create a free-standing compost pile in a shaded area of your backyard. For basic composting instructions, visit EPA.gov/Recycle/Composting-Home. The Public Works Services Department offers 3' x 2' compost bins at the reduced price of \$35 to Arcadia residents and worm composting bins for \$65. To reserve yours today, please call 254-2720.



SUMMER Watering Days

	Mon	Tues	Wed	Thur	Fri	Sat	Sun
SUMMER Watering Schedule May 1-October 31							

Starting on **May 1 through October 31**, the Summer Watering Schedule begins and allowed days for outdoor irrigation are Tuesday, Thursday, and Saturday, before 9 a.m. and after 6 p.m. Avoid watering during daytime hours when the sun, heat, and wind will quickly evaporate water. Additionally, please limit sprinklers to 10 minutes per station to avoid creating runoff, which is a sign of water waste and overly saturated soil. Trees and garden plants may be watered by hand any day of the week, as long as it is done within the allowed timeframe. When using a garden hose for outdoor watering, ensure a shut-off nozzle is attached to prevent waste.

Arcadia residents and businesses can qualify for indoor and outdoor water efficiency rebates, including Metropolitan Water District's Turf Replacement rebate offering \$2 per square foot. For more information, please visit SoCalWaterSmart.com or call (888) 376-3314.



HOUSING ELEMENT UPDATE

The City of Arcadia has begun the process of updating the General Plan Housing Element for the 2021- 2029 period. The Housing Element is a multiyear policy tool that serves as a guide for future decisions that impact housing citywide. The goal of the Housing Element is to ensure the City can meet all the housing needs of Arcadia residents. The City welcomes public participation from our residents and stakeholders during the process to ensure that the most appropriate plans and policies are implemented that best fit the City of Arcadia and address the current and future housing needs. More information regarding upcoming workshops will be mailed to all City residents and updates will be posted on the City's website at ArcadiaCA.gov/Housing. You may also contact Arcadia Planning Services at 574-5423.



Friendly Pet Reminder!

Please be considerate of your neighbors by picking up after your pets and preventing nuisance barking. Contact the Pasadena Humane Society at (626) 792-7151 for assistance, information, or to report a complaint.



On-Demand Sustainability Webinars

The Public Works Services Department is hosting a webinar on sustainable gardening and water conservation for Arcadia residents. The webinar is available to view for one month only, please RSVP by emailing mjiang@ArcadiaCA.gov.

Coyote Safety Virtual Town Hall

The San Gabriel Valley Council of Governments (SGVCOG) will host a Coyote Safety Virtual Town Hall meeting for the City of Arcadia on **Thursday, May 27, 2021 from 6:00 p.m. to 7:00 p.m.** This Town Hall meeting will feature a presentation on SGVCOG's Neighborhood Coyote Program, Pasadena Humane Society and a Coyote Safety Q&A Panel that consists of wildlife experts and professionals.

Residents that wish to submit questions regarding coyote behavior, pet safety, coyote mitigation strategies, or other coyote-related topics may do so before the start of the Town Hall meeting by e-mailing Coyotes@sgvcog.org. Submitted questions will be answered during the Coyote Safety Q&A Panel of the meeting. RSVP at SGVCOG.org/coyotes-events. For more information, please contact Coyotes@sgvcog.org or call (626) 278-8039.




Amazing, Creative Programs at the Gilb Museum this Spring

The Gilb Museum is proud to present this year's first virtual exhibit: Community Collections Digital Exhibit. The Museum asks Arcadia community members to share their own personal collections to highlight and share with everyone, virtually. For more information, please visit Arcadiaca.gov/Museum or call 574-5440.

The community's response to the Museum's free educational and preschool kits has been so positive that the Museum will continue to offer them to the Arcadia community through the 2021 calendar year. Applications for kits can be found on the Museum's website, starting on the day the application period is open, and are available for curbside pickup. Educational kits for ages 5-12, preschool kits for children ages 2-5 and for children with special needs are offered. Each kit will only be available for a limited time. Each kit explores topics relating to the history of Arcadia and includes all the materials necessary to create related crafts and activities. For the year of 2020, the Gilb Museum was able to provide a total of 928 kits to members of the community and is expected to distribute 2,000 kits this year. Information and applications for educational kits can be found on the Museum's website.

Have you ever wanted to jump in a time machine and explore Arcadia's past, from the time of the dinosaurs to the Arcadia of the future? The Gilb Museum is pleased to announce the 3rd annual Virtual Summer Enrichment Program for the year 2021. During select weeks in the month of July, the Museum staff will explore different periods in Arcadia's history, while highlighting items in the Museum's collection. This year's Virtual Summer Enrichment Program will include educational videos and educational kits available on a first-come-first-serve basis. Visit ArcadiaCA.gov/Museum for more information on how to apply for kits.



It's a new season and time for two yearly favorites...but, first, something new! The Arcadia Public Library has added Dial-A-Story, a new service that enables you to dial in and listen to fun and engaging stories for kids. No Internet is needed, just a phone. Call 631-2300 anytime, anywhere and follow the voice prompts to select and listen to your choice of three stories read aloud by Library staff. New stories will be available every other week.

It wouldn't be spring without the annual Bookmark Contest. Children, ages 3 - 14 years, who are looking to creatively express themselves, are invited to submit their drawing for a bookmark on the colorful theme of "Reading Colors Your World". Entries will

be accepted through **Saturday, April 17, 2021**. Eight winning entries will be selected, professionally printed, and distributed throughout the summer months. Contest entry forms will be available at the Library's front entrance as well as on the Library's webpage at **ArcadiaCA.gov/Library**.

The Library is freshening up its traditional spring reading program. This year, the family that reads together also wins fun prizes by participating in the Arcadia Public Library's Family Reading Program. Those interested in participating may register online. Participants then read and log up to 25 book titles to earn virtual badges. There will be weekly drawings for kid participants. Kid, teen, and adult participants who earn at least one virtual badge will be automatically entered into a grand prize drawing for one of five \$25 gift cards. All reading and logging must be completed by **Saturday, May 1, 2021**. Grand prize winners will be contacted by **Friday, May 7, 2021**. Readers may access a host of great digital books through TumbleBook Library, Overdrive or Gale eBooks. All are accessible on the Library's website from the "eBooks and More" webpage.

Don't forget! The Library is still offering the popular front-door pick-up service. Order up to five items online at **Discovery.ArcadiaLibrary.org** and you'll be called to arrange a pick-up time when they are available. Happy family reading!

Half Day After School Camp



Baldwin Stocker Elementary School
Weekdays
2-6 p.m.
5-12 years of age
\$92 per week

The half day camp follows the Los Angeles County Public Health Order, including:

- Health screening and temperature check
- Face covering
- 1:10 staff to youth ratio
- Consistent weekly groups
- Cleaning protocols

For more information, please visit **ArcadiaCA.gov/Recreation** or call 574-5113.

WILDERNESS PARK day camp

June 7 - August 6

\$155 | 5-12yrs | 9:30am-3pm

Registration is on now at ArcadiaCA.gov/Recreation
 For more information, call the Recreation Office at 626.574.5113.

Sports CAMP

July 19 - August 6

\$155 | 5-12yrs | 9:30am-3pm

Registration is on now at ArcadiaCA.gov/Recreation
 For more information, call the Recreation Office at 626.574.5113



Expand Your Tech World with Arcadia Public Library

As our world becomes increasingly dependent on technology, so does our need to learn apps, tools, and products. That's where the Library comes in! Join our virtual Learning Lab classes to discover and become skilled at the technology our family, businesses, and community use. There's a class for everyone.

Can't make the live class time? Here are some other resources:

- Review the class handout and presentation by visiting **Arcadia.Libguides.com/Learninglabs**
- Watch the class micro-lesson on the Library's YouTube channel at **youtube.com/user/arcadiapubliclibrary**
- Book a Librarian for a one-on-one session in which we will work with you and answer your tech-related questions by visiting **forms.gle/ttr4WijKBMG8JkaT7**

Arcadia Public Library also offers a wide range of eResources on its webpage, including ebooks, magazines, movies, language classes, crafting instructions and ideas, reading advice, and more. It's like having your own personal library 24/7. Want to learn even more? Call the Adult Services division directly at 821-5569 or visit the Library's webpage at **ArcadiaCA.gov/Library**.

The Library Supports Arcadia Teens

Reviving the Library's Teen Advisory Group has given the Library's staff a chance to become more aware of how the Library can connect with teens, offering them the books, resources, and help they may need.

When speaking with teens, a common theme is how overwhelmed they are feeling. Being unable to hang out with friends, trying to keep up with online school, COVID worries, and the day to day stresses of being a teen add to these feelings. To help with this, the Library created a take-home de-stress kit for teens. The kit includes:

- A mini Zen garden
- A coloring bookmark
- A list of recommended books to read
- Bubble wrap- to pop when feeling stressed

This interactive kit will help teens reset. They can leave their mini Zen garden on their desk for easy access when needed. A curated list of books is included: fiction books for the health benefits that come from reading for pleasure and nonfiction books, as they relate directly to the mental wellness of teens.




During this time of great uncertainty we've been comforted, encouraged, and humbled by the outpouring of generosity and support from our community.

Remarkable people, organizations such as the Arcadia Chinese Association, community groups, and small businesses have all stepped up to support our first responders and City staff with donations of meals, personal protective equipment, and more.

To us, you are our heroes and we thank you for helping us meet the challenges of this moment, so we can continue to provide the highest level of service to our residents.

Community Connect Program



The City's Community Connect Program is a free, secure, and easy way for our community to provide critical information about their households so that the Arcadia Fire Department can adequately respond to our residents during an emergency. Some of the helpful information you can provide includes your property's type, whether or not you have fire sprinklers, best contact in case of an emergency, potential hazards at your location, mobility issues in your household, and even your pet's information.

This is a completely voluntary program and it is up to you on how much information you would like to share with our first responders. Sign up any time by visiting **ArcadiaCA.gov/Connect**.



240 West Huntington Drive
Post Office Box 60021
Arcadia, CA 91066-6021

Pre-sorted
Standard
U.S. Postage
PAID
Arcadia, CA
Permit No. 255

ARCADIA POSTAL CUSTOMER

Support Arcadia Businesses

Shop & Dine Arcadia



如果您需要有人协助翻译本期中的文章, 请与朋友或邻居联系。本期提要:

新冠病毒疫苗接种信息	1
市政厅周围的翻新改进	1
诚征市政委员会成员	2
新冠病毒疫情期间家庭安全	2
阿凯迪亚公共交通为您服务!	3
可提供住宅翻新赠款	3
将在与Duarte Road 与Holly Avenue交界处的交通信号灯上增设闪烁黄箭头	3
春季大扫除: 免费取走大件物品	4
在家中做堆肥	4
SB 1383	4
夏季浇水日	4
新建住房比例更新	5
今春Gilb博物馆推出的令人惊奇并充满新意的计划	5
友好宠物提醒!	5
即时可持续性网络研讨会	5
郊狼安全虚拟市民会议	5
阿凯迪亚公共图书馆春季儿童娱乐活动	6
半日课后活动营	6
荒野公园 (Wilderness Park) 日间营	6
运动营	6
在阿凯迪亚公共图书馆扩大您的技术视野	7
图书馆支持阿凯迪亚青少年	7
谢谢!	7
社区联系计划	7
支持阿凯迪亚企业: 在阿凯迪亚购物和就餐	8
在脸书上查看我们的信息	8


Follow Us on Facebook



[Facebook.com/ArcadiaGov](https://www.facebook.com/ArcadiaGov)


The City of Arcadia has launched an official Facebook page in the ongoing effort to enhance communications with the community and provide additional access to City information. Get the latest information on news items, events, and emergency information by following us.

facebook



ARCADIA

COMMUNITY NEWS



SUMMER 2021 CITY OF ARCADIA NEWSLETTER

City Council

Sho Tay, *Mayor*
Paul P. Cheng, *Mayor Pro Tem*
Tom Beck, *Council Member*
Roger Chandler, *Council Member*
April A. Verlato, *Council Member*

City Officials

Gene Glasco, *City Clerk*
Dominic Lazzaretto, *City Manager*

City Council Meetings

The City Council meets the first and third Tuesday of the month at 7 p.m. in the Council Chambers at City Hall. Meetings are broadcast live on the City's government access cable channel - AT&T channel 99 and Charter Communications digital channel 15-257. Meetings are also available for viewing from the City website.

ArcadiaCA.gov

Follow Us on

@EnrichArcadia
@ProtectArcadia
@ShapeArcadia
@DiscoverArcadia

City Hall 574-5400
Building 574-5416
City Council 574-5403
City Manager 574-5401
Development Services 574-5415
Fire Administration 574-5100
Graffiti Hotline 821-4333
Historical Museum 574-5440
Library 821-5567
Planning 574-5423
Police Administration 574-5151
Public Works Services 254-2720
Recreation & Community Services 574-5113
Senior Citizen Services 574-5130
Shopping Cart Removal (888) 787-2278
Water Conservation Hotline 574-3000
Water Service 254-2700



BRUSH FIRE PREPAREDNESS: FIRE RESISTANT PLANTS CAN HELP SAVE YOUR HOME

The Bobcat Fire of 2020 reminded all Arcadians of the ever present dangers of wildland fires to lives and property. If you live in an area that may be impacted by wildfire, the Arcadia Fire Department recommends the proactive measure of planting fire resistant plants to reduce the exposure to wildfires.

These plants are relatively non-flammable and burn less readily than typical chaparral plants such as Chamise or Scrub Oak. There is no such thing as a fireproof plant. Most substances – including green plants – will burn if subjected to a high degree of temperature for extended periods. The time and temperature characteristics of ignition and combustion vary considerably between species.

Most retail nurseries can provide you with more specific details on cost, planting, and maintenance of a given plant. Information on types of fire-resistant plants can also be obtained by contacting the Los Angeles County Arboretum at 821-3222, or by reviewing the websites of some of the following organizations:

California Fire Safe Council	cafiresafecouncil.org
California Native Plant Society	cnps.org
California Invasive Plant Council	cal-ipc.org
California Department of Forestry and Fire Protection	fire.ca.gov

In addition to the use and maintenance of fire resistive plants, the Arcadia Fire Department recommends the following proactive measures homeowners can do outside of their dwelling to protect it from possible damage from brush fires:

- Enclose the underside of eaves and decks with fire-resistant materials to keep out flying embers.
- Clean dead leaves and needles from the roof and rain gutters.
- Cover your chimney, attic vents, and stovepipes with 1/8-inch mesh screens.
- Move propane tanks and stack woodpiles at least 30 feet from all structures.
- Install dual-paned windows when financially feasible.
- Use only Class A or non-combustible materials when replacing your roof.

For additional fire safety information, please contact the Arcadia Fire Prevention Bureau at 574-5104 or visit the City website at ArcadiaCA.gov/Brushfire.

INSIDE THIS ISSUE

- 3 Housing Element Update
- 5 SB1383
- 6 Summer Enrichment Program
- 7 Passport Services Now Open
- 8 Follow Us on Facebook



Pool Safety

2



Summer Concerts & Movies

4




Summer Reading Program

6



As we celebrate this year's Fourth of July weekend, it is important to keep in mind that for the protection and safety of our residents, the Arcadia Municipal Code Section 3124.9 prohibits the use, sale or discharge of fireworks anywhere in the City, unless authorized by the Fire Chief.



The City of Arcadia's mass emergency notification system, Alert Arcadia, enables the City to provide secure, reliable, and relevant information to residents in real-time during emergency situations. Sign up for Alert Arcadia to receive local emergency information and other important community messages via phones, text messages, emails, and over the web. Messages may include safety alerts and instructions, shelter locations, and evacuation orders. Signing up to Alert Arcadia online is easy and fast by going to **ArcadiaCA.gov/Alert**.

SAVINGS for City of Arcadia Residents Join the Paramedic Membership Program (PMP)

A 9-1-1 call for emergency ambulance service can cost thousands of dollars. For \$51 per year, PMP provides savings with benefits to you and the rest of your family:

- ✓ Covers ALL permanent household members who live at the same address.
- ✓ Covers ALL out-of-pocket expenses not covered by insurance for emergency ambulance services.
- ✓ Reduced rates for those who live in a retirement facility (\$27 per year) or qualifying low-income residents (\$24 per year).

To get an application packet, please contact the Arcadia Fire Department at 574-5126 or download the form from **ArcadiaCA.gov/Paramedic**.

Pool Safety Tips

Swimming pools are great places for family fun especially during the summer periods. For everyone's safety, it is important to ensure everyone follows these simple safety steps to stay safer in and around water.

1. NEVER leave a child unattended in or near water.
 - Designate an official "Water Watcher," an adult tasked with supervising children in the water. This should be their only task – no reading, texting, or playing games on their phone.
 - Have a phone close by at all times in case you need to call for help.
 - If a child is missing, check the pool first.
2. Teach children how to swim. Swimming is not only fun, it's a lifesaving skill.
 - Enroll children in swimming lessons; there are many free or reduced-cost options available from your local YMCA or USA Swimming chapter.
3. Teach children to stay away from drains.
 - Do not play or swim near drains or suction outlets, especially in spas and shallow pools, and never enter a pool or spa that has a loose, broken, or missing drain cover.
 - Children's hair, limbs, jewelry, or bathing suits can get stuck in a drain or suction opening. When using a spa, be sure to locate the emergency vacuum shutoff before getting in the water.
4. Ensure all pools and spas – both in your backyard and any public pool you may visit have compliant drain covers.
 - Powerful suction from a pool or spa drain can even trap an adult.
5. Install proper barriers, covers, and alarms on and around your pool and spa.
 - Proper fences, barriers, alarms, and covers can be lifesaving devices. A fence of at least four feet in height should surround the pool or spa on all sides and should not be climbable for children.
 - The water should only be accessible through a self-closing, self-latching gate.
 - Teach children to never try to climb over the gate or fence. Install a door alarm from the house to the pool area, and keep pool and spa covers in working order.
6. Pool covers should cover the entire pool securely enough that a child or an animal cannot slip under them.
 - Make sure no standing water collects on top- children can drown in less than 2 inches of water.
 - Floating solar and winter covers are not safety covers and can increase drowning risk. Because a floating cover makes the pool surface appear solid, a small child might try to retrieve a ball or other light toy that landed on it and quickly slip underneath – often trapped and hidden from view.
7. Know how to perform CPR on children and adults.
 - Once you're CPR certified, make sure to keep your certification current.
 - CPR classes are available through many hospitals, community centers, or by contacting the American Red Cross.

For more resources in adopting essential water safety steps and ensuring that a great day at the pool does not turn into a tragic one, please visit **poolsafely.gov**.



Annual Registration Fee for the Unoccupied Residence Registry Begins July 1, 2021



Beginning **July 1, 2021**, there will be an annual registration fee of \$1,492 required for the Unoccupied Residence Registration. The fee will allow the City to continue regular inspections of these properties to help ensure they remain secured, well-maintained, and do not become a nuisance to the community.

An unoccupied residence is a single-family residence that has not been occupied for at least 30 days. Houses that are actively under construction, in escrow to be sold or transferred, or being actively marketed by an identified listing agent are not considered unoccupied.

Registration of unoccupied residences is required and includes providing up-to-date contact information for the property owner, contact information for two authorized persons, with at least one being available on a 24-hour basis, as well as the annual fee. In lieu of providing two authorized contacts, property owners may designate a property management company as their contact. The property management company should be located within 20 miles of the unoccupied residence and be available on a 24-hour basis.


Property owners of unoccupied residences, including those that are already listed on the registry, can begin paying the annual registration fee starting July 1, 2021, and may register at Arcadia City Hall, or online at ArcadiaCA.gov/UnoccupiedReg.

For more information, please contact the Code Services Division at 574-5432, or email DSDCodeServices@ArcadiaCA.gov.



HOUSING ELEMENT UPDATE

Earlier in the year, the City of Arcadia began the important process of updating its 6th Cycle Housing Element, covering the years 2021-2029. The goal of the Update is to plan for the current and future housing needs of all Arcadia residents. Community participation is a vital part of the update process. Therefore, the City has developed a community survey to find out which housing issues are important to the community, and to help the City develop a plan that best reflects the community's housing needs. The survey is anonymous and takes about 5-10 minutes to complete. The City has also developed a Frequently Asked Questions (FAQ) page to provide more detailed information on the Update. Please visit ArcadiaCA.gov/Housing to provide your input by taking the community survey, view the FAQ page, learn more about the update process, sign up for email updates, and view any upcoming announcements and opportunities for public participation.



Arcadia Transit Is Here for You!


Arcadia Transit would like to thank all frontline workers including our very own transit bus drivers who have continued to provide uninterrupted service throughout the COVID-19 pandemic. We are running our regular fixed route schedules and Dial-A-Ride service. Arcadia Transit is committed to the safety and health of our riders. Our buses are clean, safe, and convenient. For more information on our services, please visit ArcadiaCA.gov/Transit.

New to Arcadia Transit?

The Arcadia Transit app is a great way to learn about Arcadia's local transit system. The Arcadia Transit Fixed-Route provides general public transit service on three bus lines - Green, Blue, and Red. Plan your trip, get real-time schedules, and rely on our essential transportation services to get you where you need to go. Download DoubleMap Bus Tracker on the App Store or Google Play first, then select Arcadia as the transit system to view.

Dial-A-Ride

Arcadia Transit's Dial-A-Ride offers curb-to-curb shared transportation to seniors and persons with disabilities, responding to individual travel requests as they are received. Each Arcadia Transit vehicle is clearly marked and features comfortable seating, and is wheelchair accessible. The Arcadia Transit Dial-A-Ride service will take you to any destination within City limits! Visit the Community Center, Library, City Hall, or ArcadiaCA.gov/Transit for registration.



The Residential Landscaping Guide provides homeowners with the City's standards, requirements, and expectations for landscaping in the front yard and/or street side areas. To obtain a copy of the guide, visit the Development Services Department at City Hall, or go to ArcadiaCA.gov/RLG.

Free Turf Transformation Classes

With a second dryer than normal winter in a row, it's important we remember the key role landscapes play in water use efficiency. If you are looking to revamp your front or backyard, sign up for a free turf transformation class at greengardensgroup.com/turf-transform. These classes are now being offered online in English, Mandarin, and Spanish. Simply sign up for a scheduled time and an instructor will walk you through the process of removing turf grass, building a healthy soil sponge, and selecting the right plant palette. The class will also cover the \$2 per square foot turf removal rebate offered by Metropolitan Water District on socalwatersmart.com.

NEW!
CODE COMPLIANCE GUIDES
NOW AVAILABLE ONLINE

YARD SALE
Residents are advised to use caution at City Hall for the sale of goods.

REPORT GRAFFITI
When graffiti vandalism goes unreported, it can contribute to the decline of the neighborhood. Be the eyes of the community and help defeat vandals by denying them visibility. If you see graffiti within the City limits, note the location, and call the Graffiti Hotline.

Call for Removal
When graffiti vandalism goes unreported, it can contribute to the decline of the neighborhood. Be the eyes of the community and help defeat vandals by denying them visibility. If you see graffiti within the City limits, note the location, and call the Graffiti Hotline.

Call for Removal
When graffiti vandalism goes unreported, it can contribute to the decline of the neighborhood. Be the eyes of the community and help defeat vandals by denying them visibility. If you see graffiti within the City limits, note the location, and call the Graffiti Hotline.

Call for Removal
When graffiti vandalism goes unreported, it can contribute to the decline of the neighborhood. Be the eyes of the community and help defeat vandals by denying them visibility. If you see graffiti within the City limits, note the location, and call the Graffiti Hotline.

The City of Arcadia, through the Arcadia Municipal Code (AMC), requires that minimum standards be maintained related to the health, safety, and welfare of community residents. The new Code Compliance guides provide useful information on the City's codes, safety tips, and programs. They are also available in Chinese. Check them out at ArcadiaCA.gov/CodeGuides.

Carcadia - SGV's Most Eclectic Car Show

Now in its eighth year, Carcadia is one of the longest-running and biggest regularly scheduled car meets in not only the San Gabriel Valley but the entire Southern California area. Founded by Arcadia natives, Carcadia is a family-friendly environment where you'll find incredible diversity of cars and car lovers who attend. The City has partnered with Carcadia to offer a free used oil kit (used oil container, rags, and used oil funnel), while supplies last. Come and get your used oil kit Arcadia car enthusiasts! See below for location details:

Location: 733 West Naomi Avenue, Arcadia 91007 (Arcadia Hub Center)

Time: **Last Sunday of the month, 7:00 a.m.-9:00 a.m.**

Website: Carcadia.org

Instagram: [Carcadia66](https://www.instagram.com/Carcadia66)

Free Summer Concerts and Movies

Back to Back

CONCERTS	MOVIES
6:30pm	Dusk
COLD DUCK August 5	THE CROODS: A NEW AGE
Plus National Night Out and Arcadia's 118th Birthday	
THE ANSWER August 12	RAYA AND THE LAST DRAGON

CITY HALL WEST LAWN
240 WEST HUNTINGTON DRIVE
PARKING AVAILABLE AT CITY HALL LOT AND SANTA ANITA RACE TRACK, GATE 5

DROUGHT

This past April, Governor Newsom declared a drought emergency in 41 California counties. As of May 2021, Los Angeles County has not yet been declared under a drought emergency, although the U.S. Drought Monitor (droughtmonitor.unl.edu) already shows the County to be in extreme drought.

The City continues to monitor the drought situation and would like to remind the community that the most impactful way to use water efficiently is by being mindful of outdoor irrigation. To that end, the Summer Watering Schedule is effective through **October 30** and allows outdoor irrigation on **Tuesdays, Thursdays, and Saturdays**. To prevent evaporation, please water between **6:00 p.m. and 9:00 a.m.** when sunlight and wind are weakest. Limit sprinklers to 10 minutes per station to avoid creating runoff and ensure that leaks are fixed in a timely manner. Trees and plants may be watered manually every day within the allowed hours by a garden hose with a shut-off nozzle attachment.


If you have questions on the codified Seasonal Watering Schedule or would like to learn more about available resources, please visit ArcadiaCA.gov or contact Public Works Services at 254-2706.



SB 1383

Greenhouse gases are on the rise largely due to the increase of food waste in landfills. The California Department of Resources Recycling and Recovery (CalRecycle) found that food waste makes up 17-18% of landfilled disposal. Reducing food waste aids in decreasing methane emissions and helps repurpose resources.

1. Meal plan for the week to identify what groceries you need to purchase to avoid over-purchasing perishable foods.
2. Organize and store your fruits and vegetables so they can stay fresh for as long as possible.
3. Be mindful of fruits that emit gases ripening other produce, i.e. keep bananas away from apples, etc.
4. Try your hand at composting, it's a great way to repurpose leftover produce and yard clippings. Plus, you are upcycling your food waste into fertilizer! Check greengardensgroup.com/events for available classes and visit the Arboretum for educational resources.
5. If you have safe, unexpired, and unopened canned food that you can't consume, consider donating to local homeless shelters and nonprofits.



Summer classes have started.
Check out the Summer Buzz on our website for more information.



TRASH

CONTAINERS



Trash Containers should be removed from the curb and stored away no later than 5:00 a.m. on the day following trash collection.



This year's Children's Summer Reading Program theme, "Reading Colors Our Community", encourages Arcadians to come together and read, explore, create, and stay safe. The program runs through **Saturday, July 31, 2021**.

Kids can register online, then pick up a free summer pack from the Library. Kids (infant to 5th grade) can log their time spent reading and youth (6th to 8th grade) can complete fun challenges to earn virtual badges, and a reading reward. Participants then visit the Library to collect the reward for their highest earned virtual badge. Prizes range from Glop & Dots to light-up spinning wheels for younger kids, and checker sets and paddle ball games for youth. The Library will also offer weekly virtual storytimes, craft kits, family paint parties, and more throughout the summer. Visit the Library's website at **ArcadiaCA.gov/Library** for more information.



Summer Enrichment Program 2021

This July, the Gilb Museum will be holding its 3rd annual Summer Enrichment Program. For select weeks in the month of July the Gilb Museum will offer a live, virtual learning experience via Zoom. Lessons will be themed around different time periods in Arcadia's history. Each lesson will also include a free educational kit that students can use at home.



Arcadia Public Library Welcomes Back the Public!

Arcadia Public Library reopened to the public on May 3, over a year after it closed its doors due to the COVID-19 pandemic. The Library will be open Mondays-Tuesdays, from 4 p.m. to 8 p.m.; Wednesdays-Thursdays, from 10 a.m. to 2 p.m.; and Saturdays, from 11 a.m. to 5 p.m., until fully staffed. Library users are asked to follow masking guidelines, appropriate social distancing, and to not visit the Library if experiencing any COVID-19 symptoms, if they have been exposed to COVID-19, or have any other contagious illness. The popular front-door pick-up service will continue from 10 a.m. – 2 p.m. on Mondays-Tuesdays; 3 p.m.-7 p.m. on Wednesdays-Thursdays; and 10 a.m.-5 p.m. on Fridays. "Grab-and Go" browsing, public computers, Wi-Fi access, Passport Services, as well as printing, faxing, and copying, are also available. The Friends of the Library will continue holding their outdoor book sale on Tuesdays, Thursdays, and Saturdays.



Do you remember participating in reading programs when you were a kid? Do your children or grandchildren currently participate? Feeling a little left out of the fun? Did you know that the Arcadia Public Library has a Summer at Your Library program just for adults? Join us in June and July for our virtual reading program themed: Reading Colors Your World!

The Library uses the online platform and mobile app called Beanstack where you can keep track of your reading, complete online badges, and enter to win one of three raffle prizes at the end of the summer. Writing short book reviews to share your reading with the community earns you bonus entries for the raffle. The raffle prizes include a Kindle Fire 7, Bluetooth earbuds, and a craft kit bundle. These prizes will be on display over the summer, so be sure to stop by to check them out.

If you're not sure what to read next or need help getting started, please reach out to a librarian. We're happy to help with book recommendations and connect you to materials of interest. We've got something for everyone, so be sure to join us for Summer at Your Library! We also offer helpful and fun newsletters that will keep you up to date on bestsellers and what's new at Arcadia Public Library. Please call the Arcadia Public Library at 821-5569 for information.

Passport Services Open for Business at Arcadia Public Library

As the world slowly reopens for travel and summer wanderlust beckons, Arcadia Public Library's Passport Services Office is open for business! The Passport Services staff is available for processing new passports for adults and children, assisting with renewing passports for children, taking photos, and answering your questions. As the State Department is estimating that it will take 10 to 12 weeks to process a new passport and 4 to 6 weeks to process an expedited passport, allowing enough time to submit and receive your passport is crucial.

There are few things to keep in mind:

- Appointments are required. Please call 294-4848 to schedule an appointment.
- Appointments are available Monday through Thursday evenings, Monday and Tuesday mornings, and Saturdays from 10 a.m. to 1 p.m.
- Please, for the time being, wear a mask and observe social distancing.
- Fillable forms, essential information, and timely updates are available on the State Department's Passport Services website at **Travel.State.gov**. The website also lets customers look for open Passport agencies and acceptance offices by zip code.
- Adult Passport renewals are accepted and processed by mail only. If your passport expired within the last five years, visit **Travel.State.gov** for the necessary form (DS-82) and instructions. Children under 16 must apply for a new passport when their passports expire.
- Passport services staff are here to help! Please call 294-4848 for assistance, appointments, and information.

Seniors, Teen Interns Contribute to Arcadia Oral History

In 2020, Museum staff worked with Girl Scout Kira Camacho on her Gold Award. Ms. Camacho created the Senior Series Project, collecting oral histories from residents in the City of Arcadia. Having to modify her original plans of creating a physical exhibit, Ms. Camacho created a virtual exhibit of her project. The virtual launch of the exhibit is now live and you can find the virtual exhibit link on the Museum's website at **ArcadiaCA.gov/Museum**. The Faces of Arcadia Oral History Project lets teen interns interview members of the Arcadia community, including business owners, members of civic organizations, educators, members of local government, and more. The Faces of Arcadia Oral History Project will help preserve the history of Arcadia by asking members of the Arcadia community to contribute their stories. These oral histories will be added to the Gilb Museum's collections. For more information on the internships or to participate in 30-minute oral history interviews on topics relating to Arcadia's past and present, please contact the Gilb Museum at 574-5440.

Anthony Wilkinson Collection Transcription Project

The Anthony W. Wilkinson Letter Collection is composed of approximately 700 letters and postcards which were written to and by Edith Hartzell Grandy, a former army medic in the U.S. Civil War, between the 1860s and 1960s. These letters have been assessed by Gilb Museum staff as invaluable for their inclusion of the perspective of a woman living in California during the Civil War. Thus, the Gilb Museum intends to digitize these letters to make the information more available for a wider audience. Through the digitization and transcription of Hartzell-Grandy's 700 letters and postcards, the Gilb Museum intends to make these letters available for researchers and reach a state-wide, national, and international audience. If you wish to help transcribe these letters, check out the Museum's website and look at the Transcription Project for more information.

2021 Gilb Museum Kits

Kits are available for preschoolers, children aged 5 to 12, and children with special needs. Each kit includes a history lesson and challenges children to be creative.

Register today for your free kits!



Preschoolers and students ages 5-12 can apply to participate in the wildly popular "Community Kits" program sponsored by the Museum. So far this year, the Gilb Museum has provided 458 kits to local children and is happy to continue to offer free kits to the Arcadia community throughout the 2021 calendar year. Each kit will only be available for a limited time. Applications for kits can be found on the Museum's website starting on the day the application is open and are available for curbside pickup. We offer Community Kits for ages 5-12 and Preschool Kits for children ages 2-5 and for children with special needs.

Community Connect Program

The City's Community Connect Program is a free, secure, and easy way for our community to provide critical information about their households so that the Arcadia Fire Department can adequately respond to our residents during an emergency. Some of the helpful information you can provide includes your property's type, whether or not you have fire sprinklers, best contact in case of an emergency, potential hazards at your location, mobility issues in your household, and even your pet's information.

This is a completely voluntary program and it is up to you on how much information you would like to share with our first responders. Sign up any time by visiting **ArcadiaCA.gov/Connect**.



240 West Huntington Drive
Post Office Box 60021
Arcadia, CA 91066-6021

Pre-sorted
Standard
U.S. Postage
PAID
Arcadia, CA
Permit No. 255

ARCADIA POSTAL CUSTOMER

Support Arcadia Businesses

Shop & Dine Arcadia



如果您需要有人协助翻译本期中的文章, 请与朋友或邻居联系。本期提要:

灌木丛火灾预防工作: 防火植物可保护您的住宅	1
本市禁止的事项	2
请登记以便收到阿凯迪亚市紧急情况通知系统发出的警示	2
帮助拯救阿凯迪亚市居民的生命	2
参加医疗救护队 (PMP)	2
泳池安全提示	2
从2021年7月1日开始, 空置住所登记收取年度登记费	3
阿凯迪亚市公共交通局为您服务!	3
新建住房比例更新	3
阿凯迪亚市居民住宅园林景观指南	3
免费草坪改造课程	4
Carcadia SGV “新能源车”车展	4
法规合规指南	4
免费暑期音乐会和电影	4
干旱	5
暑期课程已经开始	5
SB 1383	5
垃圾桶	5
2021年暑期阅读课程	6
2021年暑期加强课程	6
阿凯迪亚市公共图书馆重新开放!	6
图书馆成人暑期网上活动	6
阿凯迪亚市公共图书馆开放护照服务	7
年长者和青少年实习生为阿凯迪亚市口述历史做出贡献	7
Anthony Wilkinson藏品转录项目	7
2021年吉尔伯特博物馆资料集	7
社区联系计划	7
在阿凯迪亚市购物和用餐	8
在脸书上查看我们的信息	8

Follow Us on Facebook



[Facebook.com/ArcadiaGov](https://www.facebook.com/ArcadiaGov)

The City of Arcadia has launched an official Facebook page in the ongoing effort to enhance communications with the community and provide additional access to City information. Get the latest information on news items, events, and emergency information by following us.

facebook

MARCH 2021

THE ARCADIA HOT SHEET

HIGHLIGHTING NEWS AND EVENTS FROM AROUND OUR TOWN!



Family Reading Program

The Library is freshening up its traditional spring reading program. This year, the family that reads together also wins fun prizes by participating in the Arcadia Public Library's Family Reading Program. Those interested in participating may register online, beginning **Monday, March 22**. Participants then read and log up to 25 book titles to earn virtual badges. There will be weekly drawings for kid participants. Kid, teen, and adult participants who earn at least one virtual badge will be automatically entered into a grand prize drawing for one of five \$25 gift cards. All reading and logging must be completed by **Saturday, May 1, 2021**. Grand prize winners will be contacted by **Friday, May 8, 2021**. Readers may access a host of great digital books through TumbleBook Library, Overdrive or Gale eBooks. All are accessible on the Library's website from the "eBooks and More" webpage.




Don't forget, the Library is still offering the popular front-door pick-up service. Order up to five items online at **Discovery.ArcadiaLibrary.org** and you'll be called to arrange a pick-up time when they are available. Happy family reading!

2021 Gilb Museum Kits

The community's response to the Museum's free educational and preschool kits has been so positive that the Museum will continue to offer them to the Arcadia community through the 2021 calendar year. Applications for kits can be found on the Museum's website, starting on the day the application period is open, and are available for curbside pickup. Educational kits for ages 5-12, preschool kits for children ages 2-5 and for children with special needs are offered. Each kit will only be available for a limited time. Each kit explores topics relating to the history of Arcadia and includes all the materials necessary to create related crafts and activities. For the year of 2020, the Gilb Museum was able to provide a total of 928 kits to members of the community and is expected to distribute 2,000 kits this year. Information and applications for educational kits can be found on the Museum's website.

Spring Bunny Grams

Send a bunny gram to your favorite peeps and give them a treat that they will keep. Grams will be available for purchase for \$20 each. Purchase a bunny gram at **ArcadiaCA.gov** and Mr. Bunny will deliver it to an address in Arcadia! Deliveries will be made from **March 22 to April 2**.



Spring Camp

Dana Gym, 1401 S. 1st Avenue
8 a.m.—6 p.m.
5-12 years of age
\$27 per child, per day

Featuring arts and crafts, fitness, and games! Registration begins **March 1**. Select the day(s) you wish to register your child: **Tuesday, April 6, Wednesday, April 7, Thursday, April 8, and Friday, April 9**. Pack a daily lunch for your child. Safety measures will be in place such as health screenings, temperature checks, face coverings, 1:10 staff to youth ratio, and cleaning protocols. For more information, please call Recreation and Community Services at 574-5113.

Housing Element Update

The City of Arcadia has begun the process of updating the General Plan Housing Element for the 2021- 2029 period. The Housing Element is a multiyear policy tool that serves as a guide for future decisions that impact housing citywide. The goal of the Housing Element is to ensure the City can meet all the housing needs of Arcadia residents.



The City welcomes public participation from our residents and stakeholders during the process to ensure that the most appropriate plans and policies are implemented that best fit the City of Arcadia and address the current and future housing needs.

More information regarding upcoming workshops will be mailed to all City residents and updates will be posted on the City's website at **ArcadiaCA.gov/Housing**. You may also contact Arcadia Planning Services at 574-5423.

Home Safety During COVID

Though only 27% of fires happen in homes, these blazes are responsible for most fire deaths (79%) and injuries (73%). A combination of fewer working fire sprinklers and smoke alarms in residences and the presence of elderly individuals contribute to these statistics. With the COVID-19 ongoing stay at home orders, more people are forced to stay home and work remotely, and the risk of fire continues to grow.

While 2020 data is still being collected, it is reasonable to assume we will see an annual increase in fires as more people spend more time in their residences, especially as cooking becomes more common.

The National Fire Protection Association's (NFPA) latest report on "Home Structure Fires" studied incidents between 2013-2017 and determined that of the average 354,400 home structure fires per year, most were caused by cooking (49%), followed by the following:

- Heating equipment (14%), which presents an added level of risk during winter lockdowns
- Electrical distribution and lighting equipment (10%)
- Intentional (8%), this includes arson and fires started by children
- Smoking materials (5%)

Stay at home orders have understandably created a stressful environment for all. However, fire safety should still be of paramount concern for the home.

Cooking Fire Safety

- If you're cooking with quicker-acting equipment, stay in the room and keep an eye on things.
- Turn off the stove, fryer, broiler, or grill if you have to leave the kitchen.
- Use a timer for longer cooking tasks.
- Keep fuel sources, such as towels or empty boxes away from the stove.
- Always try to keep small kids out of an active kitchen.



Can you find the hidden  x3 ?

Winter Watering Schedule

November 1- April 30

Tuesday & Saturday

No watering between 9:00 a.m. and 6:00 p.m.

Limit 10 minutes per station

Arcadia Transit Is Here for You!

Arcadia Transit is here for your essential trips during the ongoing COVID-19 crisis and Los Angeles County's path to recovery. We are running our regular fixed route schedules and dial-a-ride service. Arcadia Transit is committed to the safety and health of our riders. Our buses are clean, safe, and convenient. For more information on our services, please visit ArcadiaCA.gov/Transit.

Have you downloaded the Arcadia Transit App?

Plan your trip, get real-time schedules, and rely on our essential transportation services to get you where you need to go. Download DoubleMap Bus Tracker on the App Store or Google Play first, then select Arcadia as the transit system to view.


Protect yourself when using Arcadia Transit

- A Federal directive requires a face mask to be worn on public transit at all times. Wear a mask over your nose and mouth when in public settings.
- We ask riders to spread out whenever possible, allowing yourself six feet of physical distance from others.
- Please avoid riding Arcadia Transit if you are feeling sick.

COVID-19 Vaccination Implementation Information

Please visit the County Public Health's website at PublicHealth.LACounty.gov for the latest COVID-19 vaccine implementation information. The webpage includes:

- FAQs
- Responses to myths and misinformation
- Information about scams
- A place to sign up for email updates
- A Vaccine Distribution page that explains the phases and tiers of distribution
- A COVID-19 vaccine management dashboard where people can track how much vaccine has been distributed



Who Will Get Vaccine When


The Vaccine Distribution page describes the phases and tiers of vaccination, with more information about how these phases may roll out. This page is being updated regularly as the groups within each phase and tier are further refined.

**Note: Additional groups may be added as more vaccinations become available. Check the Los Angeles County website at VaccinateLACounty.com for the latest information and to book an appointment if you are in the eligible group.*

APRIL 2021

THE ARCADIA HOT SHEET

HIGHLIGHTING NEWS AND EVENTS FROM AROUND OUR TOWN!



Candidates Being Sought for City Boards and Commissions

The Arcadia City Clerk's Office is currently accepting applications from residents who would like to serve on a City Board or Commission. Arcadia's Board and Commission members serve without compensation. To serve on a Board or Commission, applicants must be 18 years or older, a registered voter, and a resident of the City of Arcadia.

Arcadia's Board and Commission members serve in an advisory capacity and provide critical input on quality of life issues in Arcadia. The Arcadia Beautiful Commission, Human Resources Commission, Library Board of Trustees, and Senior Citizens' Commission each have openings.

Anyone with an interest in serving may obtain a Citizen Service Resume by visiting the City's website at **ArcadiaCA.gov/Service**. Applications must be mailed to the City Clerk's Office on or before the close of business on **Thursday, May 20, 2021**. Appointments are expected to be made at the **Tuesday, June 15, 2021**, City Council meeting.

Please contact the City Clerk's Office at 574-5455 if you would like further information about Board and Commission service in the City of Arcadia.

2021 Gilb Museum Kits

The community's response to the Museum's free educational and preschool kits has been so positive that the Museum will continue to offer them to the Arcadia community through the 2021 calendar year. Applications for kits can be found on the Museum's website, starting on the day the application period is open, and are available for curbside pickup. Educational kits for ages 5-12, preschool kits for children ages 2-5 and for children with special needs are offered. Each kit will only be available for a limited time. Each kit explores topics relating to the history of Arcadia and includes all the materials necessary to create related crafts and activities.

For the year of 2020, the Gilb Museum was able to provide a total of 928 kits to members of the community and is expected to distribute 2,000 kits this year. Information and applications for educational kits can be found on the Museum's website.



Spring Cleaning: Free Bulky Item Pickup

Are you moving or simply looking to get rid of old furniture and appliances? Arcadia residents residing in single-family homes have four (4) free bulky item pickups per year. Multi-family complex residents have two (2) free pickups per unit, per year. Contact Waste Management at (800) 266-7551 or online at **Home.WM.com/Arcadia** to arrange your bulky item pickup today. These items may include:

- Couches, rugs, and other large furniture
- Refrigerators, washing machines, and other large appliances
- Mattresses and box springs
- Water heaters
- Large bundled branches that do not fit in your green waste container
- Bulky electronic waste (computers, TVs, printers, etc.)



Housing Element Update

The City of Arcadia has begun the process of updating the General Plan Housing Element for the 2021- 2029 period. The Housing Element is a multiyear policy tool that serves as a guide for future decisions that impact housing citywide. The goal of the Housing Element is to ensure the City can meet all the housing needs of Arcadia residents.

The City welcomes public participation from our residents and stakeholders during the process to ensure that the most appropriate plans and policies are implemented that best fit the City of Arcadia and address the current and future housing needs.

More information regarding upcoming workshops will be mailed to all City residents and updates will be posted on the City's website at **ArcadiaCA.gov/Housing**. You may also contact Arcadia Planning Services at 574-5423.



Home Safety During COVID-19

Though only 27% of fires happen in homes, these blazes are responsible for most fire deaths (79%) and injuries (73%). A combination of fewer working fire sprinklers and smoke alarms in residences and the presence of elderly individuals contribute to these statistics. With the uncertainty surrounding COVID-19, more people are forced to stay home and work remotely, and the risk of fire continues to grow.

While 2020 data is still being collected, it is reasonable to assume we will see an annual increase in fires as more people spend more time in their residences, especially as cooking becomes more common.

The National Fire Protection Association's (NFPA) latest report on "Home Structure Fires" studied incidents between 2013-2017 and determined that of the average 354,400 home structure fires per year, most were caused by cooking (49%), followed by the following:

- Heating equipment (14%)
- Electrical distribution and lighting equipment (10%)
- Intentional (8%), this includes arson and fires started by children
- Smoking materials (5%)



Fire safety should always be of paramount concern for the home.

Composting at Home

Composting at home is a sustainable practice that turns unwanted food scraps and yard trimmings into a rich, pesticide-free soil conditioner. You can use a compost bin, worm composting bin, or create a free-standing compost pile in a shaded area of your backyard. For basic composting instructions, visit

EPA.gov/Recycle/Composting-Home. The Public Works Services Department offers 3' x 2' compost bins at the reduced price of \$35 to Arcadia residents and worm composting bins for \$65. To reserve yours today, please call 254-2720.

Can you find the hidden  x3 ?

Winter Watering Schedule

November 1- April 30

Tuesday & Saturday

No watering between 9:00 a.m. and 6:00 p.m.
Limit 10 minutes per station

Arcadia Transit Is Here for You!

Arcadia Transit is here for your essential trips during the ongoing COVID-19 crisis and Los Angeles County's path to recovery. We are running our regular fixed route schedules and dial-a-ride service. Arcadia Transit is committed to the safety and health of our riders. Our buses are clean, safe, and convenient. For more information on our services, please visit **ArcadiaCA.gov/Transit**.

Have you downloaded the Arcadia Transit App?

Plan your trip, get real-time schedules, and rely on our essential transportation services to get you where you need to go. Download DoubleMap Bus Tracker on the App Store or Google Play first, then select Arcadia as the transit system to view.

Protect yourself when using Arcadia Transit

- A Federal directive requires a face mask to be worn on public transit at all times. Wear a mask over your nose and mouth when in public settings.
- We ask riders to spread out whenever possible, allowing yourself six feet of physical distance from others.
- Please avoid riding Arcadia Transit if you are feeling sick.

COVID-19 Vaccination Implementation Information

Please visit the County Public Health's website at **PublicHealth.LACounty.gov** for the latest COVID-19 vaccine implementation information. The webpage includes:

- FAQs
- Responses to myths and misinformation
- Information about scams
- A place to sign up for email updates
- A Vaccine Distribution page that explains the phases and tiers of distribution
- A COVID-19 vaccine management dashboard where people can track how much vaccine has been distributed



Who Will Get Vaccine When

The Vaccine Distribution page describes the phases and tiers of vaccination, with more information about how these phases may roll out. This page is being updated regularly as the groups within each phase and tier are further refined.

Note: Additional groups may be added as more vaccinations become available. Check the Los Angeles County website at **VaccinateLACounty.com for the latest information and to book an appointment if you are in the eligible group.*

AUGUST 2021

THE ARCADIA HOT SHEET

HIGHLIGHTING NEWS AND EVENTS FROM AROUND OUR TOWN!



Grilling Safety 101

Using your grill is a wonderful way to enjoy the warm summer months. However, being aware of grilling safety is important. Grilling sparks more than 10,000 home fires on average each year. To help make this summer both safe and enjoyable, here are some helpful grilling safety tips:

- Always supervise a grill when in use.
- Do not wear loose clothing while cooking at a barbeque.
- Do not add lighter fluid to an already lit fire because the flames can flash back up into the container and explode.
- Keep all matches and lighters away from children and make sure to supervise children around outdoor grills.
- Dispose hot coals properly—douse them with plenty of water and never place them in plastic, paper, or wooden containers.



Free Turf Transformation Classes

Due to dryer than normal conditions, it is important to remember the key role landscapes play in water efficiency. If you are looking to revamp your front or backyard, sign up for a free turf transformation class at greengardensgroup.com/turf-transform.



These classes are now being offered online in English, Mandarin, and Spanish. Simply sign up for a scheduled time and an instructor will walk through the process of removing turf grass, building a healthy soil

sponge, and selecting the right plant palette.

The class will also cover the \$2 per square foot turf removal rebate offered by Metropolitan Water District on socialwatersmart.com.

CITY OF ARCADIA

LEADERSHIP ACADEMY

Coming this Fall

The Arcadia Leadership Academy is a free, interactive civic education program for Arcadia residents 18 years and older who are interested in becoming better acquainted with City operations.

The purpose of the program is to provide an interesting perspective into the workings of Arcadia, to develop civic leadership, and to build a stronger community through well-informed and engaged citizens.

If you are interested in applying to be a part of the Fall program, which is scheduled to take place September 29 through December 7, please visit the City website at ArcadiaCA.gov/Academy for the current application. **The deadline to apply is August 20, 2021.**

For additional information, please call the City Manager's Office at 821-4314.

Drought

The City continues to monitor the drought situation and would like to remind the community that the most impactful way to use water efficiently is by being mindful of outdoor irrigation. The Summer Watering Schedule is effective through October 30 and allows outdoor irrigation on **Tuesdays, Thursdays, and Saturdays**.

To prevent evaporation, please water between 6:00 p.m. and 9:00 a.m. when sunlight and wind are weakest. Limit sprinklers to 10 minutes per station to avoid creating runoff and ensure that leaks are fixed in a timely manner. Trees and plants may be watered manually everyday within the allowed hours by a garden hose with a shut-off nozzle attachment.

If you have questions or would like to learn more about available resources, please visit ArcadiaCA.gov/Waterconservation or contact Public Works Services at 254-2706.

Hide it, Lock it, Keep it

Many thieves look for easy and inviting targets when it comes to selecting a vehicle to burglarize. Here are some basic tips that will make your vehicle a little less inviting to a thief:

- Always lock your car.
- Always park in well lighted areas.
- Install and use a vehicle alarm.
- Do not leave valuables in plain view.
- Look around for anything suspicious when you park. If you notice anything suspicious, alert on-site security or staff or call the police.



Housing Element Update

Earlier in the year, the City of Arcadia began the important process of updating its 6th Cycle Housing Element, covering the years 2021-2029. The goal of the update is to plan for the current and future housing needs of all Arcadia residents.

Community participation is a vital part of the update process. Therefore, the City has developed a community survey to find out which housing issues are important to the community, and to help the City develop a plan that best reflects the community's housing needs. The survey is anonymous and takes about 5-10 minutes to complete. The City has also developed a Frequently Asked Questions (FAQ) page to provide more detailed information on the update.

Please visit **ArcadiaCA.gov/Housing** to provide your input by taking the community survey, view the FAQ page, learn more about the update process, sign up for email updates, and view upcoming announcements and opportunities for public participation.



Homeless Forum - Register to Attend

Saturday, August 7, 2021 at 9:00 a.m.

Arcadia Performing Arts Center

To register for in-person or virtual attendance, visit

arcadiahomelessforum.eventbrite.com

Can you find the hidden



x3 ?

Sharps Disposal

It is illegal to dispose of hypodermic needles, lancets, syringes, and similar medical instruments known as "sharps" in household trash. These materials must be disposed of properly in order to prevent injuries and the spread of germs.



The City of Arcadia offers a free 1-quart sharps waste disposal container. Used "sharps" are to be placed inside this leak proof and puncture resistant container for safe storage. Once the container is full, seal the container, place it into the postage prepaid container, and take it to the post office or give it to the mail carrier. The container is then delivered to a medical waste processing facility for proper disposal.

To obtain a free sharps disposal container, please call Public Works Services at 254-2720. Proof of Arcadia residency will be required.

Code Compliance Guides

The City of Arcadia, through the Arcadia Municipal Code (AMC), requires that minimum standards be maintained related to the health, safety, and welfare of community residents. The new Code Compliance guides provide useful information on the City's codes, safety tips, and programs. They are also available in Chinese. Check them out at **ArcadiaCA.gov/CodeGuides**.

Free Summer Concert & Movie Series

Summer concerts and movies are back and will be held back-to-back **on Thursday evenings at 6:30 p.m.** on the City Hall lawn.

Parking is available at the City Hall parking lot and the Santa Anita Race Track, Gate 5 only!



August 5 - Cold Duck

The Croods: A New Age -PG

August 12 - The Answer

Raya and the Last Dragon- PG

Commemorate Arbor Day

Free tree saplings will be available at the August 12 Summer Concerts & Movie Series. Check out the Arcadia Beautiful Commission Booth to get a free tree sapling while supplies last.



SEPTEMBER 2021

THE ARCADIA HOT SHEET

HIGHLIGHTING NEWS AND EVENTS FROM AROUND OUR TOWN!



Fire Prevention Week

During the week of October 3-10, the Arcadia Fire Department will be promoting this year's Fire Prevention Week campaign: "Learn the Sounds of Fire Safety!"



The campaign works to educate everyone about small but important actions they can take to keep themselves and those around them safe. The Arcadia Fire Department encourages all residents to embrace the 2021 Fire Prevention Week theme. Here are some safety tips to help you "Learn the Sounds of Fire Safety":

- A continuous set of three loud beeps means smoke or fire. Get out, call 9-1-1, and stay out.
- A single chirp every 30 or 60 seconds means the battery on a smoke alarm is low and must be changed.
- Chirping that continues after the battery has been replaced means the alarm is at the end of its life and the unit must be replaced.

Remember that all smoke alarms must be replaced after ten years. It is also important to make sure your smoke and carbon monoxide alarms meet the needs of all your family members, including those with sensory or physical disabilities. For more information, visit **FirePreventionWeek.org** or contact the Arcadia Fire Prevention Bureau at 574-5104.

Anthony Wilkinson Collection Transcription Project

The Anthony W. Wilkinson Letter Collection is composed of approximately 700 letters and postcards which were written to and by Edith Hartzell Grandy, a former Army medic in the U.S. Civil War. These letters have been assessed by Gilb Museum staff as invaluable. The Gilb Museum intends to digitize these letters to make the information more available for a wider audience. Through digitization and transcription, the letters will be available for researchers. If you wish to help transcribe these letters, visit **ArcadiaCA.gov/Museum**.



Housing Element Update

Have you heard? The City is in the process of updating its Housing Element for the next cycle which is from 2021-2029. As part of the public outreach process, the City received over 500 responses from the online community survey. These responses will help the City develop plans and policies that best reflect the community's housing needs. The City will be hosting a community meeting to discuss any potential changes as part of this Housing Element. Please stay involved, and for weekly updates, visit the City's Housing Element webpage at **ArcadiaCA.gov/Housing**.



Water Conservation Update

As of May 2021, California entered another significant drought cycle. Governor Newsom declared a drought emergency in 41 counties. While Los Angeles County has not been declared to be in a drought, the City is committed to being a good water steward of our local groundwater supplies. To mitigate the current drought's inevitable impact on local supplies, the City continues to observe the codified Water Conservation Ordinance, which includes Seasonal Watering Schedules. The Summer Watering Schedule is effective through October 30 and allows outdoor irrigation on **Tuesdays, Thursdays, and Saturdays**.

To prevent evaporation, please water between 6:00 p.m. and 9:00 a.m. when sunlight and wind are weakest. Limit sprinklers to 10 minutes per station to avoid creating runoff and ensure that leaks are fixed in a timely manner. Trees and plants may be watered manually everyday within the allowed hours by a garden hose with a shut-off nozzle attachment.



For more information, visit **ArcadiaCA.gov/Waterconservation**.

Calling Potential Police Cadets

Are you interested in pursuing a career in law enforcement? Join the Arcadia Police Department as a Police Cadet. Police Cadets must be between 18 to 21 years of age. To obtain more information, call 574-5172 or email **lperalta@ArcadiaCA.gov**.

Save by Joining the Paramedic Membership Program

A 9-1-1 call for emergency ambulance service can cost thousands of dollars. For \$51 per year, the Paramedic Membership Program (PMP) provides savings with benefits that you do not want to miss:

- Covers ALL permanent household members who reside at the same address.
- Covers ALL out-of-pocket expenses for emergency ambulance services.
- Reduces rates for those who live in retirement facilities and qualifying low-income residents.

For more information, or to obtain an application packet, please contact the Arcadia Fire Department at 574-5126 or visit ArcadiaCA.gov/Paramedic.



The Arcadia Library Offers Wonderful Books About the Moon Festival

The Moon Festival is a traditional Chinese celebration observed when the moon is full and at its brightest. Visit the Arcadia Library and check out books with information on the unique cultural traditions of the Moon Festival.

For more information, visit ArcadiaCA.gov/Library.

The First Flush– Protect Water Quality

In the summer, pollutants from pet waste, cigarette butts, oil, grease, and pesticides accumulate on the street. In the rainy season, the first storm, known as the first flush, is dangerous because it carries these toxic pollutants in high concentrations into the ocean. By being mindful, we can help protect public health, the beaches, and aquatic life. Help prevent pollution by:

- Picking up pet waste and placing it into the appropriate trash container.
- Properly disposing of leaves. Do not blow, sweep, hose, or rake leaves into the street, gutter, or storm drains.
- Avoid applying fertilizer or any other chemical on lawns and gardens before watering or predicted rain event.
- Properly disposing of trash; throw litter into trash cans, not into the streets.
- Reporting illegal dumping by calling the Public Works Service Department at 254-2720.

{ Can you find the hidden  x3 ? }

Arcadia Police Department Explorer Program

The Arcadia Police Department is seeking Explorers. An Explorer is a volunteer scout that assists with searches for evidence, report writing, desk officer duties, command post operations, crime prevention surveillance, disaster assistance, crowd and traffic control, and more. It's an excellent way to start pursuing a career in law enforcement.



The Arcadia Police Department Explorer Program is designed for youth between 14 to 18 years of age. After graduating from the San Gabriel Valley Law Enforcement Explorer Academy, Explorers are assigned to Explorer Post 101. Police Officers then work with Explorers in an effort to provide community service. For more information, call 574-5172 or email lperalta@ArcadiaCA.gov.

Bear Safety Tips

Often bears emerge in residential neighborhoods in search of food and water. Bears have keen noses and can smell from miles away. To protect your family and property, follow these simple tips:



- Purchase and properly use a bear-proof garbage container. The City of Arcadia offers 95-gallon bear resistant carts to residents. For more information, visit ArcadiaCA.gov/TrashandRecycling.
- Keep barbeque grills clean and stored in a garage or shed when not in use.
- Only provide bird feeders during November through March.
- Don't leave any scented products outside, even non-food items such as suntan lotion, insect repellent, soap, or candles.
- Harvest fruit off trees as soon as the fruit is ripe, and promptly collect fruit that has fallen.
- Securely block access to potential hibernation sites such as crawl spaces under decks and buildings. This can be done by sealing all openings with caulking, foam insulation, or wood. Make sure to continuously monitor the exterior of your home for new possible points of entry.

In the event of immediate danger from any type of wildlife, please do not hesitate to call the Arcadia Police Department at 792-7151 or 9-1-1 in an emergency. For more bear safety tips and Information, visit ArcadiaCA.gov/Wildlife.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

6. Public Comments

One inquiry regarding the housing element was received during the planning period. The City also posted the Public Review Draft on the City's website for comment from September 30 through November 1, 2021. The Draft was advertised through various outlets such as Twitter, Facebook, WeChat, and Nextdoor. Despite outreach efforts, no comments were received during the Public Review Period.

-----Original Message-----

From: [REDACTED]

Sent: Saturday, October 2, 2021 3:09 PM

To: Lisa Flores <lflores@arcadiaca.gov>

Cc: [REDACTED]

Subject: Re: Draft Housing Element - Public Review

CAUTION: This email originated from outside your organization. Exercise caution when opening attachments or clicking links, especially from unknown senders.

Hi Lisa:

First, I want to thank you for replying to my request for the Draft Housing Element. As you know, we already had several meetings with you discussing our feasibility study of the development of 30-60 E Live Oak. With the Draft Housing Element in process, we will consider including affordable housing units in our development to help the City fulfil some of its affordable housing needs. To do an analysis of including affordable housing units, we need to know the affordable sales price for very low, low, and moderate income, we just wonder if the City has such data/formula available. Please advise. Thanks.

Regards

[REDACTED]

From: Lisa Flores <lflores@arcadiaca.gov>

Sent: Thursday, September 30, 2021 4:12 PM

Subject: Draft Housing Element - Public Review

Good afternoon,



CITY OF ARCADIA 6TH CYCLE Housing Element Update

6. Additional Outreach

The City conducted additional outreach to the following groups:

- Planning Commission
- HOA Boards
- Arcadia Association of Realtors
- Chamber of Commerce
- Arcadia Chinese Association
- Downtown Improvement Association
- Interested Parties List

A letter for the second revision to the Housing Element Update was provided to the following organizations to engage the low income and moderate income population.

- Assistance League of America
- Foothill Unity Center Inc.
- Habitat for Humanity
- Residents at Naomi Gardens



May 27, 2022

City of Arcadia

CDBG Home Improvement Program & Recipients of the Program
240 West Huntington Drive
Arcadia, CA. 91007

Development Services Department

Jason Kruckeberg
*Assistant City Manager/
Development Services
Director*

RE: CITY OF ARCADIA HOUSING ELEMENT

Dear Tim Schwehr:

As you may be aware, the City of Arcadia is in the process of finalizing its "Housing Element". The Housing Element is a requirement of the State of California that mandates all cities to submit their plan for providing housing over the next nine-year planning period. Much of this housing must be affordable housing. The City Council of the City of Arcadia approved our Housing Element on February 15, 2022, and authorized that it be sent to the State Department of Housing and Community Development (HCD). Since the Council approval of the project, the City has received additional comments from HCD, and we have been incorporating these comments into our Draft Element and related materials. A new version of the Draft Element has just been posted on our website that includes our responses to HCD's comments.

The reason we are sending you this correspondence is that you or your clients or residents may be interested in the City's plans for affordable housing and strategies to provide it. We invite you to review the revised Draft on the Housing Element Update website at www.ArcadiaCA.gov/housing

If you have any comments on the Housing Element or on any of the associated documents, or if you have any questions at all about affordable housing, please email Arcadia Planning Services at Planning@ArcadiaCA.gov

Sincerely,

City of Arcadia Development Services Department

240 West Huntington Drive
Post Office Box 60021
Arcadia, CA 91066-6021
(626) 574-5415
(626) 447-3309 Fax
www.ArcadiaCA.gov



CITY OF
ARCADIA

Technical Background Report

Appendix C

Glossary of Terms





CITY OF ARCADIA 6TH CYCLE Housing Element Update

Appendix C: Glossary of Terms

Above Moderate Income Household. A household with an annual income usually greater than 120% of the area median family income adjusted by household size, as determined by a survey of incomes conducted by a city or a county, or in the absence of such a survey, based on the latest available legibility limits established by the U.S. Department of housing and Urban Development (HUD) for the Section 8 housing program.

Affirmatively Furthering Fair Housing (AFFH). Affirmatively Furthering Fair Housing (AFFH) is a legal requirement that federal agencies and federal grantees further the purposes of the Fair Housing Act. AFFH means "taking meaningful actions, in addition to combating discrimination, that overcome patterns of segregation and foster inclusive communities free from barriers that restrict access to opportunity based on protected characteristics. Specifically, affirmatively furthering fair housing means taking meaningful actions that, taken together, address significant disparities in housing needs and in access to opportunity, replacing segregated living patterns with truly integrated and balanced living patterns, transforming racially and ethnically concentrated areas of poverty into areas of opportunity, and fostering and maintaining compliance with civil rights and fair housing laws.

Apartment. An apartment is one (1) or more rooms in an apartment house or dwelling occupied or intended or designated for occupancy by one (1) family for sleeping or living purposes and containing one (1) kitchen.

Assisted Housing. Generally multi-family rental housing, but sometimes single-family ownership units, whose construction, financing, sales prices, or rents have been subsidized by federal, state, or local housing programs including, but not limited to Federal state, or local housing programs including, but not limited to Federal Section 8 (new construction, substantial rehabilitation, and loan management set-asides), Federal Sections 213, 236, and 202, Federal Sections 221 (d) (3) (below-market interest rate program), Federal Sections 101 (rent supplement assistance), CDBG, FmHA Sections 515, multi-family mortgage revenue bond programs, local redevelopment and in lieu fee programs, and units developed pursuant to local inclusionary housing and density bonus programs.

Below-Market-Rate (BMR). Any housing unit specifically priced to be sold or rented to low or moderate income households for an amount less than the fair-market value of the unit. Both the State of California and the U.S. Department of Housing and Urban Development set standards for determining which households qualify as "low income" or "moderate income." (2) The financing of housing at less than prevailing interest rates.

Build-Out. That level of urban development characterized by full occupancy of all developable sites in accordance with the General Plan; the maximum level of development envisioned by the General Plan. Build-out does not assume that each parcel is developed to include all floor area or housing units possible under zoning regulations.

Community Development Block Grant (CDBG). A grant program administered by the U.S. Department of Housing and Urban Development (HUD) on a formula basis for entitled communities and administered by the State Department of Housing and Community Development (HCD) for non-entitled jurisdictions. This grant allots money to cities and counties for housing rehabilitation and community development, including public facilities and economic development.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Condominium. A structure of two or more units, the interior spaces of which are individually owned; the balance of the property (both land and building) is owned in common by the owners of the individual units. (See “Townhouse.”)

Covenants, Conditions, and Restrictions (CC&Rs). A term used to describe restrictive limitations that may be placed on property and its use, and which usually are made a condition of holding title or lease.

Deed. A legal document which affects the transfer of ownership of real estate from the seller to the buyer.

Density Bonus. The allocation of development rights that allow a parcel to accommodate additional square footage or additional residential units beyond the maximum for which the parcel is zoned, usually in exchange for the provision or preservation of an amenity at the same site or at another location.

Density, Residential. The number of permanent residential dwelling units per acre of land. Densities specified in the General Plan may be expressed in units per gross acre or per net developable acre.

Developable Land. Land that is suitable as a location for structures and that can be developed free of hazards to, and without disruption of, or significant impact on, natural resource areas.

Down Payment. Money paid by a buyer from his own funds, as opposed to that portion of the purchase price which is financed.

Duplex. A detached building under single ownership that is designed for occupation as the residence of two families living independently of each other.

Dwelling Unit (DU). A building or portion of a building containing one or more rooms, designed for or used by one family for living or sleeping purposes, and having a separate bathroom and only one kitchen or kitchenette. See Housing Unit.

Elderly Housing. Typically, one- and two-bedroom apartments or condominiums designed to meet the needs of persons 62 years of age and older or, if more than 150 units, persons 55 years of age and older, and restricted to occupancy by them.

Emergency Shelter. A facility that provides immediate and short-term housing and supplemental services for the homeless. Shelters come in many sizes, but an optimum size is considered to be 20 to 40 beds. Supplemental services may include food, counseling, and access to other social programs. (See “Homeless” and “Transitional Housing.”)

Extremely Low Income Household. A household with an annual income equal to or less than 30% of the area median family income adjusted by household size, as determined by a survey of incomes conducted by a city or a county, or in the absence of such a survey, based on the latest available eligibility limits established by the U.S. Department of Housing and Urban Development (HUD) for the Section 8 housing program.

Fair Market Rent. The rent, including utility allowances, determined by the United States Department of Housing and Urban Development for purposed of administering the Section 8 Program.

Family. (1) Two or more persons related by birth, marriage, or adoption [U.S. Bureau of the Census]. (2) An Individual or a group of persons living together who constitute a bona fide single-family housekeeping unit in a dwelling unit, not including a fraternity, sorority, club, or other group of persons occupying a hotel,



CITY OF ARCADIA 6TH CYCLE Housing Element Update

lodging house or institution of any kind [Governor's Office of Planning and Research, General Plan Guidelines].

General Plan. A comprehensive, long-term plan mandated by State Planning Law for the physical development of a city or county and any land outside its boundaries which, in its judgment, bears relation to its planning. The plan shall consist of seven required elements: land use, circulation, open space, conservation, housing, safety, and noise. The plan must include a statement of development policies and a diagram or diagrams illustrating the policies.

Goal. A general, overall, and ultimate purpose, aim, or end toward which the City will direct effort.

Green Building. Green or sustainable building is the practice of creating healthier and more resource-efficient models of construction, renovation, operation, maintenance, and demolition. (US Environmental Protection Agency)

Historic Preservation. The preservation of historically significant structures and neighborhoods until such time as, and in order to facilitate, restoration and rehabilitation of the building(s) to a former condition.

Historic Property. A historic property is a structure or site that has significant historic, architectural, or cultural value.

Household. All those persons—related or unrelated—who occupy a single housing unit. (See “Family.”)

Housing and Community Development Department (HCD). The State agency that has principal responsibility for assessing, planning for, and assisting communities to meet the needs of low and moderate income households.

Housing Element. One of the seven State-mandated elements of a local general plan, it assesses the existing and projected housing needs of all economic segments of the community, identifies potential sites adequate to provide the amount and kind of housing needed, and contains adopted goals, policies, and implementation programs for the preservation, improvement, and development of housing. Under State law, Housing Elements must be updated every five years.

Housing Payment. For ownership housing, this is defined as the mortgage payment, property taxes, insurance and utilities. For rental housing this is defined as rent and utilities.

Housing Ratio. The ratio of the monthly housing payment to total gross monthly income; also called Payment-to-income Ratio or Front-End Ratio.

Housing Unit. The place of permanent or customary abode of a person or family. A housing unit may be a single-family dwelling, a multi-family dwelling, a condominium, a modular home, a mobile home, a cooperative, or any other residential unit considered real property under State law.

Housing and Urban Development, U.S. Department of (HUD). A cabinet-level department of the federal government that administers housing and community development programs.

Implementing Policies. The City's statements of its commitments to consistent actions.

Implementation. Actions, procedures, programs, or techniques that carry out policies.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Infill Development. The development of new housing or other buildings on scattered vacant lots in a built-up area or on new building parcels created by permitted lot splits.

Jobs-Housing Balance. A ratio used to describe the adequacy of the housing supply within a defined area to meet the needs of persons working within the same area. The General Plan uses SCAG's definition which is a job total equal to 1.2 times the number of housing units within the area under consideration.

Land Use Classification. A system for classifying and designating the appropriate use of properties.

Live-Work Units. Buildings or spaces within buildings that are used jointly for commercial and residential purposes where the residential use of the space is secondary or accessory to the primary use as a place of work.

Low Income Household. A household with an annual income usually no greater than 51%-80% of the area median family income adjusted by household size, as determined by a survey of incomes conducted by a city or a county, or in the absence of such a survey, based on the latest available eligibility limits established by the U.S. Department of Housing and Urban Development (HUD) for the Section 8 housing program.

Low Income Housing Tax Credits. Tax reductions provided by the federal and State governments for investors in housing for low income households.

Manufactured Housing. Residential structures that are constructed entirely in the factory, and which since June 15, 1976, have been regulated by the federal Manufactured Home Construction and Safety Standards Act of 1974 under the administration of the U.S. Department of Housing and Urban Development (HUD). (See "Mobile home" and "Modular Unit.")

Mixed-Use. Properties on which various uses, such as office, commercial, institutional, and residential, are combined in a single building or on a single site in an integrated development project with significant functional interrelationships and a coherent physical design. A "single site" may include contiguous properties.

Moderate Income Household. A household with an annual income usually no greater than 81%-120% of the area median family income adjusted by household size, as determined by a survey of incomes conducted by a city or a county, or in the absence of such a survey, based on the latest available eligibility limits established by the U.S. Department of Housing and Urban Development (HUD) for the Section 8 housing program.

Monthly Housing Expense. Total principal, interest, taxes, and insurance paid by the borrower on a monthly basis. Used with gross income to determine affordability.

Multiple Family Building. A detached building designed and used exclusively as a dwelling by three or more families occupying separate suites.

Ordinance. A law or regulation set forth and adopted by a governmental authority, usually a city or county.

Overcrowded Housing Unit. A housing unit in which the members of the household, or group are prevented from the enjoyment of privacy because of small room size and housing size. The U.S. Bureau of Census defines an overcrowded housing unit as one which is occupied by more than one person per room.

Parcel. A lot or tract of land.



CITY OF ARCADIA 6TH CYCLE Housing Element Update

Planning Area. The area directly addressed by the general plan. A city's planning area typically encompasses the city limits and potentially annexable land within its sphere of influence.

Policy. A specific statement of principle or of guiding actions that implies clear commitment but is not mandatory. A general direction that a governmental agency sets to follow, in order to meet its objectives before undertaking an action program. (See "Program.")

Poverty Level. As used by the U.S. Census, families and unrelated individuals are classified as being above or below the poverty level based on a poverty index that provides a range of income cutoffs or "poverty thresholds" varying by size of family, number of children, and age of householder. The income cutoffs are updated each year to reflect the change in the Consumer Price Index.

Program. An action, activity, or strategy carried out in response to adopted policy to achieve a specific goal or objective. Policies and programs establish the "who," "how" and "when" for carrying out the "what" and "where" of goals and objectives.

Redevelop. To demolish existing buildings; or to increase the overall floor area existing on a property; or both; irrespective of whether a change occurs in land use.

Regional. Pertaining to activities or economies at a scale greater than that of a single jurisdiction and affecting a broad geographic area.

Regional Housing Needs Assessment. A quantification by the local council of governments of existing and projected housing need, by household income group, for all localities within a region.

Rehabilitation. The repair, preservation, and/or improvement of substandard housing.

Residential. Land designated in the General Plan and zoning ordinance for building consisting of dwelling units. May be improved, vacant, or unimproved. (See "Dwelling Unit.")

Residential Care Facility. A facility that provides 24-hour care and supervision to its residents.

Residential, Multiple Family. Usually three or more dwelling units on a single site, which may be in the same or separate buildings.

Residential, Single-Family. A single dwelling unit on a building site.

Retrofit. To add materials and/or devices to an existing building or system to improve its operation, safety, or efficiency. Buildings have been retrofitted to use solar energy and to strengthen their ability to withstand earthquakes, for example.

Rezoning. An amendment to the map to effect a change in the nature, density, or intensity of uses allowed in a zoning district and/or on a designated parcel or land area.

Second Unit. A self-contained living unit, either attached to or detached from, and in addition to, the primary residential unit on a single lot. "Granny Flat" is one type of second unit.

Section 8 Rental Assistance Program. A federal (HUD) rent-subsidy program that is one of the main sources of federal housing assistance for low income households. The program operates by providing "housing assistance payments" to owners, developers, and public housing agencies to make up the difference between the "Fair Market Rent" of a unit (set by HUD) and the household's contribution toward



CITY OF ARCADIA 6TH CYCLE Housing Element Update

the rent, which is calculated at 30% of the household's adjusted gross monthly income (GMI). "Section 8" includes programs for new construction, existing housing, and substantial or moderate housing rehabilitation.

Shared Living Facility. The occupancy of a dwelling unit by persons of more than one family in order to reduce housing expenses and provide social contact, mutual support, and assistance. Shared living facilities serving six or fewer persons are permitted in all residential districts by Section 1566.3 of the California Health and Safety Code.

Single-Family Dwelling, Attached. A dwelling unit occupied or intended for occupancy by only one household that is structurally connected with at least one other such dwelling unit. (See "Townhouse.")

Single-Family Dwelling, Detached. A dwelling unit occupied or intended for occupancy by only one household that is structurally independent from any other such dwelling unit or structure intended for residential or other use. (See "Family.")

Single Room Occupancy (SRO). A single room, typically 80-250 square feet, with a sink and closet, but which requires the occupant to share a communal bathroom, shower, and kitchen.

Subsidize. To assist by payment of a sum of money or by the granting to terms or favors that reduces the need for monetary expenditures. Housing subsidies may take the forms of mortgage interest deductions or tax credits from federal and/or state income taxes, sale or lease at less than market value of land to be used for the construction of housing, payments to supplement a minimum affordable rent, and the like.

Substandard Housing. Residential dwellings that, because of their physical condition, do not provide safe and sanitary housing.

Supportive Housing. Housing with no limit on length of stay, that is occupied by the target population as defined in California Health and Safety Code Section 53260(d), and that is linked to onsite or offsite services that assist the supportive housing resident in retaining the housing, improving his or her health status, and maximizing his or her ability to live and, when possible, work in the community. "Target population" means adults with low incomes having one or more disabilities, including mental illness, HIV or AIDS, substance abuse, or other chronic health conditions, or individuals eligible for services provided under the Lanterman Developmental Disabilities Services Act and may, among other populations, include families with children, elderly persons, young adults aging out of the foster care system, individuals exiting from institutional settings, veterans, or homeless people. [California Health and Safety Code Sections 50675.14(b) and 53260(d)]

Target Areas. Specifically, designated sections of the community where loans and grants are made to bring about a specific outcome, such as the rehabilitation of housing affordable by Very Low and Low income households.

Tax Increment. Additional tax revenues that result from increases in property values within a redevelopment area. State law permits the tax increment to be earmarked for redevelopment purposes but requires at least 20 percent to be used to increase and improve the community's supply of very low and low income housing. Arcadia currently allocates 30 percent of its tax increment to increase and improve the community's supply of very low and low income housing.

Tenure. A housing unit is owner-occupied if the owner or co-owner lives in the unit, even if it is mortgaged or not fully paid for. A cooperative or condominium unit is owner-occupied only if the owner or co-owner



CITY OF ARCADIA 6TH CYCLE Housing Element Update

lives in it. All other occupied units are classified as renter-occupied including units rented for cash rent and those occupied without payment of cash rent.

Townhouse. A townhouse is a dwelling unit located in a group of three (3) or more attached dwelling units with no dwelling unit located above or below another and with each dwelling unit having its own exterior entrance.

Transitional Housing. Shelter provided to the homeless for an extended period, often as long as 18 months, and generally integrated with other social services and counseling programs to assist in the transition to self-sufficiency through the acquisition of a stable income and permanent housing. (See “Homeless” and “Emergency Shelter.”)

Undevelopable. Specific areas where topographic, geologic, and/or superficial soil conditions indicate a significant danger to future occupants and a liability to the City.

ACRONYMS USED

ACS: American Community Survey

BMPs: Best Management Practices

CALTRANS: California Department of Transportation

CEQA: California Environmental Quality Act

CHAS: Comprehensive Housing Affordability Strategy

CIP: Capital Improvement Program

DDS: Department of Developmental Services

DIF: Development Impact Fee

DU/AC: Dwelling Units Per Acre

EDD: California Employment Development Department

FAR: Floor Area Ratio

FEMA: Federal Emergency Management Agency

HCD: Department of Housing and Community Development

HOA: Homeowners Association

HUD: Department of Housing and Urban Development

LAFCO: Local Agency Formation Commission

MFI: Median Family Income



CITY OF ARCADIA 6TH CYCLE Housing Element Update

NPDES: National Pollutant Discharge Elimination System

RTFH: Regional Task Force on the Homeless

RTP: Regional Transportation Plan

SCAG: Southern California Association of Governments

SPA: Sectional Planning Area

STF: Summary Tape File (U.S. Census)

TOD: Transit-Oriented Development

TDM: Transportation Demand Management

TSM: Transportation Systems Management

WCP: Water Conservation Plan